Gaekwad's Oriental Series

Published under the Authority of the Maharaja Sayajirao University of Baroda.

General Editor:
B. J. Sandesara,
M. A., Ph. D.

No. 134

A DICTIONARY OF SANSKRIT GRAMMAR

A DICTIONARY

OF

SANSKRIT GRAMMAR

bу

Mahāmahopādhyāya KASHINATH VASUDEV ABHYANKAR, M.A.

Retired Professor of Sanskrit, Gujarat College, Ahmedabad. Hon. Professor of Sanskrit, Bhandarkar Oriental Research Institute, Poona



ORIENTAL INSTITUTE BARODA 1961 First Edition: 1000 Copies.

Printed (on behalf of the M. S. University of Baroda Press) by M. N. Chapekar, Aryasanskriti Mudranalaya, 1575/2 Sadashiv, Tilak Road, Poona 2, and Published on behalf of the Maharaja Sayajirao University of Baroda by Dr. Bhogilal, J. Sandesara, Director, Oriental Institute, Baroda, March, 1961.

Price Rs. 25=00

Copies can be had from— Manager,

The University Publications Sales Unit,
M. S. University of Baroda Press (Sadhana Press),
near Palace Gate, Palace Road, BARODA.

DEDICATED


to

The Memory of

the late Mahamahopadhyaya

VASUDEV SHASTRI ABHYANKAR

my father, whose example has inspired me to undertake this and similar other works on Sanskrit Grammar.



FOREWORD

We take this opportunity to place before the world of Sanskrit seholars this Dictionary of Sanskrit Grammar, which, we are confident, will be an indispensable reference book for all students working in this field as well as allied branches of knowledge.

Prof. Kashinath Vasudev Abhyankar has the good fortune to inherit traditional Sanskrit learning from his father, Mahāmahopādhyāya Pandit Vasudevashastri Abhyankar, who is well known for his translations of The Brahmasūtra Śānkara Bhāsya and The Pātanjala Mahābhasya. Prof. Abhyankar had a brilliant academic career and is a reputed teacher and a very well known scholar of Sanskrit Grammar and Prakrit language and literature. He has himself edited several books, and is at present bringing out revised editions of The Pātanjala Mahābhāsya and Paribhāṣenduśekhara and has compiled a Paribhāṣāsangraha all'of which are being published by the Bhandarkar Oriental Research Institute, Poona. His exhaustive introduction to The Pātanjala Mahābhāsya is enough to show that he is pre-eminently qualified for preparing this Dictionary of Sanskrit Grammar, which is a valuable product of a life-time of devoted scholarship.

We are thankful to the University Grants Commission and the State Government for the liberal financial assistance they have given towards publication of this work.

Oriental Institute, Baroda, } 17-3-1961.

B. J. SANDESARA Director

INTRODUCTION

Object of this Dictionary

No apology is needed for undertaking the compilation of the present 'Dictionary of Sanskrit Grammar', which, although concise, is expected to meet the needs of Sanskrit scholars and research students of Vyakarana and other Shastras by serving as a useful reference book in their study of, and research work in, any branch of Sanskrit learning. The many independent treatises in the several Shastras and the learned commentaries upon them, as also the commentaries on classical poems and dramas, are, in fact, full of grammatical explanations of words and constructions, involving a liberal use of grammatical expressions and technical terms at several The elementary knowledge of grammar which a general scholar of Sanskrit possesses, is not found sufficient for his understanding fully the grammatical references in these books, especially so at present, when the practice of sending young boys to the Tolls and Sanskrit Pathashalas to study the standard classical works with commentaries along with some standard elementary treatises on grammar, has already stopped. The number of Sanskrit Pandits and Shastris, who had to obtain a sound footing in grammar before they undertook the study of the higher texts of the several Shastras, and who therefore could be consulted by young scholars and research workers in the several Shastras, has also diminished considerably. The usual Sanskrit Dictionaries such as those of Monier Williams, V.S.Apte and others are found of no avail in supplying explanations of the grammatical technique which confronts modern scholars at every step in their critical reading of the several Sanskrit texts. In these circumstances it is only the technical dictionaries of the type of the present Dictionary of Sanskrit Grammar' that can render a valuable assistance to scholars and research workers in their reading of the higher Sanskrit texts in the several Shastras.

Beginnings of Sanskrit Grammar

Every science has necessarily its own terminology and a special vocabulary. The remark is true with respect to Sanskrit Grammar or Vyākaraṇaśāstra which has developed as a science during the last two thousand years and has got several technical terms and numerous words with a special grammatical significance. The origin of grammar can wellnigh be traced to the Period of the Brāhmaṇas i. e. about 2000 B.C., when Vedic scholars began to discuss the meaning of the inspired Vedic hymns by carefully showing disconnected, the words of the Vedic hymns and noting down the differences in accents as also the changes caused by their coalescence in the continuous recital or the Samhitāpātha. They also tried to explain the sense of the Vedic words by tracing them back to the roots of suitable senses and laid down rules for their proper and correct

pronunciation. These three pursuits viz. (a) the discussion of the features of the Pada text, (b) the derivation of words, and (c) directions regarding the proper pronunciation of the Vedic words, were carried on with vigour with a view to preserving the Vedic texts intact, and the treatises dealing with these three branches were respectively called by the names Prātisākhya, Nirukta and Śikṣā, all of which could rightly be called Vyākaraṇa or Grammar, as they were devoted to determining the correct words as distinguished from the incorrect ones. Although a number of books were written by Vedic scholars in these three branches, not more than five or six Prātišākhya works, a solitary Nirukta work, and a few Śikṣā works are the only available works at present.

Development of Sanskrit Grammar

In course of time, on the analogy of the derivation of words, an analysis of the word into its constituent elements such as the base, the affix, the augments and the modifications, was undertaken by grammarians. This separation of the different elements of a word constituted Vyākaraņa or grammar, which was developed as an art by ancient grammarians like Āpišali, Sākatāyana and others before Pāņini. It was Pāņini who carried it to perfection, and his work, the Astadhyavi, compact yet exhaustive, and laconic yet clear, is simply a marvellous product of art by a man of amazing intelligence. As a result, the works on grammar by all ancient scholars who flourished before Pāṇini disappeared in course of time leaving only a few quotations behind them. Panini was followed by a number of grammarians who wrote popular treatises on grammar, based, no doubt, on Pāṇini's grammar, some of which, in their turn came to have auxiliary works, glosses and explanatory commentaries. These different treatises, written by Sarvavarman, Candragomin, Devanandin, Palyakirti Sakatayana, Hemacandra, Kramadisvara, Jumaranandin, Supadina and others with their auxiliary works and commentaries, came to be looked upon as different systems of grammar. These treatises present two kinds of treatment: some of them are arranged in Sūtras in the same manner as the Astādhyāyi of Pāpini which treats one after another the several grammatical elements such as technical terms, padas of roots, case-relations, compound words, krt affixes, taddhita affixes, substitutes, accents and cuphonic changes; while others give a topic-wise treatment following in that respect the ancient grammarians before Pāṇini such as Indra, Vedic Śākaṭāyana and others who treated one after another the different topics of grammar such as the euphonic changes, declension, conjugation, compound formation, nouns derived from roots, nouns derived from nouns and the like. The special feature of all these grammars was that they entirely omitted the Vedic peculiarities and accents.

Sanskrit Grammar as a Science

The subject of Sanskrit grammar was first treated as a science by the two epoch-making grammarians, first by Kātyāyana a few centuries after Pāṇini,

and then by Patanjali, the exponent of Katyayana who lived in the second century B. C. It was carried to perfection by the stalwart grammarian Bhartrhari of the seventh century A. D. Later grammarians, prominent among whom were Jayaditya, Vamana, Kaiyata, Haradatta, Bhattoji, Kondabhatta and Nagesa, developed by their substantial contributions, the work of Panini as a science to such an extent that the number of smaller and greater works well nigh rose to eight hundred and that of the authors to four hundred. The grammar of Panini, which is looked upon as the standard one at present gives about a hundred technical terms, more than two hundred suffixes, about two thousand primary roots and more than five thousand special words arranged in more than two hundred and fifty classes according to the special grammatical peculiarities shown by each class. The number of independent primary words, besides these five thousand special words, if roughly estimated, may exceed even twenty-five thousand. Besides these primary roots, primary nouns, affixes and technical terms in the different Shastras, there is a vast number of secondary roots and secondary nouns, which is rather impossible even to be approximately determined.

Nature and Scope of this Dictionary

The preparation of a comprehensive dictionary of Sanskrit Grammar, a subject which has been developed fully by Sanskrit Grammarians for the last two thousand years, is certainly a stupendous work which can only be done by a band of grammarians who have got a sound footing in the subject. In the light of what has been said above, the present dictionary is only an honest and humble attempt in that direction, made by the compiler who was inspired to undertake this rather arduous venture by his close study of the subject for more than sixty years according to the traditional method of the East, combined with the critical and comparative method of the West. As the work was done single-handed, and finished within a limited time with a view to making it available to students and scholars of Sanskrit at as early a date as possible, the number of books consulted was a limited one. The number of entries is more than four thousand out of which the important ones are in the form of short articles supplying very briefly the necessary information from the different sources with quotations from or references to the original works. All the standard works in grammar have been carefully consulted including the available Prātišākhya works, the Mahābhāsya, the Kāśikā, the Vākyapadīya, the Siddhānta-Kaumudī and others. The Kātantra, the Sākatāyana, the Jainendra, the Haima and other grammars, as also the different Paribhasa works have been consulted at important places. Minor works and commentaries are not consulted as the important words and topics occurring therein have been mostly included here on account of their occurrence in the major works. Attention is, of course, paid to grammatical importance and significance, and only such such words and such senses of them as have a grammatical significance, have been included in the present dictionary along with affixes, augments, substitutes and technical terms mostly given in Pāṇini's grammar. Names of authors and books, printed as well as found in a manuscript form, have been included as far as practicable in the present work. A scrupulous attention has been paid to the Prātiśākhya works, the Mahābhāṣya and the Kāśikā which are looked upon as supremely authoritative in the field of Sanskrit grammar. It must be admitted that the scholarly index works of Dr. Bōthlingk and Dr. Renou were found very useful in providing references to standard grammar works. The abbreviations for the titles of books consulted and those of grammatical terms are given separately at the beginning of the present Dictionary of Sanskrit Grammar.' Names of books and authors have been sometimes given in the Roman script and sometimes in the Devanāgari script.

Conclusion

Acknowledgements are due to Mr. M. N. Chapekar, Aryasanskriti Mudranalaya, Poona, who has given ample co-operation in getting this Dictionary printed in the shortest possible time. For facility of printing, accents of Vedic passages and words are not shown, nor italics have been used for Sanskrit terms written in the Roman script nor the breaking of a word at the end of a line is done scrupulously at the end of a syllable or a constituent part. In spite of all possible care, some slips have crept in for which the indulgence of the reader is craved. It is expected that Sanskrit scholars will make full use of this work and offer their valuable suggestions for future undertakings of this type.

A sincere sense of gratitude must be conveyed to Dr. Bhogilal J. Sandesara, the Director of the Oriental Institute, Baroda, at whose initiative the project of this 'Dictionary of Sanskrit Grammar,' undertaken some years ago, but postponed from time to time, was not only pursued with vigour, but completed and turned into a volume in the Gaekwad Oriental Series.

601-2 Sadashiv Peth, Laxmi Road, Poona 2. Varshapratipada, Shaké 1883. 17-3-61.

K. V. ABHYANKAR.

HINTS FOR THE USE OF THIS DICTIONARY

- 1. Words in this dictionary are arranged in the serial order of the Sanskrit alphabet which is current everywhere, viz. the fourteen vowels beginning with 3 and ending with 3, and then the thirtythree consonants consisting of the five guttural, the five palatal, the five cerebral, the five dental and the five labial consonants and then the four semi-vowels and the four sibilants. 3 is taken as a combination of \$\opi\$ and \$\opi\$, and \$\opi\$ as one of \$\opi\$ and \$\opi\$.
- 2. Words are given in their noun-base (प्रातिपादिक) such as अकर्मक, अकार, अक्षर etc., without the addition of any case affix.
- 3. At places of option where any one of the anusvara and the parasavarna could be used, the anusvara is consistently used, and a place after the vowels and before the consonants is assigned to it in the alphabetical order. For example, the words containing anusvara such as संकर्ष, संकम, संचय, संज्ञा, संतान, सिंघ, संप्रसारण, संयोग, संवरण, संसर्ग, संहिता etc., are all placed after स and before सक्, सकर्मक etc.
- 4. Each word entered, has got only one paragraph assigned to it, although the explanation of the word may cover sometimes a full page or more.
- 5. The meaning or meanings of a word are given immediately after it, and therefore no capital letter is used at the beginning of the word with which each meaning begins.
- 6. The various senses of a word are given one after another with serial numbers placed before them. The several senses of a word are arranged as far as possible in their chronological order of origin.
- 7. The various senses are usually illustrated with quotations from standard authors with full references as far as possible. From among the Prātiśākhya works, the Rkprātiśākhya is generally quoted, while from among the numerous grammar works, the Mahābhāṣya and the Kāśikā are quoted profusely.
- 8. The first figure in references, which is generally the Roman one, refers to the main section such as the adhyāya or the Kāṇḍa or the Patala, while the next one refers to the subordinate sections, such as the stanza or the Sūtra or the like. When there are three figures they refer to the adhyāya, the pāda and the Sūtra in the case of Pāṇini, and to the Maṇḍala, the Sūkta and the stanza in the case of the Rksanhitā.
- 9. When a particular form is illustrated, the illustration begins with the abbreviation 'e.g.'; while usually, when the sense given, is illustrated, the explanation or the quotation in Sanskrit begins with the abbreviation 'cf.'.

- 10. Each of the different senses of a word or of the uses of a word in different ways, begins with a separate number (1), (2), (3), etc.; when however, the same sense is given with different shades of it, by words which are practically synonymous, no separate numbers are given, the shades of senses being separated by a colon, or by a comma.
- 11. As the senses given in such dictionaries are more or less technical or conventional, the literal or the usual sense of the words is given only when it is allied to the conventional sense.
- 12. Sanskrit words are generally given in the Devanagari script; when, however, the Roman script is used, the diacritical marks which are in current use at present, are employed.

LIST OF WORKS AND AUTHORS CONSULTED

(In order of abbreviations used)

A. Pr.=Atharvaveda Prātisākhya. Astādhyāyī=Pāṇini's Astādhyāyī.

Bh. Vr. = Bhāṣāvṛṭti of Purusottamadeva.

Bhār. Śīks = Bhāradvāja Śīkṣā.

C. Vy., Cān. Vy. = Cāndra Vyākaraņa.

Dhātuvrtti = Mādhavīyā Dhātuvrtti. Durgācārya = Durgācārya's commen-

tary on the Nirukta.

Durgasimha=Durgasimha's Kātantra-Sūtravṛtti.

Durgh. Vr = Durghatavrtti of Saranadeva.

Hem.=Hemacandra's Sabdānusāsana. Hem. Pari.=Hemacandra's Paribhāṣāpātha as given by Hemahamsagaṇi.

Jain., Jain. Vy.=Jainendra Vyākaraņa by Pūjyapāda Devanandin.

Jain. Pari. - Jainendra Paribhāṣāvṛtti by K. V. Abhyankar.

Kaiy., Kaiyata = Kaiyata's Mahābhāsyapradīpa.

Kālāpa - Kālāpa-Vyākaraņasūtra. Kāś. - Kāśikā of Jayāditya and Vāmana. Kās. viv. = Kāsikāvivaraņapanjikā, known by the name Nyāsa.

Kāt. = Kātantra Vyākaraņa Sūtra.

Kāt. Pari. Durg. = Kātantra Paribhāsāvītti by Durgasimha.

Kav. Prak. = Kavyaprakasa of Mammata.

Laghumanjūsā = Laghumanjūsā of Nāgesa.

M. Bh. = Mahābhāṣya of Patañjali on the Sūtras of Pāṇini (Dr. Kielhorn's edition).

Mahābhāṣya Vol. VII=The Volume of the introduction in Marāthi to the Pātañjala Mahābhāṣya, written by K. V. Abhyankar and published by the D. E. Society, Poona.

Mahābhāsyadīpikā = commentary on the Mahābhāsya by Bhartrhari.

Muktāvalī = Nyāyamuktāvalī of Visvanāthapancānana.

Nandikeśvara=Nandikeśvarakārikā.

Nir.=Nirukta of Yāska.

Nyāsa=Kāśikāvivaraņapañjikā, a commentary on the Kāśikāvṛtti by Jinendrabuddhi, called Nyāsa.

P., Pāņ=Pāṇini's Aṣṭādhyāyī.

Padamañjarī = Padamañjarī, a commentary on the Kāśikāvṛtti by Haradatta.

Pān. Sik. = Siksā of Pānini.

Par. Bhās. = Paribhāṣābhāskara of Haribhāskara Agnihotrī.

Par. Sek. = Paribhāṣenduśekhara of Nāgeśa.

Paramalaghumanjūsā = Paramalaghumanjūsā of Nāgesabhatta.

Pari. Sang. = Paribhāṣāsamgraha by K. V. Abhyankar.

Phit. Sūtra = Śāntanava's Phitsūtra.

Pradīpa = Kaiyaṭa's Mahābhāṣyapra-dīpa.

Purusotta m=Purusotta madeva's Paribhāsāvṛtti.

R. Pr. = Rgvedaprātiśākhya by Saunaka (Sanskrit Sāhityapariṣad Edition, Calcutta.)

R. T. = Rktantra Prātiśākhya.

R. V., Rgveda, Rk. Samh = Rgveda-samhitā.

Śabdakaustubha = Śabdakaustubha of Bhattojī Dīksita.

Śāk. = Śākatāyana's Śabdānuśāsana.

Śāk. Pari = Śākaṭāyana Paribhāṣāpāṭha.

S. K. Sid.Kau. = Siddhāntakaumudī. Sīradeva = Sīrradeva's Paribhāṣāvrtti.

Šiva Sūtra = Māheśvarasūtras.

Śṛing-Prak. = Śringāraprakāśa of Bhoja.

T. Pr. = Taittirīya Prātiśākhya.

Tait. Samh.=Taittirīya Samhitā.

Tattvabodh. = Tattvabodhinī by Jūānendrasarasvatī.

Tattvacintāmaņi = Tattvacintāmaņi of Gangesopādhyāya.

Tribhāṣyaratna = commentary on the Taittirīya Prātisākhya.

Uddyota = Mahābhāṣya-Pradīpoddyota by Nāgeśa.

Uņ. Sūtra = Uņādisūtrapancapādī.

Uņ. Sūtravr. = Uņādisūtravṛtti by Ujjvaladatta.

Upamanyu = Nandikeśvarakārikābhāṣya by Upamanyu.

Uvvata = Uvvata's Bhāṣya on the Pratiśākhya works.

V. Pr. = Vājasaneyi Prātisākhya.

Vaidikābharaņa = commentary on the Taittirīya Prātišākhya.

Vaiyākaraṇabhūṣaṇa=Koṇḍabhaṭṭa's Vaiyākaraṇabhūṣāṇasāra.

Vāk. Pad. = Vākyapadīya of Bhartṛhari.

Vāk. Pad. tīkā = Commentary on Bhartrhari's Vākyapadīya.

V., Vārt. = Vārttikas on the Sūtras of Pāṇini as given in the Mahābhāṣya (Dr. Kielhorn's edition.)
Vyāḍi = Vyāḍiparibhāṣāsūcana.

ABBREVIATIONS USED.

abl. ablative case.

above a reference to some preceding word, not necessarily on the same page.

acc. accusative case.

adj. adjective.

adv. adverb.

Āhn. Āhnika of the Pātanjala Mahābhāsya.

aor. aorist.

Atm. or Atmanep. Atmanepada.

caus. causal.

cf. confer, compare.

com. commentary.

comp. compound.

cond. conditional.

conj. conjugation.

dat. dative case.

deside desiderative.

dual. dual number.

ed. edition.

e.g. exempli gratia, for example.

etc. et cetera, and others.

f., fem. feminine.

freq. frequentative.

fut. future.

gen. genitive case.

gend. gender.

gr. grammar.

i.e. id est, that is.

imperf. imperfect.

impera. imperative.

ind. indeclinable.

inf. infinitive.

ins., inst. instrumental case.

krt. krt (affix).

lit. literally.

loc. locative case.

masc. masculine gender.

ms. manuscript.

neut. neuter gender.

nom. nominative case.

Pān. Pānini.

p.p.p. past passive participle.

Parasmai. Parasmaipada.

pari. paribhāṣā.

part. participle.

pass. passive voice.

perf. perfect.

pers. person.

pl. plural.

pres. present tense.

pron. pronoun.

sec. second.

sing. singular.

subj. subjunctive.

suf. suffix.

tad. taddhita affix.

Vārt. Vārttika (on the Sūtra of

Pāṇini).

Ved. Vedic.

vide see

v. l. varia lectio, another reading.

voc. vocative case.

A Dictionary of Sanskrit Grammar.

अ (1) the first letter of the alphabet in Sanskrit and its derived languages, representing the sound a (3): (2) the vowel a (3) representing in grammatical treatises, except when prescribed as an affix or an augment or a substitute, all its eighteen varieties caused by accentuation or nasalisation or lengthening; (3) personal ending a (अ) of the perf. sec.pl.and first and third pers.sing.; (4) krt affix a (왕) prescribed especially after the denominative and secondary roots in the sense of the verbal activity e. g. बुभुक्षां, चिन्ता, ईक्षा, चर्चा etc.cf. अ प्रत्ययात etc. (P.III. 3.102-106); (5) sign of the agrist mentioned as an (অভ্) or can (অভ্) by Panini in P. III 1.48 to 59 e.g. अगमत्, अचीकरत्; (6) conjugational sign mentioned as śap (হাণু) or śa (হা) by Pānini in P. III.1.68, 77. e. g. भवति, तुदति etc.; (7) augment am (अम्) as prescribed by P. VI.1.58; e. g. द्रष्टा, द्रक्याति; (8) augment at (अट्) prefixed to a root in the imperf. and aorist tenses and in the conditional mood e. g. अभवत्, अभूत्, अभाविष्यत cf. P. VI.4.71; (8) krt affix a (अ) prescribed as अङ, अच्,अञ्, अण्, अन्, अप्, क, ख, घ, ञ, ट, डे, ण, etc. in the third Adhyaya of Panini's Astādhyāyī; (9) tad. affix a (খ) mentioned by Panini as अच्, अञ्, अण, अ etc. in the fourth and the fifth chapters of the Astadhyayi of Pāṇini; (10) the samāsānta assix a (अ), as also stated in the form of the samāsānta affixes (ভল্, अच, टच, षच्, ष, अप्, and अञ्) by Pānini in V.4. 73 to 121; (11) substitute a (अश्) accented grave for

before case-affixes beginning with the ins. case; (12) remnant (अ) of the negative particle নুস after the elision of the consonant n (ন) by নুন্তাণা নুস: P. vi. 3.73.

अं (-) nasal utterance called अनुस्वार and written as a dot above the vowel preceding it. cf. स्वरमनु संलीनं शन्द्यते इति; it is pronounced after a vowel as immersed in it. anusvāra is considered (1) as only a nasalization of the preceding vowel being in a way completely amalgamated with it. cf. T. Pr. V. 11,31; XV. 1; XXII. 14; (2) as a nasal addition to the preceding vowel, many times prescribed in grammar as nuț (नुट) or num (नुम्) which is changed into anusvāra in which case it is looked upon as a sort of a vowel, while, it is looked upon as a consonant when it is changed into a cognate of the following consonant (परसवर्ण) or retained as n (\overline{a}). cf. P. VIII.4.58; (3) as a kind of consonant of the type of nasalized half g (1) as described in some treatises of the Yajurveda Prātiśākhya; cf also R. Pr.1.22 V. Pr.14.148-9. The vowel element of the anusvara became more prevalent later on in Pali, Prakrit, Apabhramsa and in the spoken modern languages while the consonantal element became more predominant in classical Sanskrit.

अशिसमास the same as एकदेशिसमास or अवयवसमास or अवयवधीतत्पुरूप prescribed by the rule पूर्वापराधरोत्तरमेकदेशिनैका-

धिकरेण P. II.2.1 and the following P. II.2.2 and 3; c. g. पूर्वकायः, अपरकायः, अर्धापिव्यली etc.

শহ্যাতা, also গ্রহাবিশ্য a class of words headed by গ্রহা which have their last vowel accented acute when they stand at the end of a tatpurusa compound with the word খাবি as the first member. cf. P. VI. 2. 193.

अ:(:) visarga called visarjanīya in ancient works and shown in writing by two dots, one below the other, exactly of the same size, like the pair of breasts of a maiden as jocularly expressed by Durgasimha. cf. अ: इति विसर्जनीय: । अकार इह उच्चार-णार्थः । कुमारीस्तनयुगाकृतिर्वणी विसर्जनीयसंज्ञी भवति (दुर्गेसिंह on कातन्त्र I.1.16). विसर्ग is always a dependent letter included among the Ayogavaha letters and it is looked upon as a vowel when it forms a part of the preceding vowel; while it is looked upon as a consonant when it is changed into the Jihvāmūlīya or the Upadhmānīya letter.

अ द्रक् (द्र) जिह्नामूळीय, represented by a sign like the बज in writing, as stated by Durgasimha who remarks बजा-कृतिवंगों जिह्नाम्ळीयसंज्ञो भवति. The Jihvā-mūlīya is only a voiceless breath following the utterance of a vowel and preceding the utterance of the gutteral letter क् or ख्. It is looked upon as a letter (बर्ग), but dependent upon the following consonant and hence looked upon as a consonant. e. g. विण्णु द्र करोति.

अ र प् (रं) Upadhmānīya represented by a sign like the temple of an elephant as stated by Durgasithha who remarks " गजकुम्माकृतिर्वर्ण उपम्मानीयसंशो भवति." Kāt.I. It is a voiceless breath following the utterance of a vowel and preceding the utterance of the labial letter p (प्) or ph (प्). It

is looked upon as a letter (वर्ष), but dependent upon the following consonant and hence looked upon as a consonant.

अ:আম name given to the nom. case in the Taittiriya Prātiśäkhya. cিস:দ্বাহ হুরি মুখদাবিশক্তিয়বজ্ঞবিদ্ধ T. Pr. I. 23.

अक् (1) condensed expression (এন্যাহার) representing the letters अ, इ, उ, क and छ in Pānini's Grammar cf. P. VI. 1. 12, 101; VII. 4. 2. (2) sign (বিক্লো) of the benedictive in Vedic Literature in the case of the root হয় e. g. খিনা ব হথিব P. III. 1.86 V 2; (3) remnant of the termination अकब् P. V. 3. 71; (4) substitute (आदेश) अकङ् for the last vowel of the word सुधार (P. IV. 1. 97) e. g. सोधातकिः

अक. (1) affix अक substituted for the affix g given in Pānini's Grammar as—ण्डुच as in आशिका, शाधिका (P.III. 3. 111); ण्डुट as in कारक:, भोजको वजित, विचर्चिका (P. III. 1. 133, III. 3. 10, 108); दुच् as in उपक: (P.V.3.80); दुञ् as in निन्दक:, राजकम, भाल्वक: (P. III. 2. 146, IV. 2. 39, 53 etc.); दुच् as in प्रवक:, सरक:; क्रमक:, पदक:. III.1. 149, IV. 2. 61 etc.

अकङ् substitute (आदेश) for the last letter of the word মুগাৰ prescribed along with the tad. affix হৃষ্ by P. IV. 1. 97. c. g. ধীঘানাদি:

अकच् affix prescribed before the last syllable of pronouns and indeclinables without any specific sense for it (P. V.3.71) c. g. सर्वकः, उच्चकेः etc.

সক্ষিত্ৰ not mentioned by any other case-relation such as স্বাধ্যন, संম্বান and স্থিক্যো; stated with respect to the indirect object, governed by roots possessing two objects such as বৃহ, যান্ and others, which in the passive voice is put in the nominative case. The in-

direct object is called a kathita because in some cases there exists no other case-relation as, for example, in पौरवं गां याचते or मिक्षते, or माणवक पन्थानं पुन्छति; while, in the other cases, the other case-relations (with the activity expressed by the verb) are wilfully suppressed or ignored although they exist, as for instance in गां दोग्य पय:, अन्ववस्णिद्ध गां त्रजम्: see अकथितं च P. 1. 4.51 and the Mahābhāṣya thereon.

अकिम्पत not shaken; tremulous; said with respect to vowels in Vedic utterance, kampa being looked upon as a fault of utterance. cf अकिम्पतान् । कम्पनं नाम रगराश्रितपाठदेश्वः प्रायेण दाक्षिणात्यानां भवति । तमुपळक्ष्य स वर्षः। R. Pr. III. 31.

अकर्त a case-relation excepting that of the subject to the verbal activity. cf. अकर्तार च कारके संज्ञायाम् P. III. 3.19.

अकर्मक intransitive, without any object, (said with regard to roots which cannot possess an object or whose object is suppressed or ignored). The reasons for suppression are briefly given in the well-known stanza; धातोरथीन्तरे वृत्तेषीत्वथेनीपसंग्रहात्। प्रसिद्धरिववसातः कर्मणोऽ कर्मिकानित्रया।। In the case of intransitive roots, the verbal activity and its fruit are centred in one and the same individual viz. the agent or कर्ता cf. फळच्यापारयोरकानिष्ठतायामकर्मक: Vāk. Pad.

अकाण्डताण्डच name of the commentary by Harinātha on the Paribhaṣenduśekhara (परिभाषेन्दुशेखर) of Nāgeśabhaṭṭa.

अकाम (अकामसंधि) an invariable (नित्य) euphonic change (संधि) such as the dropping of the consonant r (र्) when followed by r.cf. R. Pr. IV, 9. रेफोदयो छुप्यते द्वाचितोपधा हरसस्या

कामनियता उभाविमो । e. g. युवा रजांसि, सुयमासो अथा रथ: R. V. I. 180.1.

अकार the letter a (अ) inclusive of all its eighteen kinds caused by shortness, length, protraction. accentuation and nasalization in Pāṇini's grammar, in cases where a (अ) is not actually prescribed as a termination or an augment or a substitute. cf. अगुदित्सवर्णस्य चाप्रत्ययः P. I. 1.73. The letter is generally given as the first letter of the alphabet (वर्णसमाम्राय) in all Prātisākhya and grammar works except in the alphabet termed Varnopadesa, as mentioned in the Ŗk Tantra cf. एओ ऐऔआऋ ऌ ई ऊ ऋ ल इ उ आ: । रयवला: । ङञ्जानमा: । ····अ: ४क ४पा:। हं कुं खुंगुं धुं अं आं एवमुपदेशे etc. R. T. I. 4.

अकारक not causing any verbal activity; different from the kārakas or instruments of action such as the agent, the object, the instrument, the recipient (सपदान), the separated (अपादान) and the location, (अधिकरण) cf. M. Bh. on I.4.23, 29 and 51 and on II.5.1.

अकार्य not a grammatical positive operation: e. g. elision (लोप.) cf. ननु च लोप एवेत्कार्य स्यात्। अकार्य लोप:। M. Bh. on I.3.2.

সমান্তম (1) not limited by any timefactors for its study such as certain periods of the day or the
year. (2) not characterized by anytechnical terms expressive of
time such as adyatani, parokṣā
occurring in the ancient Prātiśākhya and grammar works. The
term akāl tha is used by the
writers of the Kāsikāvṛtti in connection with the grammar of
Paṇini. cf. "বাণি-বুদর্দকাত্রক আক্রেণ্ড্র্য
Kās. on P. II.4.21 explained by
the writer of the Padamañjarī as

पूर्वाणि ब्याकरणानि अद्यतनादिकालपरिभाषा- | युक्तानि तद्रहितम् ।

अकालापक different from the Kālāpa or the revised Kātantra Grammar cf. पाणिन्युपञ्चमकालापकं व्याकरणम् Kāś. on P. II.4.21.

आक्रेत् not marked by the mute letter k (क्) and hence not disallowing guna or viddhi substitutes for the preceding vowel, cf. सुजिह्हशोई ल्यमिकृति P. VI. 1.58; दिशिंड-कित: P. VII. 4.83.

अञ्चल lit. non-kṛt; an assix applied to a root, but different from the conjugational assixes. cs. अङ्गरसार्व- धातुक्रयोदींच: P. VII. 4.25.

अफ़त not established; said of a grammatical operation which has not taken place e.g. अफ़तसंधिकार्यम् M. Bh. on V. 2.100, V. 3.84. also फ़्ताझ्तप्रसाङ्गि नित्यम् M. Bh. on VI. 4.62.

अकृतकारि doing or accomplishing what is not done or accomplished; the expression is used in connection with grammatical operations like हस्यक्रण or दिविकरण only in cases where it is necessary i. e. where already there is no hrasva or dirgha of. अकृतकारि स्वस्थि शास्त्रमित्रत् । तद्यथा । अभियदस्थ तद्दति । M. Bh. on VI. 1.127. The rules of Grammar, like fire, are applied to places where they produce a change.

अकृतन्यूह short expression for the grammatical maxim अकृतन्यूहा: पाणिन्तीया: which means "the followers of Pāṇini do not insist on the taking effect of a rule when its cause or causes disappear." See Par. sek. Par. 56.

अकृतसंधि word or expression without the necessary euphonic changes cf. वरुणादीनां च तृतीयात् स च अकृतंसंधीनाम् P. V. 3.84 vart. 1.

अकृतसंहित words ending with a breathing or visarga which are not looked upon as placed immediately before the next word and hence which have no combination with the following vowel e.g. एष देवो असत्य: R. V. IX.3.1.

সমূখিন non-technical; not formed or not arrived at by grammatical operations such as the application of afflixes to crude bases and so on; natural; assigned only by accident, cf. the gram, maxim কুমিনাই মিন্না: কুমিন কার্যক্ষেত্র which means "in cases of doubt whether an operation refers to that expressed by the technical sense or to that which is expressed by the ordinary sense of a term, the operation refers to what is expressed by the technical sense." Par. Sek. Par. 9 also M. Bh. on I. 1.23.

अफ्रस्न-अफ्रस्ना, an epithet applied to the pronunciation of Veda words improperly which does not serve any useful purpose. cf. अम्रस्ना अप्रयोजना एत्यर्थ: Uvața on R. Pr. XIV. 68.

अङ्कित not possessing the mute letter k (क्) or g (ज) or n (ङ) and hence not preventing the guna and viddhi substitutes for the preceding vowel, if they occur. e. g. मृजरिक्कृत्स प्रस्तेषु मृजिप्रस्ते मार्जिः साधुर्मेवति । M.Bh. on P. I.I.I. Vart.10.

अक्त definite, known or specified definitely. cf. अक्तपरिमाणानामधीनां वाचका भवन्ति य एतं संख्यादाद्दाः परिमाण- शब्दाश्च M. Bh. I.1.72.

अफियाज not a result of a verbal activity; the expression is used in connection with qualities (on a substance) as opposed to the activities found in it. cf. आध्यश्राक्षियाज्ञश्र सोड सत्त्वप्रज्ञातिर्गुण: M. Bh. on IV. 1.44.

अक्षचूतादिगण a class of words headed by अक्षचूत which take the tad. affix thak (इक) in the sense of 'resulting from' e. g. आक्षचूतिक वेरम्, जानुबह्यतिकम्, गातागातिकम् etc. cf. P IV.4.19.

अक्षर a letter of the alphabet, such as. α (अ) or i (ξ) or h (ξ) or y (ξ) or the like. The word was originally applied in the Prātisākhya works to vowels (long, short as also protracted), to consonants and the ayogavāha letters which were tied down to them as their appendages. Hence অধ্বা came later on to mean a syllable i. e. a vowel with a consonant or consonants preceding or following it, or without any consonant at all. cf. ओजा हस्त्राः सप्तसान्ताः स्वराणामन्ये दीर्घा उभये अक्षराणि R Pr. I 17-19 cf.एकाक्षरा, द्यक्षरा etc. The term aksara was also applied to any letter (वर्ण), be it a vowel or a consonant. cf. the terms एकाक्षर, सन्ध्यक्षर. समानाक्षर used by Patanjali as also by the earlier writers. For the etymology of the term see Mahābhāsya अक्षरं न क्षरं विद्यात्, अश्रोतेर्वा सरोऽश्वरम्। वर्ण वाहु: पूर्वसूत्रे । M. Bh. Ahnika 2 end.

अक्षरपङ्कित name given to the dvipadā virāj verses divided into pādas of five syllables. cf विराजो द्विपदाः केचित् सर्वा आहुश्चतुष्पदाः । कृत्वा पञ्चाक्षरान्पादांस्तास्तथाऽक्षरपङ्कतयः R. Pr. XVII. 50.

aa्तरसमाद्वाय alphabet; traditional enumeration of phonetically independent letters generally beginning with the vowel a (अ). Although the number of letters and the order in which they are stated differ in different treatises, still, qualitatively they are much the same. The Sivasūtras, on which Pāṇini's grammar is based, enumerate 9 vowels, 4 semi-vowels, twenty five class-consonants and 4 sibilants. The nine vowels are five

simple vowels or monothongs (समा-নাজং) as they are called in ancient treatises, and the four diphthongs, (सन्यक्षर). The four semi-vowels y, v, r, l, (युव्रूल्) or antasthāvarna, the twenty five class-consonants or mutes called sparsa, and the four üsman letters s, s, s and h (রাগুলুরু) are the same in all the Prātisākhya and grammar works although in the Prātiśākhya works the semi-vowels are mentioned after the class consonants. The difference in numbers, as noticed, for example in the maximum number which reaches 65 in the Vajasanevi-Prātiśākhya, is due to the separate mention of the long and protracted vowels as also to the inclusion of the Ayogavāha letters, and their number. The Ayogavāha letters are anusvāra, visarjanīya, jihvāmūlīya, upadhmānīya, nāsikya, four yamas and svarabhaktī. The Rk Prātiśākhya does not mention l (豆), but adding long ā (आ) i (ই) ū (জ) and r (\Re) to the short vowels. mentions 12 vowels, and mentioning 3 Ayogavāhas (४ क्, ४ ए and अं) lays down 48 letters. The Rk Tantra Prätiśäkhya adds the vowel १ (छ) (short as also long) and mentions 14 vowels, 4 semivowels, 25 mutes, 4 sibilants and by adding 10 ayogavāhas viz. yamas, nāsikya, visarjanīy**a** jihvāmūlīya, upadhmānīya and two kinds of anusvāra, and thus brings the total number to 57. The Rk Tantra makes a separate enumeration by putting diphthongs first, long vowles afterwards and short vowels still afterwards, and puts semi-vowels first before mutes, for purposes of framing brief terms or pratyāhāras. This enumeration is called varnopadesa in contrast

with the other one which is called varnoddeśa. The Taittirīya Prātisäkhya adds protracted vowels and lays down 60 letters; Siksā of Pāṇini lays down 63 or 64 letters, while the Vajasanevi-Prātiśākhya gives 65 letters. cf. V. Pr. VIII. 1-25.alphabet of the modern Indian Languages is bassed Varnasamāmnāya given in Vājasanevi-Prātisākhya. The Prātiśākhyas call this enumeration by Varņa-samāmnāya. name The Rk.tantra uses the terms Aksarasamāmnāya and Brahmarāśi which are picked up later on by Patañjali.cf. सोयमक्षरसमामायो वाक्समाम्नाय: पुष्पितः फलितश्चन्द्रतारकवत् प्रतिमण्डितो वेदि-तब्यो ब्रह्मराशिः । सर्ववेदपुण्यफलावातिश्चास्य ज्ञाने भवति । मातापितरौ चास्य स्वर्गे लोके महीयते । M. Bh. Ahnika 2-end.

अक्षराङ्ग forming a part of a syllyble just as the anusvāra (nasal utterance) or svarabhakti (vowclpart) which forms a part of the preceding syllable. cf. अनुस्वारी ब्यञ्जनं चाक्षराङ्गम् R. Pr. I.22, also स्वरभक्तिः पूर्वभागक्षराङ्गम् R. Pr. I.32.

প্রবাহ্য unitary import; the meaning of a sentence collectively understood.

अगाति (1) absence of any other recourse or alternative. cf. अगत्या हि खलु परिभाषाधीयते. Purusottamadeva-Pari. vṛtti Pari.119; (2) which is not a word termed gati. cf. चनचिदिवगोत्रा-दितदिताम्रेडितेष्वगते: P. VIII.1.57.

अगमकत्वे non-communicativeness, inability to communicate adcquately the intended meaning. cf. सिवशेषणानां वृत्तिस्तिर्हे कस्मान भवति। अगमकत्वात् M. Bh on II. l.1; cf. also अगमक: निर्देश: अनिर्देश: !

अगुण non-secondary, principal; cf. ध्रुवचेष्टितयुक्तिषु चाप्यगुणे तदनल्पमतेवैचनं स्मरत M. Bh. on I. 4.51.

अगृहीत uncomprehended, unincluded ed cf.नापहीतिविदेषणा द्याक्तिविदेष्यमुपसंकामित । cf. also नाच्झन्ये इस्यत्र अपहीतस्वर्णानामचां महणम् Padamanjari on Kās VIII. 3.57.

आग्ने a term in the Kātantra grammar for a word ending in $i(\xi)$ or $u(\Xi)$ cf. इनुदक्षि: Kāt. II. 1.8, अभ्नेरमोऽ कार: Kāt. II. 1.50.

अग्निपदादिगण a class of words headed by the word अग्निपद to which the tad. affix अण् is added in the senses of 'given there' or 'done there'e. g. अग्निपदम. cf. अण्नकरण अग्निपदादिभ्य उपसंख्यानम् P. V.1.97 Vart. 1.

अभिवेश्य an ancient writer of Vedic grammar mentioned in the Taittirīya Prātisंग्रेkhya. ef. कपवर्गपरश्च (विसर्गः) अभिवेश्यवास्मीक्योः (मतेन जन्माणं न आपयते) T.Pr. IX. 4.

अश्चित्रयायन an ancient writer of Vedic grammar, mentioned in the Taittiriya Prātikākhya. cf. नामिनस्या-यनस्य (मते उदात्तपर: स्वरितपरो वा अनुदात्तः स्वरितं नापवते इति न) Tait. Pr. XIV.32.

अहोकरवाणिन्याय analogy conveyed by the expression अहा करवाणि implying permission to the agent to do certain other things in a sacrificial session when, as a matter of fact, he is only permitted to work as an agent at the sacrificial action (अहोकरण), by virtue of the reply 'कुर' to his request made in the sentence अहो करवाणि. cf. अहोकरवाणिन्यायेन मिन्यति M. Bh. on. II. 2.24.

সম the original Samhita text as opposed to pratṛṇṇa (গুনুজা) or padapāṭha, (ব্ৰুঘান্ত) which is the recital of separate words.

অস্থ্যান্ত (Vāsudeva-Śaraṇa Agravāla), a modern scholar of Sanskrit grammar, the author of "India as known to Pāṇini". प्रथमो

अग्रहण non-inclusion, non-comprehension. cf. विभक्ती लिङ्गविशिष्टाग्रहणस् Par. Sekh. Par. 72, M. Bh. VII. 1.1 Vārt. 13.

अग्लोप elision of the vowel a, i, u, r or l (अ, इ, उ, ऋ or ल) which prevents Sanvadbhāva cf. सन्बद्धश्रानि चङ्परेऽनग्लापे P. VII. 4.93, as also नाग्लोपिशास्त्रदिताम् VII. 4.2 where the elision prevents the shortening of the penultimate vowel if it is long. अघोष unvoiced, merely breathed; a term applied to the surd consonants, ś, s s, and visarga which are uttered by mere breathing and which do not produce any sonant effect. cf. T. Pr. I. 12; R. Pr.I. 11. The term jit (जित्) is used for these letters as also for the first two consonants of a class in the cf. हो हो Vajasaneyi-Pratisakhya

I. 50.51.

আই The vikaraṇa before lun affixes, substituted for the affix cvi (चिष) in the case of the roots mentioned by Pānini in Sūtras III.1.52-59;(2) the Vikaraṇapratyaya in Vedic Literature before the benedictive affixes prescribed by Pānini in Sūtra III. 1.86; (3) kṛt affix in the feminine gender showing verbal activity applied to roots marked with the mute letter জ্ and the roots भिद्, छिद् and others. P. III. 3 104-106. e.g. जरा, त्रपा, भिदा, छिद्। etc.

जित्; ऊष्माणश्च हवर्जम् V. Pr.

आङित् not marked with the mute letter \dot{n} (ङ्) signifying the absence of the prohibition of the guṇa or the vṛddhi substitute. cf. अङ्गित गुणप्रतिषेध: (वक्तज्य:) M. Bh. III. 3.83 Vārt. 2. In the case of the preposition \bar{a} (आ) unmarked with \dot{n} (ङ्), it signifies a sentence or remembrance of something cf. वाक्यरमणयोराङित् e.g. आ एवं नु मन्यसे, आ एवं किल तत् cf. M. Bh. on I. 1.14.

अङ्ग (1) the crude base of a noun or a verb to which affixes are added: technical term in Pānini's grammar for the crude base after which an affix is prescribed e. g. उपगु in ओपगव,or क् in करिष्यति etc. cf. यसात् प्रत्यविधिस्तदादि प्रत्येश्डम् P.I.4·13; (2) subordinate part. constituent part cf. पराङ्मवद in सुवामान्त्रित पराङ्मवरस्वरे P. II. 1. 2, also विध्यङ्गभूतानां परिभाषाणां Par. Sek. Par. 93·10; (3) auxiliary for an operation, e. g. अन्तरङ्ग, बाहेरङ्ग etc. cf. अत्राङ्गराब्देन शब्दरूपं निमित्तमेव गृह्यते Par. Sek. Par. 50; (4) element of a word or of an expression cf. अङ्गब्यवाये चाङ्गपर: R. T. 190, अङ्गे च कुम्ब्यादौ R.T. 127. ब्यञ्जनं स्वराङ्गम् T. Pr. 21.1.

अङ्गवत् considered as auxiliary or part' of another e. g. पूर्वाङ्गवद्भावः, पराङ्गवद्भावः; cf. सुवामन्त्रिते पराङ्गवत्स्वरे P. II. 1.2 and the Vārtika thereon " परमपि च्छन्दिस पूर्वरयाङ्गवद् भवतीति वक्तव्यम्."

अङ्गन्त an operation prescribed in the section named aṅgādhikāra; comprising the fourth quarter of the sixth book and the whole of the seventh book of Pāṇini.

সাঘিকাৰ a large section of Pāṇini's Astādhyāyī covering five quarters (VI. 4.1 to the end of VII) in which the various operations undergone by crude bases before various affixes etc. are prescribed.

अङ्गुल्यादिगण class of words headed by अङ्गुलि to which the tad. affix टक् (इक) is added in the sense of comparison (इवार्थ); e. g. अङ्गुलीव आङ्गुलिक: cf. Kās. on P. V. 3. 108.

अस् the short term or pratyāhāra in Pāṇini's Grammar representing a vowel, e.g. अजन्त (ending with a vowel), अन्संधि (vowel coalescence or combination).

अचिकित्स्य impossible to amend, not to be discussed. cf. एवं च 'पूजितो यः सुरेरपि' इति अचिकित्स्य: अपशब्द:; Padamañjarī on P. II. 2·12.

अजादिगण class of words headed by अज to which the fem.affix आ is added, somettimes inspite of the affix ई being applicable by other rules such as जातेरस्त्रीविषयात P. IV. 1.63 and other rules in the section. e. g. अजा, एडका: त्रिफला, उष्णिहा, जेटा, दंष्ट्रा. cf P. IV. 1. 4.

आजितसेन author of the Cintamaniprakāśikā a gloss on Cintāmani, the well known commentary by Yakṣayarman on the Śabdānūśāsana of Ṣākatāyana. Ajitasena was the grand pupil of Abhayadeva; he lived in the 12th century A.D.

आर्जिपादिगण class of words headed by the word अजिर which do not allow lengthening of the final vowel by P. VI. 3 119. although they form technical terms e. g. अजिरवती, पुलिन-वती etc. cf. Kas on P. VI, 3. 119.

अज्मिकि See under खरमिक.

পাস্ (1) tad. affix a (প) with the mute letter ñ (ञ्), prescribed (i) after the words उत्स and others in various senses like progeny, dyed in, produced in, come from etc.P. IV 1.86, (ii) after the words विद and others in the sense of grandson and other descendents.P. IV.1.104. For other cases see P. IV. 1. 141, 161; IV. 2.12, 14 etc. IV. 3.7 etc. IV. 4.49. The feminine is formed by adding i (\(\xi\)) to words ending with this affix अञ्, which have the vrddhi vowel substituted for their initial vowel which gets the acute accent also e.g. ओत्स:, ओत्सी, ओदपान:, बेद:, बेदी.

অহ (1) token term standing for vowels and semi-vowels excepting l (ত্) specially mentioned as not interfering with the substitution of n

(ण्) for a (न्) e.g. गिरिणा, आर्यण, स्रवेण etc. See P. VIII. 4.2; (2) augment a (अट्ट) with an acute accent, which is prefixed to verbal forms in the imperfect and the agrist tenses and the conditional mood. e.g. अभवत्, अभृत्, अभविष्यत् See P.IV.4.71; (3) augment a (अट्) prescribed in the case of the roots रुद्, स्त्रपु etc. before a Särvadhätuka affix beginning with any consonant except y (य), c.g. अरोदत्, अस्वपत्, अजक्षत्, आदत् ctc.; see P. VII.3, 99, 100;(4) augment a (अट) prefixed sometimes in Vedic Literature to affixes of the Vedic subjunctive (Ez) e.g. तारिवत्, मन्दिपत् etc. sec P. III. 4.94.

अडच् tad. affix अट prescribed after the word कर्भन् by the rule कर्मण घटोड टच् टि कर्मण घटते कर्मट: पुरुष: Kās. on p. V. 2. 35.

अडच् tad. affix अड applied in the sense of pitiable or poor to a word preceded by the word उप when the whole word after उप is dropped. e. g उपड (उपन्द्रदर्भ + अड) see. p. V. 3. 80.

अण् (1) token term (प्रसाहार) for all vowels and semivowels which, when prescribed for an operation, include all such of their sub-divisions as are caused by length, protraction, accent or nasalization. cf अणुदित्सवर्णस्य चापत्ययः P. I. 1. 69;(2) token term for the vowels अ, হ and win all Panini's rules except in the rule I. I. 69 given above e.g. see दृत्रोपे पूर्वस्य द्यांचीय: P. VI. 3. 111, केडम: P. VII. 4. 13. and अजोड प्रगह्मस्य. P. VIII. 4. 57; (3) tad. affix a (अ) prescribed generally in the various senses such as 'the offspring,' 'dyed in,' 'belonging to 'etc. except in cases where other specific affixes are prescribedt cf प्राग्दीब्यतोऽण् P. IV. 1. 83; (4) kr.

affix a (अ), applied, in the sense of an agent, to a root with an antecedent word (उपपद) standing as its object. e. g. कुम्मकार:, see P.III. 2.1; काण्डलाव:, see P.III.3.12.

अणादि—a term applied to all taddhita suffixes collectively as they begin with अण् cf. P. IV. 1. 83.

अणु the minimum standard of the quantity of sound, which is not perceived by the senses, being equal to one-fourth of a Mātrā; cf. अणोस्तु तत्प्रमाणं स्थात् मात्रा तु चतुराणवात्।। see T. Pr. 21.3, V. Pr. 1.60, A. Pr. III.65. Rk. tantra, however, defines अणु as half-a-mātrā. cf. अर्थमणु (R.T. 1.41).

अणुदिच्छास्त्र— the rule prescribing cognateness (सावर्ण्य) of letters. The term refers to Pāṇini's sūtra अणुदित्सवर्णस्य चाप्रत्ययः P. I. 1. 69. The terms प्रहणकशास्त्र and सवर्णशास्त्र are used in the same sense.

अण्णेयाचार्य author of लिङ्गनिर्णयभूअण, who was a Tamil Brahmana by caste.

अत् (1) tech. term in Pāṇini's grammar for short अ, cf तपरस्तत्कालस्य P. I. 1. 70; अंदेङ् गुण: P. 1. 1. 2; personal ending अ for इ (इट्) of the 1st pers. sing. Atm. in the Potential, P III. 4. 106; (3) caseaffix in the case of युष्मद् and अस्मद् for abl. sing. and pl. P. VII. 1.31, 32; (4) tad-affix अत् (3) prescribed after किन् in the sense of the loc. case before which किम् is changed to 页, 新 being the tad. formation; cf. P. V. 3.12 and VII.2.105; (5) substitute अत्(য়নু) for लड् forming the present and future participles in the Parasmaipada. active voice cf. लट: शतृशानचौ॰ P.III. 2.124 and लूट: सद्घा P. III. 3.14.

अतङ् non-Ātmanepadin verbal affixes ति, तः...मस्. P. III.4.78, Cān. I.4.11, Sāk. 1.4.101.

अतत्काल not taking that much time only which is shown by the letter (vowel) uttered, but twice or thrice, as required by its long or protracted utterance: the expression is used in connection with vowels in Pāṇini's alphabet, which, when used in Pāṇini's rules, except when prescribed or followed by the letter त, includes their long, protracted and nasalized utterances; cf. अणुदिस्तवर्णस्य चाप्रस्ययः I.1.69.

अतद्नुबन्धक not having the same mute significatory letter, but having one or two additional ones, cf. तदनुबन्धकग्रहणे नातदनुबन्धकस्य ग्रहणस् (Par. Sek. Pari. 84.)

अतिद्धित an affix which is not a taddhita affix. cf. लशकतिद्धते P.1.3.8; M. Bh. I.3.4, V.3.1 etc.

अतन्त्र implying no specific purpose; not intended to teach anything, अविविक्षित; e.g. हरवग्रहणमतन्त्रम् Kāś. and Si. Kau. on तस्यादित उदात्तमधंहस्वम् P.1.2.32; cf. also अतन्त्रं तरनिर्देश: (the use of तर्ष does not necessarily convey the sense of the comparative degree in Panini's rules) M. Bh. on P. I.2.33. This statement has been given as a distinct Paribhāsā by Vyādi and Sākatāyana. The author of the Mahābhāsya appears to have quoted it from the writings of Vyādi and the earlier grammarians. See also M. Bh. on अल्पान्तरम P. II.2.34.

अतसुच् (अतस्) tad. aff. अतस् applied to the words दक्षिण, उत्तर, पर and अवर; e.g. दक्षिणतो वसति; उत्तरत आगतः, परतो समणीयम्, परस्ताद्रमणीयम्, अवरत आगतः अवरस्ताद्वसति. cf. P. V. 2. 28, 29.

अतादृप्यातिदेश conveyance of only the properties of one to another without conveying the actual form, described as the significance of antādivadbhāva. cf. न वा अताहप्याति-देशात M. Bh. on P. VI.1.85 Vart. 26. See ताद्रप्यातिदेश below.

अताम personal affix of the third pers. pl. Atm. in the Imperative (लेह). cf. P. III. 4, 90.

अतिक्रम passing over a word in the क्रमपाठ without repeating it; passing beyond, cf. अतिक्रम्य परिग्रहः R. Pr. X.7, which means catching a word for repetition by coming back after passing over it, e. g. इन्द्रामी अपात् । इन्द्रामी इति इन्द्रामी । or अन दक्षि। दक्षि दावने। दक्षीति दक्षि।

अतिजगती one of the varieties of -in fact, the first variety of - the Aticchandas metre, which see above; this Atijagatī consists of 52 syllables. e. g. तमिन्द्रं जोहवीमि मघवानमुप्रम् Rk. Samh. 8.97.13 cf. प्रथमातिजगत्यासां सा द्विपञ्चादादक्षरा R. Pr. XVI.80.

अतिदेश extended application; transfer or conveyance or application of the character or qualities or attributes of one thing to another. Atidesa in Sanskrit grammar is a very common feature prescribed by Panini generally by affixing the tad. affix मत or वत to the word whose attributes are conveyed to another. e. g. लोटो लङ्बत P. III. 4.85. In some cases the atidesa is noticed even without the affix भत् or वत्. e. g.गाङ्क्रटादिभ्योऽञ्णिन ङित P. I.2.1. Atidesa is generally seen in all grammatical terms which end with 'vadbhāva' e. g. स्थानिवद्भाव (P. I.1.56-59), सन्वन्द्राव (P.VII.4.93). अन्तादिवद्भाव (P. VI. 1.85), अभूततद्भाव (P.IV.60) and others. Out of these atidesas, the स्थानिवद्भाव is the most important one, by virtue of which sometimes there is a full reprei. c. substitution sentation the original form called sthanin place of the secondary form called ādeśa. This representation is called हपातिदेश as different from the usual one which is called कार्यातिदेश, cf. M. Bh. VIII.1.90 $V\bar{a}$ rt. 1 and VIII.1.95. Vārt.3. Regarding the use of अतिदेश there is laid down a general dictum सामान्यातिदेशे विशेषानितदेशः when an operation depending on the general properties of a thing could be taken by extended application, an operation depending on special properties should not be taken by virtue of the same; e. g. भूतवत in P. III. 3.132 means as in the case of the general past tense and not in the case of any special past tense like the imperfect (अन्यतन) or the perfect (परोक्ष). See Par. Sek. Pari. 101, M. Bh. on P. III. 3, 132. There is also a general dictum आনি-देशिकमानित्यम् – whatever is transferred by an extended application, need not be necessarily taken. See Par. Sek. 93.6 as also M. Bh. on P.I.1.123 Vart.4, I.2.1 Vart. 3, II.3.69 Vart. 2 etc., Kaiyata on II. 1.2 and VI. 4.22 and Nyāsa on P. 1.1.56 and P. I.2.58 Vart. 3. The dictum आतिदेशिकमनित्यम् is given as a Paribhāsā by Nāgesa cf. Pari. Sek. 93. 6.

आतिधाते one of the varieties of Aticchandas consisting of 76 syllables. e. g. स हि दाधी न मारुत नुविष्यणिः Rk. Samh. I.127.6.

अतिनिचृत् a variety of the Gayatri metre consisting of 20 syllables, cf. R. Pr. XVI.22.

आतेपत्ति absence of any possibility; Sec क्रियातिपात्ते. cf. P. III.3.139 Can. 1.3.107.

अतिप्रयत्न intense effort; characteristic effort as required for uttering a yowel with विक्रमस्वरित.

अतिप्रसङ्ग over-application of a definition which is looked upon as a serious fault; e. g. अतिप्रसङ्गो त्रश्चा- दिषु P. VI.1.66 Vart. 3.

आतिबहु too much, rather unnecessary; e. g. इदं चाप्यद्यत्वे अतिबहु क्रियते, M. Bh. on I.1.38, इदमतिबहु क्रियते M. Bh. on I.4.63, VI.1.145; नातिबहु प्रयोक्तब्यम् M. Bh. on VIII.1.4.

अतिरिक्त surplus, redundant; cf. Nir.
' IV.20; see Kaiyaṭa on M. Bh. V.
1.131.

अतिन्यक्त quite distinct; used with respect to pronunciation नातिन्यकं न चान्यक्तमेवं वर्णानुदीरयेत् । cf. T. Pr. XVII.8.

अतिव्यस्त quite apart, used with respect to lips which are widely apart (विश्विष्टी) in the utterance of long आ and ओ; cf. T. Pr. II. 12, 13.

अतिन्याप्ति the same as अतिप्रसन्न, which see above. Extensive application with respect to a rule which applies to places where it should not apply. See Par. Sekh on Pari. 28, Pari. 85; also Padamañj. on Kās. II. 1. 32.

स्रतिशकरी a variety of Aticchandas metre consisting of 60 syllables. e. g. सुषुमा यातमद्रिभि: Rk. Samh. I. 137. 1. cf. R. Pr. XVI.82.

अतिशय excess or excellence as shown by the affixes तर and तम cf. तरतम- योश्चातिशय V. Pr. V. 2; क्रियाप्रधानमाख्यातं तस्मादातिशय तरवृत्यद्यते M. Bh. on VI. 2.139; VIII.1.71; (2) desire as shown by the affix क्यच् in Pāṇini's grammar; cf. यश्च अतिशय R. T. 126.

अतिशायन excellence, surpassing; the same as अतिशय in V. Pr. V. 2 cf. अतिशायने तमिष्ठनो P. V. 3.55, also cf. भूमनिन्दाप्रशंसासु नित्ययोगेऽतिशायने । संसर्गेऽ स्तिविवक्षायां भवन्ति मतुबादयः M. Bh. on V. 2.94, where अतिशायन means अतिशय. Patañjali, commenting on P. V. 3.55 clearly remarks that for अतिशय, or for अतिशयन, the old grammarians, out of fancy only, used the term अतिशायन as it was a current term in popular usage; cf. देश्याः सूत्रनिबन्धाः क्रियन्ते यावद् ब्रूयात् प्रकर्षे अतिशय इति तावदितशायन इति M. Bh. on P. V. 3. 55.

आतिस्पर्शे excess of contact, which to a certain extent spoils the pronunciation and leads to a fault. अतिस्पर्श is the same as दुःस्पर्श, the letter ळ being called दुःस्पृष्ट on account of excess of contact. This exeess of contact (अतिस्पर्श) in the case of the utterance of the letter र् results into a fault as it practically borders on stammering; cf. अतिस्पर्शो पर्वरता च रेफे. R. Pr. XIV. 26.

अतिस्वार्थ (अतिखार also) name of the seventh musical note in the singing of Sāman. cf. कुष्ट्रप्रथमदितीयतृतीय-चतुर्थमन्द्रातिस्वार्थाः T. Pr. XXIII. 13.

आतिहार transfer of a consonant in a Stobha. See पुष्पसूत्र.

अतु short term used by Pāṇini to signify together the five affixes क्तवतु, ड्वतुप्, ड्मतुप्, मतुप् and वतुप् ;cf.अत्वसन्तस्य चाधातो: P. VI.4.14.

अतुल्यवल not having the same force; not belonging to the same type out of the four types of rules viz. पर, नित्य, अन्तरङ्ग and अपबाद. cf. अतुल्य-बल्यो: स्पर्धों न भवित Jainendra Pari. 66.

अतुस् personal ending of perf. 1st pers. dual. cf. परस्मैपदानां णलतुसुस्थलथु- सणल्वमाः P. III.4.82.

- अतृन kit affix अत् applied to the root जू in the sense of past time. cf जीर्यतेरतृन P. III.2.104.
- अते personal ending of pres. 3rd per. pl. substituted for झ (अन्त), the अ of झ (अन्त) being changed into ए and न being omitted; see झोन्त: (P.VII.1.3) अदम्यस्तात् (P.VII. 1.4) and दित आत्मनेपदानां देरे (P. III. 4.79).
- अत्यन्तगति complete contact of the verbal activity (किया); cf.P. V.4.4.
- अत्यन्तसंयोग constant contact; complete contact, uninterrupted contact. cf. अत्यन्तसंयोग च P. II. 1.29; II. 3.5.
- अत्यन्तापह्नच complete or absolute denial or concealment of facts; cf. परोक्षे छिट्। अत्यन्तापह्नवे च। 3.2.115, Vart. 1.
- अत्यय past happening, cf. अत्ययो भूतत्वमतिक्रम: । अतीतानि हिमानि निर्हिमम् । निःशीतम । Kāś. on P. II. 1.6.
- अत्यत्प rather too little, an expression used by Patanjali idiometically cf. अत्यत्पामिदमुच्यते M. Bh. on I. 1.69 etc.
- अत्यरपस्प्र having a very slight contact (with the organ producing sound), as in the case of the utterance of a vowel.
- अत्याप्टि a variety of Aticchandas metre consisting of 68 syllables. e. g. अथा रुचा हरिण्या पुनान: Rk. Sam. 8.111.1.
- अत्यादिगण the group of prepositions headed by अति which are compounded with a noun in the acc. case; cf. अत्यादयः क्रान्ताद्यथे द्वितीयया M. Bh. on P. II. 2.18.
- अत्युचनीच characterized by a sharp utterance; a name of the grave accent:
- अत्युपसंहत very closely uttered, uttered with close lips and jaws,

- (said in connection with the utterance of the vowel अ); cf. T. Pr II. 12. See आतेसंश्चिष्ट.
- **अत्व** also अन्व change of a vowel into short अ.
- अत्वत् possessing or having a short अ vowel in it; archaic form used by Pāṇini in उपदेशेऽत्वत: (P. VII. 2.62) instead of अद्धत् the correct one; cf. छन्देवत्त्त्व्याणि भवन्ति M. Bh. on I. 1. 1 and I. 4. 3.
- अथ Uṇādi affix अथ prescribed in Uṇādi Sutras 393-396 e.g. see शपथ, अवभूथ, आवसथ etc.
- अथवेप्रातिशाख्य the Prātišākhya work of the Atharva veda believed to have been written by Saunaka. It consists of four Adhyāyas and is also called शोनकीया चतुरस्यायिका.
- अथुन् kṛt. assix अधु with उ accented, applied to roots marked by Pāṇini with the mute syllable इ in the sense of verbal activity; e. g. वेपथु: श्वयथु:; cf द्वितोधुन् P. III. 3.89.
- अथुस् conjugational affix of perf. 2nd pers. dual Parasmai. substituted for the personal ending थर cf. P. III. 4.82.
- अदन्त ending with the short vowel अ: cf. P. VIII. 4.7; a term applied to nouns of that kind, and roots of the tenth conjugation which are given with the letter अ at their end which is not looked upon as mute (इत्) e.g. कथ,गण. etc. Mark also the root पित्र described by पतझिल as अदन्त cf. पिनिरदन्तः M. Bh. on I.1.56., M. Bh. on II. 4.43.
- अद्शीन a term in ancient grammars and Prātiśākhyas meaning non-appearance of a phonetic member वर्णस्यादर्शन लोप: (V. Pr 1.141), explained as अनुपलिध by उज्बर. Later on, the idea of non-appearance came to be associated with the idea of expectation and the definition of

ন্তাপ given by Pāṇini in the words স্বর্মান ভাপ: (as based evidently on the Prātiśākhya definition) was explained as non-appearance of a letter or a group of letters where it was expected to have been present. See M. Bh. on I. 1.60 Vārt. 4 and Kaiyata thereon.

अदादि name given to the class of roots belonging to the second conjugation, as the roots therein begin with the root अद्. The word अदिप्रमृति is also used in the same sense; cf. अदिप्रमृतिम्यः ज्ञषः p. II. 4.72; cf.also अदाचनदाचोरनदादेखे given by Hemacandra as a Paribhaṣa corresponding to the maxim हिक्करणाहिक्करणयोरङ्किकरणस्य Hem. Pari. 61.

अदि Uṇādi affix अदि e.g. शरद, दरद; cf. शुद्धभसोऽदि; Uṇ. 127;

अदिप्रभृति See अदादि above.

अदुक् aug. अद् added to the word एक before the negative particle न; e.g. एकानविंशति:, एकानिंशित् cf. P. VI 3.76.

अहम् not seen properly; doubtful; indistinct; said with respect to a letter which is not distinctly deciphered in the Samhitapatha; e.g. तनः (R. Sam. I. 107.3); the last letter त of तत् is deciphered in the Pada-patha which is given as तत्-नः cf. अहम्रक्षे प्रथमे चोदकः स्थात् प्रदर्शकः R. Pr. X. 15.

अदोष absence of fault; absence of inconvenience. The expression साप्यदोशे भवति often occurs in the Mahābhāṣya; cf. MBh. on I. 3.62; I. 4.108, etc.

अद्इ substitute for case affixes मु and अम् added to words ending with the affixes डतर and डतम and to the words अन्य, अन्यतर and इतर. cf. P, VII. 1.25.

अद्यतनी tech. te rm of ancient gramsignifying in general marians the present time of the day in question, the occurrence of the immediate past or future events in which is generally expressed by the agrist (लूड्ड) or the simple future (ਲੂਟ੍); the other two corresponding tenses imperfect first future (viz. লজু and ভুহু) being used in connection with past and future events respectively, provided the events do not pertain to that day which is in question; cf. 'वा चाद्यतन्याम् ' M.Bh. P.III. 2.102 Vēr . . . अट्तन्याम् P. VI. 4.114. Vart. 3; (2) term for the tense showing immediate past time called প্ৰকৃ in Pănini's grammar e. g. मायोगे अद्यतनी । मा काषीत Kāt. III. 1.22, Hem. III. 3.11.

अद्भव्यवाचिन् not expressive of any substance which forms a place of residence (of qualities and actions); cf. तथा व्याकरणे विप्रतिषिद्धं चानधिकरण- वाचि (P. II. 4. 13); इत्यरव्यवाचीति गम्यते। M.Bh. on II. 1.1.

अहियोनि lit. not made up of two elements, and hence, produced with a single effort, an expression used for simple vowels (समानाक्षर) such as अ, इ, उ, क, ल, and simple consonants क, ख, ग etc. as distinguished from diphthongs (सन्ध्यक्षर) such as ए, ऐ, ओ, औ and conjunct consonants क, धृ etc. which appear to have been termed दियोनि cf. अपृक्तमेकाक्षरमाहियोनि यत् R. Pr. XI.3.

अह्रचुपसर्ग not preceded by (two or more) prepositions; i. e. preceded by only one preposition. cf. छादेचेंऽद्रचुपसर्गस्य P. VI. 4.96 prescribing short अ for the long आ of the root छाद् before the krt. affix व. e.g. प्रच्छदः.

अधिक (1) additional or surplus activity which a rule in grammar sometimes shows: अधिक: कार: or अधिकं कार्यम्; cf. M. Bh. on I. 3.11, Kāś, on III. 2.124, Bh. Vr. on III. 4.72; (2) surplus subject matter e. g. अयाख्याः समाम्नायाधिकाः प्राग्निभितात (V. Pr. I.33.)

अधिकरण (1) support; a grammatical relation of the nature of a location; place of verbal vity. cf. आधारोऽधिकरणम P. I. 4.45; (2) one of the six or seven Kārakas or functionaries of verbal activity shown by the locative case cf. सप्तम्यधिकरणे च P.II.4.36;(3)substance, 'dravya' cf. अनिधकरणवाचि अद्रब्यवाचि इति गम्यते M.Bh. on II. 1.1.

अधिकार governing rule consisting of a word (e.g. प्रत्यय:, घातो:, समासान्ता: etc.) or words (e.g. ङचाप्पातिपादिकात्, संवेस्य देetc.) which follows or is taken as understood in every following rule upto a particular limit. meaning of the word अधिकार is discussed at length by Patanjali in his Mahabhasya on II. 1. 1, where he has given the difference between अधिकार and परिभाषाः cf. अधिकारः प्रतियोगं तस्यानिर्देशार्थं इति योगे योगे उपतिष्ठते। परिभाषा पुनरेकदेशस्था सती सर्व शास्त्रमभिज्बलयति प्रदीपवत् । See also Mahābhāsya on I.3.11, I. 4.49 and IV. I.83. The word or wording which is to repeat in the subsequent rules is believed to be shown by Panini by characterizing it with a peculiarity of utterance known as स्वरितोचार or स्वरितत्वेन उच्चारणम्. The word which is repeated in the following Sūtras is stated to be अधिकृत. The Sabda Kaustubha defines adhikāra as एक्त्रीपात्तस्यान्यत्र न्यापारः अधिकारः Kaus. on P. 1.2.65. Sometimes the whole rule is repeated e. g. प्रत्यय: P. III. 1.1, अङ्गस्य P. VI.

समासान्ताः P. V. 4.68, while on some occasions a part only is seen repeated. The tion goes on upto a particular limit which is stated असिद्धवदत्रामात् P. VI. 4.22, प्राग्रीधरानि-पाता: P. I. 4.56. Many times the limit is not stated by the author of the Sūtras but it is understood by virtue of a counteracting occurring later on. On still other occasions, the limit is defined by the ancient traditional interpreters by means of a sort of convention which is called स्वरितस्वधातिज्ञा. This अधिकार or governance has its influence of three kinds: (1) by being valid or present in all the rules which come under its sphere of influence, c. g. क्षियाम or अङ्गस्य; (2) by showing additional properties e.g. the word अपादान being applied to cases where there is no actual separation as in सांकास्थ-केम्य: पाटलिपुत्रका अभिरुपतराः; (3) by showing additional force such as setting aside even subsequent rules if opposing. These three types of the influence which a word marked with स्वरित and hence termed अधिकार possesses are called respectively अधिकारगति, अधिक कार्य and आधिक कार. For details see M.Bh. on I.3.11. This अधिकार or governing rule exerts its influence in three ways: (1) generally by proceeding ahead in subsequent rules like the stream of a river, (2) sometimes by jumps like a frog omitting a rule or more, and (3) rarely by proceeding backward with a lion's glance; cf. /सिंहावलोकितं चेव मण्डकप्छतमेव च । गङ्गाप्रवा-/ हवचापि अधिकारान्त्रिधा मताः॥

अधिकारसूत्र a superintending aphorism, which gives no meaning of itself where it is mentioned, but gives its meaning in the number of aphorisms that follow; e.g. the rules प्रत्यय:, परस्च and आद्यदात्तस्च P. III. 1, 1, 2, 3 or सह सुपा. P. II.1.4.

अधिस्पर्शम् incompletely pronounced, referring to a letter so pronounced.

अधुना tad. affix applied to the pronoun इदम् which is changed into इ before the affix and then elided by P. VI.4.148, or changed into अ in which case धुना or अधुना could be looked upon as a tad. affix.

अध्यवसाय determination to begin an activity with a view to get the fruit. cf. य एष मनुष्य: प्रेक्षापूर्व-कारी स बुद्ध्या कीचदर्थ संपन्यति, संदर्ध प्रार्थना, प्रार्थिते अध्यवसायः, अध्यवसाये आरम्भः, आरम्भे निर्शृतिः, निर्शृतौ पत्नावातिः cf. M. Bh. on I. 3 14 and I. 4. 32.

अध्यात्मादि name of a class of words headed by the word अध्यात्मन् to which the tad. affix ठम् is added in the sense of 'तत्र मव: 'i.e. found therein, or existing therein. e. g. आध्यात्मिकम्, आधिदैविकम्, etc.cf. M.Bh. on IV. 3. 60.

अध्यास superimposition; a relation between a word and its sense according to the grammarians; cf. Vāk. Pad. II.240. (2) appendage; cf. आहुस्लेकपदा अन्ये अध्यासनिकपातिन: R. Pr. XVII. 43.

अध्याहार supplying the necessary element. cf. गम्यमानार्थस्य वाक्यस्य स्वह्मेणोपा-दानं वाक्यस्याध्याहारः Kāś. on P. VI. 1. 139., cf also Nir. I. 1. 13 and M. Bh. on Siva Sutra I Vārt 14.

अध्ये, अध्येन krt affixes substituted in the place of तुम् of the infinitive in Vedic Literature (P. III. 4. 9.), e. g. पित्रध्ये: when अध्येन् is substituted, the initial vowel of the word becomes उदात्त e. g. कर्मण्युपान्यस्थे।

अन tad. affix अ (अन) (1) added to the word नीली in the sense of 'dyed in', to form the word नील, cf. P. IV.2. 2. Vārt. 2.; (2) added to the word अषाढा in the sense of 'produced in' cf अषाढा: उपद्याति M. Bh. on IV. 3. 34 Vārt. 2; (3) added after the affix तीय in the same sense as तीय e. g. द्वितीयो भागः, तृतीयो भागः cf. पूरणाद् भागे तीयादन P. V. 3.48.

अन substitute for the affix यु (युच्, ण्युट् ल्युट्, ल्यु, ट्यु, ट्युल् and others of which only यु remains), cf. युने-रनाको P. VII. 1. 1. e. g. कारणा, हारणा, करणम्, हरणम्, नन्दनः, सायंतनम् etc.

अनङ् (1) substitute अन as Samāsānta at the end of a Bahuvrihi comp. in the feminine for the last letter of the word अध्य and for that of धन्स in all genders e.g. কুণ্টাগ্নী (by applying ई to कुण्डोधन्), शाङ्गधन्वा, अधिज्यधन्वा; cf. P V. 4. 131, 132; (2) substitute अन् for the last letter of the words अस्थि, दिघ etc. before the affixes of the instrumental and the following cases beginning with a vowel e. g. अस्थ्रा, दक्षा, अक्ष्मा etc. cf. P. VII. 1.75; (3) substitute अन for the last letter of the word साख, of words ending in ऋ, as also of उश्चन्स् and others before the nominative sing. affix सुं. e. g. सखा, कर्ता, उदाना; cf. P. VII. 1. 93, 94.

अनच्क possessing no अच् or vowel in it. cf इन्द्रे द्वौ अचौ, एको यस्येतिलोपेनापहृतो- ऽपर एकादेशेन ततः अनच्कः इन्द्रशब्दः संपन्नः cf. Par. Śek. on Par. 52.; M.Bh. on I. 4.2 Vart. 22.

अनञ् a word without the negative particle (नञ्) before it, e.g. धेतु-रनिञ कमुत्पादयति, a sūtra in Āpisali's grammar quoted in M. Bh. on IV.2.45 see also P. II. 1.60, VII. 1.37.

अनत uncerebralized; not changed into a cerebral (मूर्यन्य) letter. cf.

दन्त्यस्य मूर्धन्यापात्तर्नितिः Uvața on R. Pr. IV.34. -

अनितिदेख not resulting from any extended application or अतिदेश, cf. प्रकृत्याश्रयं अनितिदेशं भवति M.Bh. on IV. 1.151.

अनत्यन्तगति absence of the verbal activity in all ways or respects; incomplete activity; e.g. छिनकम् not completely cut, cf. अनत्यन्तगती क्तात् P. V. 4.4.

শ্বনন period of time not pertaining to the day in question; used in connection with past time, to express which the imperfect is generally used; also in connection with the future time, to express which the first future is generally used e g. হা: ব্যান, শ্ব: কর্না etc. cf. P. III. 2.111, 113; III. 3.15, 135; V. 3.21.

अननुबन्धक without any mute significatory letter attached; अननुबन्धकपरिभाषा is the short name given to the maxim—'अननुबन्धकप्रहणे न सानुबन्धकस्य प्रहणम्' See M.Bh. on I. 3.1; V. 2.9. There is a reading in the Par. Sek. निरनुबन्धकप्रहणे for अननुबन्धकप्रहणे, in which case the परिभाषा is called निरनुबन्धकपरिभाषा. See Par. Sek. Pari. 81.

अनन्तर (1) immediate, contiguous अन्यवहित. cf. हलोनन्तराः संयोग: P.1. 1.7. also गतिरनन्तर: P. VI. 2.49; cf. अनन्तरं संयोग: V. Pr. I. 48.; (2) nearest, as compared with others of the same type; cf. अनन्तरा या प्राप्ति: सा प्रतिषिध्यते M.Bh. on I. 1.43; cf. Pari. Sek. अनन्तरस्य विधिवां भवति प्रतिषेषो वा, which means that a prescriptive or prohibitive rule applies to the nearest and not to the distant one. Par. Sek. 61, Can. Par. 30.

अनन्त्य non-final cf. अनन्त्यविकारे अन्त्यस-देशस्य when a change does not concern a final letter then it concerns that which immediately precedes the final, Par. Sek. Pari 95. cf. also M.Bh. VI. 1.13 Vārt 5.

अनन्य not different, the same; cf. एकदेशविकृतमनन्यवत् that which has got a change regarding one of its parts is by no means something else; Par. Sek. Pari. 37.

अनन्यवद्भाव being the same, being looked upon as not different. See अनन्य above.

अनिभावान inability to express meaning desired. The expression न वा अनिभयानात् frequently occurs in the Mahābhāsya referring to such words or phrases as could be formed by rules of grammar or could be used according to rules but, are not found in current use recognized by learned persons or scholars: cf. तच्चानभिधानं यत्राप्तिरुक्तं तत्रेय, अन्यत्र तु यथालक्षणं भवत्येव । Padamañj. on III. 2.1; also cf. अनाभधानाद व्यधिकरणानां बहुत्रीहिनं भविष्यति । यत्र त्वभिधानमस्ति तत्र वैयधिकरण्येपि भवत्येव समासः, कण्डकाल इतिः Nyāsa on II. 2.24; for examples of अनभिधान, see also M.Bh.अभिधानलक्षणाः कृत्तद्वितसमासाः अनभिधानात्र M. Bh. on III. 3.19. also on III. 2.1. V. 5, IV. 2.1. See Kāś. on III, 1.22, III. 3.158.

अनिभिनेत्रेत्त that which is not applied; lit. (an operation or vidhi) which has not taken place or which has not been effective; cf. प्रसक्तस्य अनिभिनेत्रेत्तस्य प्रतिपेधेन निष्ठतिः शक्या कर्ते नानिभिनेत्रेत्तस्य M. Bh. on I. 1.5; IV. 1.37. Cf. also न चानिभिनेत्रेते विहरङ्गे अन्तरङ्गं प्राप्नोति। तत्र निभित्तमेव बहरङ्गे सन्तरङ्गस्य M.Bh. on VI. 4.22; VIII. 3.15.

अनिभिद्धित not conveyed or expressed by another i.e. by any one of the four factors viz. verbal affix, krt affix,taddhita affix and compound. The rule अनिभिद्धेत (P. II. 3.1) and the following rules lay down the different case affixes in the sense of the different Kārakas or auxiliaries of the verbal activity, provided they are not shown or indicated in any one of the abovementioned four ways; e. g. see the acc. case in कट करेगित, the inst. case in दोत्रण छुनाति, the dat. case in देवद्त्ताय गां ददाति, the abl. case in प्रामादाग्डाति, or the loc.case in स्थाल्यां पचाति.

अनभ्यास a wording which does not contain any reduplicative syllable; an epithet applied to such roots as are not to be reduplicated a second time before affixes of the perfect, as they are already reduplicated; cf. लिट घातोरनभ्यासस्य P. VI. 1.8.

अनर्थक (1) without any signification; lit. having no meaning of themselves, i.e.possessing a meaning only when used in company with other words or parts of words which bear an independent sense; (the word is used generally in connection with prepositions);e.g. अधिपरी अनर्थको P.I.4.93, cf. अनर्थान्तरवाचिनावनर्थकौ । घातुनोक्तां क्रिया-माहतु: । तदिवाशिष्टं भवति यथा शङ्के पयः ॥ M. Bh. on P. I. 4.93; cf. न निर्वद्धा उपसर्गा अर्थानिराहरिति शाकटायनः Nir. I. 1.3; cf. also अनर्थको अनर्थान्तरवाचिनै। Kāś. on I. 4.93, explained as সন্থা-न्तरवाचित्वादनर्थकावित्यक्तम् न त्वर्थामावादिति दर्शयति by न्यासकार; (2) meaningless, purposeless; cf. प्रमाणभूत आचार्यो दर्भव-वित्रपाणि: महता यत्नेन सूत्रं प्रणयति स्म । तत्राद्यक्यं वर्णेनाप्यनर्थकेन भवितुं किं पुनरियता स्त्रेण M.Bh. on I. 1.1, as also सामर्थ्ययोगान हि किंचिद-रिमन पश्यामि शास्त्रे यदनर्थकं स्यात M.Bh. on P. VI. 1 77. See for details M.Bh. on I. 2.45 Vārt. 12; III.1.77 Vārt. and Kaiyata and Uddyota thereon; (3) possessed of no sense absolutely as some nipatas केचन निपाताः सार्थकाः, केचन च निरर्थकाः

on R. Pr. XII. 9; निपातस्यानर्थकस्यापि प्रातिपदिकत्वम् P. I. 2.45 Vārt. 12 cf. also जन्या इति निपातनानर्थक्यं P. IV. 4.82. Vārt. 1, एकागाराजिपातनानर्थक्यं P. V. 1.113 Vārt. 1, also 114 Vart.1.

अनर्थान्तरम् synonym, synonymous, conveying no different sense, e.g. सङ्घः समृहः समुदाय इत्यनर्थान्तरम् । M.Bh. on P. V. 1.59; अपि च बुद्धिः संप्रत्यय इत्यनर्थान्तरम् M.Bh. on P. I. 1.56.

अनर्थान्तरवाचिनः not conveying any different sense, अनर्थान्तरवाचिनौ अनर्थकौ M.Bh. on I. 4.93.

अनारिवाधि opp. of अल्बिधि; an operation not concerning a single letter, e.g. स्थानिवदादेशोऽनिल्वधौ P. I. 1.56 and M. Bh. thereon; cf. स्थानिवदादेशो ह्मवर्णविधौ Kāt. Pari. 39.

अनवकारा having no occasion or scope of application; used in connection with a rule the whole of whose province of application is covered by a general rule, and hence which becomes technically useless, unless it is allowed to set aside the general rule; cf. अनवकाशा हि विधयो बाधका भवन्ति-rules which have no opportunity of taking effect (without setting aside other rules) supersede those rules; M.Bh. on V. 4.154, also Par. Sek. on Pari. 64.

अनवकाशत्व absence of any opportunity of taking effect, scopelessness; considered in the case of a particular rule, as a criterion for setting aside that general rule which deprives it of that opportunity; cf. अनवकाशत्वं निरवकाशत्वं वा बाधकत्वे बीजम्. This अनवकाशत्वं is slightly different from अपवादत्व or particular mention which is defined usually by the words सामान्य-विधिक्तसर्गः। विशेषविधित्पवादः।

अनवगतसंस्कार (a word) whose formation and accents have not been explained; cf. Nir. IV. 1; V. 2.

अनवयव lit. having no parts; impartite; without any concern with the individual component parts; application in totality; cf. सिद्धं तु घमोपदेशने अनवयविज्ञानाद्यमा लोकिकवैदिकेषु P. VI. 1.84 Vart 5 and the Bhasya thereon; अस्मिल् शास्त्रे अनवयवेन शास्त्राधंपप्रस्पय: स्यात्। a rule in grammar applies to all cases where its application is possible; it cannot be said to have its puorpose served by applying to a few cases only.

अनवस्था fault of having no end; endlessness; cf. एवमप्यनवस्था स्याद्या मूळक्षय-कारिणी Kāv. Pr.; cf.अवस्यं ह्यनेन अर्थानादि-शता केनचिच्छव्देन निर्देश: कर्तव्यः स्यात् । तस्य च तावत्केन कृतो येनासौ क्रियते । अथ तस्य केनचित्कृतस्तस्य केन कृत इत्यनवस्था । M. Bh. on II. 1.1.

अनवस्थान indefiniteness; cf. उचनीच-स्थानवस्थानात्मंशाया अप्रसिद्धि: M. Bh. on I. 2.30 Vart 1.

अनवस्थित undetermined, indefinite; see M.Bh. quoted above on अनवस्थान; cf. also आर्घवातुकीयाः सामान्येन भवन्ति अनवस्थितेषु प्रत्ययेषु । M. Bh. on I. 1.56; III. 1.4, VII. 2.10, VII. 4.9. The substitutes caused by an ārdhadhātuka affix are, in fact, effected by virtue of the prospective application of the ārdhadhātuka affix before its actual application.

अनह्न tech. term used by the writers of the Prātiśākhya works for frequentative formations such as रीरिष:, चाक्रुपत् etc.; cf. A. Pr. 4.86.

अनाकाङ्क not depending on another for the completion of its sense; cf. न यद्यनाकाङ्क्षे P. III. 4.23, and Nyāsa thereon which explains अनाकाङ्क्षे as न विद्येत आकाङ्क्षा अपेक्षा यस्य तस्मिन.

अनारुति not capable of presenting (on its mere utterance) any tangible form or figure; the word is used in connection with a technical term (संज्ञाशब्द) which presents its sense by a definition actually laid down or given in the treatise; cf. अनाकृतिः संज्ञा। आकृतिमन्तः संज्ञिनः M. Bh. on I. 1.1.

अनादर absence of consideration; disregard; cf. षष्ठी चानादरे P. II. 3.38.

अनादि non-initial; e. g. अनादेश्च मुङ्कचनम् P. III. 4.102, Vārt. 4; also M. Bh. on VII. 1. 3.

अनादिप्ट not replaced as a substitute; e. g. यः अनादिप्रादचः पूर्धस्तस्य विश्विं प्रति स्थानिवद्भावः M.Bh. on I. 1.57 Virt. 1, III. 2.3 Vārt. 2, and VI. 1.12 Vārt. 10.

अनादेश (1) original, not such as is substituted; e.g. युप्पदस्मदोरनादेश P.VII. 2.86; (2) absence of statement, अनिदेश e.g. कर्तरि कृद्धचनमनादेश स्वार्थविशानात् P. III. 4.67, Vart. 1; cf. the Pari. अनिर्दिशर्थाः प्रत्ययाः स्वार्थ भवन्ति । Par. Sck. Pari. 113.

अनानन्तर्थे not a close relation; distance; cf. क्राचिच्च संनिपातकृतमानन्तर्य शास्त्र-कृतमनानन्तर्ये क्राचिच्च नैय संनिपातकृतं नापि शास्त्रकृतम् । M. Bh. on VIII. 3.13.

अनानुपूट्येसंहिता that samhita which has an order of words in it, which is different from obtains in the Pada-patha, and which appears appropriate according to the sense intended in the passage. There are three places of such combinations of words which are not according to the succession of words in the Pada-patha, quoted in the R.Pr. गुनश्चिन्छपं निदित सहस्रात् Rk. Sam. V.2.7, नरा वा दास पुषणमगी-ह्मम् Rk. Sam. X. 64.3; नरा च शसं देव्यम् Rk. Samh. IX. 86. 42. cf. एता अनानुपूर्व्यक्षीहताः । न ह्येतेषां त्रयाणां पदानुपूर्व्यण संहितास्ति Uvvata on R. Pr. 11.78.

अनान्तर्य absence of proximity, absence of cognateness; cf. इह तर्हि खट्वस्यों मालस्य इति दीर्घवचनादकारे। न, अनान्तर्योदेकारीकारी न। M. Bh. on Śiva Sūtras 3-4.

अनाप्य having or possessing no āpya or object; intransitive (root); cf. चालराव्दार्थाद् अनाप्याद् युच् Cāndra I.2 97 standing for चलनराव्दार्थाद् अकर्मकाद् युच् P. III. 2.148.

अनार्ष (1) non-vedic; not proceeding from any Rsi, or Vedic Seer, cf. संबुद्धी शाकल्यस्यंती अनार्षे P. I. 1.16; also Kās. on the same; cf. किमिदमुपस्थितं नाम।अनार्षे इतिकरणः M.Bh.on VI.1.129; (2) pertaining to the Padapātha which is looked upon as अनार्षे i.e. not proceeding from any Vedic Seer; cf. अनार्षे इतिकरणः । स च द्यक्षर आद्यदान्तश्च, Uvvaṭa on R. Pr. III. 23; cf. also A. Pr. III. 1.3.

अनि kṛt affix in the sense of curse, e. g. अजीवनिस्ते राठ भूयात्; cf.आक्रोरो निम्न अनि: P. III. 3.112. This affix अनि gets its न् changed into ण् after ऋ or रेफ of the preceding preposition as in अप्रयाणि:;cf. Kāś. on VIII.4.29.

अनिच् samāsānta affix after the word धर्म and some other words prescribed by P. V. 4. 124-6, e.g. कल्याणधर्मा, सुजम्भा, दक्षिणमा.

अनिट् (1) not admitting the augment इट् to be prefixed to it; the term is strictly to be applied to ārdhadhātuka affixes placed after such roots as have their vowel characterized by a grave accent (अनुदात्तस्य); the term अनिट् being explained as आनेडादि qualifying the आर्थानुक affix; (2) in a secondary way, it has become customary to call such roots अनिट् as do not allow the augment इट् to be prefixed to an ārdhadhātuka affix placed after them. Such roots are termed अनुदात्त verily because they are possessed of an

anudatta vowel. e. g. कृ, भृ, जि, गम्, हन् etc. as against मू, धू, तृ, श्वि, वृ, वद्, ਪਲ, ਕਲ, etc. which have their vowel characterized by an acute (उदात) accent. For a complete list of such roots see the well-known stanzas given in the Siddhantakaumudī incidentally on आत्मनेपदेप्ब-नत: P. VII. 1.5. जददन्तैयातिरुक्ष्णुशाङ्स्नु-.....निहताः स्मृताः ॥ १॥ शक्कपचुमुचि-रिच्वच्विच्.....धातवो द्यधिकं रातम् ॥ as also some lists by ancient grammarians given in the Mahabhasya on एकाच उपदेशेनुदात्तात्. P. VII. 2.10 or in the Kāśikā on the same rule P. VII. 2.10.

अनिट्कारिका (I) name given to Stanzas giving a complete list of such roots as do not allow the augment इ (इट्ट) to be prefixed to ārdhadhātuka affix placed such Kārikās them. For see Sid. Kaum. on VII. 1.5 as also Kāsīkā on VII. 2.10; (2) a short treatise enumerating in 11 verses the roots which do not admit the augment इट् before the The work ārdhadhātuka affixes. is anonymous, and not printed so far, possibly composed by a Jain writer .The work possibly belongs to the Katantra system and has got short glosses called व्याख्यान, अवचूरि, विवर्ण, टीका, टिप्पणी and the like which are all anonymous.

अनिद्कारिकाविवरण a short commentary by Ksamāmānikya on the work Anitkārikā, which see above.

आनिङ्गच not separable into two padas or words by means of avagraha; cf. संध्य ऊष्माप्यनिङ्गच; R. Pr. V. 41; cf. also R. Pr. IX. 25, XIII. 30. See इङ्ग्य below.

अनित्य (1) not nitya or obligatory; optional; (said of a rule or paribhāṣā whose application is volun-

tary). Regarding the case and conjugational affixes it can be said that those affixes can, in a way, be looked upon as nitya or obligatory, as they have to be affixed to a crude nominal base or a root, there being a dictum that no crude base without an affix can be used, as also, no affix alone without a base can be used. On the other hand, the taddhita and krt affixes as also compounds are voluntary as, instead of them an independent word or a phrase can be used to convey the sense. For a list of such nitya affixes see M. Bh. on V. 4.7; (2) the word अनित्य is also used in the sense of not-nitya, the word नित्य being taken to mean कृताकृतप्रसाि occurring before as well as after another rule has been applied, the latter being looked upon as आनित्य which does not do so. This 'nityatva' has got a number of exceptions and limitations which are mentioned in Paribhāsās 43-49 in the Paribhasendusekhara.

अनिदंप्रथम an underived word; an ancient term used by writers of the Prātisākhyas to signify 'original' words which cannot be subjected to निर्वचन.

अनिपात्य not necessary to be specifically or implicitly stated, as it can be brought about or accomplished in the usual way: e.g. इन्द्रम् । लिङ्गम-शिष्यं लोकाश्रयत्याछिङ्गस्य । तत्र नपुंसकत्यमनि-पात्यम् M. Bh. on VIII. 1.15. See also M. Bh. on VIII. 2.27 and VI. 1.207.

अतिभित्त not serving as a cause, not possessing a causal relation; e.g. संनिपातलक्षणे विधियनिमित्तं ताद्वित्रातस्य Par. Sek. Pari. 85. See also M. Bh. on I.1.39.

अनियत not subject to any limitation; cf. प्रत्यया नियता:, अर्था अनियता:, अर्था अनियता:, अर्था नियता:, प्रत्यया अनियता: M. Bh. on II. 3.50. In the case of नियमिविध (a restrictive rule or statement) a limitation is put on one or more of the constituent elements or factors of that rule, the limited element being called नियत, the other one being termed अनियन; also see Kās. on II. 2. 30.

अनियतपुरुक whose sex—especially whether it is a male or a female—is not definitely known from its mere sight; small insects which are so. The term कुझ in P. IV.1. 131 is explained in the Mahābhāsya as कुझ नाम आनियत्नुंक्स अञ्चर्धना वा M. Bh. on P. IV. 1. 131.

अनिद्धिर्थ whose sense has not been specifically stated; the word is used with reference to such affixes as are not prescribed in any specific sense or senses and hence as are looked upon as possessing the sense which the base after which they are prescribed has got; cf. आनिधार्थाः प्रत्ययः स्थापं भवन्ति—affixes, to which no meaning has been assigned, convey the meaning of the bases to which they are added; cf. Par. Sek. Pari. 113; cf. also M. Bh. on III. 2.4, III, 2.67, III. 5.19, III. 4.9, VI. 1.162.

अनिष्ट an undesired consequence or result; cf. अनिष्टं च प्राप्नांति ह्यं च न निष्यति M. Bh. on I. 3.1; also cf. नानिश्यां शास्त्रपञ्चीतः M. Bh. on VI. 1.2.

अनिष्टिज्ञ ignorant or inattentive to what the Grammarian intends or desires to say. cf. तथ भौयभगवताकम्— अनिष्टिज्ञो वाडवः पटित । इप्यत एव चतुमीत्रः म्हुतः M. Bh. on VIII. 2.106.

अनीयर् kit assix, termed इत्य also forming the pot. pass. part. of a

root; cf. तब्यस्तब्यानीयर: P.III.1.96. e.g. see the forms करणीयं, हरणीयं, the mute र showing the acute accent on the penultimate vowel.

अनुकरण

अनुक्रण (1) imitation; a word uttered in imitation of another; an imitative name; cf. अनुकरणं चानितिपरम् P. I. 4.62; अनुकरणं हि दिश्शिशिशिषातिषिदेषु यथा लौकिकनैदिकेषु, Siva sutra 2 Vārt 1; cf. also प्रकृतिबद् अनुकरणं स्वति an imitative name is like its original Par. Sek. Pari. 36; also M.Bh. on VIII. 2.46; (2) imitative word, onomatopoetic word; cf. एवं ह्याहु: कुक्कुट् इति । नैवं त आहु: । अनुकरणमेतरेषाम् M. Bh. on I.3.48. cf. also दुन्दुभि: इति शब्दानुकरणम् Nir. IX. 12.

अनुकर्ण dragging (from the preceding rule) to the following rule taking the previous rule or a part of it as understood in the following rule or rules in order; the same as अनुश्चित्; cf. अनुकर्षणार्थश्चकार: Käs. on II. 4. 18, III. 2.26, VII. 1.48; cf. also the Paribhāṣā चानुकृष्टं नोत्तरत्र—that which is attracted from a preceding rule by the particle च is not valid in the rule that follows; Par. Sek. Pari. 78.

अनुकृष्ट attracted from a previous rule as is frequently done in Panini's rules. See the word অনুকৰ্মণ above.

अनुक्त not actually stated or expressed in a rule; cf. चकारोऽनुक्तसमुच्चयार्थ: Kāś. on II. 4.18, III. 2. 26, VII. 1. 48; also cf. Nyāsa on P. II. 2.9

अनुक्रम right or regular order in a Vedic recital, called क्रम. e. g. वायव: स्थ.

अनुक्रमण enumeration (in the right order as opposed to ज्युक्तम); e. g. अथ किमर्थमुत्तरत्र एवमादि अनुक्रमणं कियते M. Bh. on II. 1. 58; also on IV. 2.70; verbal forms of the root क्रम् with अनु occur in this sense very

frequently; e.g. यदित ऊर्ध्व अनुक्रामिष्याम:; so also the p.p. p. अनुक्रान्तं occurs frequently in the same sense.

अनुतन्त्र lit. that which follows Tantra i.e. Śāstra which means the original rules of a Śāstra; technical term for Vārtika used by Bhartrhari; cf. सूत्राणां सानुतन्त्राणां भाष्याणां च प्रणेतृभि: Vāk. Pad. I.23, where the word अनुतन्त्र is explained as Vārtika by the commentator.

अनुत्तम other than उत्तम or the first person; cf. विभाषितं सोपसर्गमनुत्तमम् P. VIII 1.53 and Kāsikā thereon.

अनुत्पात्त non-production of an element of a word such as an affix or an augment or the like; cf. वावचन चानुस्पर्थम् P. III. 1.2 Vart. 7, तंशा-स्पित्वी प्रसद्धाः यथा तद्धिते P. III. 1. 94 Vart. 2, also कृष्यादिषु चानुस्पत्तिः (णिचः) P. III. 1.26, Vart. 3.

अनुद्वात non-udatta, absence of the acute accent; one of the Bahyaprayatnas or external efforts to produce sound. This sense possibly refers to a stage or a time when only one accent, the acute or उदात was recognized just as in English and other languages at present, This udatta was given to only one vowel in a single word (simple or compound) and all the other vowels were uttered accentless.i.e. Possibly with this idea in अनुदात्तः view, the standard rule 'अनुदात्तं पदम-कवर्जम ' was laid down by Pānini. P. VI. 1.158. As, however, the syllable, just preceding the accented (उदात्त) syllable, was uttered with a very low tone, it was called अनुदात्ततर, while if the syllables succeeding the accented syllable showed a gradual fall in case they happened to be consecutive and more than two, the syllable succeeding the उदात was given a mid-way tone, called स्वरित; cf.

उदात्तादनुदात्तस्य स्वरित:. Thus, in the utterance of Vedic hymns the practice of three tones उदात, अनुदात्त and स्वरित came in vogue and accordingly they are found defined in all the Prātiśākhya and grammar works;cf. उन्वेरदात्तः, नीचेरनुदात्तः समाहारः स्वरित: P. I. 2. 29-31, T.Pr. I. 38-40, V. Pr. I. 108-110. Anudātta is defined by the author of the Kāsikāvrtti as यस्मिन्तुच्चार्यमाणे गात्राणामन्त्रवसर्गो नाम शिथिलीभवनं भवति, स्वरस्य मृदुता, कण्ठ-विवरस्य उरता च सः अनुदात्तः cf. अन्ववसर्गा खस्प्रति नीचै:कराणि मादेवम्हता M. Bh. on I. 2. 29,30. उदात्तश्चानुदात्तश्च स्वरितश्च त्रयः स्वराः । आयाम-विश्रम्माक्षेपैस्त उच्यन्तेऽक्षराश्रयाः ॥ R. Pr. III. 1. The term anudātta is translated by the word 'grave' as opposed to 'acute' (udatta,) and 'circumflex' (svarita); (2) a term applied to such roots as have their vowel अनुदात or grave, the chief characteristic of such roots being the non-admission of the augment इ before an ārdhadhātuka affix placed after them. (See अनिट्.).

अनुदात्ततर quite a low tone, completely grave; generally applied to the tone of that grave or anudatta vowel which is immediately followed by an acute (उदात्त) vowel. When the three Vedic accents were sub-divided into seven tones viz. उदात्त, उदात्ततर, अनुदात्त, अनुदात्ततर, स्वरित, स्वरितस्थादात्त and एकश्रुति corresponding to the seven musical notes, the अनुदात्ततर was the name given to the lowest of them all. अनुदाचतर was termed सन्ततर also; cf. उदात्तस्वरित-परस्य सन्नतर: P. I. 2.40; cf. also M. Bh. on I. 2.33.

अनुदात्ता a term meaning 'having a grave accent,' used by ancient grammarians. Cf. किामियमेकश्रुतिरदात्ता उत अनुदात्ता M. Bh. on I. 2.33.

अनुदात्तेत lit. one whose mute significatory letter is uttered with a grave accent; a term applied to a root characterized by an indicatory mute vowel accented grave, the chief feature of such a root being that it takes only the Atmanepada affixes; e.g. आस्ते, वस्ते, etc.; cf. अनुदात्तिङ्त आत्मनेपदम् P. I. 3.12; such a root, in forming a derivative word in the sense of habit, takes the affix युच e. g. वर्सन:, वर्धन: etc. provided the root begins with a consonant; cf. अनुदासेनश्च इलादे: P. III. 2.149.

अनुदात्तोपदेश (a root) pronounced originally i. e. pronounced in the Dhatupatha with a grave accent; see the word अनुदास above; cf. अनुदात्तोपदेशवनतितनोत्यादीनामनुनासिकलेणो झिल क्विति P. VI. 4.37. See also the word अनिट् above.

अनुदेश (1) reference, mention, statement referring to a preceding element. cf. यथासंस्थमनुदेश: समानाम् P. I. 3.10; cf. असिद्धयचनात् सिद्धमिति चेन् उत्स्था- छक्षणानामनुदेश: M. Bh. I.1.57, Vart. 3. (2) declaration, prescription: the same as अतिदेश. cf. स्थान्यादेशपृथकत्वादादेश स्थानिवद् अनुदेशा गुरुषद् गुरुपुश इति यथा P. I.1.56 Vart. 1; (3) a grammatical operation cf. यथामंच्यमनुदेश: समानाम् । समसंबन्धी विधियथासंख्यं स्थात् Sid. Kau. on P.I. 3.10. See the word अनुदेश in this sense cf. संख्यातानामनृदेशा यथा- संख्यम् V. Pr. I.143.

अनुनाद् a fore-sound; a preceding additional sound which is looked upon as a fault; e. g. इयामि when pronounced as अह्यामि. This sound is uttered before an initial sonant consonant. It is also uttered before initial aspirates or viṣarga. cf. बोषवतामनुनाद: पुरन्ताद् आदिस्थानां, क्रियते घारणं वा । सोप्मोष्मणामनुनादोप्यनाद: प्र. Pr. XIV.18,19.

अनुनासिक (a letter) uttered through the nose and mouth both, as different from anusvāra which is uttered only through the nose. cf. मुखनासिका• वचनानुनासिक: P.I.1.8, and M. Bh. thereon. The anunasika or nasal letters are the fifth letters of the five classes (i.e. ङ्,ज़, णु, न्, म्) as also vowels अ, इ, उ and semivowels when so pronounced, as ordinarily they are uttered through mouth only; (e.g. अँ, आँ, etc. or य्यॅ, ब्वॅ, ल्लॅ etc. in सय्यॅन्ता, सब्वॅत्सर:, सॅंब्लीन: etc.) The अनुनासिक nasalized vowels are named रङ्गवर्ण and they are said to be consisting of three mātrās. cf. अशे आद्यानवसानेऽप्रगृद्यान् आन्वार्या आहरनुना-सिकान स्वरान । तालामात्र शाकला दशेयन्ति R. Pr. I. 63. 64; cf. also अप्रप्रहा: समानाक्षराणि अनुनासिकानि एकेषाम् T. Pr XV.6. Trivikrama, a commentator on the Kat. Sutras, explains अनुनासिक as अनु पश्चात् नासिकास्थानं उच्चारणं एषां इत्यन्नासिकाः । पूर्वे मुखस्थानमुच्चारण पश्चा-नासिकास्थानमुच्चारणमित्यर्थः । अनुप्रह्णात्केवल-नासिकास्थानोच्चारणस्य विजनस्वारस्य नेयं संज्ञा ! and remarks further पूर्वाचार्यप्रसिद्धसंज्ञे-यमन्वर्था। Com. by Tr. on Kat. I 1.13. Vowels which are uttered nasalized by Pānini in his works viz. सूत्रपाठ, घातपाठ, गणपाठ etc. are silent ones i. e. they are not actually found in use. They are put by him only for the sake of a complete utterance, their nasalized nature being made out only by means of traditional convention. e. g. एघ, स्पर्ध etc. cf. उपदेशेऽजनुनासिक इत् P. I. 3.2; cf also प्रातिज्ञानुनासिक्याः पाणिनीया: Kās' on I.3.2.

अनुन्यास a commentary on न्यास (काशि-काविवगरपञ्जिका by जिनेन्द्रबुद्धि). The work is believed to have been written by इन्दुमित्र. It is not available at present except in the form of references to it which are numerous especially in Sīradeva's Paribhā-sāvītti.

अनुपपांत्र discord, absence of validity, incorrect interpretation; cf. प्रथमानुपप- तिस्तु M.Bh on I. 4.9.

अनुपपद्यमाना impossibility of being explained; cf. तत्र सिद्धायां अनुपपद्यमा- नायां इतरथा उपपादियेषेत्, Nir II.2.

अनुपपन्न impossible to be explained, not consistent; cf. अथाप्यनुपपनार्था भवन्ति। ओषधे त्रायस्वैनम्। Nir. I. 15.

अनुपरिपाद्य (संहिता) the Pada text of the Vedic Samhitā.

अनुपसर्जन not subordinated in wordrelation, principal member; cf. अनु-पसर्जनात् P. IV. 1. 14 and M. Bh. thereon; cf. also Par. Sek Pari. 26.

अनुप्रदान an effort outside the mouth in the production of sound at the different vocal organs such as ক্যুত, নান্ত etc. which is looked upon as an external effort or bāhyaprayatna अनुप्रदान is one of the three main factors in the production of sound which are (1) स्थान, (2) करण or आभ्यन्तरप्रयत्न and (3) अनुप्रदान or बाह्यप्रयतनः cf. स्थाकरणप्रयतेनस्या वर्णा जायन्ते Can. The commentator on T. Pr. describes अनुप्रदान as the मुलकारण or उपादानकारण, the main cause in the production of articulate sound; cf. अनुप्रदीयते अनेन वर्ण: इति अनुप्रदानम्; cf. also अनुप्रदीयते इत्यनुप्रदानं प्रयत्न इत्यर्थः ; Uvvata on R. Pr. XIII. 1. Generally two main varieties of बाह्यप्रयत्न are termed अनुप्रदान which are mentioned as (i) श्वासानुप्रदान (emission of breath) and नादानप्रदान (resonance), the other varieties of it such as विवार, संवार, घोष, अधोष, अल्पप्राण, महाप्राण, उदात्त, अनुदात्त स्वरित being called merely बाह्यप्रयत्ने.

अनुप्रयोग subsequent utterance; lit. post-position, as in the case of the roots कृ, भू and अम् in the periphrastic perfect forms; cf. आम्प्रत्यवत् कृञाऽ नुप्रयोगस्य, P. I. 3. 63; यथाविष्यनुप्रयोगः पूर्विस्मन् III 4. 4.

अनुबन्ध a letter or letters added to a word before or after it, only to signify some specific purpose such as (a) the addition of an affix (e. g. 4িন্ন, अथुच्, अङ् etc.) or (b) the substitution of गुण, बृद्धि or संप्रसारण vowel or (c) sometimes their prevention. These anubandha letters are termed इत् (lit. going or disappearing) by Pāṇini (cf. उपदेशेजनुनासिक इत् etc. I.3.2 to 9), and they do not form an essential part of the word to which they are attached, the word in usage being always found without the Ed letter. For technical purposes in grammar, however, such as आदित्व or अन्तत्व of affixes which are characterized by इत् letters, they are looked upon as essential factors, अनेकान्ता अनुबन्धाः, एकान्ताः, etc, Par. Sek. Pari. 4 to 8. Although पाणिनि has invariably used the term হব for अनुबन्ध letters in his Sūtras, Patanjali and other reputed writers on Pānini's grammar right on upto Nāgeša of the 18th century have used the term अनुबन्ध of ancient grammarians in their writings in the place of इत्. The term अनुबन्ध was chosen for mute significatory letters by ancient grammarians probably on account of the analogy of the अनुबन्ध्य पशु, tied down at sacrifices to the post and subsequently slaughtered.

अनुभूतिस्वरूपाचार्यः a writer of the twelfth century who wrote a work on grammar called सरस्वर्ता-प्रक्रिया or सारस्वतप्रक्रिया. He has also written

घातुपाठ and आख्यातप्रक्रिया. The grammar is a short one and is studied in some parts of India.

अनुम् not allowing the addition of the augment नुम् (i.e. letter न्) after the last vowel; The term is used, in connection with the present part. affix, by Pāṇini in his rule शतुरनुमें। नश्चादी VI. 1.173.

अनुमान inference, suggestion, cf. अद्यक्त्या किया निष्डीभृता निद्यीचितुम् । सासाननुमानगम्या M. Bh. on I. 3. 1.

अनुलोम in the natural order (opp. to प्रतिलोम), cf. तेडन्यसरमंत्रवानुलोमा: in R. Pr. II. 8. अनुलोममंथि is a term applied to Saindhis with a vowel first and a consonant afterwards.

अनुलोमसांघे combination according to the alphabetical order; a kind of euphonic alteration (सीघ) where the vowel comes first. e.g. हुन्यवार् + अभि: where द् is changed to दु;एप: देवं:=एप देव: cf. R. Pr. II. 8. (See अनुलोम).

अनुवर्तन continuation or recurrence of a word from the preceding to the succeeding rule; the same as anuvitti; cf. अनुवर्तन्ते नाम विधयः । न चानुवर्तनोदय मवन्ति । किं ताई । यत्नाद्भवन्तीति M. Bh. on I. 1. 3.

अनुवर्त्य to be observed, to be obeyed: cf. न लक्षणन पदकारा अनुवर्त्याः । पदकारेनीम लक्षणमनुबर्त्यम् M. Bh. on 111. 1.109.

सनुवाद repetition of a rule already laid down or of a statement already made: cf. प्रमाणान्तरावरातस्य अर्थस्य दान्दिन संकीतनमात्रमनुवाद: Kās. on II. 4.3.

अनुविधि operation in conformity with what is found. The expression छन्दिस हमनुविधिः is often found in the Mahābhāsya; cf. M. Bh. on I. 1.5, I. 1.6, I. 1.21, III. 1.9, III. 1.13, VI. 1.6, VI. 1.77, VI. 1.79, VI. 4.128, VI. 4.141, VIII. 2.108. 25

अनुवृत्ति repetition or recurrence of a word from the previous to the subsequent rule or rules, which is necessary for the sake of the intended interpretation. The word is of common use in books on Pānini's grammar. This recurrence is generally continuous like the stream of a river (गङ्गास्रोतोवत्); sometimes however, when it is not required in an intermediate rule, although it proceeds further, it is named मण्डुकष्ट्रत्यानुत्रस्ति. In rare cases it is taken backwards in a sūtra work from a subsequent rule to a previous rule when it is called अपकर्ष.

अनुशासन traditional instruction; treatment of a topic; e.g. अथ शन्दानुशासनम् M. Bh. I. 1.1 where the word is explained as अनुशिष्यन्ते संस्कियन्ते ज्युत्पा-यन्ते अनेन इति अनुशासनम्.

अनुषद्ध (1) lit.attaching, affixing; augment, अनुषद्धते असी अनुषद्ध:; (2) a term for the nasal letter attached to the following consonant which is the last, used by ancient grammarians; cf. अल्यासूची मस्त्ररनुषद्धसंयोगादिलापर्थम् cf. P.I. 1.47 Vārt. 2 and M.Bh. thereon; cf. यभान्तानां चानुषिद्धणाम् Kāt. IV. 1.13. The term अनुषद्ध is defined in the Kātantra grammar as ब्यजनान अनुषद्ध: The term is applied to the nasal consonant न preceding the last letter of a noun base or a root base; penultimate nasal of a root or noun base; Kāt. II.1.12.

अनुसंहार independent mention, a second time, of a thing already mentioned, for another purpose; cf. ' अलेश्न्यस्य ' इति स्थाने विज्ञातस्यानुसंहार: P.I.1.53 Vart. 1.

अनुसंदिवं according to the Sainhitā text of the Vedas; cf.एतानि नोहं गच्छित्त अश्रिगो अनुसंहितम् Bhartrihari's Mahābhāṣyadīpikā p. 9; cf. also R. Pr. XI. 31, also XV. 33, where the

word is explained as संहिताकमेण by Uvata.

अनुस्वार see above under अं.

अन्क said afterwards, generally in imitation; cf. अन्कागन् अन्चानः। अन्किभित्येवान्यत्र M.Bh. on III. 2,109.

अनूक्ति statement with reference to what has been already said; the same as anvādeśa.

अनुदेश statement or mention immediately afterwards; the same as the word अनुदेश used by Pāṇini in I.3.10, cf. संख्यातानाम देशो यथासंख्यम् । अर्देश ; पश्चाहुँदश: Uvața on V. Pr. I. 143.

সনক্ষি having no ekasesa topic in it; a term applied to the Daiva Grammar which does not discuss the ekasesa topic to which Pāṇini has devoted ten rules from I. 2.64 to 73.

अनेकस्चर having many vowels or syllables in it; the same as अनेकाच् of Pāṇini; cf. Hem. III. 4.46

अनेकाक्षर having many syllables in it; cf. अनेकाक्षरयोग्त्वसंयोगाद्यवौ Kāt. II.2.59.

अनेकाच् having many vowels (two or more) in it; opp. to एकाच्; a term frequently used in Pāṇinī's grammar meaning the same as अनेकखर or अनेकाक्षर, which see above; cf. P. VI. 3.42, VI. 4.82

अनेकान्त (1) not forming an integral part, the same as अनव्यव; cf. अनेकान्ता: अनव्यवा इत्यर्थ: Par. Sek. Pari 4. (2) absence of any definite view cf. अनेकान्तत्वाच। येषां चाप्यारम्यते तेषासप्यनेकान्तः। .. मामहान उदयपानम्। समहान इति च। M. Bh. on VI. 1. 7

अनेकार्थ (1) possessed of a plural sense: referring to many things. cf. अनेकार्थ युप्पदस्मदी M. Bh. on P.II. 2.98 also अनेकार्थाश्रयक्ष पुनरेकदेश: P.I. 2.64 Vart. 15; (2) possessed of

many senses, cf. अनेकार्था अपि धातवो मवान्ते M. Bh. on P.III. 2.48; also cf. यान्यनेकार्थानि एकशब्दानि तान्यतोनु- क्रिमच्याम: Nir. IV.1.

अनेकाल् possessed of many letters; lit. possessed of not one letter, cf. अनेकालशित् सर्वस्य P. I. 1.55.

अनेजन्त not ending in a diphthong; cf नानुबन्धकृतमनेजन्तत्वम् Par. Śek. Par. 7

अनेकान्तिक undetermined, indefinite; एतदप्यनैकान्तिकं यदलप्राणस्य सर्वोञ्चेस्तन्महा-प्राणस्य सर्वनीचै: M. Bh. on I. 2.30, also M. Bh. on VI. 1.37; not invariable, cf. अनैकान्तिकं ज्ञापकम् M. Bh. on VII. 2.102, VIII. 3.34

अनौमित्तिक not possessed of any definite cause; अनैमित्तिको द्यनुबन्धलेष: M. Bh. on I. 1.20 also on I. 1.59 and I. 2.64.

अन्त final, phonetically last element remaining, of course, after the mute significatory letters have been dropped. cf. अनुत्तरक्षणोन्त: M. Bh. on I. 1.21 Vart. 6.

अन्तकरण lit. bringing about as the final; an affix (which is generally put at the end); ancient term for an affix; cf. एत: कारितं च यकारादिं चान्त-करणम्। अस्ते: गुद्धं च सकारादिं च। Nir. I. 13.

अन्तःकार्य lit. interior operation; an operation inside a word in its formation-stage which naturally becomes antaranga as contrasted with an operation depending on two complete words after their formation which is looked upon as bahiranga.

अन्तः पद्म inside a word; explained as पदस्य मध्ये by उज्बद्धः cf. नुश्चान्तः पद्दरे फे V. Pr. IV. 2 cf. also अन्तः पदं विश्वत्तयः R. Pr.II. 13.

अन्तः पात insertion of a letter or phonetic element such as the letter क

between ছ and a sibilant, or the letter হ between ण and a sibilant; cf. স্ন্তুক্ स বিশ্বা, বারিল্ ভ্ লুখিছি; cf. Pāṇ. VIII. 3.28, 29, 30, 31; cf. तेऽन्त:पाता: अकृतसंहितानाम् R. Pr. IV. 20

अन्त:पाद्म् inside the foot of a verse explained as पादस्य मध्ये by Uvvaṭa; cf. प्रकृत्याऽन्त:पादमन्यपेर. P. VI.1. 113.

अन्तःस्थ, अन्तःस्था f., also writen अन्तस्थ, अन्तस्था /, semivowel; cf. अथान्तस्था: । थिति रिनि छिति चिनिः V. Pr. VIII. 14-15; cf. चतलेन्तःस्थाः explained by उब्बट as -स्पर्शोप्भणामन्तः मध्ये तिष्टन्तीति अन्तःस्थाः R. Pr. I. 9. also पराश्चतस्त्रान्तस्थाः T. Pr. I. 8. The ancient term appears to be अन्तःस्था f. used in the Prätisäkhya works. The word अन्तःस्थानाम् occurs twice in the Mahabhasya from which it cannot be said whether the word there is अन्तःस्थ m. or अन्तःस्था f. The term अन्तस्थ or अन्तस्था is explained by the commentators on Kātantra as स्वस्य स्वस्य स्थानस्य अन्त तियन्तीति ।

अन्तर interval between two phonetic elements when they are uttered one after another; hiatus, pause; वर्णान्तरं परमाणु, R. T. 31; also विरामा वर्णवामध्यप्यमुकालाण्यसंयुन Vyosasiksa; (2) space between two phonetic elements. e. g. स्वरान्तरे explained as स्वर्योरन्तरे (between two vowels) by Uvvata cf. अन्तस्थान्तरेपाकिङ्गा विभाष्तिमुण: Nir X.17.

সন্তা a highly technical term in Pāṇini's grammar applied in a variety of ways to rules which thereby can supersede other rules. The term is not used by Pāṇini himself. The Vārtikakāra has used the term thrice (Sec I. 4. 2 Vārt. 8, VI. 1. 106 Vart. 10 and VIII. 2. 6 Vārt. 1) evidently in the sense of 'imme-

diate', 'urgent', 'of earlier occurrence' or the like. The word is usually explained as a Bahuvrīhi compound meaning 'अन्त: अङ्गानि निमित्तानि यस्य ' (a rule or operation which has got the causes of its application within those of another rule or operation which consequently is termed बहिरङ्ग). अन्तरङ्ग, in short, is a rule whose causes of operation occur earlier wording of the form, or in the process of formation. As an अन्तरङग rule occurs to the mind earlier, as seen above, it is looked upon as stronger than any other rule, barring of course अपवाद rules or exceptions, if the other rule presents itself simultaneously. The Vartikakāra, hence, in giving preference to अन्तरङ्ग rules, uses generally the wording अन्तरङ्गबलीयस्त्वात which is paraphrased by अन्तरङ्गं बहिरङ्गाद् बलीय: which is looked upon as a paribhāṣā. Grammarians, succeeding the Vārtikakāra, not only looked upon the बहिरङ्ग operation as weaker than अन्तरङ्ग, but they looked upon it as invalid or invisible before the अन्तरङ्ग operation had taken place. They laid down the Paribhasa असिद्धं बहिरङ्गमन्तरङ्गे which has been thoroughly discussed by Nagesa in Paribhāsenduśekhara. अन्तरङ्गत्व is taken in a variety of ways by Grammarians: (1) having causes of application within or before those of another e. g. स्योन: from the root सिव (सि+ड+न) where the यण substitute for इ is अन्तरङ्क being caused by 3 as compared to guna for उ which is caused by न, (2) having causes of application occurring before those of another in the wording of the form, having a smaller number of causes, (4) occurring earlier in the order of several operations which take place in arriving at the complete form of a word, (5) not having संज्ञा (technical term) as a cause of its application, (6) not depending upon two words or padas, (7) depending upon a cause or causes of a general nature (सामान्यापेक्ष) as opposed to one which depends on causes of a specific nature (विद्यापोपक्ष).

अन्तरङ्गपरिभाषा the phrase is used generally for the परिभाषा 'असिद्धं बहि-रङ्गमन्तरङ्गे' described above. See the word अन्तरङ्ग. The परिभाषा has got a very wide field of application and is used several times in setting aside difficulties which present themselves in the formation of a word. Like many other paribhāṣās this paribhāṣā is not a paribhāṣā of universal application.

अन्तरङ्गवलीयस्व the strength which an antaranga rule or operation possesses by virtue of which it supersedes all other rules or operations, excepting an apavāda rule, when or if they occur simultaneously in the formation of a word.

अन्तरङ्गलक्षण characterized by the nature of an antarang.i operation which gives that rule a special strength to set aside other rules occurring together with it.

अन्तरतम very close or very cognate, being characterized (1) by the same place of utterance, or (2) by possessing the same sense, or (3) by possessing the same qualities, or (4) by possessing the same dimension; of स्थानेन्तरतमः P. I. 1.50 and Kas. thereon आन्तर्य स्थानार्थगुणप्रमाणतः। स्थानतः दण्डाग्रम्, अर्थतः वतण्डी चासौ युवतिश्च वातण्ड्य-युवतिः। गुणतः पादः, त्यागः, रागः। प्रमाणतः अमुष्मे अमूम्याम्॥

अन्तर्गेण a group of words mentioned inside another group of words (गण);

cf. पुषादिदिवाद्यन्तर्भणो यह्यते, न म्वादिकया-द्यन्तर्भण: रिद्धे on III. 1.55; also काण्यादिर्भगिद्यन्तर्भण्थः Kās on IV.2.111.

अन्तर्भाच inclusion of an element (of sense) in what has been actually assigned. e. g. देवदसमुपरमति । उपरगय-तीति यावत् । अन्तर्भावितण्यथींच सभिः Küs on P. I.3.84, अन्तर्भावितण्यथीं सुधिः सकर्मका भवति । राजयुष्वा Küs on P.111. 2. 95.

अन्तर्हित separated by a dissimilar element; cf. यूनि चान्तर्हित अप्राप्ति: P.IV. 1.93 Vārt. 5. व्यञ्जनान्तर्हिताम उदाराज्यरः अनुदात्तः स्वरितमापद्यते T. Pr. XIV. 20; cf. also R. Pr. III.9.

अन्तवद्भाव supposed condition of being at the end obtained by the single substitute (एकदिश) for the final of the preceding and the initial of the succeeding word. cf. अन्तादि- चच्च । योयमे कदिशः स पूर्वस्थान्तवत् परस्थादिवत स्यात्। Sid. Kau. on अन्तादिवच्च । VI. 1.84.

अन्तस्था f. also अन्तस्थः semi-vowel; see under अन्तःस्थ.

अन्तादिबद्धांच condition, attributed to a single substitute for the final of the preceding and initial of the succeeding word, of being looked upon cither as the final of the preceding word or as the initial of the succeeding word but never as both (the final as well as the initial) at one and the same time; cf. उभयत आश्र्य नान्तादिवत् Sir. Pari 39 also M. Bh. on I.2.48.

अन्ताम् affix of the impera. 3rd pers. plur. Ātm., substituted for the original affix झ, e. g. एघन्ताम्.

अन्ति affix of the pres. 3rd pers. pl.
Paras. substituted for the original
affix झि, e. g. दुर्वन्ति, मनन्ति.

अन्तु affix of the impera. 3rd pers. pl. Paras. substituted for the original affix क्षि. e. g. भवन्तु, दुर्वन्तु.

अन्ते affix of the pres. 3rd pers. pl. Atm. substituted for the a signal affix झ, e g. एड-ते, वर्त-ते.

अन्तोद्दास a word with its last sowel accented acute. Roots, crud i noun bases and compound words generally have their last vowel secented acute; cf. दिन: (मानि दिकस्) अन्त उदात्त: स्थान् Phip Sutra 1-1; धाते: (P. VI. 1.162) अन्त उदार: स्थान् ।

अस्त्व (1) final letter; अन्ते भवसन्त्रम् । (2) final consonant of each of the five groups of components which is a nasal अस्योगाशास्त्रः R. T. 17.

अस्यतरतः optionally; lit. in another way; cf. वर्णके व अन्यत्तरतः V.P.V.15.

প্রদান বিষয়ে are also used in the same sense.

अन्यपदार्थ another sense, sense different from what has been expressed by the wording given; cf. अनेकमन्य-पदार्थे P. II.2.24; also अन्याहार्थप्रधानी बहुनंदि: M. Bh. on II. 1.6.

अन्ययुक्त connected with the word अन्य; connected with another; e.g. अन्या गवां म्हाभाति।...व ध्यत्र गायोन्ययुवता: 1 कसाई। खासी, M.Bh. on P.H.3.22.

अन्य सहसाधिकरण an object which is different from what is mentioned, yet similar to it; cf. निजवसुक्तम-व्याहशा- थिकरण तथा ह्यर्थगतिः । अधाहणमान्येन्युक्तं शहणबहरा आनीवते । नार्भ छोऽमानीय धृती मवति । M. Bh. on P. III.I.12

अन्याच्य irregular; cf. सर्यविश्रामा भूमिरि-त्येवमाहिश्रं प्रयोगमन्याय्योमव मन्यन्तः Käs. on P. VII.3.34.

अन्यार्थ (1) having another purpose or signification; cf. अन्यार्थ प्रकृतं अन्यार्थ भवति M. Bh. on 1.1.23; (2) another sense which is different from what is expressed; cf. अन्यार्थी बहुनीहि: Can. II.2.46.

अन्योन्य संश्रय reciprocally dependent and hence serving no purpose; same as इतरेत्तराश्रय which is looked upon as a fault. cf. अन्यान्यतंश्रयं त्येतत्। स्त्रीकृतः शब्दः शब्दकृतं च स्त्रीत्यम् M.Bh. on IV.1.3.

अन्वक्षरसांघि a combination of letters according to the order of the letters in the Alphabet; a samdhi euphonic combination of a vowel and a consonant. अन्वक्षर-अनुलोमसंधि where precedes a consonant; and अन्ब-क्षरप्रतिलोमसंधि where a consonant precedes a vowel, the consonant in that case being changed into the third of i's class; एव स्य स च स्वराश्च पूर्वे भवति ब्यजनम्त्तरं यदेभ्यः । तेन्वक्षरसंघ्यानुलोमाः प्रातेलोमाश्च विपर्यये त एव ।। R Pr. II.8.9 e. g. एष देव:, स देव: and others are instances of अन्वश्वरानुलोमलीघ where विसर्ग after the vowel is dropped; while हृत्यवाडु अग्नि: is an instance of अन्वक्षरप्रतिलोमसंधि where the consonant ই precedes the vowel अ.

अन्वय (1) construing, construction; arrangement of words according to their mutual relationship based upon the sense conveyed by them, रान्दानां परस्परमथानुगमनम् । (2) continuance, continuation; cf. वृतवरस्तैलवर इति निषिक्ते घृते तैले या अन्वयाद्विराजणं भवति अयं वृतवरः, अयं तैलवर इति M. Bh. on P.II. 1.1.

अन्वर्थक given in accordance with the sense; generally applied to a technical term which is found in accordance with the sense conveyed by the constituent parts of it; e. g. सर्वनामसंज्ञा, cf. महत्याः संज्ञायाः करण एतत् प्रयोजनमन्वर्थसंज्ञा यथा विज्ञायेत M. Bh. on P I.1.23.

अन्वर्थसंज्ञा A technical term used in accordance with the sense of its constituent parts; e. g. सर्वनाम, संख्या, अन्यय उपसर्जन, कारक, कर्मप्रवचनीय, अन्ययी-

भाव, प्रत्यय, उपपद etc. All these terms are picked up from ancient grammarians by Paṇini; cf. तत्र महत्या: संज्ञाया एतत् प्रयोजनम् । अन्वर्थसंज्ञा यथा विज्ञायेत । संख्यायंत अनया संख्येति । cf. M. Bh. on I.1.23; also cf. M.Bh.on I.1.27,I. 1.38,I.2.43, I.4.83, II.1.5, III. 1.1, III.1.92 etc.

अन्वचसर्ग relaxation or wide opening of the sound-producing organs as done for uttering a vowel of grave accent. cf. अन्वचसर्ग; गात्राणां विस्तृतता Tait. Pr. XXII.10.

অন্বাক্ষ্য a word attracting a previous word such as the word च, in the Sūtra texts.

अन्वाचय aggregation of a secondary element along with the primary one; यत्रैकस्य प्राधान्यमितरदप्रधानं तदनुरोधे- नान्वाचीयसानता अन्वाचयः Nyāsa on P.II 2.29. One of the four senses of च, e.g.भिक्षामट गां चानय; cf. प्लक्षश्चेत्युक्ते गम्यत एतत्त्रोपेक्षोयं प्रयुज्यत इति।

अन्वादेश (1) lit. reference to the anterior word or expression; cf.अन्वादेशान्त्यस्य (नि: शब्दस्य in T.Pr.VII.3, अकारस्य in V-8) T. Pr. I.58; (2) reference again to what has been stated previously; cf. इदमोन्वादेशेशनुदात्तस्तृतीयादी अन्वादेशश्च कथितानुकथनमात्रम् P. II. 4.32 and Vart. 2 thereon; एकस्वैशाभिधेयस्य पूर्व शब्दन प्रतिपादितस्य द्वितीयं प्रतिपादनमन्वादेश: Kas on the above.

अन्वादेशक a word capable of attracting a word or words from previous statements; cf. चापीत्यन्वादेशको T Pr. XXII.5; same as अन्वाकर्षक.

अप् (1) kṛt affix अ, in the sense of verbal activity (भाग) or any verbal relation (कारक) excepting that of an agent, (कर्तृ) applied to roots ending in ऋ or उ and the roots मह, इ, ह etc. mentioned in P. III.3.58 and the following rules in preference to the usual affix घम. e. g. करः, गरः, शरः, यगः, छनः, पनः, महः, स्वनः etc. cf. P.III.

3.57-87; (2) compound-ending अप् applied to Bahuvrīhi compounds in the feminine gender ending with a Pūraṇa affix as also to Bahuvrīhi compounds ending with लें। सन् preceded by अन्त or बहिर् e.g. कल्याणीपञ्चमा रात्रयः, अन्तलेंगः, बहिलींसः पटः. cf. P. V. 4.116, 117.

अपकर्ष (1) deterioration of the place or instrument of the production of sound resulting in the fault called निरस्त; cf. स्थानकरणयोरपकर्षण निरस्तं नाम दोष उत्पद्यते, R. Pr. XIV.2; (2) drawing back a word or words from a succeeding rule of grammar to the preceding one; cf. °वश्यित तस्यायं पुरस्तादपक्षेः, M. Bh. on II.2.8. (3) inferiority (in the case of qualities) न च द्रब्यस्य प्रकृषीपकर्षें। स्तः।

अपत्य a descendent, male or female, from the son or daughter onwards upto any generation; cf तस्यापत्यम् P. IV. 1.92.

अपभंश degraded utterance of standard correct forms or words; corrupt form; e. g. गावी, गोणी and the like, of the word गी, cf. गी: इत्यस्य शब्दस्य गावी गोणी गीता गोपीतलिका इत्यस्य शब्दस्य गावी गोणी गीता गोपीतलिका इत्यस्य अपभ्रंशाः M. Bh. on I. 1.1; cf. शब्दसंस्कारहीनो यो गीरिति प्रयुग्धिते । तमपभ्रंशमिच्छन्ति विशिधार्थनिविशाम् Vāk. Pad I.149; सर्वस्य हि अपभ्रंशस्य साधुरेय प्रकृतिः com. on Vak. Pad I. 149.

अपवर्ग achievement; cf. पळप्राती सत्यां कियापस्तिमाति: अपवर्ग: sec Kās. on अपवर्गे तृतीया P. II.3.6.

अपवर्ण a letter which is phonetically badly or wrongly pronounced. cf. कुर्ताथादागतं दग्धमपवर्णे च भित्रतम्। न तस्य पाठ भेक्षोस्ति पापाहेरिव किल्वियात् Pāṇ. Sīk. 50.

अपवाद a special rule which sets aside the general rule; a rule forming an exception to the general rule. e. g. आतोनुपसर्ग क: III. 2. 2 which is an exception of the general rule कर्मण्यम् III. 2. 1; cf. यन नामातो

यो विधिरारम्यते स तस्य वाधको भवति, तदपवा-दांत्रं यागा भवति; Pari. Sekh. Pari 57; for details see Pari. Sekh. Pari. 57-65; cf. न्यायेभिश्रानपवादान् प्रतीयात् । न्याया उत्सर्गाः महाविधयः । अपवादा अल्प-विषयाः विश्वयः । तानुत्सर्गण भिश्रानकीकृताञ् जानीयात् । अपवादाविषयं मुक्त्वा उत्सर्गाः प्रवर्तन्त इत्यर्थः । K. Pr. I. 23 and com. thereon; (2) fault; cf. द्यास्त्रा-पवादात् प्रतिपत्तिभदात्... R. Pr. XIV. 30 on which उत्यट remarks द्यास्त्राणाम-पवादा दोषाः सन्ति पुनक्तत्तता अविस्पर्धार्थता, कट्याव्दता...

अपनाइन्याय the convention that a rule laying down an exception supersedes the general rule; cf. निद्धं लग्धादन्यायेन P. I.3.9 Vart. 7

अपनाद्वलीयस्त्व the convention that a special rule is always stronger than the general rule.

अपवादविप्रतिषेष्र a conflict with a special rule, when the special rule supersedes the general rule; cf. 'अलान्त्यस्य' इति उस्तर्गः । तस्य 'आदे: परस्य' 'अनेकार्शिनसर्वर्म्य' इत्यपवादी अपवादिव्यतिपेशासु सर्विदेशो भविष्यति । M. Bh. on I.1.54 Virt. 1.

अपत्रुक्त that which has already happened or taken place; cf. न्यास्या स्थेपा भृतकालता । कुतः । आययवर्गात् । आदि-स्त्रापयुक्तः । एप्र च नाम न्यास्यो भृतकालो अव किंचिदपत्र्यतं हस्यते M.Bh. on III.2.102

अपराब्द corrupt form of a correct word, called क्लिश also; cf. क्लिशे ह वा एव यदपशस्द: M. Bh. on I. 1.1. अस्तु वापि तरस्तन्माद नापशब्दो भविष्यति । वाचकश्चेत्रयोगनन्यो वाचकश्चेत्रयुःयताम् ॥ M. Bh. on V. 3. 55.

अपाणिनीय not in conformity with the rules of Pāṇini's grammar; cf. विध्यत्वेवभपाणिनीयं तु भवति M. Bh. on I. 1. 1.

अपादान detachment, separation, ablation; technical term for अपादानकारक which is defined as ध्रुवमपायेऽपादानम्

in P. I. 4.24 and subsequent rules 25 to 31 and which is put in the ablative case; cf. अपादाने पञ्चमी P. II. 3.28.

अपाय (1) point of departure, separation; cf. ध्रुवमपायेपादानम् P. I. 4.24; (2) disappearance; cf. संनियोगशिष्टानामन्यतरापाये उभयोरप्यपाय:। तद्यथा। देवदत्तपज्ञदत्ताभ्याभिदं कर्म कर्तव्यम् । देवदत्तापाय यज्ञदत्तीपि न करोति M. Bh. on IV.1.36.

अपार्थक without any purpose or object, useless; cf. ततोनिशदर्शनादपार्थक- मतत् Nyāsa on P. I. 4.80.

अपि also, in addition to; अपि is used sometimes to mean absolute of or unqualified by any condition; cf. अन्यम्योपि दृश्यते । अपिशृह्दः सर्वापाधिव्यमिन्वारार्थः । निरुपपदादिप भवति । धीवा पाँवा । Kās. on P. III. 2.75, III. 2.101, VII. 1.38; cf. अपिग्रहणं व्यमिन्वारार्थम् । Durgasimha on Kāt. II. 3. 64.

अपित् not marked with the mute letter प. A Sārvadhātuka affix not marked with mute प is looked upon as marked with इ and hence it prevents the guṇa or vṛddhī substitution for the preceding vowel or for the penultimate vowel if it be अ. e. g. दुस्तः तनुतः, दुविन्त where no guṇa takes place for the vowel उ cf. सार्वधातुकमापित्. P. I. 2.4.

अपूर्व (1) not existing before; cf. आगमश्च नाम अपूर्व: राब्दोपजन: M. Bh. on I.1.20, I.1.46; (2) not preceded by any letter or so, cf. अपूर्वलक्षण आदि: M. Bh. on I.1.21; (3) a rule prescribing something not prescribed before; cf. तज्ञ अपूर्वो विधिरस्तु नियमोस्तु इति अपूर्व एव विधिभीवष्यित न नियम: M.Bh. on I.4.3., III.1.46, III.2.127, III.3.19.

अपृक्त lit. unmixed with any (letter); a technical term for an affix consisting of one phonetic element, i.e. of a single letter. cf. अपृक्त एकाल्प्रत्यय: P. 1. 2.41.

अपेक्षा relation of dependance; cf. अयुक्तैवं बहुनोपेक्षा M. Bh. on IV. 2.92.

अपोद्धार disintegration of the constituent elements of a word; analysis; अपोद्धार; पृथक्करणम् com. on Vāk. Pad. II. 449; cf. अपोद्धारनदार्था ये ये चार्था: स्थितलक्षणा: Vāk. Pad. I.24.

अप्यद्शिक्त, अप्यद्शिक्त A famous versatile writer of the sixteenth century A. D. (1530-1600), son of रङ्गराजाध्यरान्द्र a Dravid Brahmana. He wrote more than 60 smaller or greater treatises mainly on Vedanta, Mīmāmsā, Dharma and Alamkāra śāstras; many of his works are yet in manuscript form. The Kaumudī-prakāśa and Tinantaśeṣasamgraha are the two prominent grammatical works written by him. Pandit Jagannātha spoke very despisingly of him.

अप्रकृतिस्वरत्व non-retention of the original word accents; cf. तज्ञ यस्य गतर-प्रकृतिस्वरत्वं तस्मादन्तादात्वं प्राप्नाति M. Bh. on VI.2.49. See the word प्रकृतिस्वरत्व.

अप्रातिपाचि (1) impossibility to obtain the correct form; (2) absence or want of apprehension, of राज्यानां चाप्रतिपत्तिः प्राप्तोति M. Bh. on I. 1.1, I. 1. 44 Vart. 8.

সমনিষ্য useless prohibition; unnecessary prohibition; cf. অন্থক: সনিষ্য: সমনিষ্য: সমনিষ্য: M. Bh. on I. 1.6; I. 1. 20. I. 1. 22 etc.

अप्रत्यय (1) lit. absence of any affix; an affix such as किप् or किन् which wholly vanishes; cf. पिपठिषते: अप्रत्ययः पिपठी: M.Bh. on I. 1.6. कण्डूयतेरप्रत्ययः कण्डू: M. Bh. on I. 1.58; (2) that which is not an affix. cf. अप्रत्ययस्थताः संज्ञा मा भूवन् M. Bh. on I. 1. 61, I. 1.69; (3) that which is not prescribed, अधियोयमान,अप्रत्याय्यमान; M.Bh. on I. 1. 69.

अप्रधान (1) non-principal, subordinate, secondary, cf. अप्रधानमुपसर्जन- मिति, M. Bh. on I. 2.43; (2) non-essential, non-predominent, cf. सहयुक्तेऽप्रधान P. II. 2.19 and the instance पुत्रेण सहागत: पिता । Kas. on II. 2.19.

अप्रयुक्त not found in popular or current use, e.g. the words ऊन, तेर, धक etc. यद्यध्यप्रयुक्ता अवस्य दीर्धसत्त्रवळ्ळाणनानु- विधया: M. Bh. on I. 1. 1, also यथाळळ्ळामप्रयुक्ते M. Bh. on I. 1. 24

अप्रयोग (1) non-employment of a word in spite of the meaning being available; cf. संभावनेलमित चितिद्धाप्रयोग P. III.3. 154; (2) non-employment cf.उक्ताथानामप्रयोग: a standard dictum of grammar not allowing superfluous words which is given in M.Bh. on P.I.1.44 Vart. 16 and stated in Candra and other grammars as a Paribhāṣa.

अप्रयोगिन not-found in actual use among the people although mentioned in the śāstra-texts; a mute indicatory letter or letters. cf. अप्रयोगी इत् Sāk. I. 1.5 Hem I. 1.37 Jain. I.2.3 and M.Bh. Pradīpa on III. 8. 31.

अप्रसङ्ग non-application of a rule of grammar or of a technical term; cf. अन्यत्र सह्वचनात् समुदाये संज्ञाऽप्रसङ्गः M. Bh. on P. I. 1. 1 Vart. 11.

अप्रासिद्ध Not well-known; secondary (used in connection with sense) cf. एवं चाप्रसिद्धत्वं गौणलाक्षणिकत्वं चाग गौणत्वम् Par. Sek Parī. 15

अप्रासिद्धि absence of clear sense or interpretation; cf. इतरतराश्रयत्वादप्रसिद्धिः M. Bh. on I. 1.1. Vart. 8, I. 1. 38 Vart. 4.

अप्राप्तिकित्प same as अप्रातिवभाषा one of the three kinds of optional application of a rule; cf. निसंदायास्तु भवन्ति प्राप्ते अप्राप्ते उभयत्र चिति । M. Bh. on P. I. 1.44 Vart. 20; optional application of a rule prescribing an operation; e.g. ऊर्णतिर्विभाषा. अनुपसर्गोद्वा I. 3. 43. हकोरन्यतरस्याम् । अभिवादयति गुरुं माणवेकन पिता । अप्रातिविकत्यत्यापृतीयव Kās. on I.1.53. विभाषा सपूर्वस्य । स्यूलपति; स्यूलपत्नी । अधातिविभाषेयसयप्रसंयोगत्यात् ।

সমামন্ত্রিয়ান prescription of a new thing. cf. বন্নামানন্ত্রিয়ান মানমন্ত্রিয়া M. Bh. on VI. 4.171 Vart. 2.

স্মান্তবিখি prescribing an operation which otherwise cannot be had. স্মাবিত্যমানিবিধ: ধনালগ্রনিব্য: P. III. 4. 24 Vārt 1.

अप्राप्तिविभाषा see above अप्राप्ताविकत्य.

अप्राप्ति (1) non-occurrence or non-realization of a grammatical operation or rule— अप्राप्तिकेशः M. Bh. on I. 156 Värt. 8; (2) prohibition of the occurrence of a rule or operation, cf. अप्राप्तिकी । अथवानन्तरा या प्रतिः सा प्रतिपिथ्यंत M. Bh. on I 1. 43, I. 1. 63.

अप्दुत non-protracted vowel cf. अता रारच्छ्रनादच्द्रते P. VI. 1. 113.

अवाधक not coming in the way of rules otherwise applicable; the word is used in connection with निपातन i. e. constituted or announced forms or specially formed words which are said to be saugat i.e. not coming in the way of forms which could be arrived at by application of the regular rules. Siradeva has laid down the Paribhāsā अवाधकान्यपि निपातनानि भवन्ति defending the form प्रातन in spite of Panini's specific mention of the word पुराण in the rule पुराणके।क्तिपुर IV. 3. 105.

अभक्त not-forming an integral part of another; quite independent (used in connection with augments). cf. कि पुनर्य पूर्वान्त आहास्थित् परादिराहोस्थिद् अमकाः M. Bh. on I. 1. 47, I.1.51. एवं तहाभक्तः करिप्यतं M. Bh. on VI. 1.71, VI. 1.135, and VII. 2.82.

अभयजन्द्र a Jain grammarian who wrote प्रक्रियासंग्रह, based on the Sabdānusāsana Vyākaraņa of the Jain Sākatāyana. His possible date is the twelfth century A. D.

अभयतिलक a Jain writer of the thirteenth century who wrote a commentary on the Śabdānuśāsana Grammar of Hemacandra.

अभयनान्दिन् a reputed jain Grammarian of the eighth century who wrote an extensive gloss on the जेनेन्द्रज्याकरण. The gloss is known as जेनेन्द्रज्याकरणमहावृत्ति of which बृहज्जेनेन्द्रज्याकरण appears to be another name.

अभाव absence; absence of any following letter which is technically called avasāna. cf. विरामोऽवसानम् । वर्णानामभावोऽवसानसंज्ञ: स्यात् S. K. on P. I. 4.110.

अभाषित पुंस्क that which does not convey a masculine sense; a word which is not declined in the masculine gender; a word possessing only the feminine gender e.g. खड्डा, लता etc. cf. अभाषितपुंस्का P. VII. 3. 48.

अभिकृति a variety of long metres called अतिच्छन्द्स; it consists of 100 syllables. cf. अभिकृति:— देवा अग्नि: स्विष्टकृत R. Pr. XVI. 60.

अभिक्रम the first of the two utterances of a word which characterise the krama method of recital; e. g. in the krama recital of प्रण इन्दो etc. प्रण: । न इन्दो । the first recital प्रण: is called अभिक्रम, or प्रथमचचन while न इन्दो is called द्वितीयवचनः cf. अभिक्रमे पूर्वविधानमाचरेत् पुनर्बुवंस्त्तरकारितं क्रमे R. Pr. XI.21.

अभिघात depression or sinking of the voice as required for the utterance of a circumflex vowel. अभिधान designation, denotation, expression of sense by a word which is looked upon as the very nature of a word. The expression अभिधानं पुनः स्वामाविकम् (denotation of sense is only a natural characteristic of a word) frequently occurs in the Mahābhāsya; cf. M. Bh. on I.2.64 Vārt 93, II. 1.1, cf. नपुंसकं यदूष्मान्तं तस्य बह्वभिधानजः (R. Pr. XIII.7) where the word बह्वभिधान means बहुवचन.

अभिधेय object or thing denoted by a word; sense of a word; cf. आभि-धेयवाहिः ङ्गवचनानि भवन्ति M. Bh. on II. 2. 29.

अभिनिधान lit. that which is placed before; the first near ordoubled class consonants: mute or sparsa consonant arising from doubling and inserted before a mute; cf. अधो-षादृष्मण: पर: प्रथम: अभिनिधान: स्परीपरात्तस्य संस्थान: (T. Pr. XIV. 9.) explained by त्रिभाष्यरत्न as स्पर्शपरादघोषाद्रव्मणः परः प्रथम आगमस्तस्य स्पर्शस्य समानस्थानः अभिनिधानो भवति । अभिनिधीयते इत्यमि-निधानः आरोपणीयः इत्यर्थः । यथा यः क्कामयेत अदम्म वर्जम् । यः प्याप्मना । The Prātiśākhya explains the term अभिनिधान somewhat differently: cf. अभिनिधानं कृतसंहितानां स्पर्शान्तःस्थानामषवाद्य रेफम् । संघारणं संवरणं श्रुतेश्च स्पर्शोदयानामपि चावसान R. Pr. VI. 5, explained by उब्बट as स्पर्शपराणां स्पर्शानां रेफं वर्जयित्वा अन्तःस्थानां च वर्णानां कृतसंहितानां च सतां संघारणं वणश्रतेश्च संवरणं भवति । तदेतद् अभि-निधानं नाम। यथा उप मा षड् द्वा द्वा। ऋ. सं ८।६८।१४ इह षड्ड इत्यत्र आमिनिधानम् ॥ अमिनिधान possibly according उब्बंद here means the first of the doubled letter which, although the second letter is attached to it, is separately uttered with a slight pause after it. अभिनिधान means, in short, something like 'suppression.'

The Rk. Tantra takes a still wider view and explains अभिनिधान as the first of a doubled consonant. cf. अभिनिधान: । कमजं च पूर्वीन्तजस्वरं भवति । R. T. 21.

अभिनिर्द्वाति development of an activity; manifestation; cf. ह्रव्यपु कर्म-चोदनायां द्रयोरेकस्याभिनिर्द्वितिर्भवति M. Bh. on VI. 1.84.

अभिनिविष्ट that which has already entered on functioning or begun to function; cf. स्थानवत एतेवां शब्दानां एतेव्बर्थेषु अभिनिविश्वानां निक्षित्रत्येन अन्वास्यानं कियते। M. Bh. on II. 1.1. cf. पूर्वमपवादा अभिनिविश्वन्ते पश्चादुत्सर्गाः, M. Bh. on II. 3.46; Pari. Sek. Pari. 62.

अभि।निष्टान Resonance (of a visarga utterance).

अभिनिहित used in connection with a सन्धि or euphonic combination in which the vowel अ, as a first or a second member, is absorbed into the other member. e. g. रथेग्यः + अमे = रथेम्याऽमे also दागुषेडमे, where अ of अमे is absorbed or merged in ओ of रथम्यः or ए of दागुषे; cf. अथा-भिनिहितः संधिरतैः प्राकृतवैद्वतैः । एकाम्वित पादादिरकारस्तेत्र संधिजाः; R. Pr. II. 13 to 25; cf.एङ: पदान्तादित P. VI. 1. 109.

अभिनिहितस्वार name given to the circumflex vowel which is the resultant of the अभिनिहित्तंथि.

अभिप्राय (1) अभिप्रायसंधि a kind of euphonic combination where the nasal letter न् is dropped and the preceding vowel (आ) is nasalised e.g. दघन्वाँ यः। स्ववाँ यातु। (2) view, purpose, intention; cf. तद् व्यक्तमाचार्यस्थाभिप्रायो गम्यत, इदं न भवतीतिः M. Bh. on I.1.27; cf. also स्वरिताञ्चतः कर्जभिप्राये कियाफ P. I.3.72.

अभिविधि inclusive extension to a particular limit; inclusive limit; cf. आङ् मर्यादाभिविष्याः P. II.1.13, आङ् मर्यादाभिविष्योरिति वक्तव्यम् M. Bh. on I.4.89; (2) full or complete exten-

sion cf. अभिविधो भाव इनुण् । अभिविधिर-भिव्यातिः । सांसादिणं वर्तते Kās. on P. III. 3.44.

आसिन्यादान absorption of a vowel when two long vowels of the same kind come together c.g. ता आनः = तानः, अवसा आ = अवसा, the resultant vowel being pronounced specially long consisting of one more matra, which is evidently, a fault of pronunciation. cf. आदानं आरम्भः; विपृत्तं विशालं या आदानं व्यायानम् । अभिन्यानं अभिन्यादानम् Uvvata on R. Pr. XIV. 27.

अभिन्धाहार expression; cf. यदेव समाने पादे समानाभिज्याहारे भवति तःज्ञानि भवति । हिरण्य-स्पः स हिरण्यसंदृक् Nir X.16.

अभिसारिणी name of a metre in which two feet have ten syllables and the other two have twelve syllables; cf. बेराजजागते: पाइंबी वाचेत्यगि-सांगि R. Pr. AVI. 43.

आभिस्वरित provided with a svarita or circumflex accent.

अभिहित expressed (used in connection with the sense of a word) एतेनेवाचित्र सूत्रेण M. Bh. on I.2.64, I.3.1; expressed actually by a word or part of a word, same as कथित M. Bh. on I.4.51.

अभूततन्त्राच being what it was not before, cf. ভিৰিখা अभृतकद्वाबग्रहणस् P. V.4.50 Värt. 1.

अभेद्क not bringing about a difference; not making different; non-discriminant;cf. गुणा अभेदका: Par.Sek. Pari. 109 cf. मनु च भो अभेदका अपि च गुणा इक्यते M. Bh. on I.1.1.

अभेद्संसर्ग a connection of unity, as noticed between the nominative case affix of the subject and the ending ति of a verb, which produces the sense.

अभेदान्वय relation of non-difference as stated by the Vaiyakaranas between an adjective and the substantive qualified by it. e, g. নাল্যদ্বলন্তম্ is explained as নাল্যাদিলদ্বলন্তম্.

अभ्यन्तर interior; contained in, held in; cf. अभ्यन्तरश्च समुदाये अवयवः । तद्यथा वृक्षः प्रचळन्तहावयवैः प्रचळति M. Bh. on I.1.56.

Abhyankar 1785-1870 A. D.) an eminent scholar of Sanskrit Grammar who prepared a number of Sanskrit scholars in Grammar at Sātārā. He has also written a gloss on the Paribhāsendusekhara and another one on the Laghu-Sabdendusekhara.

(VASUDEVA SHASTRI Abhyan-kar 1863-1942 A. D.) a stalwart Sanskrit Pandit, who, besides writing several learned commentaries on books in several Sanskrit Shastras, has written a commentary named 'Tattvādarśa' on the Paribhūśenduśekhara and another named 'Gūḍhārthaprakūśa' on the Laghuśabdenduśekhara.

(KASHINATH VASUDEVA Abhyankar, 1890-) a student of Sanskrit Grammar who has written महाभाष्यप्रस्तावना — स्वण्ड, and जेनेन्द्रपरिभाषावृत्ति and compiled the परिभाषासंग्रह and the present Dictionary of Sanskrit Grammar.

अभ्यम् substitute for dat. and abl. pl. affix भ्यस् after the words युग्मद् and अस्मद्; cf भसोऽभ्यम् P. VII.1.30.

अभ्यस्त repeated, redoubled word or wording or part of a word. The term अभ्यस्त is applied to the whole doubled expression in Pāṇīnis grammar, cf. उमे अभ्यस्तम् P. VI.1.6: (2) the six roots with जक्ष placed at the head viz. जक्ष, जागृ, दरिश, चकास, शास, दीधी and बेबी which in fact are reduplicated forms of घस, गृ, हा, कास, शस, भी and बी.

अभ्याद्वाचि inclination towards an action; tendency to do an act; cf. संख्याया: कियाभ्यावृत्तिगणने कृत्वसुच् । P. V. 4.17 अभिमुखी प्रवृत्तिरभ्याद्वाति: (M. Bh. on V.4.19) is the explanation in the Mahābhāṣya, while पोन: पुन्यमभ्यावृत्ति: (Kās. on V.4.17) is the one given in Kāsikā.

अभ्यास lit, doubling or reduplication; technically the word refers to the first portion of the reduplication, which is called the reduplicative syllable as opposed to the second part which is called the reduplicated syllable; cf. पूर्वोभ्यास: P. VI. 1.4. (2) Repetition, the second part which is repeated; cf. दोऽभ्यासे(R.T.165) explained as दकार: अभ्यासे लुप्यते । पटपयेति । इसद् सेति ।; (3) repeated action; cf. अभ्यास: पुन: पुन: करणमावास: Kās. on P. I-3. 1.

अभ्याहत omission of any sound; a fault of utterance.

अम् (1) a technical brief term in Pāṇīni's grammar including vowels, semi-vowels, the letter ह् and nasals; (2) a significant term for the accusative case showing change or substitution or modification; cf. अ विकारस्य T. Pr. I.23 explained as अभिति शब्दो विकारस्यास्य, भवति। अभिति द्वितीय विभक्तेस्पळ्थणम्। (3) augment अ applied to the penultimate vowel of मृत & हश् (P. VI.1.58, 59 and VII.1.99) (4) substitute for 1st pers. sing. affix भिष्. by P. III.4 101 (5) Acc. sing. case affix अम्.

अमर called अमरसिंह ancient an in the grammarian mentioned काविकल्पद्रम by बे पदेव. believd to have some written works on grammar, such as ক্ষত্রণ his famous existing work, however, being the Amarakosa or Nāmalingānusāsana.

- अमरचन्द्र a Jain grammarian who is believed to be the writer of स्यादिशन्दसमुच्चय, परिमल etc.
- अमु tad. affix अम् applied in Vedic Literature to किम्, words ending in ए, indeclinables and the affixes तर and तम; e. g. प्रतरं नयाम: प्रतरं वस्यः cf. अमु च च्छन्दिस P. V. 4.12.
- अमृतभारती a grammarian who is believed to have written सुबोधिका, a gloss on the सारस्वतब्याकरण.
- अमृतस्मृति called also अमृतस्नृति, a commentary on the प्रक्रियाकोमुदी of रामचन्द्रशेष.
- স্থাটার্ঘর্ষ A Jain grammarian of the ninth century who wrote the gloss known as স্থামান্ত্রান on the Sabdānusāsana of Sikatāyana; the ন্থান্ত is quoted by মাধ্য in his ধান্তব্যন্তি.
- अमोघा also अमोघाद्यति, a gloss on the grammar of Sīkaṭāyana. See अमोघ-वर्ष above.
- অম্বানর্সী a commentary on Nāgeśa's Paribhāṣenduśekhara named so, as it commences with the words স্থান্য ক্রী etc.
- अम्बूकत utterance (of words) accompanied by water drops coming out of the mouth; a fault of utterance or pronunciation; मुखात विप्रुषो निर्गमनम्. It is explained differently in the Rk. Pratisakhya; cf. ओष्ठाभ्यां नद्धं अम्बूकृतम् (R. Pr. XIV.2.) held tight between the lips which of course, is a fault of pronunciation; cf. प्रस्तं निरस्तमाविलाभितं निर्हतं अम्बूब्र तैं भातम्यो विकम्पितम्. MBh. I. 1. परपशाहिक.
- अय् (1) substitute for the causal sign णि before आम्, अन्त, আন্ত etc. by P. VI. 4.55 (2) substitute for ए before a vowel by P. VI. 1.78.
- अयङ् the substitute अय for the final ई of the root शो by P. VII. 4.22.

- अयज् tad. affix अय substituted optionally for तय after द्वि and त्रि by P. V.2.43. e.g. इयन, द्वितयम; अयम् त्रितयम,
- अयाञ्,अयाद् substitutes for inst. sing affix हा in Vedic Literature. e. g. स्वप्रया, नावया.
- अयावन non-mixture of words where the previous word is in no way the cause of (any change in) the next word. अयावन अमिश्रक्त Uv. on R. Pr. XI. 12 e.g. अग्रिमीके where the क्रमपाठ is अग्रिंगेके ।
- अयुज् a term applied to the odd feet of a stanza; cf युग्माव अपरी पादावयुकी हादशाक्षरी । या सतीवृह्ती नाम R. Pr. XVI. 39.
- अयोगवाह the letters or phonetic elements अनुस्वार, विभर्ग, जिद्यामृत्याय, उपभ्यानीय and यम called so, as they are always uttered only in combination with another phonetic element or letter such as अ or the like, and never independently; cf. अकारादिना वर्णममा- स्रायेन संहिताः सन्तः य वहन्ति आसमलाभं ते अयोगवाहाः Uvvața on Văj. Pr. VIII. 18. These अयोगवाह letters possess the characteristics of both, the vowels as well as consonants: cf. अयोगवाहानामत्म उपदेशः कर्तव्यः णव्यं प्रयोगनम्। दार्षु जम्मावन्से प्रयोजनम्। M. Bh. on शिवस्य इस्वरूट.
- अर a technical term for Ardhadhatuka affixes in the Mugdhabodha grammar.
- अरक्तसन्धि a word, the coalescence of which is not nasalized, as the word आ in मन्त्रमा बेरण्यम् as contrasted with अभ्र आ अप:; cf. R. Pr. XI-18.
- अरङ् a Visarga which is not rhotacized; the term अरिपित is used in the same sense.
- अरिफित not rhotacized; not turned into the letter र; cf. विसर्जनीयोऽरिफिता दीर्घपूर्व: खरादयः आकारम् । R. Pr II. 9.

अरीहणादि a group of words given in P.IV. 2.80 which get the taddhita affix बुज् (अक) added to them as a cāturarthika affix e.g. आरीहणकम, द्रौवणकम् etc.see Kāśikā on P.IV.2.80.

अर्क the strong blowing of air from the mouth at the time of the utterance of the surd consonants; cf Vāj. Sikṣā. 280.

अर्थ (1) lit.signification, conveyed sense or object. The sense is sometimes looked upon as a determinant of the foot of a verse; cf. प्रायोशी वृत्तमित्येते पादज्ञानस्य हेतव: R. Pr. XVII 16. It is generally looked upon as the determinant of a word (पद). A unit or element of a word which is possessed of an independent sense is looked upon as a Pada in the old Grammar treatises: cf. अर्थः पदमिति ऐन्द्रे; cf. also अर्थः पदम् V. Pr. III.2, explained by 3592 as अर्थाभिधायि पदम् । पद्यते गम्यते ज्ञायतेऽर्थी-नेनेति पदम् । There is no difference of opinion regarding the fact that, out of the four standard kinds of words नाम, आख्यात, उपस्री and निपात, the first two kinds नाम and आख्यात do possess an independent sense of their own. Regarding possession of sense and the manner in which the sense is conveyed, by the other two viz. the Upasargas (prepositions) and Nipātas (particles) there is a striking difference of opinion among scholars of grammar. Although Pāṇini has given the actual designation पद to words ending with either the case or the conjugational affixes, he has upon the different units or elements of a Pada such as the base, the affix, the augment and the like as possessed of individually separate senses. There is practically nothing in Pānini's sūtras to prove that Nīpātas and Upasargas do not possess an independent sense. Re: Nipātas, the rule न्वादयोऽसन्वे, which means that a and other indeclinables are called Nipātas when they do not mean सन्त, presents a riddle as to the meaning and the like should which convey if they do not mean सत्त्व or द्रब्य i. e. a substance. Nipātas cannot mean भाव or verbal activity and if they do not mean सत्त्व or द्रब्य, too, they will have to be called अन्धेक (absolutely meaningless) and in that case they would not be termed Prātipadīka, and no caseaffix would be applied to them. To avoid this difficulty, the Vartikakāra had to make an effort and he wrote a Vārtika निपातस्य अनर्थकस्य प्रातिपदिकत्वम । P. I.2.45 Vār. 12. As a matter of fact the Nipātas ব, বা and others do possess a sense as shown by their presence and absence (अन्वय and व्यतिरेक). The sense, however, is conveyed rather in a different manner as the word समृह, or समदाय, which is the meaning conveyed by च in ব্যম: কুজ্ঞা, cannot be substituted for \(\foatsize \) as its synonym in the sentence যুদ: কুল্মপ্স. Looking to the different ways in which their sense is conveyed by nouns and verbs on the one hand, and by affixes, prepositions and indeclinables on the other hand, Bhartrhari, possibly following Yaska and Vyādi, has developed theory of द्यातकस्व as contrasted with वाचकत्व and laid down the dictum indeclinables, affixes prepositions (उपसर्गंड) do not directly convey any specific sense as their own, but they are mere signs to show some specific property or excellence of the sense conveyed by the word to which they are

attached; cf. also the statement ' न निर्वेद्धा उपसर्गा अर्थानिसहरिति दाविटायनः नामाख्यातयोस्त करोविसंयोगचीतका भवानत । Nir I.3. The Grammarians, just like the rhetoricians have stated that the connection between words and their senses is a permanent one (नित्य), the only difference in their views being that the rhetoricians state that words are related, no doubt permanently, to their sense by means of संकेत or convention which solely depends on the will of God, while the Grammarians say that the expression of sense is only a natural function of words; cf. 'अभिधान पुनः स्वामाधिकम् ' Vārttika No.33. on P. I.2.64. For द्यातकत्व see Vakyapadīya of Bhartrhari II. 165-206.

अर्थगति comprehension of sense; cf. अर्थगत्यर्थः शब्दप्रयोगः अर्थ संप्रत्यायिष्या-मीति शब्दः प्रयुज्यते । M. Bh. on P. I. 1.44, III.1.7 etc.

अर्थग्रहण use of the word 'अर्थ'; cf. अर्थग्रहणं करोति तज्ज्ञापसत्यान्त्रार्थः M. Bh. on I.1.11.

अर्थनिर्देश mention or specification of sense. cf. अवस्यमुत्तरार्थमर्थनिर्देश: कर्तव्य: M. Bh. IV.1.92.

अर्थवर्ग्रहणपरिभाषा a well known maxim or Paribhāṣa of grammarians fully stated as अर्थवर्गर्ग नानर्थ-कस्य ग्रहणम्, deduced from the phrase अर्थवर्गर्गात् frequently used by the Vārttikakāra. The Paribhāṣā lays down that 'when a combination of letters employed in Grammar, is possessed of a sense, it has to be taken as possessed of sense and not such an one as is devoid of sense.'

अर्थाभिधान conveyance or expression of sense, cf. अर्थाभिधानं पुनः स्वाभाविकम् P. I.2.64 Vart. 33. It is only a nature of words that they convey their sense.

अर्थेक a fault in the utterance of a vowel of the kind of abridgment of a long utterance. अर्थहरस्म explained as हस्सस्यार्थम्—half the utterance of the short vowel; cf.तस्यादित उदात्तमर्थहस्सम् P. I.2.32. cf. also तस्यादिर्श्यस्तरामुदात्तादनन्तरे। यावदर्दे हस्यस्य Tai. Pr. I.44.

अर्धेजरतीय a queer combination of half the character of one and half of another, which is looked upon as a fault; cf. न चेदानीमर्थनस्तीयं लभ्यं चृद्धिमें मिविष्यति स्वरो नेति। तद्यथा। अर्धे जरस्याः कामयते अर्ध नेति; M.Bh. on IV. 1.78; cf. also अर्ध जरस्याः पाकाय अर्धे च प्रसवाय।

अर्थमात्रा half of a mātra or 'mora'., cf. अर्थमात्रालाध्येन पुत्रोत्सवं मन्यन्ते वेयाकरणाः Par. Sekh. Pari. 122, signifying that not a single element of utterance in Paṇīni's grammar is superfluous. In other words, the wording of the Sūtras of Paṇini is the briefest possible, not being capable of reduction by even half a mora.

अर्थमातिक taking for its utterance the time measured by the utterance of half a mātrā or mora; a consonant, as it requires for its utterance that time which is measured by half a mātrā (mātrā being the time required for the utterance of short अ); cf. R. Pr. I.16, T. Pr.I.37, V. Pr. I.59.

अर्घेचोदि a group of words given in P. II. 4.31 which are declined in both-the masculine and the neuter genders; e.g. अर्धनी:, अर्धनीम : यूथा, यूथम; यहः परम, etc.; cf अर्धनी: पुंसिन्न P. II. 4.31.

अर्घविसर्ग a term used for the Jihvāmūliya and Upadhmānīya into which a visarga is changed when followed by the letters इ, ख, and the letters १, ६ respectively.

- अर्थहरूबोदात्त the acute (उदात्त) accent which becomes specially उदात्त or उदात्ततर when the vowel, which possesses it, forms the first half of a खरित vowel.
- अर्शआदि a class of words which take the taddhita affix अच् (अ) in the sense of the affix मतुप् i.e. in the sense of possession; cf. अर्ज्ञाल अस्य विद्यन्ते अर्ज्ञाल: । उरसः । आङ्गतिगणश्चायम् यत्राभित्रक्ष्पेण राज्देन तद्वतोभिधानं तत् सर्वभिद्द द्रप्रक्यम् Kas. on P. V. 2.127.
- अल् a प्रत्याहार or a short term signifying any letter in the alphabet of Pāninī which consists of 9 vowels, 4 semi-vowels, 25 class-consonants, and 4 sibilants.
- अलक्षण that which is not a proper लक्षण i. e. Sūtra; a Sūtra which does not teach definitely; a Sūtra which cannot be properly applied being ambiguous in sense. cf. ब्याख्यानतो विशेषप्रतिपत्तिनीह संदेहादलक्षणम् Par. Sek. Pari. I.
- अलाक्षणिक (1) not used in a secondary sense; (2) not accomplished by the regular application of a grammar rule; cf. निपातनै: सह निर्देशादत्रापि किंचिदला- क्षणिकं कार्यमस्ति Kās. on III.2.59.
- अिक्ष्म (1) not possessed of a definite gender; cf. अलिङ्गमसंख्यमन्ययसंत्रं भवति M. Bh. on I.1.38; II.4.82;(2)आङ्क्षे ह्याप्म-दस्मदी (Sid. Kau. on P.VII. 2.90)
- अिङ्गचन not possessed of a definite gender and number; a term generally used in connection with अन्ययुड or indeclinables.
- अलुक् absence of elision or omission.
- अञ्चलसमास a compound in which the case-affixes are not dropped. The Aluk compounds are treated by Pāṇini in VI.3.1 to VI.3.24.

- अलोन्त्यिविश्वि an operation, which, on the strength of its being enjoined by means of the genitive case, applies to the last letter of the wording put in the genitive; cf. नानर्थकेलोन्त्यविश्वरनम्यास्थिकार M. Bh. on I.1.65; cf. अलोन्त्यस्य । षशीनिर्दिशेन्त्यस्यादेश: स्यात् S.K. on P. I.1.52.
- अलोप absence of elision of an affix etc. cf. सुप: अलोप: भवति वाक्ये। राज्ञः पुरुष इति। M. Bh. on II.1.1.
- अलोकिकिविश्वह the dissolution of a compound not in the usual popular manner. e. g. राजपुरुष: dissolved as राजन् इस पुरुष सु, as contrasted with the लोकिकिविश्वह viz. राज्ञ: पुरुष: I see also अधिहरि dissolved as हरि डि. in the अलोकिकविश्वह.
- अरुग्रहण (1) the word अन् actually used in Pāṇinī's rule e.g. अपृक्त एकाल् प्रत्यय: P.I.2.41. (2) the wording as अल्, or wording by mention of a single letter; e.g. अचि शुधातुसुवांको: P. VI.4.77.
- अल्पतर feebler effort required in the production of sound or in the utterance of a letter cf. तैराज्यज्ञनपाद. चुत्त्योरस्पतर; (प्रयत्न:) Tait. Pr.XX.12.
- अल्पप्रयोग not of frequent occurence in the spoken language or literature the term is used in connection with such words as are not frequently used; cf.सन्त्यस्पप्रयोगाः इताच्यैक-पदिकाः । त्रंततिर्दम्नाः जाट्य आट्णारा जागरूको द्विंहोमीति Nīr I.14.
- अरुपमाण (1) non-aspirate letters; letters requiring little breath from the mouth for their utterance as opposed to mahāprāṇa; (2) non-aspiration; one of the external articulate efforts characterizing the utterance of non-aspirate letters.
- अल्पान्तर having a smaller number of vowels in it; such a word is generally placed first in a Dvandva compound; cf. अल्पान्तरम्, P.II.2.34.

अस्पान्तरं पूर्वे भवति प्लक्षन्यग्रोधाः; अस्पान्तर is the same as अस्पान्क used in the प्रक्रियाकौमुदी or अस्पस्वरतर in Kutantra (Kāt. II. 5.12).

अल्पापेक्ष an operation requiring a smaller number of causes, which merely on that account cannot be looked upon as अन्तरहा. The antaranga operation has its causes occurring earlier than those of another operation which is termed बाहरङ्ग cf. बहिरङ्गान्तरङ्गशान्दाभ्यां बहुपेक्षत्वाल्पा-पेक्षत्वयोः शन्दमर्यादयाऽलामाच्च । तथा सति असिद्धं बहुपेक्षमस्पापेक्ष इत्येव वदेत् ॥ Par.Śck. Parī. 50.

अह्नोप elision or omission of a single phonetic element or letter; cf. अह्नोपोऽन: P. VI.4.134.

आत्विधि an operation prescribed with reference to one single letter; cf. स्थानिवदादेशोऽ निश्विधा P. I.1.56.

अवकाश occasion; possibility of application; cf. इको गुणवृद्धी इत्यस्यावकाशः । चयनं चायकः लवनं लावकः इति। इहोभयं प्राप्तोति । मेद्यति । मार्शिति । M. Bh. on I.1.3. Vart. 6.

अवग्रह (1) separation of a compound word into its component elements as shown in the Pada-Pātha of the Vedic Samhitās. In the Padapātha, individual words are shown separately if they are combined by Samdhi rules or by the formation of a compound in the Samhitapāṭha; e.g. पुरोहितम् in the Samhitāpātha is read as पुर:ऽहितम्. In writing, there is observed the practice of placing the sign (S) between the two parts, about which nothing can be said as to when and how it originated. The Atharva-Pratisakhya defines अनुग्रह as the separation of two padas joined in Samhitā. (A. Pr. II. 3.25; II. 4.5). In the recital of the pada-patha, when the word-elements are uttered separately, there is a momentary pause measuring one mātrā or the time required for the utterance of a short vowel. (See for details Vāj, Prāt. Adhāya 5), (2) The word अनुमह is also used in the sense of the first out of the two words or members that are compounded together. See Kāšīkā on P.VIII.4.26; cf. also तस्य (इक्वयस्य) पुर्वषद्मवग्रहः यथा देवायत इति देव-यो. Tai. Pr. I. 49, The term अन्त्रह is explained in the Mahābhāsya as 'separation, splitting up of a compound word constituent parts; cf. छन्दस्यानङेक्ष्प्रहो रूथ्येत पितामह । इति । (M. Bh. on IV. 2.36); also cf. युव्यस्यप्रह: प्राप्निति । न त्वक्षणन पदकारा असवत्याः । पदकारैनीम लक्षणमनुबन्धेम् । यथालक्षणं पदं कर्तन्यम् (M. Bh. on III. 1. 109) where the Bhäsyakāra has definitely stated that the writers of the Padapātha have to split up a word according to the rules of Grammar. (3) In recent times, however, the word अवसह is used in the sense of the sign (2) showing the coalescence of 의 (short or long) with the preceding 34 (short or long) or with the preceding ए or ओ.e.g .রিবার चर्यः, अत्राडडगच्छ. (4) The word is also used in the sense of a pause, or an interval of time when the constituent elements of a compound word are shown separately; cf. समामेनप्रहो ह्यस्यसमकाल: (V. Pr. V.1). (5) The word is also used in the sense of the absence of Sandhi when the Sandhi is admissible.

अवग्रहिचराम the interval or pause after the utterance of the first member of a compound word when the members are uttered separately. This interval is equal to two moras according to Tait. Pr. while, it is equal to one mora according to the other Prātišākhyas.

- अवङ् substitute अव् for the final ओ of the word गा; cf. अवङ् स्फोटायनस्य, P. VI. 1.123, I24.
- अवचन something which need not be specifically prescribed or stated, being already available or valid; cf तृतीयासमासे अर्थप्रहणसनर्थकं अर्थगितिर्हे अवचनात् P. II. 1.30 V.1.
- अवचूरि a short gloss or commentary on a standard work.
- अवच्छेद exact limitation; cf. उपदेशत्वा-वच्छेदेन एकाजित्यर्थाच्च, Par. Sek. 120.3.
- अवधारण restriction; limitation; cf. अवधारणमियत्तापीरच्छेद: । यावदमत्रं ब्राह्मणाना-मन्त्रयस्य Kāś. on P. II. 1.8.
- अवधि limit, which is either exclusive or inclusive of the particular rule or word which characterizes it; cf. सर्वश्च हुल तं तमवधिं प्रति अन्त्यो भवति M. Bh. on I. 3.3.
- अवधिमत् object of limit; cf. दूरे चेदव-धिमान् अवधिभवति Kas. on P.V.3.37.
- अवयव member or portion, as opposed to the total or collection (समुदाय) which is called अवयाविन् ; cf. अवयवप्रसिद्धेः समुदायप्रसिद्धिवंद्याया Par. Sek. Pari. 98. The conventional sense is more powerful than the derivative sense.
- अवयवषष्टी the genitive case signifying or showing a part; cf. वश्यत्यादे-शप्रत्यययोरित्यवयवषधा एव M.Bh. on I. 1.21.
- अवर्ण the letter अ; the first letter of the Sanskrit alphabet, comprising all its varieties caused by grades, (हस्य, दीर्घ, प्छत) or accents or nasalization. The word वर्ण is used in the neuter gender in the Mahābhāṣya; cf. सर्वमुख्तस्थानमवर्णम् M. Bh. I.1.9, मा कदाचिदवर्ण भूत् M.Bh. I.1.48 Vārt. 1; cf. also M. Bh. on I.1.50 Vārt. 18 and I.1.51 Vārt. 2; cf. also हस्यमवर्ण प्रयोगे संवृतम् Sīradeva Pari. 17.

- अवशंगम name of a Samdhi when a class consonant, followed by any consonant is not changed, but retained as it is; cf.स्पर्शा: पूर्वे व्यञ्जनान्युत्त-राणि आस्थापितानां अवशंगमं तत् R.Pr.IV. 1; e g. आरेक् पन्थाम् R.V. I. 113.16, वषट् त (R.V. VII.99.7) अजानन् पुत्र: (R. V. X.85.14).
- अविशिष्टालेङ्ग (v.l. अविशिष्टालेङ्ग) a term occurring in the Linganusasana meaning'possessed of such genders as have not been mentioned already either singly or by combination' i.e. possessed of all genders. Under अवशिष्टलिङ्ग are mentioned indeclinables, numerals ending in g or न, adjectives, words ending with krtya affixes i. e. potential passive participles. pronouns, ending with the affix अन in the sense of an instrument or a location and the words कति and युष्मद्. (See पाणिनीय-लिह्नानुशासन Sutras 182-188).
- अवश्यम् necessarily; the expression अवश्यं चैतदेवं विज्ञेयम् is very frequently used in the Mahābhāṣya when the same statement is to be emphasized.
- अवसान panse, cessation, termination; cf. विरामोऽवसानम् । वर्णानामभावः अवसान-संज्ञः स्यात् S. K. on P. 1. 4. 110.
- अवस्था stage, condition; stage in the formation of a word; e.g. उप-देशावस्था, लावस्था, etc.
- अवस्थित of a uniform nature; cf. सिद्धं त्ववस्थिता वर्णाः, वक्तुश्चिराचिरवचनाद् वृत्तयो विशिष्यन्ते, M. Bh. I. 1.70 V. 5.
- জনাপ্ত্ৰৰ deficient in one or more syllables. The word is mostly used in connection with a Vedic Mantra.
- अवाग्योगविद् one who is not conversant with the proper use of language: cf. अथ योऽनाग्योगिवद् विज्ञानं तस्य शरणम्; M. Bh. I.1.1.
- अविद्यातार्थे meant for not preventing the application (of a particular

term) to others where it should apply. The word is frequently used in the Kāśikā; cf अजाद्यतद्यप् ! टकार: सामान्यप्रहणाविचातार्थ: । Kāś. on P. IV. 1.4, also see Kāś. on III. 1. 133; III. 2.67, 73; IV. 1.78.

अविचालिन immutable. The term is used frequently in the Mahābhāsya in connection with letters of the alphabet which are considered 'nitya' by Grammarians; cf. नित्येषु च शब्देषु क्टस्थरिवचालिभिर्वणर्भ-वितन्यमनपायोपजानविकारिभि: M. Bh. I. 1. Āhn 2; cf. also नित्यपर्यायवाची सिद्ध-शब्द: । यत्कृटस्थेष्वविचालिषु मावेषु वर्तते M. Bh. on I. 1.1.

সবিधি non-application, non-prescription (প্রবিধান); cf. প্রভ্যাপুন যুনপুনী প্রবিধিনিষ্টিরন্থ M. Bh. on VII. I. 30; Par. Sek. Pari. 92.

अविभक्तिक without the application of a case termination. The term is used frequently in connection with such words as are found used by Pānini without any case-affix in his Sūtras; sometimes, such usage is explained by commentators as an archaic usage; cf. अविभिक्ति निर्देश: । इन उ: रः छ: । M. Bh. I. Āhn. 2; also M. Bh. on I. 1.3; III. 1.36, VII. 1.3 etc.

अविभागपक्ष a view of grammarians according to which there are words which are looked upon as not susceptible to derivation. The terms अखण्डपक्ष and अन्युत्पन्नपक्ष are also used in the same sense.

अविरिक्तन्याय a maxim mentioned by Patanjali in connection with the word आधिक where the taddhita affix उक् (इक), although prescribed after the word अधि in the sense of 'flesh of sheep' (अवे: मांसम्), is actually put always after the base अधिक and never after अधि. The maxim shows the actual application of an affix to something allied to, or similar to the base, and not to the actual base as is sometimes found in popular usc.cf. द्वयोः शब्दयोः समानार्थ-योरकेन विग्रहोऽपरस्मादुत्पत्तिभीविष्यात अविर-विकन्यायेन। तद्यथा अवर्मासमिति विग्रह्म अविक-शब्दादुत्पत्तिभीवति आविकिमिति। M. Bh. on IV. 1.88; cf. also M. Bh. on IV. 1.89; IV. 2.60; IV. 3.131, V. 1.7, 28; VI. 2.11.

अविलम्बित name of a fault in pronouncing a word where there is the absence of a proper connection of the breath with the place of utterance; 'अविलम्बित: वर्णान्तरामंभिन्न: ' Pradipa on M.Bh 1.I.l. There is the word अवलम्बित which is also used in the same sense; cf यस्तं निरस्तमय-लम्बितं निह्तम् M. Bh on I. 1. 1.

अविवक्षा non-intention; connivance; cf. सतोप्यविवक्षा भवति । अलोभिका एडका । अनुद्ररा कन्या । also cf. प्राप्तद्रेरविवक्षातः कर्मणोऽकर्मिका क्रिया.

अविवक्षित (1) not taken technically into consideration, not meant; cf. अविवक्षित कर्मण पर्ध भवति M.Bh on II.3. 52; (2) unnecessary; superfluous; the word is especially used in connection with a word in a Sutra which could as well be read without that word. The word अतन्त्रं is sometimes used similarly.

अविशेष absence of specification; cf. गामादाग्रहणेष्याचेशेष:M.Bh.I.1.20 Vart 1; Par. Sek. Pari. 106.

अविशोषित not specified, mentioned without any specific attribute; cf. एवमि प्रयत्न: अविशेषित: भवति M.Bh. on I.1.9; cf. also Kātan. VI.1.63.

अञ्चाति absence of, or prohibition of, a vitti or composite expression; nonformation of a composite expression; cf.समानाधिकरणानां सर्वत्राद्वतिरयोगादेकेन M.Bh. on III. 1. 8.

अनुद्ध lit.not beginning with the vowel आ, ऐ or ओ; a word which has got no आ or ऐ or ओ as its first vowel, as for example ग्डचुक, अहिचुम्बक etc. इरावती, नर्मदा यमुना etc; cf. प्राचामवृद्धात फिन् बहुलम् P. IV. 1. 160. also अवृद्धाभ्यो नदीमानुषीभ्यस्तन्नामिकाभ्यः P. IV. 1.113.

अव्यक्त (1) indistinct; inarticulate; cf. अव्यक्तानुकरणस्यात इतो P. VI. 1.98 also P. V. 4.57; अव्यक्त अपरिस्कृटवर्णम् Kāś. on P. VI. 1.98; (2) a fault of pronunciation; cf. नातिव्यंक्तं न चाव्यक्त-मेवं वर्णानुदरियेत् ।

अन्यपत्रक्त unseparated, undivided, inseparable, mixed; cf. नाज्यपत्रक्तस्य अवयवे तिद्विधिः यथां द्रज्येषु M. Bh. on Siva-sutra 4. V. 9 whereon Kai-yata remarks ज्यपत्रक्तं भेदः। अज्यपत्रक्तं अभिन्नलुद्धिविषयमेकत्वालम्बनज्ञानम्राह्मं समुदा-यरूपम्।

अन्यय indeelinable, lit. invariant, not undergoing a change. Pāṇini has used the word as a technical term and includes in it all such words as स्वर्, अन्तर्, प्रातर् ete. or composite expressions like अन्ययीमावसमास, or such taddhitānta words as do not take all case affixes as also kṛdanta words ending in म् or ए, ऐ, ओ, औ. He gives such words in a long list of Sutras P. I. 1. 37 to 41; cf. सहर्श त्रिष्ठु स्विध् स्विध- विभ- किषु। वचनेषु च सविष्ठु यन व्यति तदव्ययम् Kāś. on P. I. 1. 37.

अन्ययसंग्रह name of a treatise on indeclinable words attributed to Śākatāyana.

अव्ययार्थनिरूपण a work on the meanings of indeclinable words written in the sixteenth century A. D. by Vitthala Sesa, grandson of Rāmacandra Sesa the author of the Prakriyā Kaumudī.

अन्ययोभाव name of a compound so called on account of the words for-

ming the compound, being similar to indeclinables; e. g. निर्माक्षिकम्, अधिहरि, यथामित, यावर्ज्ञावम् etc.; ंदी. अनव्ययं अव्ययं भवतीत्यव्ययीभावः M. Bh. on II. 1. 5. The peculiarity of the avyayībhāva compound is that the first member of the compound plays the role of the principal word; cf. पूर्वपदार्थप्रधानोऽब्ययीभावः M. Bh. on II. 1.6.

अध्यवधान absence of intervention between two things by something dissimilar; close sequence; cf. अतजातीयकं हि लांके व्यवधायकं भवति M. Bh. on I.1.7. Vārt. 8; cf. also येन नाज्यवधानं तेन व्यवहितीप वचनप्रामाण्यात् M. Bh. on VII. 3. 44, VII 3.54, VII. 4. 1, VII. 4. 93. The term अव्यवधा is used in the same sense.

अन्यवस्था absence of proper disposal; absence of a proper method regarding the application of a rule; cf. पुनर्काच्छिमाव; पुनराडिति चक्रकमन्यवस्था प्राप्नेति M. Bh. on I. 3. 60 V. 5.

अन्याप्ति insufficient extension, as opposed to अतिब्याप्ति or over application; cf. सर्वोपाधिब्यभिचारार्थम् । अब्याप्त्यति-ब्याप्त्यसभवादिदोषपरिहारार्थम् । Padamanjari on II. 132.

अन्याप्य an intransitive root; a technical term in the Cāndra Vyākaraņa (C. Vy. I. 4. 70) as also in Hemacandra's S'abdānusāsana; cf. अन्याप्यस्य मुचेमोंग् वा। मुचेरकमंकस्य सकारादी सिन परे मोक् इत्ययमादेशो वा स्यात्। न चास्य द्वि:। मोक्षति मुमुक्षति चैत्र:। मोक्षते मुमुक्षते वा वत्स; स्वयमेव Hem. IV. 1.19.

अञ्चुत्पत्तिपक्ष the view held generally by grammarians that all words are not necessarily susceptible to analysis or derivation, an alternative view opposed to the view of the etymologists or Naīruktas that every word is derivable; cf. पाणिनस्त्वच्युत्पत्तिपक्ष एवति शब्देन्दुशेखरे निरूपितम् Pari. Sekh. Pari. 22; वाचक उपादान: स्वरूपवानिति अच्युत्पत्तिपक्ष Vyādi's Samigraha.

अध्युत्पन्न underived, unanalysable; cf. उणादयोऽज्युत्पन्नानि प्रातिपद्क्ञिनि M. Bh. I. 1.61 Vart. 4; Par. Sek. Pari. 22.

अन्युत्पन्नपक्ष same as अन्युत्पत्तिपक्ष. See above the word अन्युत्पत्तिपक्ष.

अश् (1) Pratyāhāra or a brief term standing for all vowels, semi-vowels, and the fifth, fourth and third of the class-consonants; all letters excepting the surds and sibilants; (2) substitute अ for the word इदम् before affixes of cases beginning with the instrumental, and for एतर् before the tad. affixes अ and तस्; see P. II. 4.32 and 33; (3) substitute अ for the gen. sing. case-affix ङम् after the words युप्पर् and अस्मर्; see P. VII.1.27.

अशक्ति incapacity to pronounce words correctly; cf. अशक्त्या कयाचिद् श्राह्मण्या क्तक इति प्रयोक्तन्ये रुतक इति प्रयुक्तम् M.Bh. on Siva-sutra 2.

आशिष्य unnecessary to be prescribed or laid down.; cf.तदशिष्यं संज्ञाप्रमाणस्वात् P. I.2. 53; also लिङ्गं अशिष्यं लोकाश्रयत्वा- लिङ्गस्य M.Bh. on II, 1. 36.

अदमादि a class of words headed by the word अध्मन् to which the taddhita affix र is applied in the four senses specified in P. IV. 2. 67 to 70; e.g. अस्परः ऊषरम्, नगरम्, पामरः गहरम् etc. cf. P.IV. 2.80.

अश्वयासादि compounds like अश्ववास which cannot be strictly correct as चतुर्थीसमास, but can be बधीसमास if the word तद्यं in the rule चतुर्थी तद्यांथीन बिहितसुखरिक्षते: be understood in the sense of 'meant for' a particular thing which is to be formed out of it; cf. विकृति: प्रकृत्येति चेदश्यासादीनासुपसंख्यानम् M.Bh. on II. 1, 36.

अश्वपत्यादि a class of words headed by अश्वपति to which the taddhita affix अण् (अ) is added in the senses mentioned in rules before the rule तेन दोन्यति • P. IV.4. 2. which are technically called the Pragdivyatiya senses. c g. आश्वपतम्, गाणपनम्. गाहपतम् etc.

अश्वत्थनारायण a commentator who wrote a gloss on Pāṇini's Aṣṭā-dhyāyī in the Tamil language.

अभ्वादि (1) a class of words headed by the word अश्व to which the affix फुल् (आयन) is added in the sense of गोत्र (grandchildrenetc.); e.g. आश्वायन: जातायन:, ओल्लायन: etc.; cf. P. IV. 1. 110; (2) a class of words headed by the word अश्व to which the taddhita affix यत् is added in the sense of a cause of the type of a meeting or an accidental circumstance; e.g. आश्विकम् आरिमकम् cf. P. V. 1.39.

अप्रक another name for the famous work of Pāṇini popularly called the Aṣṭādhyāyi; cf. अधावःयायाः परि-माणमस्य स्त्रस्य अश्वकं पाणिनीयम् । दशकं वियान् व्यदीयम् । त्रिकं काशकुत्सम्। Kās on P. V. I. 58; (2) students of Pāṇini's gramınar, c. g. अश्वकः पाणिनीयाः ; cf. स्त्राच्च कोपधात् । Kās. on P.IV. 2. 65.

अप्रम a term used by ancient grammarians for the vocative case.

अप्रमङ्गला name of a commentary on the Katantra Vyākaraņa by Rāmakisoracakravartin.

अप्राच्याची name popularly given to the Sütrapātha of Pāṇini consisting of eight books (adhyāyas) containing in all 3981 Sütras, as found in the traditional recital, current at the time of the authors of the Kāsikā. Out of these 3981 Sütras, seven are found given as Vārtikas in the Mahābhāsya and two are found in Gaṇapātha. The author of the Mahābhā ya has commented upon only 1228 of these 3981 sütras. Originally there were a very few differences of readings also, as observed by Patañjali (see Mbh on I.4.1); but the text

was fixed by Patañjali which, with a few additions made by the authors of the Kāsikā, as observed above, has traditionally come down to the present day. The Aṣṭādhyāyī is believed to be one of the six Vedānga works which are committed to memory by the reciters of Rgveda. The text of the Aṣṭādhyāyī is recited without accents. The word अञ्चास्यायो was current in Patañjali's time; cf. शिष्टजानार्थो अञ्चास्यायो M. Bh. on VI. 3.109.

अद्यक्षरा a metre having eight syllables in a foot;cf.गायत्री सा चतुर्विदात्यक्षरा। अद्यक्षरास्त्रयः पादाः चत्वारो वा षडक्षराः R. Pr. XVI. 9.

अप्रि name of a metre of four feet consisting of 64 syllables in all, 12 syllables in the odd feet and 20 in the even feet; e.g. त्रिकदुकेषु महिष: etc. R.V. II. 22. 1.

अस् (1) case affix of the nominative and accusative plural and the ablative and genitive singular (जस्, হাদু, ভাধি and ভদু); (2) taddhita affix अस (अस) added to पूर्व, अधर and अवर, by P. V.3.39; (3) compoundending अस् (असिच्) applied to the words प्रजा and मेघा standing at the end of a Bahuvrihi compound (P. V.4. 122); (4) Unadi affix अस् prescribed by the rule सर्वधातुम्योऽपुन् and subsequent rules (628-678) to form words such as मनम्, सरम् etc.(5) ending syllable अन, with or without sense, of words in connection with which special operations are given in grammar; cf. P.VI. 4.14; cf. also अनिनस्मन्ग्रहणान्यर्थवता चानर्थकेन च तदन्तविधि प्रयोजयन्ति Par. Sek. Pari. 16.

अस affix अस mentioned in the Nirukta in the word अवस (अव् + अस) cf.असो नामकरण:। तस्मात्रावयह्वन्ति NirI.17.

असंख्य not possessing any notion of number; the word is used in con-

nection with avyayas or indeclinables; यथेव हि अलिद्भमन्ययमेवमसंख्यमपि M. Bh. on II. 4.82.

असंज्ञ a term used for the C'andra Grammar, as no samjñas or technical terms are used therein; cf.चान्द्रं चासंज्ञकं स्मृतम्.

असँज्ञा not used as a technical term or name of a thing; cf. पूर्वपरावरदक्षिणोत्त-रापराधराणि व्यवस्थायामसंज्ञायाम् P.I.1.34.

असंनिकर्ष (:) separatedness as in the case of two distinct words; (2) absence of co-alescence preventing the sandhi; cf. R.T. 68,70.

असंनिधान the same as असंनिकर्ष; see above; e. g. भरा इन्द्र; तमु अभिप्रगायत.

असंप्रत्यय failure to understand the sense; cf. इतरथा ह्यसंप्रत्ययोऽक्वात्रेमत्वाद्यथा लोके M. Bh. on I.1.23 Vart. 3.

असंभव Impossibility of occurrence (used in connection with an operation); cf. नावस्यं द्विकार्ययोग एव विप्रतिषेध: । किं तर्हि । असंभवोषि । M. Bh. I.1.12 Vārt. 3; (2) impossibility of a statement, mention, act etc. cf. असंभव: खरुवि अर्थादेशनस्य M. Bh. on II. 1.1.

असंयोग absence of the conjunction of consonants; cf. असंयोगाहिट् किन् P. I. 2.5.

असंहिता absence of juxta-position, absence of connectedness; cf. यदि तानत्संहितया निर्देशः क्षियते भ्वादय इति भिवतन्यम् । अथासंहितया भू आदय इति भिवतन्यम् M. Bh. on I. 3.1.

असन्व (1) absence of सन्व or entity;
(2) other than a substance i. e. property, attribute, etc. cf. प्राद्य: असन्ववचना निपातसंज्ञा भवन्ति M. Bh. I. 4. 59; cf. also सोऽसन्वप्रकृतिर्गुण: M. Bh. on IV. 1.44. cf. also चादयोऽ सन्वे P. I. 4. 57.

असमर्थे (1) syntactically not connected, e. g. राज्ञ: and पुरुष: in the sentence भायी राज्ञ: पुरुषो देवदत्तस्य। (2) unable to enter into a compound word, the term is used in connection with a word which cannot be compounded with another word, although related in sense to it, and connected with it by apposition or by a suitable case affix, the reason being that it is connected more closely with another word; cf. सापेक्षमसमर्थ भवित M. Bh. II. l.l.; e.g. the words कर्ष and शित: in the sentence महत् कर्ष शित:

असमर्थसमास a compound of two words, which ordinarily is inadmissible, one of the two words being more closely connected with a third word, but which takes place on the authority of usage, there being no obstacle in the way of understanding the sense to be conveyed; e. g. देवदत्तस्य गुरुकुलम्। देवदत्तस्य दासभार्या। असूर्यप्यानि मुखानि, अश्राह्मभोजी श्राह्मणः M. Bh. on II. 1.1.

असमस्त not compounded, not entered into a compound with another word; cf. समासे असमस्तस्य Hem. II. 3.13.

असमास (1) absence of a compound. उपसर्गादसमासेपि णोपदेशस्य P. VIII. 4.14; (2) an expression conveying the sense of a compound word although standing in the form of separate words; चार्ये इन्द्रबचन असमासेपि चार्थसंप्रत्ययादिन्धं प्राप्नोति । अहरहर्नयमाने गामश्चं पुरुषं पशुम् M. Bh. on II.2.29.

असरूप not having the same outward form or appearance; e. g. the affixes अण्, अच्, ण, अज्, ज, and the like which are, in fact, सहप as they have the same outward form viz. the affix अ. अण् and यत् are असहप; cf. वाऽसहपोऽस्त्रियाम् P. III. I.94.

असर्वविभक्ति not admitting all caseaffixes to be attached to it; cf. तद्धितश्चासर्वविभक्तिः P. I. 1. 38; यस्मान्न सर्वविभक्तेरत्पत्तिः सोसर्वविभक्तिः । ततः यतः तत्र यत्र । Kāś. on I. 1.38.

असामर्थ्य absence of a syntactical connection; cf. दक्षा पट्टः । घृतेन पट्टः । असामर्थ्यादत्र समासो न भविष्यति । कथम-सामर्थ्यम् । सोपेक्षमसमर्थे भवतीति । न हि दक्षः पट्टना सामर्थ्यम् । केन तर्हि । भुजिना । दक्षा मुङ्क्ते पट्टरिति । M. Bh. on II. 1.30.

असारूप्य dissimilarity in apparent form (although the real wording in existence might be the same) c. g. टाप्, डाप्, चाप्; cf. नानुवन्धकृतमसाहस्यम् । Pār. Sek. Pari. 8.

असि (1) Uṇādi affix अम्; (2) tad. affix अम्. Sec above the word अम्.

आसेच् samāsa-ending assix अस्. Sce above the word अम्.

असिद्ध invalid; of suspended validity for the time being; not functioning for the time being. The term is frequently used in Pānini's system of grammar in connection with rules or operations which prevented, or held in suspense, in connection with their application in the process of the formation of a word. The term (असिद्ध) is also used in connection with that have applied or operations that have taken place, which are, in certain cases, made invalid or invisible as far as their effect is concerned and other rules are applied or other operations are allowed to take place, ordinarily have been prevented by those rules which are made invalid had they not been inva-Pāṇini has laid down this invalidity on three different occasions (1) invalidity by the rule पूर्वत्रासिद्धम् VIII. 2.1. which makes a rule or operation in the second, third and fourth quarters of the eighth chapter of the Astādhyāyi invalid when any preceding rule is to be applied, (2) invalidity by the rule असिद्धबदत्रामात् enjoins mutual invalidity which in the case of operations prescribed in the Abhīya section beginning with the rule असिद्धवत्राभात (VI. 4.22.) and going on upto the end of the Pada (VI.4.175), (3) invalidity of the single substitute for two letters, that has already taken place, when g is to be substituted for स, or the letter त is to prefixed, cf. षत्वतकोरासिद्धः (VI. 1.86). Although Pānini laid down the general rule that subsequent rule or operation, in case of conflict, supersedes the preceding rule, in many cases it became necessary for him to set that rule aside, which he did by means of the stratagem of invalidity given above. Subsequent grammarians found out a number of additional cases where it became necessary to supersede the subsequent rule which they did by laying down a dictum of invalidity similar to that of Pāṇini. The author of the Varttikas, hence, laid down the doctrine that rules which are nitya or antaranga or apavada, are stronger than, and hence supersede, the anitya, bahiranga and utsarga rules respectively. Later gram. marians have laid down in general, the invalidity of the bahiranga rule when the antaranga rule occurs along with it or subsequent to it. For details see Vol. 7 of Vyākarana Mahābhāsya (D. E. Society's edition) pages 217-220. See also Pari. Sek. Pari. 50.

आसिद्धत्व invalidity of a rule or operation on account of the various considerations sketched above. See असिद्ध.

असिद्धपरिभाषा the same as Antaranga Paribhasa or the doctrine of the invalidity of the bahiranga operation. See the word असिद्ध above. For details see the Paribhasa " asiddham bahirangam range" Par. Sek. Pari. 50 and the discussion thereon. Some grammarians have given the name असिद्धपरिभाषा to the Paribhāsā असिद्धं बहिरङ्गमन्तरङ्गे as contrasted with अन्तरङ्गं बहिरङ्गाद् वलीय: which they have named as बहिरङ्गपरिभाषा.

असुक् the augment अस seen in Vedic Literature added to the nom. pl. case-affix जस following a nounbase ending in अ; e.g. जनास:, देवास: etc. cf आजसरसुक् P. VII. 1.50, 51.

असुङ् substitute अस् for the last letter of the word पुंस् before the सर्वनाम- स्थान affixes i. e. before the first five case affixes, e.g. पुमान् पुमांसी etc.; cf. पुंसोऽसुङ् P. VII. 1. 89

असुन् Uṇādi affix अस् (असुन्) by सर्व-धातुभ्योऽसुन् वक्तव्यः Uṇ. Sū.628; cf. न वेत्तीति नेत्रदाः । वेत्तिरसुन्त्रत्ययान्तः Kāś. on P. VI. 3. 75.

असे kṛt affix in the sense of the infinitive (तुमर्थे) in Vedic Literature,e.g. जीवसे; cf. तुमर्थे सेसेनसे॰ P. III. 4. 9

अस्ताति tad. affix अस्तात् in the sense of the base itself, but called विभाक्त, prescribed after words in the sense of 'direction', e. g. पुरस्तात्, अधस्तात् etc. cf. दिक्शब्देभ्य: सतमीपञ्चमीप्रथमाभ्यो दिग्देशकालेषु अस्ताति: P. V. 3. 27.

अस्थ अ, आ and आई. This term is used in Rk Tantra cf. अस्थनामिनी सन्ध्यम् R. T. 94. अस्थ possibly means 'belonging to अ i. e. all the three grades हस्व, दोर्च and खुत of अ'.

अस्पष्ट less in contact with the vocal organ than the semi-vowels; the term occurs in Hemacandra's Grammar (Hem. I. 3. 25) and is explained by the commentator as ईष्ठत्रपृष्टतरी प्रत्यासत्त्रपंकारकारी. अस्पष्ट stands for the letters य and य which are substituted for the vowels ए पे and ओ औ when followed by a vowel; cf. also Sak I. 1. 154.

अस्पृष्ट not in contact with any vocal organ; the term is used in connection with the effort required for the utterane of vowels, अनुस्वार and sibilants when no specific contact with a vocal organ is necessary; cf. स्वरानुस्वाराष्ट्राणामस्पृष्टं करणं स्थितम् R. Pr. XIII. 3.

अस्मद् first person; the term is used in the sense of the first person in the grammars of Hemacandra and Sākaṭāyana. cf. त्रीणि त्रीण्यन्ययुष्मदस्मीद (Hem. III. 3.17);

अस्वपद्विग्रह a term used for those compounds, the dissolution of which cannot be shown by the members of the compound; c. g. सुमुखी; cf. भवति वे कश्चिदस्वपद्विग्रहोपि वहुनीहि:। तद्यथा। शोभन मुख्यमस्याः सुमुखीति।
M.Bh. on V. 4. 5.

अस्वयंद्रष्ट A term used for the perfect tense; cf. कु चकारमस्वयंदृष्टे (R.T. 191).

अस्व not homogeneous; asavarṇa. cf. इवर्णादे: अस्वे स्वरे यवरलम् Hem. I. 2.21, also अस्वे Śāk. I. 1.73.

अस्वरक untoned; a word without an accent, as different from a word which has an accent, but which is not uttered with that accent; cf. अक्रियमाणे ह्यपदेशिवद्वावे...आन्तर्यंत आदेशा अस्वरकाणामस्वरकाः स्युः M.Bh. on VII. 1.2, VII. 1.89.

311

आ (1) the long form of the vowel अ called दोर्घ, consisting of two matras. in contrast with (1) the short आ which consists of one matra and the protracted आ३ which consists of three mātrās; (2) substitute आ of two matras when prescribed by the word दार्च or बाद्ध for the short vowel अ; (3) upasarga आ (আৰু) in the sense of limit e. g. आ कडारादेका संज्ञा (P. I. 4.1.) आकुमार यदा: पाणिन: Kās. on II. 1.13. आ उदकान्तात् (M. Bh. on I. 1.14.); (4) indeclinable at in the sense of remembrance e. g. आ एवं नु मन्यसेः cf. ईषदर्थे क्रियायोगे मर्यादाभिविधो च यः। एतमातं डितं विद्याद्वाक्यस्मरणयोर्डिन् M. Bh. on I.1.14; (5) augment आ (आ変) as seen in चराचर, वदावद etc. cf. M. Bh. VI. 1.12 Vart. 6; (6) augment आ (आर्) prefixed to roots in the tenses ভুহু, ভুহু and ভুফু; (7) substitute on prescribed for the last letter of pronouns before the tad. affixes हक,हरा, हक्ष and यत्, as in ताहक, ताह्य etc.; (8) feminine affix आ (राप, हाप or चाप) added to nouns ending in আ; (9) substitute আ (আ or আনু, or ভা or আনু) for case affixes in Vedic literature उभा यन्तारी. नामा पृथिव्या: etc.

আ indeclinable আ pronounced nasalized, e. g. অন্ন আ অব: M. Bh. I. 3.2.

आक् see above the word आ sense (5).

आकम् the substitute आक्षम् for साम् of the gen. pl. after the words युप्पत् and अस्मत् c. g. युप्पाकं, अस्माक्षम् cf. P. VII. 1.33.

आकर्षक (a word) attracting another word stated previously in the context e. g. the word च in the rules of Pāṇini.

आकर्षादि a class of words headed by the word आकर्ष to which the taddhita affix कन् (क) is applied in the sense of clever or expert; e. g. आकर्षकः, त्सरुकः, राकुनिकः etc.; cf. P. आकर्षदिस्यः कन् P. V.2.64.

आकाङ्क (or साकाङ्क also) expectant of another word in the context, e. g. कूज and ब्याहर in अङ्ग कूज ३,अङ्ग ब्याहर ३ इदानीं ज्ञास्यास जाल्म Kāś. on अङ्गयुक्तं तिङाकाङ्कम् (P.VIII. 2.96).

आकाङ्का expectancy with regard to sense-completion, generally in compounds such as साकाङ्का, निराकाङ्का etc. cf. अस्त्यस्मिनाकाङ्का इत्यतः साकाङ्काम् M. Bh. on III. 2. 114.

আকাহ্ব a word for which there is expectaney of another word for the completion of sense.

आकार the letter आ; cf. अकारस्य विवृतोप-देश आकारम्रहणार्थः । M. Bh. I. l Ahn. 2.

आिकनिच् tad. aff. आिकन् affixed to the word एक in the sense of 'single,' 'alone'; cf. एकादािकिनिचासहाये P. V. 3.52.

आकुरमीय a group of 43 roots of the चुरादि class of roots beginning with the root चित् and ending with कुरम् which are Atmanepadin only.

आकृति lit. form; individual thing; cf. एकस्या आकृतिश्चरितः प्रयोगो द्वितीयस्यास्तृतीयस्याश्च न भवति M. Bh. on III. 1.40 Vart. 6. The word is derived as आकृयेत सा आकृति: and explained as संस्थानम्; cf. आकृयेत व्यव्यते अनया इति आकृति: संस्थानमुच्यते Nyāsa on IV.1.63; (2) general form which, in a way, is equivalent to the generic notion or genus; cf. आकृत्युपदेशास्तिद्धम् । अवर्णाकृतिस्पिद्ध सर्वमर्गाकुलं प्रहीष्यति M. Bh. I. 1. Ahn. 1; (3) notion of genus;

cf. also यत्ति तद् भिनेष्यभिनं छिनेष्यन्छिनं सामान्यभूतं स शब्द: । नेत्याह । आकृतिनाम सा. M. Bh. I. 1. Āhn.1; (4) a metre consisting of 88 letters; cf. R. Prāt. XVI. 56, 57.

आक्रातिगण a class or group of words in which some words are actually mentioned and room is left to include others which are found undergoing the same operation; cf. श्रेण्यादय: कृतादिभि: । श्रेण्यादय: पठ्यन्ते कतादिराकतिगण: M. Bh. II.1. 59. Haradatta defines word as प्रयोगदर्शनेन आकृतिग्राह्यो आकृतिगणः । अत्र आदिरान्दः प्रकारे । आकृति-गणेपि उदाहरणरूपेण कतिपयान् पठति कृत मत इत्यादि Padamañjarī on II.1. 59 ; cf. Pradīpa of Kaiyata also on II. 1. 59. Some of the ganas mentioned by Pāṇīni are ākṛtigaṇas, e.g. अश-आदिगण, मूलविभुजादिगण, स्नाल्यादिगण, शिवादिगण, पचादिगण, and others.

आक्षरसमाञ्चाधिक directly or expressly mentioned in the fourteen Pratyāhāra Sūtras of Pāṇini; a letter actually mentioned by Pāṇini in his alphabet 'সহত্ত্যু', 'সক্ত্যু' etc.

आक्षिस (1) taken as understood, being required to complete the sense; cf. किविप आक्षितो भवति M. Bh. on III.2. 178;(2) a term used for the circumflex accent or खरित as it is uttered by a zig-zag, motion of the organ in the mouth caused by the air producing the sound; cf. आक्षेपो नाम तिर्थग्यमनं गात्राणां वायुनिमित्तं तेन य उच्यते स स्वरित: Uvvata on R. Pr. III. 1.

आक्षेप a zig-zag motion of the organs producing sound caused by the air; see आक्षित above.

आख्या designation, conventional name; cf. देवदत्तो मुण्डचपि जट्यपि स्वामा- ख्यां न जहाति M. Bh. on I.1.1; cf. also स्वमज्ञातिषनाख्यायाम् P. I. 1.35; cf. also वर्ण: कारोत्तरो वर्णाख्या Tai. Prāt. I. 16.

verb; cf. आख्यात verbal form, भावप्रधानमाख्यातं सत्त्वप्रधानानि नामानि Nir. चत्वरि पदजातानि नामाख्यातोपसर्गनि-पाताश्च M. Bh. I.1. Ahnika 1; also A.Prāt. XII. 5. आकार पदादिश्च M. Bh. I. 2.37 Vart. आख्यातमारव्यातेन क्रियासातत्वे Sid. Kau. II. 1. 72, क्रियावाचकमाख्यांत V. Pr. V.1; cf. भारद्वाजकमाख्यातं भागीवं नाम भाष्यते । भारद्वाजेन दृष्टलादाख्यातं भारद्वाज-गोत्रम V. Prat. VIII. 52; cf. also Athar. Prāt. I. 1. 12, 18; 1. 3. 3, 6; II. 2. 5 where ākhyāta means verbal form. The word also meant in ancient days the root also, as differentiated from a verb or a verbal form as is shown by the lines तन्नाम येनाभिद्धाति सत्त्वं, तदारव्यातं येन भावं स धातुः R. Pr. XII. 5 where ' आख्यात ' and 'খার' are used as synonyms. As the root form such as कृ, भृ etc. as distinct from the verbal form, is never found in actual use, it is immaterial whether the word means root or verb.In the passages quoted above from the Nirukta and the Mahābhāsya referring to the four kinds of words, the word akhyata could be taken to mean root (भात) or verb (कियापद). The ākhyāta or verb is chiefly concerned with process of being and becoming while nouns (नामानि) have sattva or essence, or static element as their meaning. Verbs and nouns are concerned not merely with the activities and things in this world but with every process and entity; cf. पूर्वापरीभूतं भावमाख्यातेनाच्छे Nir. I.; अस्ति-भवतिविद्यतीनामर्थः सत्ता । अनेककालस्थायि-नीति कालगतपौर्वापर्येण कमवतीति तस्याः किया-लम् । Laghumañjūsā. When a krt. affix is added to a root, the static element predominates and hence a word ending with a krt. affix in the sense of bhava or verbal activity is treated as a noun and regularly declined; cf. इन्दिमहिता भावा द्रन्यवद् भवति M.Bh. on II. 2. 19 and III. 1.67, where the words गति, त्रज्या, पाक and others are given as instances. Regarding indeclinable words ending with krt. affixes such as कर्ते, इत्ला, and others, the modern grammarians hold that in their case the verbal activity is not shadowed by the static element and hence they can be, in a way, looked upon as ākhyātas; cf. अञ्चयक्ता भाषे Vaiyākaranabhūsana.

आख्यातप्रक्रिया a work dealing with verbs, written by Anubhūtisvarūpācārya on the Sārasvata Vyākaraṇa.

आख्यातिविके a work dealing with verbs and their activity by Kṛṣṇa-Shāstrī Āraḍe a great Nāiyāyika of the 18th century.

आस्यातन्याकरण a treatise on verbs discussing verbal forms by Vangasena.

आगन्तुक lit. adventitious, an additional wording generally at the end of roots to show distinctly their form e.g. चदि, एपि, सर्ति etc.; cf. इन्धिमवितम्यां च P I. 2. 6; cf. also भावलक्षणे स्थणुकुन्वदिन्तरिहृताभिजनि-भ्यस्ते। मुन् P. III. 4.16, मुधिनुदेश केन्न P. III. 4, 17 and a number of other sutras where gor fa is added to the root: cf. इक् दित्यी धातुनिर्देश, वर्णा-त्कार:, रादिफ: P. III. 3.108 Vart. 2.3. 4. where such appendages to be added to the roots or letters are given. The word अमन्त is an old word used in the Nirukta, but the term आगन्त्रक appears to be used for the first time for such forms by Haradatta; cf. हरेरिति ह कांटिल्य, आगन्तुकेकारे गुणेन निर्देश:Padamañjarī on VII. 2. 31. In the traditional oral explanations the second part of a reduplicated word is आगन्तुक which is placed

i.e. after the original by virtue of the convention आगन्त-नामन्ते निवेश:, although in fact, it is said to possess the sense of the root in contrast with first which is called abhyasa. A nice distinction can, however be drawn between the four kinds of adventitious wordings found in grammar viz.आगन्त, इत्, अभ्यास andआगम which can be briefly stated as follows; The former two do not form a regular part of the word and are not found in the actual use of the word; besides, they do not possess any sense, while the latter two are found in actual use and they are possessed of sense. Again the agantu word is simply used for facility of understanding exactly and correctly the previous word which is really wanted; the হুন wording, besides serving this purpose, is of use in causing some grammatical operations. अभ्यास, is the first part of the wording which is wholly repeated and it possesses no sense by itself, while, agama which is added to the word either at the beginning or at the end or inserted in the middle, forms a part of the word and possesses the sense of the word.

आगम augment, accrement, a word element which is added to the primitive or basic word during the process of the formation of a complete word or pada. The agama is an adventitious word element and hence differs from adesa, the substitute which wholly takes the place of the original or (आदेशिन्). Out of the several agamas mentioned by Pānini, those that are marked with mute & are prefixed, those, marked with \$\overline{3}\$, are affixed, while those, marked with म, are

placed immediately after the last vowel of the word. The augments become a part and parcel of the word to which they are added, and the characteristics of which they possess :cf.यदागमास्तदगुणी-भूतास्तदग्रहणेन गृह्यन्ते, also आगमानां आगमि-धार्मिवैशिष्ट्यम् Par. Sek. Pari.11. Those grammarians, who hold the view that words are unproduced and eternal, explain the addition of an augment as only the substitution of a word with an augment in the place of a word without an augment; cf. आंदेशांस्तर्हींमे भविष्यन्ति अनाग-मकानां सागमका: M. Bh. on I. 1.20; I. 1.46. The term agama is defined as अन्यत्र विद्यमानस्तु यो वर्णः श्रूयतेधिकः । आगम्यमानतस्यत्वात्स आगम इति स्मृत: Com. on Tait. Prāt.I. 23.

आङ्ग

आगमिन a base to which an augment is added: cf. एवमपि पञ्च आगमास्त्रय आगमिन: M.Bh. I.I. Āhnika 2.

आगर्वीय a class of roots forming a subdivision of the Curadigana or the tenth conjugation beginning with पद and ending with गर्व which are only ātmanepadin; e.g. पदयते, मृगयते, अर्थयते, गर्वयते.

आगस्य name of an ancient writer of Vedic grammar and Prātiśākhya works; cf. R. Pr. I.2.

scholar ancient आग्रायण an Nirukta quoted by Yāska; cf. अक्षि अष्ट: । अनक्तेरिति आग्रायण: Nir. I. 9.

आङ् the preposition आ. See the word all above.

আঙ্ক an operation prescribed in the section, called angadhikara, in the the Astadhayi of Panini, made up of five Padas consisting of the fourth quarter of the 6th adhyaya and all the four quarters of the seventh adhyāya. आङ्गात् पूर्वे विकरणा एषितब्या: M. Bh. on I. 3.60 Vart 5; cf. also वाणीदाङ्गं बलीयो भवति Par. Sek. Pari 55; also M. Bh. on III.2.3.

आच् tad. affix आ applied to the word दक्षिणा and उत्तराः cf.P.V. 3.36, 38. e. g. दक्षिणा वसति, उत्तरा रमणीयम् Kāś. on V.3. 36, 38.

आचार (1) customary usage of putting or employing words in rules; cf. आचार्याचारात्तंज्ञासिद्धः, P.I.1.1, Vārt. 4. (2) behaviour;cf. उपमानादाचारे P.III. 1.10; cf. also निवासत आचारतश्चM.Bh. on VI. 3.109.

आचारिकिए denom. affix किप् applied to any prātipadika or noun in the sense of behaviour; cf. सर्वप्रातिपदिकेम्य आचारे किब् वक्तज्यः अश्वति गर्दमति इत्येवमर्थम् M. Bh. on III. 1. 11; cf. इलन्तेम्य आचारिकियमानाच Par. Sek. on Parī.52.

आचार्य preceptor, teacher; a designation usually given to Pāṇini by Patañjali in the Mahābhāṣya; cf. the usual expression तज्ज्ञापयित आचार्यः as also आचार्यप्रहित्ज्ञीपयित; also cf. नेदानीमाचार्याः स्त्राणि कृत्वा निवर्तयन्ति; cf. also the popular definition of आचार्य given as " निराम्य यदिरं प्राज्ञा अविचार्येव तत्क्षणम्। संभावयान्ति शिरसा तमाचार्य प्रचक्षते।"

आवार्यदेशीय a partisan of the preceptor Pāṇini or the Sūtrakāra who is looked upon as having approximately the same authority as the Sūtrakāra; cf. आचार्यदेशीय आह— न बक्तव्य इति l Kaiyaṭa on I. 4. 105, Vārt. 2.

आचार्यसंपद् necessary qualification to teach the Veda with all its pāthas having the necessary knowledge of accents, mātrās and the like.Cf. पदकमविभागज्ञो वर्णकमविचक्षणः स्वरमात्राविद्यान्यसंपदम् R. Prāt.I. 8.

आचितादि a class of words headed by the word आचित which do not have their final vowel accented acute. by P. VI. 2. 146 when they are preceded by the prepositions प्र, प्रा etc. although they are used as proper nouns, e. g. आन्तिम्, निरुक्तम्, प्राश्चिष्टम्; cf. Kāsikā on P. VI.2.146.

आद (1) augment आ prefixed to roots beginning with a vowel in the imperfect, aorist and conditional, which is always accented (उदात); cf. P. VI. 4. 72; (2) augment आ prefixed to the imperative first person terminations, e.g. करवाणि, करवे etc.; cf. P. III. 4.92; (3) augment आ to be prefixed to caseaffixes which are दित् after nouns called nadī; e.g. कुमायं; cf P. VII. 3.112.

आटच् tad. affix (आट) in the sense of possession added to the word वाच्; e.g. वाचाट: cf. P.V.2. 125.

आत् (1) long आ as different from short or protracted अ prescribed by the word बृद्धि or दीर्घ in the case of अ, or by the word आत् when substituted for another vowel, as for example in the rule आदेख उपदेशेऽशिति and the following; cf. P. VI. 1.45, 57; (2) substitute for the ablative affix इन् after words ending in अ; cf. P. VII.1.12; (3) substitute आत् for a case affix in Vedic Literature, c.g. न ताद बाइणाद निन्दामि Kās. on VII. 1.39.

आताम् Atmanepada third person dual ending, technically substituted for लकार by P. III. 4.78

आति tad. affix आत् applied to उत्तर, अधर and दक्षिण by P.V.3.34.

आतिदेशिक applied by extension or transfer of epithet as opposed to ओपदेशिक. See the word अतिदेश; the term is often used in connection with rules or operations which do not apply or occur by the direct expression of the grammarian; cf. यदि आतिदेशिकेन कित्येन ऑपदेशिकं कित्वं

बाध्येत. M. Bh. on I.2.1.; cf. also आतिदेशिकमनित्यम् Par.Sek. Pari. 93.6.

आतिशायिक a tad-affix in the sense of excellence; a term applied to the affixes तम and इष्ठ as also तर and ईयस् prescribed by Pāṇini by the rules अतिशायने तमविष्टनो and द्विचन-विभन्नोपपदे तस्वीयस्नौ cf. P.V. 3.55, 57. This superlative affix is seen doubly applied sometimes in Vedic Lit. e g. श्रेष्ठतमाय कर्मणे Yaj. Sam. I.1; cf. also तदन्ताच स्वार्थे छन्दास दर्शन श्रेष्ठतमायित P.V.3.55 Vart. 3.

आतिशायिकान्त a word ending with an ātisāyika affix; cf. आतिशायिकान्तात्स्वार्थे छन्दिस आतिशायिको हक्यते M. Bh. on V. 3.55.

आत्व the substitution of long आ prescribed by the term आत् as in आंदच उपदेशेऽशिति and the following; cf. P. VI.1.45 etc.

आत्मन् agent or Kartr as in the terms आत्मनेपद or आत्मनेभाषा, cf. सुप आत्मनः क्यन्त्र III. 1.8.

आत्मनेपद् a technical term for the affixes called तङ् (त, आताम् etc.) and the affix आन (शानच्, चानश्, कानच्), called so possibly because, the fruit of the activity is such as generally goes to the agent (आत्मने) when these affixes are used. Contrast this term (Atmanepada) with the term Parasmaipada when the fruit is meant for another. For an explanation of the terms see P. VI.3.7 and 8.

आत्मनेपादेन a root which always takes the Atmanepada affixes. (See above).

आत्मनेभाष a technical term used for such roots as speak for the agent himself; the term आत्मनेभाष means the same as the term आत्मनेपदिन.

The term आत्मनेभाष is not mentioned by Pāṇini; but the writer of the Vārtikas explains it, cf. आत्मने-

भाषपरसेभाषयोद्ध्यसंख्यातम् P. VI. 3.7 and 8 Vart. 1; cf. also आत्मनेपदिनश्च घातवे। वैयाकरणेरात्मनेभाषदान्द्वेन व्यवह्नियन्ते, Kaiyata on VI.3.7. The term is found in the Atharva-Prātisākhya. III. 4.7. It cannot be said whether the term came in use after Pāṇini or, although earlier, it belonged to some school other than that of Pāṇini or, Pāṇini put into use the terms Ātmanepada and Parasmaipada for the affixes as the ancient terms Ātmanebhāṣa and Parasmaibhāsa were in use for the roots.

आत्व the substitution of आ; e.g. ताहक्, भवाहक्, अन्याहक् cf. आ सर्वनाम्न: P.VI.3. 90.

आत्वत् possessed of the vowel आ; containing the vowel आ; e.g. पाक;, दाय: etc. cf. कर्षात्वतो घनान्त उदात्तः P.VI. 1.159.

आदादिक belonging to the second conjugation or class of roots which begins with the root अद्; cf. दैशादिकस्येव ग्रहणं भविष्यति नादादिकस्य Pur.Pari. 67.

आदि (1) commencement, initial; cf. अपूर्वलक्षण आदि: M.Bh. on I.1.21, (2) of the kind of, similar; एवंप्रकार:.

आदिकर्मन commencement of an action; cf. आदिभूतः कियाक्षणः आदिकर्म Kās. on आदिकर्मणि कः कर्तरि च। P.III. 4.71.

आदित possessed of the mute indicatory letter आ signifying the non-application of the augment इ (इट्) to the past- pass. part. term क्त. e. g. क्ष्वण्ण from the root अक्षित्र; similarly खिन्न, भिन्न etc.cf. आदितश्च P.VII. 2.16.

आदिवृद्धि the Vrddhi substitute prescribed for the first vowel of a word to which a tad-affix, marked with the mute letter ज,ण, or क् is added; e.g. औपगव, दाक्षि e.c.; cf. तद्धितेष्वचामादेः P.VII.2.117, 118.

आदिष्ट (1) prescribed for substitution; specified for an operation; cf. सिद्धं दु आदिष्टस्य युड्वचनात् M.Bh. on VI.1. 155; cf. also M. Bh. on VI. 1.I58 Vārt. 3; M. Bh. on IV.3.23 Vār. 5; cf. also आदिशचैवाचः पूर्वः M. Bh. on I.1.57; (2) indicated or stated; आदिष्टा इमे वर्णाः.

आदेश (1) substitute as opposed to sthānin, the original. In Pānini's grammar there is a very general maxim, possessed of a number of exceptions, no doubt, that "the substitute behaves like the original" (स्थानिवदादेश: अनिस्ववी P.I.1.56.); the application of this maxim is called स्थानिवद्भाव; for purposes of this स्थानियद्भाव the elision (ले:प) of a phonetic element is looked upon as a sort of substitute;cf. उपधालापस्य स्थानिवस्वात Kāś. on P. I.1.58. Grammarians many times look upon a complete word or a word-base as a substitute for another one, although only a letter or a syllable in the word is changed into another, as also when a letter or syllable is added to or dropped in a word; cf. पचतु, पचन्तु ... इमेप्यादेशाः । कथम् । आदिश्यते यः स आदेशः । इमे चाप्यादिश्यन्ते । M. Bh. on I.1.56; cf. also सर्व सर्व-पदादेशा दाक्षीपुत्रस्य पाणिने: M.Bh. on P. I.1.20; cf. also अनागमकानां सागमका आदेशा: M. Bh. on 1.1.20; (2) indication, assignment; cf. योयं स्वरादेश; अन्तेदात्तं, वधराद्यदात्तत्वं, स्व: स्वरितिमिति आदेश: R.Pr.I.30-32; cf. also आदेश: उपदेश: com. on Tai.-Prāt. II.20: cf. also अनादेशे आविकार: V.Pr.IV.131, . where Uvvata remarks यत्र उदात्तादीनां स्वराणां सन्धी आदेशो न कियते तत्र अविकारः प्रत्येतन्यः। cf. also एकारा विभक्तयादेशः छन्दिस A.Pr. II. 1. 2, where प is prescribed as a substitute for a caseaffix and ले and असे are cited as examples where the acute acent is also prescribed for the substitute v. आदेशिन that for which a substitute is prescribed; the original, sthanin; cf. आदेशिनामादेशा: cf. also M. Bh. on P.I.1.56.

आद्य (1) premier; cf. इदमार्थ पदस्थानं (ब्याकरणनामकं) सिद्धिसोपानपविणाम् Vāk. Pad. I.16; (2) preceding, as opposed to succeeding (उत्तर); cf. सहार्थे- व्यंक्षने: V.Pr.I.100; (3) original; cf. आद्यप्रकृति: परमप्रकृति: (original base) Bhāṣā Vrṭṭi. IV. 1.93; (4) first, preceding, आद्ये योगे न व्यवाय तिङ: स्यु; M.Bh. on III.1-91.

आद्यन्तवस्य आद्यन्तवद्भाव, consideration of a single or solitary letter as the initial or the final one according to requirements for operations prescribed for the initial or for the final. Both these notions -- the initial and the final-are relative notions, and because they require the presence of an additional letter or letters for the sake of being called initial or final it becomes necessary to prescribe आधन्तवद्वाय in the case of a single letter; cf. সায়ন্র-वदेकस्मिन्। आदी इव अन्त इव एकस्मिन्निप कार्ये भवति । यथा कर्तव्यमित्यत्र प्रत्ययाग्रदात्तत्वं भवति एवमीपगविभत्यत्रापि यथा स्यात् । Käs. P.I.1.21; cf. also आयुन्तवच्य । अप्रक्तस्य आदिवदन्तवद्य कार्यं भवति । $T.\ {
m Pr.}$ I.55. This সায়-রয়স্থার of Pāṇini is, in fact, a specific application of the general maxim known vyapadeśivadbhāva by virtue of which "an operation which affects something on account of some special designation, which certain reasons attaches to the letter, affects likewise that which stands alone;" cf. Pari.Sck. Pari.

आयुदात्त a word beginning with an acute-accent i.e. which has got the first vowel accented acute; words in the vocative case and words

tormed with an affix marked with a mute ज or न areādyudātta; cf.P. VI.1.197, 198; for illustrations in detail see P. VI.1.189-216.

आद्यदात्तिपातन specific mention of a word with the accent udatta or acute on the first syllable; cf. आद्यदात्तिनपातनं करिष्यते M.Bh. on I.1. 56, VI. 1.12.

आधार receptacle or abode of an action;cf.आश्रयन्ते आस्मिन् किया: इत्याधार: Kāś. on P. I.4.45 also M. Bh. on III. 3.121; the Prakriyā Kaumudī mentions four kinds of ādhāras; cf. औपश्लेषिक: सामीपिको विषयो ब्यात इत्याधारश्चनुष्ठी Prak. Kau. on II.3.36.

आधाराधेयभाव a non-differential relation (अभेदसंसर्ग) between the personal endings तिप्, तस् etc. and the noun in the nominative case which is the subject of the verbal activity; relation of a thing and its substratum; cf. निपातातिरिक्तनामार्थ-धाल्वर्थनोभेदान्वयस्य अन्युत्पन्तत्वात्.

आधिक्य superfluity, superiority, notion of surplus; cf. यदत्राधिक्यं त्राक्यार्थ: स:M. Bh. on II. 3.46, II.3. 50.

आधुषीय a sub-division of roots belonging to the चुरादिगण or tenth conjugation beginning with युज् and ending with धृष् which take the Vikaraṇa णिच् optionally i.e. which are also conjugated like roots of the first conjugation; e.g. योजयित, योजयित, योजित; साहयित-ते, सहित.

आधेय a thing placed in another or depending upon another, as opposed to ādhāra or the container; cf. आधेयश्चाकियाजश्च सोसत्त्वप्रकृतिर्गुण: M. Bh. on P.IV.1.44.

आन (1) kṛt affix (য়ান র্, or বান য়) substituted for the lakāra লা and applied to ātmanepadi roots forming the present participle; (2) kṛt. affix কান র applied to ātmanepadi roots

in the sense of past time forming the perfect participle; cf. लिट: कानज्वा P.III. 2.106.

आनङ् substitute आन् in the place of the last letter (ऋ) of the first member of dvandva compounds of words meaning deities or of words showing blood-relationship which end with the vowel क; e.g. होतापोतारा, मातापितरा cf. P.VI.3.25, 26.

आनन्तर्थ (1) close proximity; absence intermediary of anv generally of the same nature: अनन्तरस्य भावः आनन्तर्यम्; cf. नाजानन्तर्ये बहिर्वप्रकुलाति: M. Bh. I.4.2. Vārt. 21: Par. Sek. Pari. 51. This close proximity of one letter or syllable or so, with another, is actually i.e. phonetically required and generally so found out also, but sometimes such proximity is theoretically existing as the letter required for proximity is technically not present there by the rule पर्वत्रासिश्दम. In such cases, a technical absence is not looked upon as a fault. cf. क्ष चिच्च सेनिपातञ्चतमानन्तर्ये शास्त्रक्रतमनानन्तर्ये यथा प्रत्ये, कचिच्च नैय संनिपातकतं नापि शास्त्रकृतं यथा जन्तवे । यत्र कुतश्चिदेवानन्तर्ये तदाश्रयिष्याम: M. Bh. on VIII. 3.13. (2) close connection by mention together at a common place etc.;cf. सर्वाद्यानन्तर्य कार्यार्थम् M. Bh. on I.1. 27.

आनन्द्दत्त name of a Buddhist grammarian, the author of the work named Cāndra-Vyākaraņa Paddhati.

आनर्थक्य absence of any utility; superfluity; absence of any object or purpose; cf. स्थानिवद्वचनानर्थक्यं शास्त्रा-सिद्धत्वात्। M. Bh. on P. VI. 1.86 Vārt. 5 cf. also P. VI. 1 158 Vārt. 4; VI. 1.161 Vārt. 1, VI. 1.166 Vārt. 1, VI.1.167 Vārt. 3.

आनि imp. 1st per. sing affix नि with the augment आ prefixed, which

has got its न changed into ण by P. VIII. 4.16.

आनुक् the augment आन्, added to the words इन्द्र, वरुण, भन and others before the fem. affix ई; e. g. इन्द्राणी, वरुणानी cf. इन्द्रवरुणभवदार्वस्द्र... आनुक् P. IV.1.49.

आनुनासिक्य nasalization; utterance through the nose, an additional property possessed by vowels and the fifth letters of the 5 classes (ङ्, ज्, ण्, न्, म्) cf. आनुनासिक्यं तेषामधिको गुण: M.Bh. on I.l. 9.

आनुपूर्वी serial order, successive order of grammatical operations or the rules prescribing them as they occur; cf. आनुपूर्व्या सिद्धमेतत् M.Bh. on V. 3. 5; cf. also ययैत चानुपूर्व्या अर्थानां प्रादुर्भावस्तयैत शब्दानामि । तद्दत् कार्यरिष भित्रक्षम् M.Bh. on. P. I. 1.57.

आनुपूर्व्ये successive order, as prescribed by tradition or by the writer; cf. ऋतुनक्षत्राणामानुपूर्व्येण समानाक्षराणां पूर्वनिपातः । शिशिरवसन्तौ उदगयनस्थौ । कृतिकारोहिण्यः । M.Bh. II. 2.34 Vārt. 3; also वर्णानामानुपूर्व्येण। ब्राह्मणक्षत्त्रियविद्शूदाः M.Bh. on II. 2.34 Vārt. 6; cf. पदानुपूर्व्येण प्रक्षिप्रान् संधीन कुर्यात् । इन्द्र आ इहि । आदौ इन्द्र आ इत्येतयोः; न तु आ इहि इत्येतयोः R. Pr. II. 2; cf. also आनुपूर्व्यात् सिद्धम् Sīra. Pari. 6.

आजुपूर्व्यसंहिता the samhitā-pātha or recital of the running Vedic text in accordance with the constituent words; e. g. गुनः रोपं चित् निदितम् or नरा रांस वा पूषणम्, as opposed to the अनानुपूर्व्यसंहिता which is actually found in the traditional recital e. g. गुनश्चिच्छेपं निदितम् Rk samh. V 2.7 or नरा वा रांस पूषणम् Rk samh. X. 64.3. See R. Prāt. II 43.

आनुमानिक obtained or made out by inference such as Paribhāṣī rules as opposed to Śrauta rules such as the Sūtras of Pāṇīni; cf. आनुमानिक स्थानित्समवयवयो; Kās. on VI. 1.85;

also cf. आनुमानिकस्थान्यादेशभावकल्पनेपि श्रोतस्थान्यादेशभावस्य न त्यागः Par. Sek. on Pari. 11; cf. also किं च पूर्वत्रत्यस्य प्रत्यक्षत्वेन आनुमानिक्या अस्या बाघ एवोचितः Pari. Sek. on Pari. 50.

आन्तरतम्य closest affinity; cf. अप्टन्-जनादिपथिमध्यात्वेषु आन्तरतम्यादनुनासिकप्रसङ्गः M.Bh. on VII. 2.84, as also आन्तर-तम्याच्च सिद्धम् M. Bh. on VII 1.96 Vart. 6.

आन्तरें proximity; close affinity; close relationship. There are four kinds of such proximity as far as words in grammar are concerned: Re: the organs of speech (स्थानतः) as in दण्डा- प्रम्, regarding the meaning (अर्थतः) as in चातण्ड्यपुत्रतिः, regarding the quality (गुण) as in पाकः रागः, and regarding the prosodial value (प्रमाण) as in अमुन्मे, अमुन्याम्; cf. अनकिथि आन्तर्य स्थानाथेगुणप्रमाणङ्कतम् Par. S'ek. Pari.13. cf. also Kāś. on I. 1.50.

आन्पद् word ending with आन् which has the consonant dropped and the preceding आ nasalized; e. g. सर्गा इत सजतम् Rk.Sam. VIII. 35. 20, महाँ इन्द्र: Rk Sam VI.19.1; cf. दीवांदि समानपाद, आतांऽटि नित्यम् P. VIII. 3.9, VIII. 3.3; cf. also इन्त देशों इति जता आन्-पदा: पदम्लय: R. Pr. IV. 26, 27.

आप् (1) common term for the fem. endings टान्, डान् and चान् given by Pāṇini in Adhy. IV, Pāda 1; cf. अञ्चयादास्तुप: P. II. 4.82. P. IV. 1.1.; P. VI. 1.68; cf. also P. VI. 3. 63. P. VII. 3. 44; P. VII. 3. 106, 116; P. VII. 4.15. etc.; (2) a brief term for case-affixes beginning with the inst. sing and ending with the loc. pl. cf. अनात्यक: P. VII. 2.112.

आपित (1) production; resulting of something into another; change; cf. दन्त्यस्य मूर्धन्यापित: नितः मूर्धन्यापित: प्रधन्यमाव: V. Prāt. I. 42 and Uvața's com. thereon; cf. also यमापित

explained as यमभावं R. Pr. VI. 9. (2) modification; cf. आपद्यते श्वासतां नादतां वा R. Pr. XIII. 1.; (3) contingency, undesired result.

आपत्य patronymic affix such as अण् and others. The term आपत्य, which is the same as the usual term अपत्य in तस्यापत्यम् P. IV. I, is found sometimes used in the Vārttikas and in the Mahābhāṣya; cf आनत्याङजीवद्वंस्यात्स्यार्थे द्वितीया युवसंशः P. IV. 1.163 Vārt 6.

आपदेव son of अनन्तदेव, the author of Sphotanirupana (17th cent. A.D.).

आपिशल (1) a work of आपिशल, possibly his grammar; cf. आपिशलमधीते M. Bh. on IV. 1.14; (2) a student of Āpiśali's grammar; आपिशलमधीते आपिशल ब्राह्मणी M. Bh. on IV 1.14; आपिशलपणिनीयन्याडीयगीतमीया; M. Bh. on VI. 2. 36.; cf. तथा चापिशलाः पाणिनीयाः पठन्ति—आगमोनुपञ्चातेन विकार-श्रोपमर्दनात् । आदेशस्तु प्रसङ्गेन लेगः सर्वापकर्षणात्.

आपिशलि an ancient grammarian mentioned by Pāṇini and his commentators like Patañjali, Helārāja and others; cf. वा सुप्यापिशले: P. IV. 3.98; तथा चापिशलेविध: M. Bh. on IV. 2.45.

आपुक् augment आप् added to the words सत्य, अर्थ and वेद before the affix णिचः cf. M. Bh. on III. 1.25 and Vart. 1 and 2 thereon; e. g. सत्यापयति, अर्थापयति, वेदापयति.

আয়ু augment (আবু) suggested in the place of আয়ুক্ by Patanjali to be prefixed to the affix णিच; cf. M. Bh. on III. 1. 25.

(the same as vyāpya). The term is used in connection with the object of a verb which is to be obtained by the verbal activity. The word আত্ম is found used in the sense of Karman or object in

the grammars of Jainendra, Sākatāyana, C'āndra and Hemacandra; cf. C'āndra II 1. 43; Jainendra I. 2. 119; Sāk. IV. 3. 120; Hem. III. 3. 31. Hence, the term साध्य is used for a transitive root in these grammars.

आवन्त ending with the fem. affix आ (टाप, डाप् or चाप्); cf. वाबन्त: P. II. 4. 30 Vart. 3.

आवाध (1) similarity of one phonetic element, for instance, in the case of ऐ with आ resulting from Samdhi; e. g. प्रजाया अरातिं निर्कत्या अकः where प्रजाया and निर्कत्या stand for प्रजाये and निर्कत्या stand for प्रजाये and निर्कत्या (2) Similarity of accent of words in the Samhitāpātha and Padapātha; (3) followed by; cf. A. Pr. II.1.14; (4) distress; cf. आवाध च, P. VIII. 1.10.

आभाच्छास्त्र a rule given in the section called आभीयप्रकरण extending from P. VI. 4. 22 to VI. 4. 175, wherein one rule or operation is looked upon as invalid to another; cf. असिद्धवदत्राभात् P. VI. 4. 22 and M. Bh. thereon; cf. also यावता अनिदितां हलः इत्यपि आभाच्छास्त्रम् Vyāḍi Pari. 38.

आभीक्ष्ण्य repetition of an action; cf. पौनः धुन्यं आभीक्ष्ण्यम् Kās. on III. 4.22; cf. M. Bh. III. 4.24; VIII. 1.4; VIII. 1.12.

आभीयकार्य an operation prescribed by a rule in the section called आभीय-प्रकरण. See आभाच्छास्त्र above.

आभीयप्रकरण a section of Pāṇini's grammar from VI. 4. 22 to VI. 4. 129, called आभीय, as it extends to the rule भस्य VI. 4. 129, including it; but as the governing rule भस्य is valid in every rule upto the end of the Pāda, the

आमीयप्रकरण also extends upto the end of the Pada. See आभाच्छास्त्र above.

आभीयासिद्धत्व invalidity or supposed invisibility of one rule with respect to another, in the section called आभीयप्रकरण. See आभाच्छास्त्र above.

आभ्यन्तरप्रयत्न internal effort made in producing a sound, as contrasted with the external one called बाह्यप्रयत्न. There are four kinds of internal efforts described in the Kāsikāvṛṭṭi.; cf. चत्वार आभ्य-तरप्रयत्नाः सवर्णसंज्ञायामाश्रीयन्ते — स्पृथ्ता, ईपल्सपृथ्ता, संवृतता, विवृतता चिति । Kās. on P. 1.1. 9. See also यत्नो द्विधा। आभ्यन्तरो बाह्यश्च etc. Sī. Kau. on I. 1.9.

आभ्यास changes prescribed in connection with the अभ्यास or reduplicative syllable; cf. अभ्यासिकार आभ्यास: M. Bh. on III. 1.6.

आम् (1) augment 'आ prescribed in connection with the words चतुर् and अनहुहू before the case-affixes called सर्वनामस्थान; cf. चतुरनड्हाराम् उदात: P. VII. 1. 98; (2) the affix आम् added before लिट् or a perfect termination by rules कास्त्रत्यवादाम् अमन्त्रे लिटि and the following (P. III 1, 35-39), as for instance, in कासांचके, ऊहांचके, दयांचके, जागरांचकार, विभयांचकार etc.; (3) geni. pl. caseaffix आम् as in हषदाम्, श्रारदाम्, with न prefixed in रामाणाम् etc., and with स prefixed in सर्वेषाम् etc.; (4) loc. sing. case-affix आम् substituted for इ (डि); cf. ड्राम् नद्यामनीभ्यः P. VI. 4. 116.

आमन्त्रण (1) calling out from a distance; (2) an invitation which may or may not be accepted; cf. विधिनिमन्त्रणामन्त्रणाभीश्यंप्रक्षप्रार्थनेषु लिङ् P. III. 3.161 whereon M. Bh. remarks अथ निमन्त्रणामन्त्रणयो: को विशेष: । अथ संनिहितेन

निमन्त्रणं भवति असंनिहितेन आमन्त्रणम् । नेषोस्ति विद्रोषः । असंनिहितेनापि निमन्त्रणं भवति संनिहितेनापि चामन्त्रणम् । एवं तर्हि यन्नियोगतः कर्तव्यं तन्निमन्त्रणम् । आमन्त्रणे कामचारः । M. Bh. on P. III.3,161.

आमिन्त्रत (1) a word in the vocative sing. cf. सामन्त्रितम् P. II.3.48; a tech. term in Pāṇīni's grammar, the peculiar features of which are पराङ्गबद्धाव (cf. P.II.1.2), अविद्यमानवद्धाव (cf. P.VIII.1.72), द्वित्व (cf. P.VIII. 1.8), आद्भुदात्तव (cf. P. VIII.1.198), सर्वानुदात्तव (cf. P. VIII.1.19), splitting of ए into आ and इ, c. g. अमे into अमा ३ इ (cf. P. VIII.2.107 Vārt. 3); (2) Vocative case, cf. ओकार आमन्त्रितज: प्रगद्ध: Rk. Prät. I.28; Vāj. Pr. III.139; II.17; II.24 VI.1.

आमन्त्रितकारक a word connected with the verbal activity possessed by आमन्त्रित e.g. छुण्डेन in छुण्डेनाटन्; cf. आमन्त्रिते या धातुवाच्या क्रिया तस्याः कारकम् Kaiyata on P. II.1.2.

आमन्त्र्य a word in the vocative case; lit. a word possessed of the sense of invocation; cf. आमन्त्र्यमाणेथं वर्तमानः हाब्द आमन्त्र्य: Sāk. I.3.88; cf. also आमन्त्र्यते यत्तदामन्त्र्यम् com. on Hem. II.1.25.

आभिनच् tad. affix आभिन in the sense of possession, applied to the word ख; cf. स्वाभिनेश्वये P. V.2.126.

आमिश्र completely mixed; cf. आमिश्र-स्यायमादेश उच्यते स नेव पूर्वप्रहणेन ग्रह्मते, नापि प्रमहणेन । तद्यथा । क्षीरोदक संपृक्ते आमिश्रस्या-न्नव क्षीरमहणेन ग्रह्मते नाप्युदकप्रहणेन M. Bh. on VI. 1.85; similarly आमिश्रस्य, आमिश्रीभूत etc.

आमु tad. assix (आम्) added to the assixes घ i. e. तर and तम which are placed after indeclinables; e. g. / किंतराम्, पचातितराम् etc. cf. P. V.4.11.

आम्रेडित (1) iterative; a repeated word, defined as द्विरुक्त पदम् cf. द्विरुक्तमाम्रेडित पदम् e. g. यज्ञायज्ञा

वो अग्नये Vāj. Prāt. I. 146; (2) the second or latter portion, of a repeated word according to Pāṇini; ci. तस्य (दिरुक्तस्य) परमाम्रोडितम् P. VIII.1.2. The Āmredita word gets the grave accent and has its last vowel protracted when it implies censure; cf. P. VIII.1.3 and VIII. 2.95. Haradatta has tried to explain how the term आम्रेडित means the first member; cf. ननु आम्रेडितशब्दे। निघण्टुजु प्रसिद्धः आम्रेडित दिक्षिरक्तमिति । सत्यमर्थे प्रसिद्धः इह तु शब्दे परिभाष्यते । महासंज्ञाकरणं पूर्वाचार्यानुरोधेन Padamañj. on VIII.1.2.

आम्रेडितसमास an iterative compound; cf. आम्रेडितसमासे तु। A. Prāt. III. 1. 5.

आय् the substitute आय् for ऐ before a vowel; e. g. चायक: for चै+अक: cf. एचोयवायाव: P VI.1.78.

आय (1) the affix आय applied to the roots गुन्, धून् and others ending with which they are looked upon as roots; cf. P. III. 1.28; P. III.1. 32. The affix is applied optionally when an ārdhadhātuka affix is to follow. e.g. गोपायिता, गोता; cf. P. III. 1.31; (2) augment; cf. असतो वर्णस्य उपजन: R. Prāt. XIV. 1 Uvata.

आयाम tension of the limbs or organs producing sound, which is noticed in the utterance of a vowel which is accented acute (उदात्त) आयामे गात्राणां दैर्घ्यमाकर्षणं वा; com. on Tait. Prāt. XXII. 9; cf. उद्यंगमनं गात्राणाम् वायुनिमित्तं Uv. on R. Prāt. III.1; cf. also उद्यंगमनं शरीरस्य com. on Vāj. Prāt. I. 31; cf. also आयामो दारण्यमणुता रवस्येत्युचे:कराणि शब्दस्य M.Bh. on P. I.2.29.

आय्य krt. affix आय्य before which णि (causal इ) is changed into अय् ;cf, अय् आमन्ताल्वाय्येत्न्विष्णुतु P. VI. 4.55. e.g. स्पृह्याय्य:

आर substitute आर for क in the words पितृ and मातृ; e.g. पितरामातरा; cf. P. VI.3.33.

आरक् tad. affix (आर) applied to the word गोधा in the sense of offspring according to the Northern Grammarians; e.g. गोधार:, (optional forms गोधेय and गोधेर acc. to others); cf. P. IV. 1.129, 130.

आरकन् tad. affix applied to the words शृङ्ग and वृन्द, e. g. शृङ्गारकः, वृन्दारकः; cf P. शृङ्गवृन्दाभ्यामारकन् P.V. 2.122 Vārt. 3.

आरडे KRISHNASHASTRI a reputed Naiyāyika of Banaras of the nineteenth century, who wrote, besides many treatises on Nyāya, a short gloss on the Sūtras of Pāṇini, called Pāṇini-sūtra-vṛtti.

आरि tad. affix applied to the word पूर्वतर when the whole word refers to a year, e.g. प्राप्त in the last year; cf. B. V. 3.22 Vart. 2.

आर krt. affix applied to the roots श्व and वन्द् in the sense of habituated etc. e.g. शराह:, वन्दाह:. cf. P. III. 2.173.

आरोप attribution or imputation of properties which leads to the secondary sense of a word; cf. अप्रसिद्ध अंजादिरिंग तद्गुणारोपादेव बुध्यते Par. Sek. on Pari. 15.

आरोपणीय same as अभिनिधान; see above अभिनिधान.

आर्थ resultant from sense; made up of sense; अर्थस्य अयम् आर्थ; cf. तदा-दितदन्तत्वमार्थसमाजप्रस्तम् Par. Sek. on Pari, 37.

आर्थसमाज combination of the meanings (of the base and affix); see the word आर्थ above.

আর্থযান্তক a term used in contrast to the term सार्वधातुक for such verbal and kṛt affixes, as are not personal endings of verbs nor marked with the mute letter A. सार्वषातुकम् । आधधातुकं तिङ् शित होब: 1 P. III. 4, 113 and 114. The personal endings of verbs in the perfect tense and the benedictive mood are termed ārdhadhātuka, cf. P. III. 4.115, 116; while both the terms are promiscuously found utilised in the Vedic Literature: cf. P. III. 4. 117. The main utility of the ardhadhatuka term is the augment इ (इट्) to be prefixed to the ardhadhatuka affixes. The term आর্থিখানুকা was in use in works of the old Vaiyākaranas; cf. अथवा आर्थधात्कास इति वश्यामि कास आर्थधातकास । उक्तिः स्र्वितः रूदिप प्रतितिषु श्रुतिषु संज्ञामु M. Bh. on II. 4.35. It cannot be said how the term ardhadhatuka originated. Probably such affixes or pratyayas, like the krt affixes generally, as could be placed after certain roots only were called ardhadhātuka, as contrasted with the verbal and the present participle affixes which were termed sārvadhātuka on account of their being found in use after every root.

আর্থিযানুকা old term for আর্থখানুক; sce আর্থখানুক.

आर्घेषातुकाधिकार the topic or section in Pāṇini's grammar where operations, caused by the presence of an ārdhatuka affix ahead, are enumerated, beginning with the rule आर्धघातुक VI. 4. 46 and ending with न स्यि VI. 4. 69. Such operations are summed up in the stanza अतो लोपो चलापश्च गिलोपश्च प्रयोजनम् । आङोप इत्वमेत्वं च चिण्वद्भावश्च सीयुटि; M. Bh. as also Kāś. on VI. 4. 46.

आर्थे derived from the holy sages; founded on sacred tradition, such as the Vedāngas; cf. कृतस्तं च वेदाङ्गमीन- न्द्रामार्थम् R. Prāt. XIV 50. The word is explained as स्वयंपाठ by the com. on Vaj Prat. IX.21, and as Vaidika samdhi on X. 13. Patanjali has looked upon the pada-pātha or Pada-text of the Samhitās of the Vedas, as anārṣa, as contrasted with the samhitā text which is ārṣa; cf. आप्याम् in the sense सहितायाम् R. Prāt. II. 27; cf also पदकार्याम लक्षणमन्त्रत्येम् M.Bh. on III. 1. 109.

স্থান্থ tad-affixes হনু, তমু etc. as also the senses in which the affixes are applied, given in the section of Paninis grammar P. V. 1. 9-71.

आल case affix in Vedic literature e.g. वमना योजा Kās, on VII. 1. 39.

আন্তৰ্ tad-affix (প্ৰাত) applied to the word গানু in the sense of 'talkative' e. g. বাখাত:; cf P. V.2, 124.

आलु tad. affix in the sense ' तन नहने ' e. g. शीताहः, उणाहुः P. V. 2.122.

आलुच् kṛt. aflix (आलु) applied to the roots स्मृह्, गृह् पत् etc.e.g. स्मृह्या हु:. गृह्या हु:, निश्च : etc. of P III. 2 158.

आवचन incomplete pronunciation, cf. ईग्रद अचनस् M.Bh. on I. 1, 8.

आवत् tad-affix applied to the word सम, cf. समानद् वसति M. Bh. on V. 4.30.

आवश्यक necessary notion or thing; cf. ओहावश्यके । अवस्थिमाव आवश्यकम् Kas. on III. 1. 125, III. 3. 170.

आविप्रलिक्स having a fixed gender as opposed to अनाविटिल्स possessed of all genders; cf. आविप्र- लिङ्गा जाविः । याङ्गितसुपादाय प्रवर्तते न ,ताङ्गितं जद्दाति M. Bh. on I. 2. 52; ✓ e. g. the word प्रमाण in प्रमाण वेदाः.

आवृत्ति repetition, c. g. पदावृत्तिः; scc com. on Vāj. Prāt. IV. 21; cf. also आवृत्तितः सप्तदशलं भवति M. Bh. I. 1. Ähn. 2.

आशिस् the benedictive mood; cf. किदारिषि P. III. 4. 104, called regularly as आशीर्लिङ्.

आश्रवोध (1) name of a work on grammar written by Taranatha called Tarka-vācaspatī, a reputed Sanskrit scholar of Bengal of the 19th century A. D. who great Sanskrit compiled the Dictionary named वाचस्पत्यकारा and wrote commentaries on Sanskrit Shastraic and classical works. The grammar called আয়ুবাঘ is very useful for beginners; (2) name of an elementary grammar in aphorisms written by रामकिंकर-सरस्वती, which is based on the Mugdhabodha of Bopadeva.

आश्रय (1) relation of dependence; cf. आश्रयात्मिद्धत्वं भविष्यति M. Bh. I. 1.12 Vārt. 4; (2) substratum, place of residence; cf. गुणवचनानां राब्दानामाश्रयतो लिङ्गवचनानि भवन्ति । गुक्रं वस्त्रम् । गुक्रा शाटी । गुक्रः कम्बलः । M. Bh. II. 2. 29.

आश्वलायनप्रातिशाख्य an authoritative Prātisākhya work attributed to Saunaka the teacher of Asvalayana, belonging prominently to the Sākala and the Baskala Sakhas of the Rgveda. It is widely known by the name Rk-Prātiśākhya. metrical composition divided into 18 chapters called Patalas, giving special directions for the proper pronunciation, recitation and preservation of the Rksamhita by laying down general rules on accents and euphonic combinations and mentioning phonetic and metrical peculiarities. It has got a masterly commentary written by Uvvata.

आसन्न nearest, most proximate; cf. विकारी यथासन्नम् V. Pr. I.142; cf. also the sūtra आसन्न: Śāk.I.1.7, explained as स्थानगुणप्रमाणादिाभिर्यथास्वमासनः; cf. also आसनः Hem. VII.4.120.

आसित close proximity of a word with another; cf. णौ इत्यस्य आसत्तिवशात्

इत एव संबन्धः। Pari. Bhaskar Pari. 97.

आस्तारपङ्कि a variety of पङ्क्ति metre of 40 letters with 8 letters in the first and second quarters or padas and 12 letters in the third and fourth quarters; cf. आस्तारपङ्किरादित: R.Pr. XVI. 40. For instances of आस्तारपङ्क्ति see Rgveda sūkta 21, Maṇḍala X.

आस्थापित (1) placed after, following, which follow; cf. आस्थापितानामनन्तरो- वतानाम् Uvvaṭa on R. Pr. IV. 1. (2) properly placed at the end e.g. सिष्यद इति सिष्यदे.

आस्य (1) place of articulation, the mouth, cf. अस्यन्त्येनन वर्णान् इति आस्यम् M. Bh. on I.1.9; (2) found in the place of articulation; e.g. the effort made for the utterance of words; cf.आस्य भवमास्यम् M. Bh. on I.1.9, also स्पृष्टादिप्रयस्तपञ्चकमास्यम् Laghuvitti on Sak. I.1.6.

आस्वदीय a sub-division of the ভুৱাবি
(Xth conj.) roots, beginning with
the root অনু and ending with the
root ভাৰু, which take the Vikarana
णিच i.e. which are conjugated like
roots of the tenth conjugation,
only if they are transitive in
sense.

आह्य tad-affix (आह) in the general Saisika senses, e.g. belonging to, produced in, etc., added to the word उत्तर, e.g. औत्तराह cf. उत्तरादाहम् वस्तव्य: 1; M.Bh. on IV.2.104.

आहि tad-affix added to the word दक्षिण in the general sense of direction but when distance is specially meant; e.g. दक्षिणाहि वसीत, दक्षिणाहि रमणीयम्. See Kāś. on आहि च दूरे P. V. 3.37.

आहिक name of Pāṇini. cf.पाणिनिश्चाहिको दाक्षीपुत्र:.

आहिताग्न्यादि a class of compound words headed by the word आहिताप्त

in which the past pass. part. is optionally placed first.e.g.आहिताझि:, अमयाहित:; जातपुत्र:, पुत्रजात:. The class आहितामयादि is stated to be आकृतिगण, cf. Kāś.on P.II.2.37.

₹

- इ (1) the vowel इ, representing all its eighteen forms viz. short, long protracted, acute, grave, circumflex, pure and nasalised; e.g. इ in स्योत च P.VI.4. 128;(2) Uṇādi affix इ (3)tad-affix इच्(इ)applied to Bahuvrihi compounds in the sense of exchange of action or as seen in words like द्विदण्ड e.g. केशाकाश, दण्डादाण्डि, द्विमुसले etc. cf. इच् कमंब्यतिहार P. V.4. 127, also V.4,128; (4) krt. affix कि (इ) cf. उपसर्गे घो: कि: P.III.3.92; (5) augment इट् (इ); see इट; (6) conjugational affix इट् of the 1st pers. sing. Ātm.
- इक् (1) short wording (प्रत्याहार) for the vowels इ, उ, ऋ and ऌ; cf. इको यणिय P. VI.1.77; एच इग्व्यस्वादेशे P. I.1.48; इको गुणवृद्धो P. I.1.3; इग्यणः संप्रसारणम् P. I.1.45, इको इस्कोऽडस्यो गालकस्य म. VI.3. 61; (2) krt. affix इक् (इ) applied to the root form to cite a root e. g. विद, जिन etc. cf. इक्श्तिपौ घातुनिदेशे P. III. 3.108 Vārt. 2; (3) krt. affix इक् applied to the roots कुष् and others in the sense of verbal activity e.g. कुषि:, किरि:, पिरि: cf. इक् कृष्यादिभ्यः P.III. 3.108 Vārt.8.
- इक्परिभाषा the Paribhāṣā rule इको गुणवृद्धी P.I.1.3; cf. गुणश्रुत्या इक्परिभाषा- पस्थानात् इक एव स्थाने गुणा यथा स्यात् Sīradeva. Pari.93.
- হক (1) substitute for the affix z given as হকু, হল or সিত by Pāṇini; cf. হন্টক: P.VII.3.50; (2) taddhita affix হক্ক, হক্ব থিকৰু mentioned in the Vārtikas on P.IV.2.60; (3) krt.

- affix इक applied to खन e.g. आखानिक: cf. इको वक्तज्य: P.III.3.125 Vart. 3. इकक् the same affix as ठक् mentioned by the वार्तिककार in the Vartikas on P. IV. 2.60.
- इकन् tad. affix इक applied to compound words with पद as the latter member e.g. पूर्वपदिक; cf. इकन्नदोत्तर-पदात् P.IV.2.60 Vart.
- इक्सबक krt. affix applied to खन् e.g. आखनिकबक: cf. इकबको वक्तब्य: P. III. 3.125 Vart. 4.
- इकार the letter इ with all its 18 varieties (इ+कार).
- इक्पदोपस्थिति the presence of the word इक् (vowels इ, उ, क and छ) in a rule, where the operations गुण and बृद्धि are prescribed by putting the words गुण and वृद्धि; e.g. सिचि वृद्धि: प्रसमेपदेषु P.VII.2.1; cf. इकी गुणवृद्धी P.I.1.3.
- इम्लक्षणवृद्धि the substitution of the vowel called वृद्धि i.e. the vowel आ, ए or औ prescribed specifically for the vowels called इक् i.e. इ, उ, क्र and लू, e.g. तस्मादिग्लक्षणा वृद्धिः P.I.1.3. Vart. 11; cf.also इंग्लक्षणवृद्धिप्रतिषेधस्तावत् Siradeva Pari. 2.
- इङ्ग the same as इङ्गय. See below. The word इङ्ग is used for इङ्गय in the Atharva Prātišākhya cf. नीहारादिष्यनि-ङ्गेशूत्तरपदे दीर्थ इङ्गेष्ठ च A.Pr. III. 3.12.
- इङ्ग्य a separable word as opposed to अनिङ्ग्य; part of a compound word which is separated or may be separated from the remaining part when the word is split up into its constituent parts. Generally the word is applied to the first part of a compound word when it is split up in the recital of the padapātha. The 'ingya' word is shown by a pause or avagraha after it which is shown in writing by the sign (s); cf. इङ्गयत विभागपदस्य संश्वा com. on Tait.

Prāt. 1. 48. सावग्रहं पदमिङ्गचम् Com.on T.Pr. I.48.

इच् (1) short wording or pratyāhāra for vowels except अ. cf. इजोदश्र गुरुमतोऽनुच्छ: P.III. 1.36; cf. also VI. I.104, VI. 3.68. VIII.4.31,32; (2) Samāsānta affix इ after Bahuvrihi compounds showing a mutual exchange of actions. e.g. केशाकेशि, दण्डादण्डि; cf. इच् कर्मन्यतिहारे P.V.4. 127 also 128.

इज् (1) krt. affix (इ), in the sense of verbal activity applied to any root, the word so formed being used in the fem. gender and in connection with narration or in interrogation; e.g. कां त्वं कारिमकाधी: । सवीं कारिमकाधी। cf. Pāṇini III.3.110; (2) krt. affix in the sense of verbal activity applied to the roots वर्ष and others e.g. वापि:, वासि: etc. cf. P.III.3.108 Vart. 7;(3) tad-affix इ in the sense of offspring applied to a noun ending iu अ; e.g. दाक्षि: cf. P.IV. 1. 95-7, 153.

इंद् (1) augment इ eprfixed, in general in the case of all roots barring a few roots ending in vowels except ऊ and ऋ and roots राक्, प्रञ्, etc., to such affixes of non-conjugational tenses and moods as begin with any consonant except इ and यु; cf. आर्थभातुकस्थेड चलादेः P.VII.2.35 to 78 and its exceptions P.VII.2.8 to 34: (2) personal ending of the third person sing. Ātm.

ण् (1) short wording or pratyāhāra for all vowels except अ and the consonants इ, य, य, य, ए, छ; cf. हणः षः P. VIII.3.39,also P. VIII.3.57,78 (2) kṛt. affix इ applied to roots such as अज् अत् etc. in the sense of verbal activity.e.g आजि:,आति:, आदि: cf.इणजादिस्य: P. III.3,108, Vārt.6.

इत् (1) a letter or a group of letters attached to a word which is not

seen in actual use in the spoken language: cf. अप्रयोगी इत, Sāk, I.1.5, Hem.1.1.37. The इत letters are applied to a word before it, or after it, and they have got each of them a purpose in grammar viz. causing or preventing grammatical operations in the formation of the complete word. Pānini has not given any definition of the word इत, but he has mentioned when and where the vowels and consonants attached to words are to be understood as इत: (cf. उपदेशेजनुनासिक इत्। हलन्त्यम्। etc. P. I. 3.2 to 8) and stated that these letters are to be dropped in actual use; cf. P.I. 3.9. It appears that grammarians before Panini had also employed such इत letters, as is clear from some passages in the Mahābhāsya as also from their use in other systems of grammar as also in the Unadi list of affixes, for purposes similar to those found served in Panini's grammar. Almost all vowels and consonants are used as इत for different purposes and the saletters are applied to roots in the Dhatupātha, nouns in the Ganapatha, as also to affixes, augments and substitutes prescribed in grammar. Only at a few places they are attached to give facility of pronunciation. Sometimes the হুর letters, especially vowels, which are said to be হ্ল, when uttered as nasalized by Pānini, are recognised only by convention; cf. प्रतिज्ञानुनासिक्याः पाण-नीयाः(S.K.on P.I.3.2). The word इत. which literally means going away or disappearing, can be explained as a mute indicatory letter. In Pāṇini's grammar, the mute vowel अ applied to roots indicates the placing of the Atmanepada affixes

after them, if it be uttered as anudata and of affixes of both the padas if uttered svarita; cf. P.I.3. 12, 72. The mute vowel आ signifies the prevention of इंडागम before the past part. affixes; cf. P. VII. 2. 16. Similarly, the mute vowel \(\xi\) signfies the augment न after the last vowel of the root: cf.P.VII.1.58; ਵ signifies the prevention of the augment इ before the past part.affixes cf.P.VII.2.14;3 signifies the inclusion of cognate letters; cf.P.I.1.69, and the optional addition of the augment इ before ला; cf. P. VII.2. 56; 5 signifies the optional application of the augment sz;cf.P.VII. 2.44; 新 signifies the prevention of हुस्व to the vowel of a root before the causal affix, cf.VII.4.2; ऌ signifies the Vikaraņa স্বৰ্ in the Aorist cf. P.III.1.55; ए signifies the prevention of Vrddhi in the Acrist,cf. P.VII.2.55; ओ signifies the substitution of \(\pi \) for \(\pi \) of the past part. cf. P. VIII.2.45; & signifies the prevention of गुण and बृद्धि, cf. P. I. 1.5; ব signifies the addition of the augment मुम् (म्) and the shortening of the preceding vowel; cf.P.VI.3. 65-66; ग signifies the prevention of गुण and बाद्धि, cf.P. I.1.5; चू signifies कुत्व, cf, P.VII.3.62; ङ्, applied to affixes, signifies the prevention of गुण and बृद्धि; cf. P.I.1.5; it causes संप्रसारणादेश in the case of certain roots, cf. P. VI.1.16 and signifies आत्मनेपद if applied to roots; cf.P. I. 3.12, and their substitution for the last letter if applied to substitutes. cf. P. I.1. 53. च signifies the acute accent of the last vowel; cf.P.VI.1. 159; ञ् signifies उभयपद i.e. the placing of the affixes of both the podas after the root to which it has been affixed;cf.P.I.3.72; z in the case of an augment signifies its application

to the word at the beginning; cf.P I.1.64, while applied to a nominal base or an affix shows the addition of the fem. affix ई (डांप्), cf.P.IV.1. 15; signifies the elision of the last syllable; cf. P.VI.4.142; m signifies वृद्धि, cf.P.VII.2.115:त signifies स्वरित accent, cf. VI.1.181, as also that variety of the vowel (हस्व, दीर्घ or ष्ट्त) to which it has been applied cf. P.I.1.70; न signifies आग्रदाचा cf. P.VI.1.193: प signifies अनुदात्त accent cf. अनदात्ती माप्पती P. III. 1.4. as also उदात for the vowel before the affix marked with g cf. P.VI.1.192; म signifies in the case of an augment its addition after the final vowel.cf.P.I-1.47, while in the case of a root, the shortening of its vowel before the causal affix for, cf. P.VI.4.92; \(\xi\) signifies the acute accent for the penultimate vowel cf.P.VI_1.217; \square signifies the acute accent for the vowel preceding the affix marked with 평; cf.P.VI. 193; ব্য় implies in the case of an affix its सावधातकत्य; cf. P. 111.4.113. while in the case of substitutes. their substitution for the whole स्थानिन् cf. P.I.1.55; प significs the addition of the fem. affix ই (ভাষ) cf.P.IV.1.41; in the case of affixes signifies पद्धंजा to the base before them, cf. P.I.4.16. Sometimes even without the actual addition of the mute letter, affixes are directed to be looked upon as possessed of that mute letter for the sake of a grammatical operation e.g. सार्वधातुकमित् P.I.2-4; असंयोगााहिट कित् P. I·2.5; गाता णित् P.VII.1.90 etc. (2) the short vowel इ as a substitute; cf. शास इदङ्हला: P. VI. 4, 34.

इतच् tad. affix इत in the sense of 'found' or 'produced in', which is affixed to words तास्का, पुष्प, मुद्धल and

others; é. g. तारिकत, मुकुळित, सुप्तित, दुःखित etc.; cf. तदस्य संजातं तारकादिम्य इतच् P. V. 2. 36.

इतरेतर possessed of interdependence; depending upon each other; cf. इतरेतरं कार्यमसद्देत् Candra Pari. 5%. Grammatical operations are of no avail if the rules stating them are mutually depending on each other. The word इतरेतर has the sense of इतरेतराश्रय here.

इतरंतरयोग mutual relationship with each other. Out of the four senses of the indeclinable च viz. समुब्रय, अन्वाचय, इतरंतरयोग and समाहार, the Dvandva compound is formed of words connected in the last two ways and not in the first two ways. The instances of द्वन्द्व in the sense of इतरंतरयोग are धवख-दिरपढाशाः, प्रक्षन्यप्रोधौ etc; cf. Kas. on P. II. 2.29; cf. also प्रक्षश्च न्यप्रोधोप प्रक्षसहाय इति M. Bh. on II. 2. 29; cf. also इतरंतरयोगः स यदा उदिक्तावयवभेदो भवति Siradeva Pari. 16.

इतरेतराश्रय depending upon each other; cf. इतरेतराश्रयाणि च कार्याणि न अकल्पन्ते । तद्यथा । नौर्नाधि बद्धा नेतरे-तरत्राणाय भवति । M. Bn. on I.1.1. See इतरेतर above.

इत्कार्य a grammatical operation caused by इत् i. e. by a mute letter which is purely indicatory; cf. एवं तिई इत्कार्याभावादत्र इत्संज्ञा न भविष्यति M. Bh. I. 3.2. See इत् above.

इस्व the substitution of short इ by स्याध्योरिच P. I. 2.17, शास इदङ्हलें।: P. VI. 4. 34, etc.

र्**इत्थंभूतलक्षण** characterization; indication by a mark; e. g. जटाभि-स्तापस: cf. इत्थंभूतलक्षणे च (तृतीत्या) P. II. 3.21.

kṛt affix mentioned by Pāṇini in VI.4.55 as causing the substitution

of अय for ण before it; e. g गदयिलु:, स्तनियलु: M.Bh. on VI. 4.55.

इत्र kit affix, added to the roots ऋ, छ, धू etc. in the sense of instrument; cf. अर्तिल्य्न्यूस्वनसहचर इत्र: P.III. 2.184-6. e. g. अरित्रम्, लवित्रम् खनित्रम् etc. The words ending in इत्र have got the acute accent on the last syllable; cf. P. VI. 2.144.

इत्संज्ञक a letter which is termed इत्; see इत् above.

इथुक् augment इथ्, e. g. यानितथः, तान-तिथः; cf. नतोरिश्रुक् P. V. 2. 53.

हित् possessed of the mute indicatory letter इ; e. g the roots निद, विदि and the like, in whose case the augment नुम् (न) is affixed to the last vowel; cf इदितो नुम् धातोः P. VII. 1.58.

इन (1) kit affix इ applied to the roots कृ, ह, प्रह, and मृ when they are preceded by certain words like स्तम्ब etc. in certain senses; e. g. स्तम्बकरि:, पळप्रहि:, आत्मभिर:; cf. P. III. 2. 24-7;(2) kit affix इन (णिनि) prescribed by P. III. 3.170 e. g. अवस्येक्सरी, शतदायी.

इन (1) substitute for the inst. case ending in आ (टा) after bases ending in अ; cf. टाङसिङसामिनात्स्या: P. VII. 1. 12; (2) tad. aff. इन affixed to पूर्व e. g. पथिमि: पूर्विणे: cf. P. IV. 4. 133.

इनङ् substitute इन् for the last vowel of the words कल्याणी, सुभगा, दुभगा and others before the affix ढ i. e. एय prescribed after these wordsi n the sense of offspring e. g. काल्याणिनेयः, सौभागिनेयः, कौळटिनेयः etc..cf.कल्याण्यादीना-मिनङ् P. IV. 1. 126, 127.

इনच্ tad. affix इन in the sense of possession applied to the word নি which is changed into ভিক, e. g. ভিকিন:;cf. হন্দ্ৰ থিত্ৰ ভিকাভি च P.V. 2. 33.

इाने (1) krt affix इन् applied to the roots की with बि, जु with प्र, and the

roots जि. इ. क्षि and others, e. g. सोमविक्रयी, प्रजवी, जयी etc. cf. P. III. 2. 93 and III. 2. 156-157; (2) tad. affix इन् affixed to the word पाण्डुकम्बल in the sense of 'covered with' (cf. P. Iv.2.11), in the sense of collection to the word खल e. g. खिलनी cf. P. IV. 2. 51, to the word अनुब्राह्मण in sense 'student of' e.g. अनुब्राह्मणी cf. P. IV. 2. 62, to the words कर्मन्द and কুয়ান্ত্র cf. P. IV. 3.111, to the word चर्ण cf P.IV. 4. 23 and to the word श्राद्ध cf. P.V. 2. 85 and साक्षात् cf. P. V. 2. 91 in specified senses and in the general sense of possession to words ending in 3, cf. P. V.2.115-117 and to certain other words cf. P. V. 2. 128-37.

इनुण् krt affix इन्. by P. III. 3. 44 followed invariably by the tad. affix अण् by P. V. 4. 15, e. g. सांरा- विणम्, सांकृटिनम्.

इन्दिरापाति author of 'परीक्षा' a commentary on the Paribhāṣendu-Śekhara of Nāgeśabhaṭṭa.

इन्दुमित्र author of अनुन्यास, a .commentary on Nyāsa, the well-known commentary on the 'Kāsīkāvṛtti' by Jinendrabuddhi. Many quotations from the Anunyāsa are found in the Paribhāṣāvṛttī of Sīradeva. The word इन्दु is often used for इन्दुमित्र; cf. एतस्मिन् वाक्ये इन्दुमैत्रेययोः शाश्वतिको विरोध: Sīra. Pari. 36.

হ**ন্ত্রপকা**হা author of a commentary on the Paribhāṣenduśekhara.

हुन्द्र name of a great grammarian who is believed to have written an exhaustive treatise on grammar before Panini; cf. the famous verse of Bopadeva at the commencement of his Dhatupatha इन्द्रश्चन्द्र: काशक्तरनापिशली शाकटायनः। पाणिन्यमरजैनेन्द्रा जयन्त्यष्टादिशाब्दिका: No work of -11 Indra is available at present. He is nowhere quoted by

Pānini. Many quotations believed to have been taken from his work are found scattered in grammar works, from which it appears that there was an ancient system prevalent in the eastern part of India at the time of Panini which could be named ऐन्द्रव्याकरणपद्धति. to which Pānini possibly refers by the word प्राचाम. From references, it appears that the grammar was of the type of प्रक्रिया, discussing various topics of grammar such as alphabet, coalescence, declension, context, compounds, derivatives from nouns and roots, conjugation, and changes in the base. The treatment was later on followed by Säkatāyana and writers of the Katantra school. For details see Mahābhāsya ed. by D. E. Society, Poona, Vol. VII pages 124-127

इन्द्रद्त author of the 'Gūḍhaphakkikāprakāśa', a gloss on the difficult passages in the Mahābhāṣya.

इप् a technical term for द्वितीया (accusative case) in the Jainendra grammar; cf. क्रमेणीप् Jain 1.4.2.

इंप् a technical term in the Jainendra Vyākarna for सत्तमी (the locative case).

इफ tad. affix applied to र (letter र्) in the sense of the consonant र; e. g. रेफ:; cf. रादिफ: P. III. 3. 108 Vart. 4.

इम् augment इ added to the base तृणह, after the last vowel, e. g. तृणिढि; cf. तृणह इम् P.VII. 3. 92.

इमन् or इमिन्च् tad. affix इमन् applied to the words पृथु, मृदु, महत्, लघु, गुरु, words showing colour and words such as दृढ, परिवृढ, भृश, शीत, उष्ण etc. in the sense of 'quality' or 'attribute'; cf. Pāṇ. V.1.122, 123. For changes in the base before the affix इमन् see P. VI.4.154-163.

- इमप् kṛt. affix इम applied to words showing भाव or verbal activity; e.g. पाकिमम्, त्यागिमम्;cf. भावप्रत्ययानतादि-मञ्चक्तन्य: Kāś. on P. IV.4.20.
- इय tad affix (घन्) in the sense of 'pity'; e. g. देविय:, यशिय:; cf. P. IV. 2. 79.
- ছয়ত্ substitute for the last ছ before a vowel generally in the case of monosyllabic roots ending in ছ and the word দ্লী; e. g. चিश্বিयु:, নিখী নিয়া, দ্লিখী দ্লিয়া: cf. স্তানি মুঘানুমূহা ফ্ল্যাথৈভূবভী P. VI. 4. 77-80.
- इया case-ending for inst. sing. in Vedic Literature; e. g. उर्विया, दार्विया; cf. P. VII. 1.39. and Vart.1 thereon.
- हर् mute indicatory ending of roots, signifying the application of the aorist sign अ (अङ्) optionally; e.g. अभिदत् or अभैत्सीत् from the root भिद् (भिदिर् in Dhātupātha); cf. also अच्छिदत्,अच्छैत्सीत from छिद् (छिदिर्); cf. P. III. 1.57.
- इरच् tad. affix (इर) in the sense of possession applied in Vedic Literature to रथ e.g. रथिरः; cf. P. V. 2. 109 Vārt. 3.
- इरन tad. affix (इर) in the sense of possession applied in Vedic Literature; to नेवा e. g. cf. P. मेविरः V. 2.109 Vart. 3.
- **इरित्** a root ending with mute indicatary ending इर्. See इर्.
- इरे (इरेच्) substitute for the perfect 3rd pers. pl. Atm. affix झ; e. g. चिकरे, ऊचिरे etc.; cf. P. III. 4.81.
- হল tad. affix applied to the words কাহা, अश्वत्थ, पलाহা and others in the four senses prescribed in P. IV. 2.67-70; e. g. কাহািল:, অশ্বনিথল:, ঘলাহাল:; cf. P. IV. 2.80.
- ইন্তর্ (1) tad. affix হল (হল্ল্) in the sense of pity; e. g. देविय:, যাঁহল:; cf.

- P.IV.2.79. The tad.affix चन् is also affixed in the same sense. See इंय. (2) tad. affix इल (इलच्) in the sense of possession, prescribed after the words फेन, लोमन् किप, सिकता, शर्करा, तुन्द, उदर, घट, यब etc.; e. g. फेनिल, लोमल, कपिल, सिकतिल तुन्दिल etc. cf. P. V. 2.99, 100, 105, 117.
- इश substitute for इदम् before an affix called 'vibhakti'; e. g. इह; cf: P. V. 3.3.
- इष्ट a word frequently used in the Vārttikas and the Mahābh-āsya and other treatises in the senses of (1) a desired object, (2) a desired purpose, (3) a desired statement, (4) a desired form i. e. the correct form; cf. इष्टान्वाख्यान खल्विप भवति: M. Bh. I.1. Ahn. 1. योगविभागादिष्टसिद्धि: Pari. Sek. Pari. 114.
- इप्रतन्त्रन्याकरण a short treatise on grammar ascribed to Jayadeva.
- हणादि a class of words headed by the word इष्ट to which the taddhita affix इन (इनि) is added in the sense of अनेन i. e. 'by him' i. e. by the agent of the activity denoted by the past pass. participles इष्ट and others: cf. इष्टी यहे, पूर्ती आहे etc. Kāś. on P. V. 2. 88.
- इष्टि a word generally used in the statements made in the Mahā-bhāsya, similar to those of the Sūtrakāra and the Vārttikakāras, which are 'desired ones' with a view to arrive at the correct forms of words; cf. प्राप्तिशे देवानां-प्रियो न त्विष्टिशः, इष्यत एतद् रूपमिति M. Bh. on II. 4.56.
- इष्ट the superlative tad. affix इष्टन् in the sense of अतिशायन or अतिशय (excellence). The commentators, however, say that the taddhita affixes तम and इष्ट, like all the taddhita affixes showing case-relations,

are applied without any specific sense of themselves, the affixes showing the sense of the base itself (खार्थ); e. g गुरतमः, गरिष्टः; पद्यतमः, पिरष्टः; पद्यतमः, पिरष्टः; पद्यतिसमाम्, कर्नृतमः, करिष्टः etc.; cf. P. V.3. 55-64. The affixes ईयस् and इष्ठ are applied only to such substantives which denote quality; cf. P. V. 3. 58.

इष्टन the same as इष्ट. See इष्ट.

इष्टबद्भाव possession of the same properties for causing grammatical operations as the tad. affix इष्टन् possesses, as for instance, the elision of the syllable beginning with the last vowel (टिलीप), substitution of the masc. base for the fem. base (पुंबद्धाव) etc., before the denom. affix णिच्; e. g. एतयित in the sense of एनी आच्छ; similarly प्रथयित, पटयित, द्वयित; cf. M. Bh. on. P. VI 4. 155 Vārt. 1.

हणा krt affix इणान् applied, in the sense of 'possessed of habitual behaviour, action, or splendid accomplishment,' to the roots अलंक, निराक्त, प्रजन, उत्पत्त etc. e. g अलंकरिष्णु:,उत्पतिष्णु:, सहिष्णु:,चरिष्णु: etc.; cf. P. III 2.1 '6-138.

इच्ये kṛt affix in Vedic Literature in the sense of the infinitive, e. g. रेहिंच्ये, अन्यथिन्ये; cf P. III. 4.10.

इस (1) substitute इस for the vowel of the roots, मी, मा, दा, धा, रभ, पत् etc. before the desiderative affix सन्; e. g. मिस्त्रति, दित्सति, आरिप्सते etc. cf.P. VII. 4.54; (2) unadi affix इस् e. g. सर्पम्.

इस्तुच् alternative affix mentioned in the Mahābhāṣya in the place of इणुच्; cf M. Bh. on III. 2. 57. See इणुच्.

20%

the long vowel & which is technically included in the vowel

ह in Pānini's alphabet being the long tone of that vowel; (2) substitute ई for the vowel आ of the roots an and well before the frequentative sign यह as for example in जेब्रीयत, देध्मीयते, cf. P. VII. 4.31: (3) substitute \(\frac{1}{2}\) for the vowel अ before the affixes न्वि and क्यच् as, for instance, in शुक्कीमवित. पुत्रीयति etc.; cf. P. VII. 4.32, 33; (4) substitute ই for the vowel আ at the end of reduplicated bases as also for the vowel আ of bases ending in the conjugational sign ना, e.g. मिमी ध्वे, दुर्नात: etc.; cf. P.VI. 4. 113; (5) substitute ਵੇਂ for the loc. case affix হ (ভি) in Vedic Literature, e.g. सरसी for सरसि in हति न गुश्कं सरसी शयानम्,; cf. Kāś. on P. VII. 1.39; (6) tad. affix \(\frac{1}{2} \) in the sense of possession in Vedic Literature as for instance in रथी:,समद्रली:, cf. Kāś on. P. V. 2.109; (7) the fem. affix ई (ভীপু, ভীন্ or ভীন্); cf. P. IV. 1.5 8, 15-39, IV. 1.40-65, IV. 1.13.

हैक tad. affix ईकक added to राकि and यिष्ट e. g. शाकिक: fem. शाकिकी; याधिक:; cf. P. IV. 4.59; (2) tad. affix ईक added to कर्क and लेहित in the sense of comparison, e. g. कार्कीक:, लेहितीक: (स्पटिक:), cf. Kās. on P. V. 3.110; (3) tad. affix ईकक added to विहम्, e. g. बाहीक:; cf. बहिष्टिलेपा यक्ष, ईककच P. IV.1.85. Vārt. 4-5; (4) tad. affix इकज् in Vedic Literature added to बहिस् e.g. बाहीक: cf. Kās. on P. IV. 1.85, Vārt.6; (5) tad. affix ईकन added to खारी e. g. बिस्वारीकम; cf. P. V. 1.33.

इद् augment ई prefixed to a Sārvadhātuka (strong) affix beginning with a consonant after the roots झू, रू, स्तु, and others e. g. अमबीत्, रोरवीति, स्तवीति, अकाशीत्, अवादीत् etc.; cf. P. VII. 3.93–98. इत long vowel ई as different from इ or ई३ prescribed as a substitute; cf. P. VI.3.27, VI.3.97.

हादित (a root) possessed of long ई as a mute indicatory ending meant for prohibiting the addition of the augment इ to the past part. terminations ह and त्वत्; e. g. लगः, दीतः etc.; cf. P VII. 2. 14.

इंग्लिन a desired object, which, in connection with transitive roots, gets the designation कर्म, when the agent has a keen desire for it; cf. कर्नुरी- स्थितनमं कर्म P. I. 4. 49.

ईमसच् tad. affix ईसस added to the word मल in sense of possession; e. g. मलीमस:, cf. P. V. 2.114.

ईय substitute for the tad. affix छ; e.g. शालीय:, मालीय: etc; cf P. VII. 1. 2 and IV. 2. 114.

इंगड् affix ईय added to the root ऋत्, ङ् showing the application of the Atmanepada affixes; e. g. ऋतीयंत; cf. P. III. 1. 29

ईयस् tad-afflx ईयमुन्, showing superiority or excellence of one individual over another in respect of a quality, added to a substantive expresive of quality; when the substantive ends in the affix नृ, that affix नृ is removed; e.g. पटीयान्, लभीयान्, गरीयान्, दोहीयसी (धेनु:); cf.P.V.3.57-64.

ईयसुन the same as ईयम् which see above.

ईरच् tad-affix added to the word अण्ड in the sense of possession; e.g. अण्डीर:;cf. काण्डाण्डादीरनीरनी P.V.2.111.

ईश substitute ई for इदम् before the tad-affixes हक्, हश् and बतु; e.g. ईहक्, ईहश: also ईहस:; cf. P.VI.3.90.

ईश्वरकान्त author of 'Dhātumālā', a short metrical treatise on roots.

ईश्वरानन्द author of (1) a gloss on Kaiyaṭa's Mahābhāṣya-pradīpa, and (2) an independent treatise Sāb-dabodhataraṇgiṇī. He is believed to have been a pupil of सत्यानन्द and lived in the latter part of the 16th century A.D.

हैषच्छ्रास an external effort (बाह्य-प्रयत्न) in the production of sound charactorized by the emission of breath, when the cavity made by the cords of the throat is kept wide apart, as found in the utterance of the consonants हा, ष and स.

इंबत्स्पृष्ट an external effort (बाह्यप्रयत्न) in the production of sound charactorized by only a slight contact of the cords of the throat, made in the utterance of semi-vowels; cf. ईवत्स्पृष्ट-मन्तः स्थानाम् S.K. on P.I.1.9.

ईषद्समाप्ति stage of the quality of a thing or of an undertaking which is almost complete, to show which, the tad-affixes करूप, देश्य and देशीय are applied to a word; e.g. पहुकरूप:, पहुदेश्य: पहुदेशीय:, पञ्चतिकरूपम्, जरूपतिकरूपम्; cf. P, V.3.67.

ইঘনাৰ an external effort characterized by slight resonance or sounding of throat cords when they slightly touch one another.

ईहा effort made for the production of sound; cf. आपद्यते श्वासतां नादतां वा वक्त्रीहायां उभयं वान्तरोभौ। ईहायाम् चेष्टायाम R.Pr.XIII.1.

ड

ਤ (1) labial vowel standing for the long ज and protracted জ in Pāṇini's grammar unless the consonant त is affixed to it, उत् standing for the short उ only; (2) Vikaraṇa affix उ of the 8th conjugation (तनादिगण) and the roots धिन्त् and कुण्यु:cf.P.III. 1.79-80; (3) substitute (उ) for the vowel अ of कृ.e.g. कुरुतः, क्रवेन्ति before weak Sārvadhātuka affixes, cf.P.VI

4.110; (4) krt. affix 3 added to bases ending in सन् and the roots आशंस, भिक्ष, विद, इष् as also to bases ending in क्यच् in the Vedic Literature,e.g. चिकीषु: भिक्षः, विन्दुः,इन्छः,सुम्नयु; (5) Unādi cf. P. III. 2.168-170; affix उ (उण्) e.g, कारुः, वायुः, साधुः, etc.; cf. Unādi I.1; (6) mute vowel 3 added to the first letters of a class of consonants in Pānini's grammar to show the whole class of the five letters; e.g. E, E, E, E, U, which stand for the Guttural, the palatal the lingual, the dental and the labial classes respectively; cf. also हुना हु: P.VIII.4.41;(7) उ added to न showing the consonant न as nasalized n; cf, \exists : V.Pr. III.133.

उक् short term (प्रत्याहार) for the vowels उ, क्र and ल; e.g. उगिदचां सर्वनामस्थानेऽ धातोः P.VII.1.80, also श्च्युकः; किति P VII.2,11, इसुसुक्तान्तान् क्तः P.VII.3,

उक (1) the kit. affix ভক্ষ্ applied to the roots ভ্ৰু, পন্, पৰ্ and others, e.g. ভাজুক:, কামুক: etc. with udatta accent on the first syllable; cf, P.III.2.154; (2) tad.affix ভক্ষ (ভক্ষ্) added to the word কৰ্মন e.g. কামুক অনু:; cf. Kas. on P.V.I.103.

ওক্ষ্ the same as ভক্ত. See ভক্ত

उक्त prescribed, taught, lit, said (already). उक्तं वा is a familiar expression in the Mahabhasya and Vārttikas referring usually something already expressed. Sometimes this expression in the Mahābhāsya, referring to something which is not already expressed, but which could be found subsequently expressed, leads to the conclusion that the Mahābhāsyakara had something 'Laghubhāsya' before him at the time of teaching the Mahābhāsya. See Kielhorn's Katyayana and Patañjali, also Mahābhāṣya D.E. S.Ed. Vol. VII, pages 71, 72.

उक्तपुंस्क a word with its meaning (in the neuter gender) unchanged when used in the masculine gender; generally an adjectival word; cf, Cāndra Vyāk. I.4.30.

उक्तार्थ a word or expression whose sense has been already expressed. The expression उक्तार्थानामप्रयोग: is frequently used in the Mahabhāṣya and the Vārttīkas and cited as a Paribhāṣā or a salutary conventional maxim against repetition of words in the Parībhāṣāpāṭhas of Vyāḍi (Par. 51), Candragomīn (Par 28) and Kātantra (Par. 46) and Kālāpa (Par. 46) grammars.

उक्ताप्रयोग see उक्तार्थ.

डाकिपद, उक्तिपदानि a short anonymous treatise on case-relations, compounds etc. written mostly in Gujarāti.

उक्तिरत्नाकर a short grammar work, written by साधुसुन्दर, explaining declension, cases and their meanings, compounds, etc. and giving a list of Prākṛta words with their Sanskrit equivalents.

उक्थादि a class of words headed by the word उक्थ to which the taddhita affix इक (उक्) is applied in the sense of 'one who studies and understands'; cf. उक्थमधीते वेद वा औरिथक:, similarly लीकायतिक: Kāś. on P. IV. 2.60.

उख्य a writer on Vedic phonetics and euphony quoted in the Taittirīya Prātišākhya; cf. उख्यस्य सपूर्वः Tai. Prā. VIII. 22.

उगित् characterized by the mute indicatory letter उ, ऋ or ल; see उक्.

उप्रभूति or उप्राचार्य writer of a gloss on the Nirukta, called 'Niruktabhāṣya' believed to have lived in the 18th century A. D; wrijer also of a grammatical work Sisyahitāvṛtti or Sisyahitānyāsa, which was sent to kāshmir and made popular with a large sum of money spent upon it, by his pupil Ānanadpāla.

उङ् a technical term for उपधा, the penultimate letter in the Jainendra Vyākaraņa; cf. इदुदुङ: Jain. V. 4.28.

उच्च the higher tone also called उदात or acute; cf. नीचमुन्चात् R. T. 55, also एते स्वरा: प्रकम्पन्ते यत्रोष्चस्वरितोदयाः R. Pr. III. 19; cf. also the terms उच्चश्रुति R. T. 61, एकोच्च R. T. 62, आद्युच्च, अन्तोच्चक. etc.

उच्चे: उच्च or acute; see उच्च above; cf. उच्चेस्तरां वा वषट्कार: P. 1.2.35.

उचारेत pronounced or uttered; the phrase उच्चरितप्रध्वासिन: is used in connection with the mute indicatory letters termed হুর in Pānini's grammar, as these letters are not actually found in use in the language and are therefore supposed to vanish immediately after their purpose has been served. The phrase 'उच्चरितप्रध्वासिनोऽनुबन्धाः ' has been given as a Paribhāsā by Vyādi (Pari.11), in the Candra Vyākarana (Par. 14), in the Kätantra Vyākarana (Pari.54) and also in Kālāpa Vyākaraņa (Par. 71). Patanjali has used the expression उच्चरितप्रश्वंसिनः in connection with ordinary letters of a word, which have existence for a moment and which also vanish immediately after they have been uttered; cf. उच्चरितप्रव्वंसिनः खब्विप वर्णाः ...न वर्णो वर्णस्य सहाय: M. Bh. on I.4. 109.

उच्चरितप्रध्वंसिन् vanishing immediately after utterance. See उच्चरित.

उचारण pronunciation, enunciation (in the Sastra). The phrase उच्चारण-सामध्यीत is often found used in Mahābhāsya and where connection with the in words of Pāṇini, everyone of which believed to have a purpose or use in the Sastra, which purpose, if not clearly manifest, is assigned to it on the strength (सामर्थ्) of its utterance; cf. उच्चारणसामर्थ्यादत्र (हिन्यो:) उत्वं न भविष्यति M.Bh. on III.4.89 V. 2; cf. also M.Bh. on IV.4.59, VI.4. 163, VII.1.12, 50, VII.2.84. In a few cases, a letter is found used by Pāṇīni which cannot be assigned any purpose but which has been put there for facility of the use of other letters. Such letters are said to be उच्चारणार्थ: cf. जिन्धः । इकार उच्चारणार्थः। नानुबन्धः। Kāś. on II 4.36. न्लि छुडि.। इकार उच्चार-णार्थ:; चकार: स्वरार्थ:। Kāś. on III.1. 43. The expressions मुख्यस्वार्थ: and श्रवणार्थ: in the Mahābhāsya mean the same as उच्चारणार्थ:.

उच्चावच diverse; cf. उच्चावचेष्वथेंबु भवित निपाताः Nir. I.3.4.

उचैस्तरां specially accented; उदात्ततर; cf. उन्चैस्तरां वा वषट्कार; P. I. 2.35.

on the Uṇādi sūtras. His work is called Uṇādisūtravṛtti, which is a scholarly commentory on the Uṇādisūtrapāṭha, consisting of five Pādas. Ujjvaldatta is belived to have lived in the 15th century A. D. He quotes Vṛttinyāsa, Anunyāsa, Bhāgavṛttī etc. He is also known by the name Jājali.

उञ् (1) short term (प्रत्याहार) for vowels excepting अ and इ, semi-vowels, nasal consonants and the cansonants इ, झ and भ्.; cf मय उञ्जा वा P. VIII.3.33; (2) the par-

ticle ভ: cf. ভাঈ ভা पदे P. VIII. 3.21, also ভস: P. 1. I.17.

उष्णादि a class of words headed by the word স্তুক্ত which have their final vowel accented acute (স্ত্রান); cf. স্তুক্ত: म्लेच्छा, जस्प:। एत घञनता इति সিল্বে: प्रात:। Kās. on P. VI. 1.160.

उद् augment उ affixed to the roots वृ and तृ before the kṛt affix तृ; cf. तृरुतृतकृत्वरुतृ वकृतृत्वरुतीरिति तरतेष्ट्रेङ्ग्नेश्च तृचि उट् ऊट् इत्येतावाग निपात्येते Kāś. on P. VII.2.34.

उण् the affix उण्, causing वृद्धि on account of the mute letter ण, prescribed after the roots कृ, वा, पा, जि, मि, स्वद्, साध् and अश्च by the rule कृतापाजिमिस्विदसाध्यश्च उण् which is the first rule (or Sūtra) of a series of rules presbribing various affixes which are called unādi affixces, the affix उण् heing the first of them. e.g. कारः, वायु, स्वादु, साधु etc.; cf. Uṇādī I, l.

उणादि affixes headed by the affix उण्, which are similar to krt affixes of Pāṇini, giving derivation mostly of such words as are not derived by rules of Panini. No particular sense such as agent, object etc. is mentioned in connection with these affixes, but, as Panini has stated in "ताम्यामन्यत्राणादय:" P. III. 4.75, the various Unadi affixes are applied to the various roots as prescribed in any Kāraka sense, except the संप्रदान and the अपादानः in other words, any one of the senses, agent, object, instrument and abode, is assigned to the Unadi affix as suits the meaning of the word. Although scholars believe that the Unadi affixes are given by a grammarian later than Pānini as there are words like ताम्बूल, दीनार and others included in the list of Unadi

words and that there are many interpolated Sūtras, still the Uṇād collection must be looked upon as an old one which is definitely mentioned by Pāṇini ín different rules; cf. Panini उणादयो वहूलम् P. III. 3.1 and ताम्यामन्यत्रो-णादयः III. 4. 75. Patañjali has given a very interesting discussion about these Unadi affixes and stated on the strength of the Vārttika, নঙ্গীणাदিप्रतिषेधः, that these affixes and the words given in the Unadi collection should not be considered as genuinely derived. The derivation is not a very systematic and logically correct one and therefore for practical purposes, the words derived by the application of the affixes 39 and others should be looked upon as underived; cf. उणाद्याऽब्युत्पन्नानि प्रातिपदिकानि. M. Bh. on. P. I. 1.16, III. 4.77, IV. 1.1, VI. 1.62, VII. 1. 2. VII. 2. 8 etc. There is a counterstatement also seen in the Mahabhasya उणादयो न्युत्पन्नानि, representing the other view prevailing at the time; cf. M. Bh. on III. 1. 133; but not much importance seems to be attached to it. The different systems of grammar have different collections of such words which are also known by the term Unadi.Out of the collections belonging to Pānini's system, three collections are available at present, the collection into five padas given in the printed edition of the Siddhanta Kaumudī, the collection into ten Pādas given in the printed edition of the Prakriya-Kaumudi and the collection in the Sarasvatīkanthabharana of Bhoja forming Padas 1, 2 and 3 of the second Adhyāya of the work,

उणादिकोश a metrical work explaining the उणादि words referred to above, with meanings assigned to them. There are two such compositions one by Rāmatarkavāgīśa or Rāmaśarmā and the other by Rāmacandra Dīksita.

उणादिमातिपदिक word form or crude base, ending with an affix of the un class, which is looked upon as practically underived. the affixes un and others not being looked upon as standard affixes applied with regular meanattached to them capable of causing operations to the preceding base as prescribed by rules of grammar; cf. उंणांद्योऽ व्युत्पन्नानि प्रातिपदिकानि । व्युत्पन्नानीति द्याक-टायनरीत्या। पाणिनेस्त्वब्युत्पत्तिपक्ष एवेति शब्देन्दु-शैखरे निरूपितम्. Pari. Sek. on Paribhāsā 22.

उणादिस्त्र, उणादिस्त्रपाठ the text of the Sūtras which begins with the Sūtra prescribing the affix उण् after the roots क, वा, पा, जि, स्वद्, साध and अश्; cf. Uṇādi Sūtra l. 1. For the different versions of the text see उणादि. Similar Sūtras in Kātantra, Āpiśali, Sakatāyana and other systems of grammar are also called Unādi Sūtras.

उणादिसूत्रद्शपादी the text of the Uņādi Sūtras divided into ten chapters believed to have been written by शाकटायन. It is printed at the end of the Prakriya Kaumudī and separately also, and is available in manuscripts with a few differences. Patanjali in his Bhasya on P.III.3.1, seems to have mentioned Sākatāyana as the author of the Unadi Sutras although it cannot be stated definitely whether there that time, a version

the sūtras in five chapters or in ten chapters or one, completely different from these, as scholars believe that there are many interpolations and changes in the versions of Unādi sūtras available at present. A critical study of the various versions is extremely desirable.

उणादिस्त्रपञ्चपादी the text of the Uṇādi Sūtras divided into five chapters which is possessed of a scholarly commentary written by Ujjvaladatta. There is a commentary on it by Bhaṭṭojī Dīkṣita also.

उणादिस्त्रवृति a gloss on the Uṇādi Sūtras in the different versions. Out of the several glosses on the Uṇādi Sūtras, the important ones are those written by Ujjvaladatta, Govardhana, Puruṣottamadeva, Rāmacandra Dīkṣita and Haridatta. There is also a gloss called Uṇādisūtrodghāṭana by Miśra. There is a gloss by Durgasimha on the Kātantra version of the Uṇādi Sūtras.

उत् (1) Short vowel उ in Pāṇini's terminology; cf, P.I.1.70, I,2.21. IV.1.44, V.1.111; (2) tad-affix उत् applied to पूर्व and पूर्वतर for which पर is substituted; e. g. परत्. See P. V. 3.22 Vārt.

उत्करादि a class of words headed by the word उत्कर, to which the taddhita affix छ is added in the four senses, the affix being popularly known as चातुर्रार्थिक; cf. उत्करीयम्, शक्रीयम् etc.; Kāś. on P. IV. 2.90.

उत्क्रम a variety of the Krama described in the Prātisākhya works.

उत्तम (1) the best, the highest, the last; (2) the last letter of the consonant-classes, the nasal; cf, A.Pr.II.4.14; R.Pr. IV.3; cf. also अनुत्तम meaning non-nasal; (3) the उत्तमपुरूष or the

premier or the first person constituting the affixes मि, वस् and मम् and their substitutes, cf. P.I.4.107.

- उत्तर (1) following, subsequent, e. g. उत्तरपद, the latter part of a compound word; (2) end of a word, पदान्त; cf. उत्तरे पदान्ते वर्तमान: Com. on T. Pr. III.1.
- उत्तरकालम् subsequently, then, afterwards; cf. तत् उत्तरकालमिदं दृष्टम् M.Bh. on I.1.1.
- उत्तरत्र in subsequent rules; cf. उत्तर-त्रानुवर्तिष्यते M. Bh. on I.1.23.
- उत्तरपद the latter member or portion of a compound word as contrasted with पूर्वपद; cf. पतिरुत्तरपदमाद्यदात्तम् A. Pr. II. 3. 11; cf. also अलुगुत्तरपदे P. VI. 3.1.

उत्तरकप ulterior form.

उत्तरार्थ serving a purpose in subsequent rules; of use in a subsequent rule; cf. योगविभाग उत्तरार्थ:, त्वाग्रहणमुत्तरार्थम् M. Bh. on I.2.22.

उत्थान elevation of tone.

- उत्पत्ति (1) production; cf. वर्णोत्पत्तिः production of a phonetic element T. Pr. 23.1; (2) production of a grammatical element such as the application of an affix or addition of an augment or substitution of a letter or letters during the process of word-formation; cf. गतिकारकोपपदानां कृद्धिः सह समासवचनं प्राक् सुबुत्पत्तः Pari. Sek. Par. 75; M. Bh. II. 2.19. Vart. 4.
- उत्पद् to be produced, to be placed after; to be annexed; (caus.) to produce, to get annexed, to add; cf. धेनुरनाञ्च कमुत्यादयति Apiśali's Vārt. quoted in M: Bh. on P.IV.2.45.
- স্ত্ৰন্থ author of a commentary on Pāṇini's Lingānusāsana. It is doubtful whether he was the same as স্বভ-

- भइ or भहोत्पल, the famous astrologer of the tenth century.
- उत्वत् possessed of short उ; cf. नोत्वद्वर्ध-विल्वात् P.IV.3.151.
- उत्सगे a general rule as contrasted with a special rule which is called अपवाद or exception; cf. उत्सर्गापवादयो-रपवादो बलीयान Hema. Pari. 56; प्रकल्प्य वापवादविषयं तत उत्सर्गोभिनिविद्यते Par.Sek. Pari.63, Sîra. Pari.97; cf. also उत्सर्ग-समानदेशा अपवादाः. For the बाध्यवाधकभाव relation between उत्सर्ग and अपवाट and its details see Nāgesa's Paribhasendusekhara on Paribhāṣās 57 to 65: cf. also न्यायैर्मिश्रान् अपवादान्प्रतीयात explained by the commentator as न्याया उत्सर्गा महाविषया विधयः अपवादा अल्प-विषया विधयः । तान् उत्सर्गेण मिश्रानेकीकृतान् जानीयात । अपवादविषयं मक्त्वा उत्सर्गाः प्रवर्तन्ते इत्यर्थः R. Pr. I.23.
- उत्सूत्र not consistent with what is taught in rules of a Sāstra; cf. अनुत्सूत्रपदन्यासा सद्वृत्तिः सन्निवन्धना । शब्द-विदेश नो भाति राजनीतिरपस्पदा Sisupālavadha II.
- उत्सङ्गादि a class of words headed by the word उत्सङ्ग, to which the taddhita affix इक् (ठ) is added in the sense of तेन हरति (takes away by means of); cf. हरतिदेशान्तरप्रापण वर्तते। उत्सङ्गेन हरति औत्साङ्गिकः। ओडुपिकः। Kāś. on P IV.4.15.
- उत्सादि a class of words headed by the word ভ্ৰম to which the taddhita affix अञ्, instead of the usual affixes अण and others, is added in the sense of an offspring; cf. औत्सः, औदपानः etc. Kāś. on P.IV.1.86.
- उद्य that which follows; a term frequently used in the Prātiśākhya works in the sense of 'following' or पर; cf. उदयस्वरादिसस्थानो हकार एकेषाम् explained by the commentator as आत्मन उपरित्वरादिसस्थान: T.Pr.II.47; cf. also ककार उदये कण्ड्यो explained by the commentator as ककारे उदये परमूत

सित R.Pr.II.11;cf. also नोदात्तस्वितोदयं P.VIII.4.67.

उद्यंकर surnamed Pāthaka who wrote a commentary on the Laghuśabdenduśekhara named Jyotsnā and a very critical work on Paribhāśās similar to Sīradeva's Paribhāśāvṛtti; the work is incomplete.

उद्यकीर्ति author of a treatise giving rules for the determination of the pada or padas of roots; the treatise is named पदन्यवस्थास्त्रकारिकाटीका. He was a Jain grammarian, and one of the pupils of Sādhusundara.

उदात the acute accent defined by Pāṇini in the words ভন্তব্যন্ত: P.I.2. 29. The word ਤਵੈ: is explained by Patanjali in the words आयामा दारुण्यं अणुता खस्य इति उच्चै:कराणि शब्दस्य' where आयाम (गात्रनिप्रह restriction of the organs), বাহত্য (হুল্লরা rudeness) and खस्य अणुता (कण्ठस्य संवृतता closure of the glottis) are given as specific characteristics of the acute accent. The acute is the prominent accent in a word—a simple word as also a compound word-and when a vowel in a word is possessed of the acute accent, the remaining vowels have the अनुदात्त or the grave accent. Accent is a property of vowels and consonants do not possess any independent accent. They possess the accent of the adjoining vowel connected with it. The accent corresponds to termed 'accent' in English and other languages.

उदात्तर raised acute, a tone slightly higher than the acute tone which is mentioned in connection with the first half of a circumflex vowel; cf. तस्योदात्तरोदात्तादर्थमात्रार्थमेव वाR.P.III.2

उदात्तानिदेश conventional understanding about a particular vowel in the wording of a sūtra being

marked acute or udātta, when ordinarily it should not have been so, to imply that a Paribhāṣā is to be applied for the interpretation of that Sutra; cf. उदाचितदेशात्सिद्धम् P.VI.1.13 Vārt.14, also Sīra. Pari. 112.

उदात्तमय an accent made up of Udătta, i. e. an accent which is a reduced udātta. It is called also प्रचय. It is mentioned in connection with an acute vowel following इति in the Padapātha, according to Kāṇva's view;cf. उदात्तमयोन्यत्र नीच एव अन्तेदान्तमध्योदात्तयोः पर्वणोरंन्यत्र इति कारणात् परो नीच उदात्तमय एव मवति प्रचित एव मवतीत्यर्थः com. on V. Pr. I.150

उदात्तश्रुति the same as एकश्रुति, accentless tone, mention d in connection with the latter half of a circumflex vowel as also with a grave vowel or vowels, if not followed by another acute or circumflex vowel; cf. नोदात्तस्वरितोदयं P.VIII.4.67.

उदात्तसम similar to udatta although not exactly acute, which characterizes the latter half of the circumflex vowel; cf. उदात्तसमञ्जाष: T.Pr.I.42.

उदाहरण a grammatical example in explanation of an interpretation; cf. नैकमुदाहरणमसवर्णप्रहणं प्रयोजयित P.VI. 1.11.

उदित characterized by short उ as a mute indicatory vowel, by virtue of which the word कु, for instance, signifies along with क् its cognate consonants ख, ग, व and ब also; cf. अणुदित्सवणस्य चाप्रत्ययः P. I. 1. 69. Roots marked with उ as mute get the augment इ optionally added before the kṛt affix क्ला; e.g. शिक्ला and शान्त्वा from the root शम् (शमु) by virtue of the rule उदितों वा P.VII.2.56,

उ**दुपधन्व** possession of short उ as the penultimate letter, e. g. इदुदुष्धस्य चाप्रस्यस्य P.VII.3.41.

उद्गात्रादि a class of words headed by the word उद्गातृ to which the taddhita affix अञ् is added in the sense of 'nature' or 'profession'; cf. उद्गातुर्भाव: कम वा औद्गात्रम् । Similarly अवित्रम् Kāś. on P. V. 1.129.

उद्ग्राह alleviation, ease, relief; name given to a Samdhi in the Prātisā-khya works when a visarga and a short vowel अ preceding it are changed into short अ, (e. g. यः + इन्द्र: = य इन्द्रः), as also when the vowel ए or ओ is changed into अ being followed by a dissimilar vowel; e. g. अमे + इन्द्रः = अम इन्द्रः; cf. R.Pr.II.10.

उद्शाहपदवृत्ति name given in the Rk.
Prātišakhya to the Udgrāhasamdhi
where the vowel আ is followed by a long vowel; e.g, কঃ ইঘন =ফ
ছ্যুন R.Pr.II.10.

उद्ग्राह्वत् name given to a saridhi in the Rk. Prātīśākhya when the vowel अ or आ is changed into अ e.g. प्र क्रमुभ्यः =प्रक्रमुभ्यः also मधुना + क्रतस्य=मधुन क्रतस्य cf. R. Pr. II. 11.

उद्धात elevation; named also उचीभाव.

उदार (1) elision, a term used in the sense of 'lopa' in the ancient grammar works; (2) name of a commentary on the Haima-lingānuśāsana.

उद्देश description; mention of qualities; cf. गुणै: प्रापणम् M. Bh. on I. 3.2; the word is used in contrast with उपदेश or direct mention; ef. कः पुनरुदेशोपदेशयोविशेषः । प्रत्यक्षमाख्यानमुपदेशो गुणै: प्रापणमुदेशः । प्रत्यक्ष तावदाख्यानमुपदेशः तद्यथा । अगोज्ञाय कश्चिद्धां सम्थिन कर्णे वा गहीत्योपदिशति । अयं गौरिति । स प्रत्यक्षमाख्यातमाह । उपदिष्टो में गौरिति । गुणै: प्रापणमुदेशः । तद्यथा । कश्चित्कंचिदाह । देवदत्तं में भवानुदिशतु इति । स इहस्थः पाटलिपुत्रस्थं देवदत्तमुदिशति । अङ्गदी कुण्डली किरीटी...ईहशो देवदत्त इति । स गुणै: प्राप्यमाणमाह । उदिष्टो में देवदत्त इति । स. Bh.

on I. 3.2; (2) spot, place, passage of occurrence; उद्देश उपदेशदेश:; cf. यथोहेशं संज्ञापरिभाषम् Pari. Sek. Pari. 2.

उद्देश्य referred to; pointed out, subject, as contrasted with the predicate मानान्तरप्राप्तमुद्देश्यम् ; cf. उद्देश्यप्र-तिनिर्दिस्यमानयोरैक्यमापादयत् सर्वनाम पर्यायेण तत्तालिङ्गमाक् । तद्यथा । दै।त्यं हि यत्सा प्रकृति-र्जलस्य, शैत्यं हि य यत्तत्प्रकृतिर्जलस्य वा ! उद्देश्य in grammar refers to the subjectpart of a sentence as opposed to the predicate-part. In the sentence वृद्धिरादेच the case is strikingly an opposite one and the explanation given by Patanjali is very interesting;cl.तदेतदेकं मङ्गलाथे आचायरय मृष्यताम् । माङ्गालिक आचार्यः महतः शास्त्रीयस्य मङ्गलार्थं वृद्धिशन्दमादितः प्रयुङ्के M. Bh. on I. 1.1.

उद्देश्यविधेयभाव relationship between the subject and the predicate where generally the subject is placed first in a sentence; cf. उद्देश्यवचनं पूर्व विधेयत्वं ततः परम् । cf. also तादात्म्यसंसर्गकस्थळ विशेष्यत्वमेन उद्देश्यं विशेष्यत्वमेन विधेयम् Padavākyaratnākara.

उद्योत the word always refers in grammar to the famous commentary by Nāgeśabhatta written in the first decade of the 18th century A. D. on the Mahābhāof Kaiyata. syapradīpa Uddyota appears to be one of the earlier works of Nagesa. also called Vivarana. The commentary is a scholarly one and is looked upon as a final word re: the exposition of the Mahabhasya. It is believed that Nagesa wrote 12 Uddyotas and 12 Sekharas which form some authoritative commentaries on prominent works in the different Sastras.

उद्योतनप्रभा name of a commentary on the 'Tantrapradipa' of Maitreya Raksita, which latter is a commentary on Jinendrabuddhi's Nyāsa which itself is a commentary on Jayāditya's Kāśikā.

उप् a technical term in the Jainendra Grammar for the terms लुन् and लुक्; cf. अन्तरङ्गानिप विधीन् बहिरङ्ग उप् बाधते. Jain. Pari. 85, प्रकृतिप्रहणे यडुवन्तस्यापि ग्रहणम् Jain Pari. 20.

उपकादि a class of words headed by the word उपक after which the taddhita affix, added in the sense of गोत्र (grand-children etc.) is optionally elided, provided the word is to be used in the plural number; cf. उपकलमका: भ्रष्टककपिष्ठला: also उपका:, औपकायना:; लमका:, लामकायना; भ्रष्टका: भ्रष्टकयः। Kāś. on P. II. 4. 69.

उपगीत a fault in the pronunciation of letters, noticed sometimes in the utterance of a letter adjoining such a letter as is coloured with a musical tone on account of the proximity of the adjacent letter which is uttered in a musical note and which therefore is called 'प्रगीत'; cf. प्रगीत: सामबदुचारित: । उपगीत: समीपवणान्तरगित्यानुरक्त:। Kaiyaṭa's Pradīpa on M.-Bh. I. Āhnika 1.

उपग्रह a term used by the ancient grammarians in the sense of the Parasmaipada and the Atmanepada affixes. The word is not tound in Panini's Astadhvavi. The Varttikakara has used the word in his Varttika उपग्रहप्रतिषेधश्च on P. III. 2.127 evidently in the sense of Pada affixes referring to the Atmanepada as explained by Kaivata in the words उपग्रहस्य आत्मने-पदसंज्ञाया इत्यर्थे: I The word occurs in the Slokavārttika सुतिङ्गप्रहलिङ्गनराणां quoted by Patanjali in his Mahabhāsya on ब्यत्ययो बहुलम् P. III. 1.85, where Nāgeśa writes ভাইয়-व्युद्धयं स्वार्थत्वादि । इह तत्प्रतीतिनिमित्ते परस्मै- पदात्मनेपदे उपग्रहशन्देन लक्षणये।च्येते । The word is found in the sense of Pada in the Mahābhāsya on P. III. 1.40. The commentator on Puspasūtra explains the word as उपगृद्यते समीपे पठ्यते इति उपग्रहः. The author of the Kāśikā on P. VI. 2.134 has cited the reading चुर्णादीन्यप्राण्युपग्रहात् instead of चुर्णादी-न्यप्राणिषष्ठ्याः and made the remark तत्रीपग्रह इति षष्ठयन्तमेव पूर्वाचार्योपचारेण गृह्यते. This remark shows that in ancient times उपग्रह meant षष्ट्यन्त i. e. a word in the genitive case. This sense gave rise to, or was based upon, an allied sense, viz. the meaning of 'বছী' i. e. possession. Possibly the sense 'possession' further developed into the further sense 'possession of the fruit or result for self or others' referring to the বিহু affixes which possessed that sense. The old sense 'ৰম্বয়ন্ত্ৰ' of the word 'उपग्रह' having gone out of use, and the sense 'पद' having come in vogue, the word 'ag?' must have been substituted for the word 'उपग्रह' by some grammarians before the time of Kāśikākāras. As Patafijali has dropped the Sütra (VI, 2.134), cannot be said definitely whether the change of reading took place before Patanjali or after him.

उपचार (1) taking a secondary sense; implication; lit. moving for a sense which is near about; the same as लक्षणा. The word आचार is explained as उपचार, employment or current usage, by Patanjali; cf. आचारात्। आचार्याणामुपचारात्। M. Bh. I. 1. 1. Vārt. 4; (2) substitution of the letter सं for विसर्ग; cf. प्रत्ययग्रहणेपचारेषु च, P.IV.1.1 Vārt. 7.

उपजन lit. origin; one that originates, augment, उपजायते असौ उपजन: I The

word is used in the sense of 'additional phonetic element'; cf. उपजन आगमः M. Bh. on Sivasūtra 5; cf. also वर्णव्यत्ययापायापजनविकारिष्वर्थदर्शनात्। Siva Sutra 5 Vārt. 15. The Rk Prātiśākhya gives म in पुरुश्चन्द्र as an instance of. उपजन cf. R. Pr. IV. 37. In the Nirukta उपजन is given as the sense of the prefix 'उप'; cf.उपेत्युपजनम्: The com. on the Nirukta explains the word उपजन as आधिक्य.

उपजीव्य a term used by later grammarians in connection with such a rule on which another rule depends cf. उपजीव्यादन्तरङ्गाच्च प्रधानं प्रवलम् Pari. Sekh. on Pari. 97, as also M. Bh. on हेतुमति च P. III. 1.26. The relationship known as उपजीव्योपजी- वक्षमान occurs several times in grammar which states the inferiority of the dependent as noticed in the world.

उपदेश instruction; original enunciation; first or original precepts or teaching; cf. उपदेश आधोच्चार म् S. K. on the rule उपदेशे जनुनासिक इत् P. I. 3. 2. cf. वर्णाना मुपदेशः कर्तव्यः; M. Bh. on Āhn. 1. Vārt. 15. For difference between उपदेश and उद्देश see उद्देश; cf. also उपदिस्यतेने नत्युपदेशः। शास्त्रवाक्यानि, सूत्रपाठः खिल्लाठश्च Kāśikā on P. I. 3.2; cf. also Vyāḍi. Pari. 5; (2) employment (of a word) for others cf. उपदेशः परार्थः प्रयोगः। स्वयमेव तु बुद्ध्या यदा परामृशति तदा नास्त्युपदेशः Kāś. on अदोनुपदेशे P. I. 4. 70.

उपदेशिन such a word as is found in the original instruction.

उपदेशिवद्भाव occurrence in the original statement before the application of any affixes etc., cf. एवमप्युपदेशिकदावी वक्तब्य:, M. Bh. on P. I. 1.56, Vart. 23.

उपदेशिवद्वचन statement to the effect that a word should be looked upon as occurring in the original instruction although it is not there. See उपदेश.cf. नुभ्विधानुपदेशिबद्धचनं प्रत्यविध्यर्थम् P. VII. 158. Vārt. 1.

उपद्भुत name of a samdhi which is described as उद्ग्राहवत् in R.Pr; e. g. न ऋते. See उद्ग्राह.

उपघा penultimate letter, as defined in the rule अलोन्त्यालूर्व उपधा P. I. 1. 65, e. g. see ह्रस्त्रोपघ, दीर्घोपघ, लघूपघ, अकारोपघ etc.; lit. उपधियते निधीयते सा that which is placed near the last letter.

उपधालोपिन a word or a noun which has got the penultimate letter omitted; cf. अन उपधालोपिनोन्यतरस्याम् P. IV. 1. 28.

उपध्मानीय a letter or a phonetic element substituted for a visarga followed by the first or the second letter of the labial class. Visarga is simply letting the breath out of the mouth. Where the visarga is followed by the first or the second letter of the labial class, its pronunciation is coloured by utterance. This coloured utterance cannot be made independently; hence this utterance called ' उपध्मा-नीय ' (similar to a sound blown from the mouth) is not put in, as an independent letter, in the वर्ण-समाम्राय attributed to महेश्वर. Patañjali, however, has referred to such dependent utterances by the term अयोगवाहवर्ण. See अयोगवाह: cf. ४क इति जिह्नामुळीय: । जिह्नामूळेन जन्यत्यात् । ४प इत्युप-ध्मानीय: । उपध्मानेन जन्यत्वात्. अयोगवाह is also called अर्घविसर्ग. See अर्घविसर्ग.

उपन्यास proposition, statement. The remark 'विषम उपन्यास:' is of frequent occurrence in the Vyākaraṇa Mahābhāṣya in connection with statements that are defective and have to be refuted or corrected; cf. M.Bh. on P.1.1.21,46,50; I.2.5 etc.

उपपद lit.a word placed near; an adjoining word. In Panini's grammar, the term उपपद is applied to such words as are put in the locative case by Pānini in his rules prescribing krt affixes in rules from III. 1, 90 to III, 4 end; cf. तत्रोपपदं सतमीस्थम P. III. 1. 92; e. g. कर्मण in कर्मण्यण P. III. 2.1. The word is also used in the sense of an adjoining word connected in sense. e. g. युष्मद्यपपदेo as also प्रहासे च मन्योपपदे० P. I. 4. 105, 106; cf. also कियार्थायां क्रियायाम् पपदे धातो भीविष्यति काले तुमन् खुलौ भवत: Kāś. on P. III. 3.10; cf. also इतरेतरान्योन्योपपदाच्च P.I.3.10, मिथ्योपपदात् कुञोभ्यासे P. I. 3.71, as also उपपदमतिङ P. II 2. 19; and गतिकारकोपपदात्कत P. VI. 2. 139. Kaiyata on P. III. 1. 92 Vārt. 2 explains the word उपपद as उपाच्चारि or उपाच्चारितं पदं उपपदम्. The word उपपद is found used in the Prātiśākhya literature where it means a word standing near and effecting some change; cf. च वा ह अह एव एतानि चप्रभृतीनि यान्यपपदानि उक्तानि आख्यातस्य विकारीणि॰ Uvata on V. Pr. VI. 23.

उपपद्विधि a grammatical operation caused by a word which is near; cf. उपपद्विधो भयाट्यादिग्रहण P. I. 1. 72 Vārt 9, also अतिप्रसङ्ग उपपद्विधो P. IV 1. 1. Vārt. 8 where rules such as 'कर्मण्यण्' and the following are referred to as उपपद्विधि, the words कर्मणि, स्तम्ब, कर्ण, etc. bing called उपपद् by the rule तत्रोपपदं सत्तमीस्थम्; P. III. 1. 92.

उपपद्विभक्ति a case termination added ed to a word on account of the presence of another word requiring the addition; cf. the well-known Paribhāṣā उपपद्विभक्ते: कारकविभक्तिकिं। यसी. Par. Śek. Pari. 94; and M.Bh. on I.4. 96 stating the possession of greater force in the case of a kāra-

kavibhakti than in the case of an upapadavibhakti.

उपपद्समास the compound of a word, technically termed as उपपद by Pāṇini according to his definition of the word in III. 1. 92., with another word which is a verbal derivative; cf. कुम्मकार:, नगरकार:. Here technically the compound of the words कुम्म, नगर etc. which are upapadas is formed with कार, before a case-termination is added to the nominal base कार; cf. गतिकारकोपपदानां कृद्धि: सह समासवचनं प्राकृ सुबुत्पत्ते: Par. Sek. Pari. 75.

उपबन्ध a technical term used in the Prātiśākhya works in the sense of words which proceed from a rule to the following rules upto a particular stated limit; cf. उपबन्धस्तु देशाय नित्यम् T. Pr I. 59 explained by the commentator as उपबन्धते इति उपबन्धः। एतस्मिनित्यधिकरणस्यः संख्यानिवध्यः प्रदेशश्च उपबन्ध उच्चते । उपबन्धे यदुक्तं तदन्यत्र न भवतीति तुशब्दार्थः।

उपन्तिमत् the fourth out of the seven stages or places in the production of articulate speech, upāmśu being the first stage; cf. सरान्दमुपद्मिमत् Tait. Pr. 23.9 explained by the commentator as: सरान्द परश्रान्यरान्दसहितम्। यत्र प्रयुज्यमानः रान्दः परेरक्षरन्यञ्जनिवेकवर्ज श्रूयते तदुपद्मिमत्संग्रं भवति।

उपमन्यु (1) the famous commentator on the grammatical verses attributed to Nandikeśvara which are known by the name नन्दिकेश्यकारिका and which form a kind of a commentary on the sūtras of Maheśvara; (2) a comparatively modern grammarian possibly belonging to the nineteenth century who is also named Upamanyu and who has written a commentory on the famous Kāśikāvṛtti by Jayāditya and Vāmana. Some believe that Upa-

manyu was an ancient sage who wrote a nirukta or etymological work and whose pupil came to be known as औपमन्यव.

उपमा a well-known term in Rhetorics meaning the figure of speech 'simile' or 'comparison'. The word is often found in the Nirukta in the same sense; cf. अथात उपमाः। 'यत् अतत् तत्सहराम्'इति गार्ग्यः। Nir III.13. Generally an inferior thing is compared to another that is superior in quality.

उपमान standard of comparison. The word is found in the Pāṇinisūtra उपमानानि सामान्यवचनै: P.II.I.55 where the Kāśikāvṛtti explains it as उपमोयतेऽनेनेत्युपमानम्।

उपमित an object which is compared. The word is found in Pāṇinisūtra उपमितं ज्याद्रादिभि: P.II.1.56, where the Kāsikā paraphrases it by the word उपमेय and illustrates it by the word पुरुष in पुरुषज्याद्र.

उपमेय an object which is to be compared. See उपामित.

उपलक्षण implication, indication; a thing indicatory of another thing. The term is very frequently found in commentary works in connection with a word which signifies something beyond it which is similar to it; the indication is generally inclusive; cf. Kāsikā on भीरम्योहेत्भये P.I.3.68 भयप्रहणम्पलक्षणार्थ विस्मयोपि तत एव। as also मन्त्रग्रहणं तु च्छन्दस उपलक्षणार्थेम् Kāś. on II. 4.80. The verbal forms of নৃষ্ণ and ভ্ৰণনৃষ্ণ as also the words लक्षयितुम्, लक्षणीय, लक्षित etc. possess the sense of 'expressing the meaning not primarily, but secondarily by indication or implication'.

उपाछिङ्गिन् a substituted word element; cf. दोवः इति सुखनाम । शिष्यतेः वकारः नाम-करणः अन्तस्थान्तरोपछिङ्गी विभाषितगुणः । शिवम् Nir. X. 17. ব্যব্দ an ancient grammarian and Mīmāmsaka believed to have been the brother of Varsa and the preceptor of Pāṇini. He is referred to, many times as an ancient writer of some Vṛttigranthas.

उपश्रेष immediate contact, as for instance, of one word with another; cf. शब्दस्य च शब्देन कान्योभिसंयन्थो भवितु- महीत अन्यदत उपश्रेपात्। M.Bh. on VI. 1.72. The word उपश्रिष्ट is also found in the Mahābhāṣya in the same context.

उपसंख्यान mention, generally of the type of the annexation of some words to words already given, or of some limiting conditions or additions to what has been already The word is often found stated. at the end of the statements made by the Vārttikakāra on the sūtras of Pāṇini.; cf. P.I.1.29 Vārt. 1: I.1.36 Vārt. 3 etc. The words वाच्य and वक्तव्य are also similarly used. The word is found similarly used in the Mahabhasya also very frequently.

उपसंग्रह inclusion of something, which is not directly mentioned; cf. प्रसिद्धयुपसंग्रहार्थमेतत् Kās. on P.I.3.48, also इतिकरणं एवंविधाना मप्यन्येपामुपसंग्रहार्थम् Kās. on P. VII.4.65.

उपसंयोग (1) union; cf. नामा स्थातयोस्तु कर्माप-संयोग द्योतका भवन्ति prepositions are signs to show that such a union with another sense has occurred in the case of the noun or verb to which they are prefixed, Nir. I.3.; (2) addition; cf. अकियमाणे हि संज्ञाप्रहणे गरीयानुपतंयोगः कर्तन्यः स्थात् M.Bh. on P. IV. 2 21. Vart, 2.

उपसंहत drawn close; cf. आंध्री त्पसंहततरी T. Pr. II.14. The root उपसंह is used in the sense of finishing in the Mahābhāṣya; cf. येनैव यत्नेनेकी वर्ण उचार्यते विन्छिने वर्ण उपसंहत्य तमन्यमुपा- दाय द्वितीय: प्रमुख्यते तथा तृतीयस्तथा चतुर्थः । M.Ph. on P.I.4. 109 Vart. 6.

उपसमस्त compounded together, joined together by special grammatical connection called समास; cf. न केवल: पाथरान्दः स्त्रियां वर्तते । उपसमस्तरति वर्तते M. Bh. on VII.1.1. Vart. 18.

preposition, prefix. The word उसपर्ग originally only 'a prefixed word '; cf. स्रेपसर्गेष नामस R. Pr. XVI. 38. The word became technically applied ancient Sanskrit Grammarians to the words प्र, परा, अप, सम् etc. which are always used along with a verb or a verbal derivative or a noun showing a verbal activity: cf. उपसर्गा: क्रियायोगे P. I. 4.59. These prefixes are necessarily compounded with the following word unless the latter is a verbal form: cf. जगतिप्रादय: P. II. Although they compounded with a verbal form. these prepositions are used in juxtaposition with it; sometimes they are found detached from the verbal form even with the intervention of one word or more. The prefixes are instrumental in changing the meaning of the root. Some scholars like Sākatāyana hold the view that separated from the roots, prefixes do not express any specific sense as ordinary words express, while scholars like Gargya hold the view that prefixes do express a sense e.g. प्र means beginning or प्रारम्भ; cf. न निर्वद्धा उपसगा अर्थानिराहरिति शाकटायनः । नामाख्यातयोस्त कर्मीपसंयोगद्योतका भवन्ति । उच्चावचाः पदार्था भवन्तीति गार्ग्यः । तद्य एष पदार्थः प्राहुरिमं तं नामाख्यातयोरर्थविकरणम् Nir. I. 8. It is doubtful, however, which view Pānini himself held. In his Atmanepada topic, he has mentioned some specific roots

as possessing some specific senses when preceded by some specific prefixes (see P. I. 3.20, 24, 25, 40, 41, 46, 52, 56, etc.), which implies possibly that roots themselves possess various senses, while prefixes are simply instrumental in indicating or showing them. On the other hand, in the topic of the Karmapravacaniyas, the same words प्र. परा etc. which, however, are not termed Upasargas for the time being, although they called Nipātas, are actually assigned some specific senses by Pānini. The Vārttikakāra has defined उपसर्ग as क्रियाविशेषक उपसर्गः 3.1. Vārt 7, leaving it doubtful whether the उपसर्ग or prefix possesses an independent sense which modifies the sense of the root. or without possessing any independent sense, it shows only the modified sense of the root which also is possessed by the root. Bhartrhari, Kaiyata and followers including Nagesa have emphatically given the view that not only prefixes but Nipātas, whi h include प्र, परा and others as Upasargas as well as Karma. pravacaniyas, do not denote any sense, but they indicate it; they are in fact द्योतक and not वाचक. For details see Nir. I. 3, Vākyapadīya II. 190, Mahābhāsya on I. 3.1. Vart. 7 and Pradipa and Uddyota thereon. The Rk Prātiśākhya has discussed the question in XII. 6-9 where, explained by the commentator, it is stated that prefixes express a sense along with roots or nouns to which they are attached. is not clear whether they convey the sense by denotation or indication, the words वाचक in stanza

6 and विशेषकृत् in stanza 8 being in favour of the former and the latter views respectively; cf उपसर्गा विशित्रर्थवाचकाः सहतराम्यामितरे निपाताः; कियावाचकभाष्यातमुपसर्गो विशेषकृत्, सत्वाभिष्यकं नाम निपातः पादपूरणः R. Pr. XII. st. 6 and 8. For the list of upasargas see R. Pr. XII. 6, T. Pr. I. 15, V. Pr. VI.24, and S. K. on P. I. 4.60.

उपसर्गद्योत्यता the view or doctrine that prefixes, by themselves, do not possess any sense, but they indicate the sense of the verb or noun with which they are connected. For details see Vākyapadīya II. 165-206; also vol. VII. pages 370-372 of Vyākaraņa Mahābhāsya ed. by the D. E. Society, Poona.

उपसर्गयोग connection with a prefix; joining of the prefix. Some scholars of grammar hold the view that the Upasarga is prefixed to the root and then the verbal form is arrived at by placing the desired terminations after the root, while others hold the opposite view; cf. पूर्व घातुः साधनेनोपयुज्यते पश्चाद्यपर्गण । अन्ये तु पूर्व धातुरपसर्गण युज्यते पश्चात्साधनेनत्याहुँ: Sīradeva's Paribhāṣāvṛtti Pari. 131, 132; cf. also vol. VII. Mahābhāṣya edited by the D. E. Society, Poona, pages 371–372.

उपसर्गेचाद् a treatise on upasargas, by Harikṛṣṇa.

उपसर्गविचार a treatise on upasargas by Gadadhara Cakravartin.

उपसर्गविवरण a short anonymous work on the nature of upasargas or prepositions explaining their meanings with illustrations.

उपसर्गवृत्ति a treatise on upasargas by Bharatamalla in the Sixteenth Century A.D. उपसर्जन (1) adjective, subordinate member which does not get the treatment of the principal member, e. g. गोस्त्रियोस्पसर्जनस्य P. I.2.48, अनुपसर्जनातु P.IV.1.14 संज्ञोपसर्जनीभूतास्तु न सर्वोदय: S. K. on P. I. 1.29, also P.I.1.27 Vart.2;(2) a word referred to by the word which is put in the nominative case in rules of Pānini prescribing compounds, e.g. 零星 (in the compound ক্যাপ্সন:) which is referred to by the word द्वितीया in the rule द्वितीया श्रितातीत॰ P.II.1.24 which prescribes the Acc. Tatpurusa compound. These words are given the first place in a compound; cf. प्रथमानिर्दिधं समास उपसर्जनम् P.I.2.43, उपसर्जन पूर्वम् P.II.2.30; (3) a word which has one and the same case when a compound in the different cases is shown as dissolved, e. g. the word काँशाम्बी in the compound निष्कोशाम्त्रिः which keeps its ablative case when the compounds निष्कीशाभ्यिम्, निष्कीशाभ्यिना, निष्कोशाम्बये etc. are dissolved: cf. एकविभक्ति चापुर्वनिपाते P.I.2.44.

उपसृष्ट attended with a prefix, generally used in connection with roots; e.g. कुघटुहोहपस्थ्योः कर्म P.I.4.38 where the Käsikā has explained the word as उपसर्गसंबद्ध.

changes in the wording of the base, such as elision, or addition or substitution of a letter or letters as caused by the addition of suffixes.

उपस्थान occurrence; presence by virtue of anuvitti i. e. recurrence or continuation of a word in the rules that follow; cf. शब्देन चाप्यिष्ठतेन कोन्यो ब्यापार: शक्योवगन्तुमन्यदत्तो योगे योग उपस्थानात् M.Bh. on I.3.11. Vart. 1.

उपस्थित a word used rather technically in the sense of the word इति

which is used in the Krama and other recitals when Vedic reciters show separately the two words compounded together by uttering the compound word first, then the word डात and then the two compound words, e.g. सुश्लोक ३ इति सु-श्लोक । विभावसो इति विभा-वसो, The Kāsikā defines the word उपस्थित as समुदायादविच्छद्य पदं येन स्वरूपे अवस्थाप्यते तद उपरिथतम् । इतिशब्दः । $K\bar{a}$ s. on VI.1.129. The Rk-Pratisakhya explains the word rather differently, but in the same context. The word after which इति is placed is called upasthita e.g. the word बाह in बाह इति or विभावसो in विभावसो इति as contrasted with स्थित i. e. the word without इति e.g. बाह or विभावसो. as also contrasted with स्थितापस्थित i.e. the whole word विभावसो इति विभाऽवसो which is also called संहित or मिलित; (2) occurring, present; cf कार्यकालं संज्ञापरिभाषम् । यत्र कार्ये तत्रोपास्थतं द्रष्टब्यम् । Pār. Sek. Pari.3.

उपहित (1) with, preceded by; e.g. दीघोंपहित, हस्वोपहित; (2) sticking to, connected with, 'उपश्लेषित'; cf.Durga on Nir.V.12;(3) coming to be placed near or in juxtaposition with the preceding word; cf. आवोन्तांपहितात् सत: R. Pr. II.15.

डपांद्र lit inaudible. The word is explained in the technical sense as the first place or stage in the utterance of speech where it is perfectly inaudible although produced; cf. उपांद्र इति प्रथम वाचः स्थानम् Com. on T. Pr. XXIII. 5.

उपाचरित (1) sibilation; substitution of a sibilant letter for a visarga; cf. प्छतोपाचरित च R. Pr. XI.19; (2) name of the samdhi in which a visarga is changed into a sibilant letter; cf. सर्वत्रेवोपाचरित: स संधि: R. Pr. IV.14 which corresponds to Pāṇini VIII. 3.18 and 19.

उपाचार change of Visarga into s (स्); sibilation of Visarga, e. g. त्रहाण: पतिः = त्रहाणस्पतिः. The words उपचार and उपाचरित are found used in the same sense by ancient Grammarians. See उपचार; cf. समापाद्यं नाम वदन्ति घत्यं, तथा णत्वं सामवशांश्च सन्धीन्।...उपाचारं लक्षणतश्च सिद्धम्, आचार्यां च्यालिशांकल्यगार्ग्याः R. Pr. VIII.12.

उपादान hypothesis, presumption, acceptance.

उपाद्य lit. near the first; second.

उपाधि condition, limitation, determinant, qualification: e.g. न हि उपाधे-रपाधिर्भवति, विशेषणस्य वा विशेषणम् M.Bh. on I.3.2 as also on V.1.16; cf. also इह यो विशेष उपाधिर्वीपादीयते द्योत्ये तरिंमस्तेन भवितन्यम् । M.Bh. on III.1.7.

उपान्त lit. near the last; penultimate. The word is generally found used in the Candra Vyakarana.

उपान्त्य see उपान्त; the word is generally found used in the grammars of Sākaṭāyana and Hemacandra.

उपोत्तम lit.one near or before the last; the term is generally used in connection with words having two or more syllables, where it means the vowel before the last (vowel); cf. उपोत्तमं रिति P. VI.1. 217 and योपवाद्गुल्पोत्तमाडुञ्च P.V.1.132 where the writer of the Kāśikā explains it as त्रिप्रभृतीनामन्त्यमुत्तमं तस्य समीपमुपोत्तमम्। giving रमणीय and वसनीय as examples where the long ई is upottama; cf. also T. Pr. XI.3. and Nir. I.19 where the word refers to the third out of the four feet of the verse.

उपोद्धलक a supporting assertion or statement; cf. तस्यैनोपोद्धलकमेतत् M.Bh. on I.2.64. Vart. 38-39.

उभयगति both the alternatives; both the senses; double signification; cf. उभयगतिरिह भवाति P.I.1.23, Vārt.4, Pari. Sek, Par. 9 where the word ubhaya

- refers to both the senses—the ordinary one (অনুসিম) and the technical one (কুসিম)—e.g. the meanings (i) numeral, and (ii) words বহু, গ্ল etc. of the word ধ্ৰ্যা.
- उभयतस्पाशा presenting a difficulty in both the ways; cf सैक्षा उभयतस्पाशा रज्जभैवति M.Bh. on VI.1.68.
- ত্তমাথনীমাথ lit. speaking or showing both the padas or voices; possessed of both the padas viz. the Parasmaipada and the Atmanepada. The word is found commonly used in the Dhātupāṭha of Pāṇini.
- ਤभयत्र in both the ways lit. in both the places; cf. ভ্রম্থন ল P. I. 1. 44 Vart. 22. The word ভ্রম্থনিশাগা is used in grammar referring to the option (विभाषा) which is সাম as also স্বাম; cf.M.Bh.on P.1.1.26 Vart.22.
- उभया in both the ways (in the case of an option, of course); cf. इन्द्रयुभयथा P.III.4.117 where the word ubhayathā refers to both the alternative uses e.g. Sārvadhātuka and Ārdhadhātuka; so also vidhilin and āsīrlin; cf. Kāsikā on P.III.4.117. The term ubhayathā is described as synonymous with 'bahulam' or 'anyatarasyām' or 'vā' or 'ekeṣām'; cf. बहुलमन्यतस्यासुभयथा वा एकेषाभित M. Bh. on P.I. 1.44; Vārt. 19; cf. also अध्यायान्तेषूभयथा स्मरन्ति R.Pr.XV.8.
- ਤभयदीयां a hiatus or a stop which occurs between two long-vowelled syllables; the term उभयदीयां is a conventional term in the Prätisākhya literature. The term उभय- हस्ता is similarly used in connection with short vowels.
- उभयनियम a restriction understood in both the ways; cf. सिद्धं त्भयनियमात्। उभयनिथमोयम् । प्रकृतिपर एव प्रत्ययः प्रयोक्तव्यः, प्रत्ययपरैव च प्रकृतिरिति । M. Bh. on P. III.1.2, Vart. 11; cf. also M. Bh. on VI:2,148.

- उभयपद (1) double voice—the Parasmaipada as well as the Ātmanepada; (2) both the words or members (in a compound); cf. उभयपदार्थप्रधानो इन्द्र; Kās on P.I.2.57.
- उभयपित् a root conjugated in both the Padas; a root to which both, the Parasmaipada and the Atmanepada terminations are assixed; e.g. roots ह, भी, मुन् etc.
- उभयप्राप्ति a case or a matter in which both the alternatives occur, as for instance, the genitive case for the subject and the object of a verbal derivative noun (कृदन्त); cf. उभयप्राप्ती कर्मणि। उभयोः प्राप्तिः यस्मिन् कृति सायपुभय-प्राप्तिः तत्र कर्मण्येत्र पटी स्थात् न कर्तरि। आश्रयों गवां दोहः अगोपालकेन Kai. on P. II. 3.66.
- उभयवत् possessed of both the kinds of properties; cf. य इदानीमुभयवान् स तृतीयामाख्यां लगते स्वरित इति M.Bh. on P.I.2.Bl; cf. also उभयवान् स्वरितः V. Pr.I.110.
- उम् the augment उ affixed to the last vowel of बच् by P.VII.4.20; c.g. अयोजत.
- उरल् tad-affix उर, with uddita accent on the last vowel, affixed to the word दन्त when it refers to protuberant teeth; cf. P.V.2.66; e.g. दन्तुर: 1
- उरः प्रभृति a class of words headed by the word उरम् to which the sama-santa affix क (कप्) is added, when these words stand at the end of Bahuvrihi compounds; cf. न्यूडम्रोस्य न्यूडोरस्क:similarly प्रियमार्थिकः, Kās. on P.V. I.151.
- उरस्य produced at the breast; cf. केनि-देता उरस्यां R.Pr.I.18, explained by the commentator as केनिदानायाः एती ह शर्यक्षिनीयां उरस्थाना इच्छन्ति ।
- उदता opening (of the hole of the throat); the words उदता खस्य are

used in the sense of 'opening of the glottis' which is described as a characteristic condition of the utterance of a vowel accented grave or अनुदात्त; cf. आयामा दारण्यमणुदा खरयेत्युच्चै; कराणि शब्दस्य । अन्ववसर्गो मार्दव पुरुता खरयेति नीचै:कराणि शब्दस्य M.Bh. on नीचैरनुदात्तः P. I. 2.30; cf. T. Pr. on XXII. 9, 10.

उरोवृहती a variety of the Vedic metre बृहती in which the first pāda consists of twelve syllables and the rest of eight syllables; cf. R. Pr. XVI. 33.

उब् (उबङ्) substitute for the vowel उ belonging to the Vikarana ধ্রু, to roots and to the noun ম্বু under certain conditions; cf প্রবি ধ্রুঘানুমুবা ব্যাধৈযক্তবলী P. VI. 4.77.

বৰত also জন্মত or জ্ঞাত a reputed Kaāsmirian scholar and writer who was the son of Vajrata. He wrote many learned commentaries, some of which are known as Bhāṣyas. Some of his important works are Rkprātisākhyabhāṣya, Vājasaneyī. prātisākhyabhāṣya, Vojasaneyīsamhitābhāṣya, Vedārthadīpikā etc.

उध्यह् (उध्यक्) name of the second of the main seven Vedic metres which are known by the name সজাपतिच्छन्दम्. The Usnik metre consists of 28 syllables divided into three padas of 8, 8 and 12 syllables. It has got many varieties such as पुरद्धिष्ट्, कद्भम् and others; for details see R. Pr. XVI 20-26.

उस् (1) substitute for झि, ending of the third pers. plu., in the perfect tense and in the present tense in the case of the roots विद and झू, e.g. विदु: and आहु: cf. P. III. 4. 82-81; (2) substitute जुस् (उस्) for झि in the potential and the benedictive moods, as also after the aorist sign स and after roots of the third

conjugation, roots ending in आ and the root विद्, e. g. पचेयु: भूयासु: अकार्षु:, अविप्:, etc.; cf. Kās. on III.4.108-112.

उसि Uṇādi affix उस् applied to the root जन् to form जनुस्; cf. जनेशस: Uṇ. sūtra. 272.

35

ক long vowel ক, ব being the short vowel.

ऊक् augment ज added to the अभ्यास or the reduplicative syllable of the root पर which is doubled before the afflx क which is used instead of घ (ঘন্ত্ৰখ कः); e.g. पार्पटः.

जक kṛt affix जक added to the root जाग to form the word जागरूक; cf. जागुरूक; P. III.2.165.

জ fem. affix জ prescribed after masculine nouns ending in the vowel জ and denoting a human being as also after some other specific masculine bases; cf. জভুন: P. IV. 1.66 and the following sūtras. e.g. ফুল:, উভুন্:, অস্থা:, কমৌজ:, মরবাল্প: etc.

जह also उद् बेंgama ज and उ prescribed after the roots त and ह before the affix तृन् or तृच् e. g. तस्तारं तस्तारं वा रथानाम्; वस्तारं वस्तारं वस्तारं वस्तारं वर्तारं वर्तार

জন্ (1) samprasāraņa vowel জ substituted for the ল্ of লাছ্ under certain conditions e.g., জন্তঃ, cf. লাছ জন্ P. VI. 4.132; (2) substitute জ for ল্ before certain affixes; e.g. লুন:, গুলা, লুনি:, নুনি: etc. cf. ভুলা: গুলুনানিক ল P. VI.4.19, 20.

ऊत् (1) long vowel ऊ which cannot be combined by rules of samdhi with the following vowel when it comes at the end of the forms of the dual number; e. g. साधू अत्र etc.; cf. হুঁবুदৈর্হিবचन সহয়ন্ P. I.l.ll; as also

इंदूती च सतम्यथे I.1.19; (2) long vowel ऊ substituted for the short उ of the root गोह् before an affix beginning with a vowel e.g. निगृहति; cf. ऊदुपधाया गोह: P. VI.4.89.

কৰে substitution of the long vowel ক্ত; see M. Bh. on P. I.1.12, VI.1.85.

जिद्ति marked with the mute indicatory letter ऊ; cf. स्वरतिसूतिस्वातिधूब्यदितो वा। prescribing the addition of the augment इ optionally in the case of ऊदित roots P. VII. 2.44.

ऊन deficient, wanting; often in compounds e. g. पादोन, द्यून, एकोन; cf. ब्यूहै: संपत्समीक्ष्योने R. Pr. VIII. 28; एकद्यूनाधिका सैव निच्चदूनाधिका सुरिक् R. Pr. XVII.1.

जन्बेबृहती (विराज्) a variety of the metre Bihatī which has three pādas of twelve syllables each; cf. त्रयो द्वादशका यस्याः सा होर्थ्वबृहती विराट् R. Pr. XVI.33.

कर्यादि a class of words headed by the words जरी उररी etc. ending in the taddhita affix न्नि, which are given the designation गति provided they are related to a verbal activity, and as a result, which can be compounded with krdanta words ending in न्या, तुम्, etc. ef; जरीकृत्य, जरीकृतम् etc.; Kāś on P. I.4.61.

কন্ত tad. affix applied to the words বাব and ৰন্ত in the sense of 'unable to bear'; e. g. বার্ত্ত:, বত্তে; see Kāś. on V. 2.122.

कष्मन् aspiration letters, spirants called breathings also: the name is given to letters or sounds produced with unintonated breath through an open posision of the mouth; cf. विवृत्तमूष्मणाम् M. Bh. on P. I. 1.10 Vārt, 3. The word refers to the letters श्, ष्, स्, ह्, visarga, jihvāmūlīya, upadhmānīya and anusvāra; cf. ऊष्मा वायुस्तस्प्रधाना वर्णा ऊष्माण: R. Pr. I.12; cf. also T. Pr. I.10.

ऊष्मसंधि name of a combination or संधि where a visarga is changed into a breathing (ऊष्मन्). It has got two varieties named ज्यापन where the visarga is changed into a breathing as for instance in यस्कनुभः, while it is called विकान्त (passed over) where it remains unchanged as for instance in यः कनुभः, यः पञ्च; cf. R. Pr. IV. 11.

उन्ह modification of a word, in a Vedic Mantra, so as to suit the context in which the mantra is to be utilised, generally by change of case affixes; adaptation of a mantra; cf. जहः खत्विष । न सर्वेलिङ्गिन च सर्वाभिविभक्तिभिवेदे मन्त्रा निगदिताः। ते च अवस्यं यज्ञगतेन यथायथं विपिश्णमियतस्याः। M. Bh. on P. 1.1 Ahnika 1.

ऋ

ऋ fourth vowel in Pāṇini's alphabet; possessed of long and protracted varieties and looked upon as cognate (सवर्ण) with ल which has no long type in the grammar of Pāṇini; cf. R.Pr.I,9; V.Pr.VIII. 3. (2) uṇādi suffix क applied to the root खा to form the word ख; e. g. सब्येश सार्थः; cf. सब्ये ख्रक्कदांस Uṇ Sū, II. 101.

ক্ষমাৰ the letter ক্ষ with its 18 varieties made up of the हस्त, হার্ম, দুরন, and ধানুনামিক varieties and characterized by the three accents. ক্ষ and ন্ত are looked upon as cognate in Pāṇini's grammar and hence, ক্ষ could be looked upon as possessed of 30 varieties including 12 varieties of ন্ত.

কালেস a work consisting of five chapters containing in all 287 sūtras. It covers the same topics as the Prātisākhya works and is looked upon as one of the Prātisākhya works of

the Sama Veda. Its authorship is attributed to Sākatāyana according to Nāgeśa, while भौदेत्राज is held as its author by some, and कात्यायन by It bears a remarkable similarity to Pānini's Astādhyāyī especially in topics concerning coalescence and changes of स and न to g and g respectively. It cannot be definitely said whether it preceded or followed Panini's work.

ऋक्प्रातिशाख्य one of the Prātiśākhya works belonging to the Asvalayana Sākhā of the Rg Veda. The work available at present, appears to be not a very old one, possibly written a century or so after Pānini's time. It is possible that the work, which is available, is based upon a few ancient Prātiśākhya works which are lost. Its authorship is attributed to Saunaka. The work is a metrical one and consits of three books or Adhyāyas, each Adhyāya being made up of six Patalas or chapters. It is written, just as the other Prātiśākhya works, with a view to give directions for the proper recitation of the Veda. has got a scholarly commentary written by Uvata and another one by Kumāra who is also called Viṣṇumitra. See आश्वलायनप्रातिशाख्य.

ऋगयनादि a class of words headed by ऋगयन to which the taddhita affix अण (अ) is affixed in the sense of 'produced therein' (तत्र भव:), or 'explanatory of' (तस्य न्याख्यानः); cf. ऋगयने भवः, ऋगयनस्य पादव्याख्यानः, **ग्या**ख्यानी वा आर्गयन: औपनिषद:, शैक्ष: etc. Kās. on P. IV. 3.73.

ऋग्विराम verse-pause equal to 3 mātrākālas or three mātrā units. cf. ऋग्विरामः पदविरामो विश्वत्तिविरामस्समान-पदिवश्चित्तिविरामः त्रिमात्रो द्विमात्र एकमात्रोधमात्र | ऋ long variety of the vowel ऋ.

आनुपूर्व्येण T. Pr. XXII. 13. According to Rk. Tantra it consists of two mātrās.

ऋत short vowel ऋ. before which the preceding vowel is optionally left as it is, i. e. without coalescence and shortened also if long; cf. ऋत्यक: P. VI. 1.128.

ऋत्वत् possessed of short ऋ; cf. रीगृत्वतः संयोगार्थम् P. VII. 4.90. Vārt. 1.

ऋदित possessed of the mute indicatory letter 事, signifying in the Grammar of Pāṇini the prevention of the shortening of the long vowel in the reduplicated syllable of the Causal Aorist form of roots which are marked with it; ८. अशशासत अबबाधत. अययाचत etc. cf. नाग्लोपिशास्त्रादिताम् P. VII.4.2.

ऋर्यादि a class of words headed by the word ऋष to which the taddhita affix क is added in the four senses prescribed in the rules IV. 2.67-70; e. g. ऋत्यकः, न्यग्रोधकः etc. cf. P. IV. 2.80.

ऋषिच्छन्द्स् the metre of the Vedic seers. The seven metres—गायत्री, उष्णिक्, अनुष्टुप्, बृहती, पङ्क्ति, त्रिष्टुप् and जगती consisting respectively of 24, 28, 32, 36, 40, 44 and 48 syllables are named ऋषिच्छन्दस् as contrasted with the metres दैव, प्राजापत्य and आसुर, which, when combined together, make the metres of the Vedic seers. For details see R. Pr. XVI. 1.5.

ऋष्यण् taddhita affix अण् in the sense of 'descendant' applied to names of ancient sages, by the rule ऋष्यन्धकवृष्णिक्रम्यश्च P. IV. 1.114; e. g. वासिष्ठ:, वैश्वामित्र:.

雍

ऋदन्त (roots) ending in ऋ which have the vowel ऋ changed into इर् by the rule ऋत इद्धाती: P. VII. 1.100; e. g. किरति, गिलति.

ल्ह

- ন্ত short vowel ল taken to be a cognate of ক্ল, and described as a vocalic form of the letter ল.
- लिंदित् (roots) marked with the mute indicatory letter ऌ, which take the substitute अ (अङ्) for चिल, the Vikaraṇa of the aorist; e. g. अपतत्, अशकत् cf. पुषादिद्युताद्यल्द्रदितः परस्मैपदेषु P. III. 1.55.

Ų

- ए diphthong vowel ए made up of अ and इ, and hence having कण्ठताल-स्थान as its place of origin. It has no short form according to Panini. In cases where a short vowel as a substitute is prescribed for it in grammar, the vowel g is looked upon as its short form. Patañjali in his Mahābhāṣya has observed that followers of the Satyamugri and Rāṇāyanīya branches of the Sāmaveda have short ए (ऍ) in their Samaveda recital and has given सुजाते अश्वसूनृते, अध्वयीं अद्रिभि: सुतम् as illustrations; cf. M. Bh. on I. 1.48; as also the article on.
- एक (1) Singular number, ekavacana cf. नो नो स मदर्थे त्रिद्धेकेषु. V. Pr. II.3; the term is found used in this sense of singular number in the Jainendra, Sākatāyana and Haima grammars; (2) single (vowel) substitute (एकादेश) for two (vowels); cf एक: पूर्वपरयो: P. VI. 1.84; अथेकमुभे T. Pr X. 1; (3) many, a certain number; (used in pl. in this sense),

- cf. इह चेत्येक सन्यते M. Bh. on P. I. 4.21.
- एक कर्मक transitive verbs having one object, as contrasted with द्विकर्मक; cf. kātantra IV. 6. 62
- एकतिङ् possessed of one verb; given as a definition of a sentence; cf. एकतिङ् P.II.1. 1. Vart 10, explained by Patanjali as एकतिङ् वाक्यसँज्ञं भवतीति वक्तव्यम् । बृहि बृहि ।
- प्किन्कि in the same direction, given as the sense of the tad. affix तस by Pāṇini; cf. तेनैकदिक्। तसिश्च। P. IV. 3. 112, 113.
- एकदेश a part or a portion of the whole;cf. एकदेशिवकृतमनन्यवत् Pari-Śek. Pari 37; also M. Bh. Śiva-Sūtra 2 Vārt 4; एकदेशोनुवर्तते M.Bh. on P.VI. 1. 93 Vārt. 5; cf. also पदेकदेशानिप तान् प्रतीयात् R.Pr. IX. 16.
- एकदेशिन (a thing or a substance) composed of parts; cf. the term एकदेशिसमास or एकदेशितत्पुरुष, used in connection with compounds of words such as पूर्ध, पर and others with words showing the constituted whole (एकदेशिन्) prescribed by the rule पूर्वपराधरोत्तरमेकदेशिनेकाधिकरणे P. II. 2. 1; (2) a partisan; cf. the word सिद्धान्त्येकदेशिन् used often by commentators.
- एकदेशिवस्तन्याय the maxim that 'a thing is called or taken as that very thing although it is lacking in a part,' stated briefly as एकदेश-विक्तमनन्यवत् Pari. Sek. Pari. 37. The maxim is given in all the different schools of grammar; cf. Sak Pari. 17; Cāndra Pari. 15, Kat. Par. Vr. 1, Jain. Par. Vr. 11, Hem. Pari. 7 etc.
- एकदेशानुमति consent to a part of the whole, admission of one part as correct.
- एकद्रव्य one and the same individual substance; cf. the words एकद्रव्यसम-

वायित्व M. Bh. on P. I. 4. 23, एक-द्रव्याभिधान on P.VIII.1. 51, एकद्रव्योप-निवेशिनी given as a definition of संज्ञा M. Bh. on P. I. 4. 1.

पकपद् made up of one word; consisting of one word; cf. अथवा सन्त्ये-कपदान्यप्यवधारणानि । यथा अन्भक्षे वायुमक्षः । अप एव भक्षयति वायुमेव भक्षयति । M.Bh. first Āhnika; (2) a continuous word paraphrased as अखण्डपद and समानपद by commentators; cf. तेनानन्तरा षष्ट्येकपदवत् V.Pr.II. 18; (3) every individual word: cf. बहुकमे क्रमेत तस्यैकपदानि निःसजन् R.Pr.XI.18.

पकपदा made up of a single word; cf. भवति नैतदेकस्मिनपि एकवर्णे पदम् एकपदा क्रक् एकर्चे सूक्तमिति। M. Bh. on P.I. 1.21 Vārt. 5; (2) made up of one foot (चरण or पाद); cf. एक एकपदेतेषां (R.Pr.XVII.24) explained by the commentator as तेषां चतुर्णा पादानामधाक्षरादीनां एक; पाद: यस्या:सा एकपदा क्रक् इस्युच्यते।

एकपातिन combined together; cf. R. Pr. com. एकपातिन; एकीभूतस्य अक्षरस्य क्रमे ध्रुवमार्थी छुप्यते; R. Pr. XI. 25, also XVII.26.

एकभाविन (vowels) combined by rules of Samdhi; cf. क्षेप्रवर्णेकभाविनाम् R. Pr. VII.22.

एकमात्रिक (1) possessed of one mātrā or mora; (2) a term used for a short vowel which measures one mātrā or mora; cf. एकमात्री हुत्व: च्यञ्जनानि च। Ath.Pr.1.60.

प्रकमुनिपक्ष a view or doctrine propounded by one of the many ancient sages or munis who are believed to be the founders of a Sāstra; a view propounded only by Pāṇini, to the exclusion of Kātyāyana and Patañjali; cf. एकमुनिपक्षे तु अचो विगलीत्यत्राच इति योगं विभज्य...व्यवस्थितविभाषात्रोक्ता Durghaṭa-Vṛtti I.1.5; see also I.4.24, II.3.18.

एकयोग (1) combination of two Sūtras into one; cf.अथवा एकयोगः करिष्यते वृद्धिरादै- जदेङ्गुण इति M.Bh.P.I.1.3,I.4.59,V.2. 25; (2) one and the same Sūtra; cf. एकयोगनिर्दिष्टानां सह वा प्रवृत्तिः सह वा निवृत्तिः Pari. Sek. Pari. 17; cf. also एकयोगनिर्दिष्टानामप्येकदेशानुवृत्तिर्भवति P. IV. 1. 27, Vārt. 2, Pari. Sek. Pari. 39.

एकयोगन्छक्षण characterized by i.e. mentioned in one and the same rule; cf. एकयोगन्छक्षण तुग्दीर्घत्वे M.Bh. on P. I. 1. 62. Vart. 10. See also M. Bh.on P. VI.1.37.

पक्रवान singular number; affix of the singular number in Pāṇini's grammar applied to noun-bases (সানি-पহিক) and roots when the sense of the singular number is to be conveyed; the singular sense can be of the form of an individual or collection or genus. The word एकवचन in the technical sense of singular number is found used in the Prātisākhyas and Nirukta also.

एकवस्त or एकवद्भाव use or treatment of the plural sense as if it is singular; cf. एकवद्भावोऽनर्थकः । समाहारैकत्वात् M.Bh. on II. 4.12. Vart. 5.

एकवर्ण (a pada) made up of a single letter; cf. एकवर्ण पदम् आ, उ इति; commentary on R.Pr. X.2; cf. also V.Pr.IV. 144-145 where एकवर्ण is defined as एकप्रयत्निर्वर्य capable of being produced with a single effort. Pāṇini gives the term अप्रवत्त to an affix made up of one single letter; cf.अप्रवत्त एकाल् प्रत्ययः P.I.2.41.

प्रवास्य an expression giving one idea, either a single or a composite one. A positive statement and its negation, so also, a general rule and its exception are looked upon as making a single sentence on account of their mutual expectancy even though they be sometimes detached from each other; cf.

विदेशस्थमपि सदेकवाक्यं भवति M. Bh. on III. 4. 67; cf. also निषेधवाक्यानामपि निषेध्यविशेषाकाङ्क्तवाद्विध्येकवाक्यतयैव अन्वयः। तत्रैकवाक्यता पर्युदासन्यायेन। संज्ञाशास्त्रस्य त कार्यकालपक्षे न पृथ्यवाक्यायेवोधः। Par. Sek. on Pari. 3. Such sentences are, in fact, two sentences, but, to avoid the fault of गौरन, caused by वाक्यभेद, grammarians hold them to be composite single sentences.

एकविभक्ति a pada having the same case in the various dissolutions of the compound word; e.g. the word कौदाम्बी in the compound word निष्कौदाम्बि:, which stands only in the ablative case कौदाम्ब्या:, although the word निष्कान्त, which stands for the word निष्कान्त, would be used in many cases. The word नियतिथमक्तिक is also used in the same sense.

एकवृत्ति single vitti or gloss on the Vedic as well as classical portions of grammar. Purusottamadeva has used this term in his Bhāṣāvitti to contrast his Vitti (মাগাবৃত্তি) with the Kāśikāvitti and the Bhāgavitti which deal with both the portions; cf. সনাগ হবৈকবৃত্তান্ত্ৰপুক্তন্ Bhāṣāvitti on I. 1. 16, cf. also Bhāṣāvitti on III. 4. 99, IV. 3.22 and VI.3.20. एकवृत्ति is possibly used by Purusottamadeva in the sense of मुख्यवृत्ति or साधारणवृत्ति i. e. the common chief gloss on both the portions.

एकशब्द a word having one sense only, as opposed to अनेकशब्द many words having the same sense or synonyms which are given in निघण्ड as also in असरकोष; cf. अथ यान्यनेकाथीनि एकशब्दानि तान्यतोनुक्रमिष्याम: Nir. IV.1.

एकरोष a kind of composite formation in which only one of the two or more words compounded together subsists, the others being elided; cf. एक: शिष्यते इतरे निवर्तन्ते वृक्षश्च वृक्षश्च वृक्षश्च । Kāšīkā on सहपाणामेकरोज एक-

विभक्तो P. I.2.64; cf. also सरूपसमुदा-याद्धि विभक्तियां विधीयते । एकस्तत्रार्थवान् सिद्धः समदायस्य वाचकः ॥ Bhāsāvrtti on P. I. There is a dictum of grammarians that every individual object requires a separate pression to convey its presence. Hence, when there is a dual sense, the word has to be repeated, as also the word has to be multiplied when there is a plural sense. In current spoken language, however, in such cases the word is used To iustify only once. single utterance for conveying the sense of plurality, Panini has laid down a general rule सन्पाणामेकदोप एकविभक्ती and many other similar rules to cover cases of plurality not of one and the same object, but plurality caused by many objects, such as plurality caused by ideas going in pairs or relations such as parents, brothers and sisters, grand-father and grand-son, male and female. For example, see the words वृक्षश्च वृक्षश्च वृक्षी; similarly वृक्षा: for many trees, पितरी for माता च पिता च; देवाँ for देवी च देवश्च; cf. also the words धगुरा, भ्रातरी, गाग्यी (for गाग्यी and गार्ग्यायण),आवाम् (for त्वं च अहं च), या (for स च यश्च) and गायः fem. अजा fem. স্বা: masc. irrespective of the individuals being some males some females. Pānini has devoted 10 Sūtras to this topic of Ekasesa. The Daiva grammar completely ignored this topic. Patanjali has very critically and exhaustively discussed this topic. Some critics hold that the topic of एकशेष did not exist in the original Astād yāyī of Pānini but it was interpolated later on, and adduce the long discussion in the Mahābhāsya especially the Pūrvapaksa therein, in support of their argument. Whatever the case be, the Vārttikakāra has commented upon it at length; hence, the addition must have been made immediately after Pāṇini, if at all there was any. For details see Mahābhāṣya on I.1.64 to 73 as also,Introduction p. 166-167, Vol.7 of the Mahābhāṣya published by the D. E. Society, Poona.

पक्करोषनिदेश statement by subsistence of one word out of many. The phrase is very often used in the Mahābhāṣya where the omission of an individual thing is explained by saying that the expression used is a composite one including the omitted thing along with the thing already expressed; cf. एक्शेषनिदेशायम्। सर्वादीनि च सर्वादीनि च सर्वादीनि M. Bh. on I. 1. 27, on I. 1. 59, I, 2.39, as also on I.3.1 Vārt. 5, I.4. 101 Vārt. 3, II. 1.1. Vārt. 19 etc.

एकश्रुति that which has got the same accent or tone; uttarance in the same tone; monotone. The word is applied to the utterance of the vocative noun or phrase calling a man from a distance, as also to that of the vowels or syllables following a Svarita vowel in the Samhita i.e. the continuous utterance of Vedic sentences; cf. एकश्रुति द्रात्संबुद्धी and the foll. P. I.2.33-40 and the Mahābhāsya thereon. In his discussion on I. 2.33 Patanjali has given three alternative views about the accent of Ekasruti syllables: (a) they possess cent between the उदात (acute) and अनुदात्त (grave), (b) they are in the same accent as is possessed by the preceding vowel, (c) Ekasruti is looked upon as the seventh of the seven accents; cf. सैषा ज्ञापकाम्यामुदात्तानुदात्तयोर्मध्यमेकश्रुति-रन्तरालं हियते।...सत स्वरा भवन्ति । उदात्तः, उदात्ततरः, अनुदात्तः, अनुदात्ततरः, स्वरितः स्वरिते य उदात्तः सोन्येन विशिष्टः, एकश्रुतिः सत्तमः । M. Bh. on P. I. 2.33.

एकस्वर possessed of one vowel, monosyllabic; a term used by Hemacandra in his grammar for the term एकाच् of Pāṇini; cf. आयोंच एकस्वरे Hem.IV.1.2. which means the same as एकाचो द्वे प्रथमस्वP.VI.1.1.

एकहलादि having a single consonant at the beginning; cf. एकहलादौ प्राथितन्येऽन्यतरस्याम् P. VI.3. 59.

एकहल्मध्य (a vowel) placed between two single consonants; e.g. the vowel अ in पच्, रम्, रण्, etc.

एकाञ्चर consisting of one single syllable; e.g. स्व, भू, बाच् etc.; cf. एकाञ्चरा- त्कृतो जाते: सतम्यां च न तौ स्मृतौ M.Bh. on P.V.2.115, as also on VI.1.168, VI.4.161.

एकाच् possessed of a single vowel, monosyllabic; cf. एकाचो द्वे प्रथमस्य P. VI. 1. 1.

एकाच्पाद name given by Sīradeva and other grammarians to the first pāda of the sixth adhyāya of Pāṇini's Āṣṭādhyāyī, as it begins with the sūtra एकाचो द्वे प्रथमस्य VI. 1.1.

एकादेश a single substitute in the place of two original units; e.g. ए in the place of अ and इ,or ओ in the place of अ and उ. The adesas or substitutes named पूर्वह्य and परह्य are looked upon as ekādesas in Pānini's although instead grammar them, the omission of the latter and former vowels respectively, is prescribed in some Pratisakhya works. गुण and दृद्धि are sometimes single substitutes for single originals, while they are sometimes ekādesas for two original vowels e.g. तवेदम्, ब्रह्मोदनः, उपैति, प्राच्छिति, गाम्, सीमन्तः etc.; see P.VI.1.87 to 111, cf. also A.Pr.II 3.6.

एकादेशस्वर an accent prescribed for the single substitute, as, for instance, by rules like उदात्तस्वरितयोर्थण: स्वरितो-नुदात्तस्य and the following rules P. VI.2.4, 5 and 6.

एकान्त part, portion. Augments or Agamas in the Vyākaraņa Śāstra are looked upon as forming a part of the word to which they are attached; cf. अथ यस्यानुबन्ध आसज्यते, किं स तस्य एकान्तो भवति आहोस्विदनेकान्तः । एकान्तस्तेत्रोपल्डभ्यः । M. Bh. on I.3.9, Vārt. 9; cf. also एकान्ताः Par. Śek. Pari. 5.

एकान्तर separated or intervened by one single thing, a letter or a word; e. g. आं पचिस देवदत्त, where देवदत्त follows आम् with one word पचिस intervening; cf. आम एकान्तरमाम-नित्रतमनितके P.VIII. 1. 55.

प्कार the letter ए; looked upon as a diphthong (संघ्यक्षर) made up of the letters अ and इ. The combination of the two constituent parts is so complete as cannot allow any of the two parts to be independently working for samdhi or any other operation with its adjoining letter; cf. नान्यपद्कास्य अवयवे तिहिधियंथा हुन्युषु M. Bh. Siva Sūtra 3 Vārt. 9.

पकार्थ (1) possessed of one sense as contrasted with बहुर्थ, द्यर्थ etc; (2) synonym, cf. बहवो हि राज्दा एकार्था भवन्ति । तद्यथा इन्द्रः शकः पुरुद्दतः पुरंदरः । M. Bh. on I. 2. 45 Vart. 9; (3) possessed of a composite sense; cf. समासे प्नरेकार्थानि M. Bh. on II. 1.1 Vart 1. The words ऐकार्थ and एकार्थत्व derived from the word एकार्थ are often found used in the sense of 'possession of a compo-, site sense' एकार्थस्य माव: एकार्थता, एकार्थ्य एकार्थत्वं वा; cf. समासस्यैकार्थत्वात्संज्ञाया अप्रसिद्धि: M. Bh. on P. I. 2.42 Vart. 1; cf. also the word एकार्थी-भाव; (4) potent to be connected; समर्थ; cr. सुप्सुपा एकार्थम् (समस्येते) C. Vy. II. 2.1; (5) analogous समाना- धिकरण cf. एकार्थे चानेकं च । एकः समानः अर्थः अधिकरणं यस्य तदेकार्थं समानाधिकरणम् Hem. Vy. III. 1.22; cf. also एकार्थं च । Śāk. II. 1.4.

एकार्थीभाव union of meanings; one of the two ways in which the word सामर्थ्य is explained; cf. एकार्थीभावो वा सामर्थ्य स्थाद् ब्यपेक्षा वा। M. Bh. on II. 1.1.

एकाल् possessed of one single phonetic element or letter; cf. अपृक्त एकाल् प्रत्यय; P. I. 2.41.

एकीमाव fusion, mixture, union, combination (of 2 or more letters); cf. उदात्तवित एकीमाव उदात्तं सन्ध्यमक्षरम्, R. Pr.III.6.एकीमाव is said to be resulting from the coalescence called अभिनिहितसन्व, cf. R. Pr. II. 16, 17.

पंगालंग (Eggeling) a well-known German scholar of Sanskrit Grammar who flourished in the 19th century and who edited the Kātantra Vyākaraṇa with the commentary of Durgasimha and many appendices in 1876.

पड़ a brief term (प्रत्याहार) for the two diphthong letters ए and ओ; cf. एड्हस्वात्संबुद्धे: P. VI. 1.69, एड: पदान्तादित VI. 1.109. etc.

एच् a short term (प्रत्याहार) in Pāṇini's grammar standing for diphthongs or letters ए,ऐ,ओ, औ; e.g. एचोयवायाव: P. VI.1.78, एच इग् हुस्वादेशे p.I.1.48.

থ্যাইন [Edgerton, Dr. Franklin] an American Sanskrit scholar and author of 'Buddhist Hybrid Sanskrit Grammar and Dictionary.'

एणीइन्त A fault in pronunciation when the voice is indistinct, and the word pronounced is not distinctly heard; cf. एणीइन्तः अविशिष्टः । किमयमोकार; अथौकार इति यत्र संदेहः Pradipa on M.Bh.I.I.1, explained as अविशिष्टः संदिश्य इति यावत् by Nāgeśa in

his Uddyota.

एण्य tad. affix एण्य applied to the word प्रावृष् in the general शैभिक senses; cf. प्रावृष एण्य:। प्रावृष्ण्य: बलाहक: Kās. on P. IV. 3.17.

एत् the vowel ए; cf. ईदूदेद्दिवचनं प्रग्छम् P. I. 1.11.

पतावस्व limitation of the kind; 'such and such' (words etc.); cf A. Pr.I.

पत्न the substitution of ए; cf. बहुवचने झल्येत् (P. VII. 3.103) इति एच्चं प्राप्तोति M.Bh. on P.V.3.10.

पत्य tad. affix applied to the indeclinable दूर; e. g. दूरेत्य: पथिक: । cf. दूरादेत्य: दूरेत्य: Kās. on P.IV.2.104; cf. also दूरादेत्या वक्तव्य: । दूरेत्य: M.Bh. on P. IV. 2.104.

पदित marked by the mute indicatory letter ए. Roots marked with indicatory ए do not allow बृद्धि for their vowel in the aorist; e. g. अरगीत, अलगीत; cf. P. VII.2.5.

एद्यवि tad. affix एद्यवि applied to the pronoun पर when the word refers to a day;cf. परस्मिन्नह्नि परेद्यवि Kāś. on P.V. 3.22.

एसुसच् tad. affix एद्युस applied to the pronouns पूर्व, अन्य, अन्यतर, इतर, अपर, अघर, उभय and उत्तर when the words so formed refer to a day; e. g. पूर्वेद्य:, अन्यद्य: etc.; cf. P. V.3.22.

एधा च tad. affix एघा substituted for the tad. affix ঘা optionally, when applied to the words দ্বি and দি. e.g. দ্বিঘা, দ্বৈঘা, দ্বীঘা, দ্বীঘা, দ্বীঘা, দ্বীঘা, দ্বীঘা, দ্বীঘা, দ্বিঘা, দ্বিঘ

पनप् tad. affix एन applied to उत्तर, अधर, and दक्षण optionally instead of the tad. affix आति in the senses of दिक्, देश and काल, e.g. उत्तरेण, उत्तरतः उत्तरात्. Words with this एन at the end govern the acc. case of the word syntactically connected with them. e. g. तत्रागारं धनपतिगृहान् उत्तरेण Kalidasa: Meghaduta; cf. एनपा द्वितीया P.II. 3.31.

Vyākaraņa for the term गुण of Pāṇini standing for the vowels अ, ए and ओ; cf. ऋतः समादेरेप Jain. Vy. V.2.122.

when a mention of it is to be made; cf. T.Pr.I.19; e.g. \%:

पालिम (1) krt. affix केलिमर e.g. पचेलिमा माषा: cf. P. III. 1.96 Vārt. 1; (2) Uṇādi affix एलिमच् applied to पच् cf. पच एलिमच् Uṇ. S.IV.37.

पञ्ज tad-affix चेला the sense of unable to bear, found in Vedic Literature only; e.g. हिमेलु: cf. हिमाचेलुवेक्त न्यः। P.V.2.122 Vart. 7.

एव (1) a particle in the sense of regulation (नियम); cf. एवकार: किमर्थ: नियमार्थ: M. Bh. on V. 3.58; (2) determinant indeclinable; cf. एव इत्यवधारणे; cf. इश्तोवधारणार्थसाहिं। यथैवं विज्ञायेत। अजादी गुणवन्त्रनादेवेति M. Bh. on V. 3.58.

एवकारकरण use of the word एव; cf. उक्तममैवान्ययन इत्यत्र एवकारकरणस्य प्रयो-जनम् M. Bh. on P. III. 4.24.

पश् (1) the substitute ए for the perfect affix त, substituted for the whole त by reason of the indicatory letter श् attached to ए; cf. लिटस्तझयोरोशेरेच् and अनेकाल्शित्सर्वस्य P. III. 4.81 and I. 1.55; (2) affix ए applied to the root चक्ष् in Vedic Literature; cf. नावचक्षे। नावच्यातव्य-मित्यर्थ: Kāś. on P. III.4.15.

एषितब्य necessary to be sought; necessary to be prescribed; cf. तसान्मृजेरिग्ळक्षणा वृद्धिरेषितब्या M. Bh. on I. 1.3. Vart. 8.

ऐ

पे diphthong vowel ऐ; composite form of आ and ए, also termed हृद्धि in Pāṇini's grammar.

ऐकपदिक given in the group of ekapadas or solitarily stated words as contrasted with anekapadas or synonyms. See एकपद above.

ऐकपद्य treatment as one single word especially found in the case of compound words (सामासिकपद) which, as a result of such treatment, have only one accent (acute), and one case affix after the whole word; cf. अयं खल्विप बहुन्नीहिरस्त्येव प्राथमकल्पिकः यस्मिनैकपद्यमैकस्वर्यमेकविभक्तित्वं च M. Bh.on P. I.].29. See एकपद.

ऐकश्रुत्य possession of the same tone or accent; uniformity of tone or accent. See the word एকপ্তুত্তি above; also see P. I. 2.39 Vārt. 1,2; VIII. 1.55 Vārt. 1.

ऐकस्बर्ध having only one principal accent (Udātta or Svarita) for the whole compound word which is made up of two or more individual words; cf. M. Bh. on P. I. 1.29.

ऐकार्थ्ये possession of a single composite sense (by all words together in a compound); cf. संघातस्य ऐकार्थ्यात् मुक्मावा वर्णात् M. Bh. on I. 2.45 Vārt 10; cf. also M. Bh. on II. 2.29 Vārt. 7; cf. also नाम नाम्नैकार्थ्यं समासो बहुलम् Hem. III. 1.18 where the commentator explains ऐकार्थ्यं as एकार्थीमान; In the com. on Hem. III 2.8 ऐकार्थ्यं is explained as ऐकार्यः

ऐच् short term (प्रत्याहार) standing for the two diphthong vowels ऐ and औ; cf. न व्याभ्यां पदान्ताभ्यां पूर्वो तु ताभ्यामेन् P. VII. 3.4; cf. ऐचाश्चोत्तरभूयस्त्यात् M. Bh. on P. I. 1.48. The short substitutes of ऐ and औ are इ and उ when prescribed; cf. P. I. 1.48; so also the protracted forms of ऐ and औ are protracted इ and उ; cf. P. III. 2.106. They are called

हिस्वर vowels in the Rk Prātisākhya. Śakatāyana says they are हिमात्र.

ऐत् the vowel ऐ; cf. एत ऐदित्यैचं M.Bh. on P. III. 4.93.

ऐस्व the substitution of पे for ए by the rule एत ऐ prescribing the substitution of the vowel ऐ for ए in the case of the imperative first person terminations; cf. P. III. 4.93.

ऐन्द्र name of an ancient school of grammar and of the treatise also, belonging to that school, believed to have been written instructions of Indra. The work is not available. Patanjali mentions that Brhaspati instructed Indra for one thousand celestial years and still did not finish his 'instructions in words'; (M.Bh. 1. 1. 1). The Taittirīva Samhitā mentions the same. Panini has referred to some ancient grammarians of the East by the word प्राचाम् without mentioning their names, and scholars like Burnell think that the grammar assigned to Indra is to be referred to by the word प्राचाम. The Brhatkathāmanjarī remarks that Pāņini's grammar threw into the background the Aindra Grammar. Some scholars believe that Kālāpa grammar which is available today is based uponAindra, just as Cāndra is based upon Panini's grammar. References to Aindra Grammar are found in the commentary on the Sārasvata Vyākarana, in the Kavikalpadruma of Bopadeva as also in the commentary upon the Mahābhārata by Devabodha.Quotations, although very few, are given by some writers from the work. All these facts prove that there was an ancient pre-Pāninian treatise on Grammar assigned to इन्द्र which was called Aindra-Vyā-karana.For details see Dr.Burnell's 'Aindra School of Sanskrit Grammarians' as also Vol. VII pages 124-126 of Vyākarana Mahā-bhāṣya, edīted by the D. E. Society, Poona.

पेप a term used in the Jainendra Grammar instead of the term इद्धि of Pāṇini which stands for आ, ऐ and औ; cf. P. I. 1. 1.

ऐरक् taddhita affix ऐर applied to the word चटका in the sense of offspring to form the word चाटकर; cf चटकाया ऐरक् P. IV. 1.128.

ऐषुकार्याद a class of words headed by the word ऐषुकारि to which the taddhita affix मक्त is added in the sense of 'place of residence'; e.g. ऐषुकारिभक्तम्, चान्द्रायणभक्तम्; cf. Kāś. on P.IV.2.54.

ऐस् substitute for the case affix भिन् after words ending in अ; cf. अतो भिस ऐस्. P. VII. 1.9 to 11.

ओ

आ (1) diphthong vowel made up of the vowels अ and उ, termed as guņa in Pāņini's grammar and prescribed sometimes in the place of the vowel उ; (2) affix ओ applied to the root गम् or गा to form a noun; cf. ओकारो नामकरण: Nir.II.5. आकार the syllable ओं called by the term प्रणव and generally recited at the beginning of Vedic works. Patanjali has commented upon the word briefly as follows; पादस्य वा अर्धर्चस्य वा अन्त्यमक्षरमुपसंहृत्य तदाद्यक्षरशेषस्य स्थाने त्रिमात्रमोंकारं त्रिम।त्रमोकारं वा विद्धित तं प्रणव इत्याचक्षते M.Bh. on VIII.2. 89. **आंत्** the vowel ओ; cf. ओत् PI.1.15,16 prescribing प्रगृह्यसंज्ञा for Nipātas like आहो, उताहा and others with a

view that the vowel at their end

should not coalesce with the following vowel. The Prātišākhya works prohibit the coalescence of क्षा in many cases with the succeeding vowel; cf. R. Pr. I. 70; V. Pr. I.94.

अोदित् marked with the indicatory letter ओ; roots marked with the mute letter ओ have the Nisthā affix त or तवत् changed to न or नवत; e. g. लगः, लग्नवान; दीनः, दीनवान etc. cf. ओदितश्च P VIII. 2. 45; cf. also स्वादय ओदितः इत्युक्तम्। सूनः सूनवान; दूनः दूनवान् Si. Kau. on P. VIII. 2. 45.

आंपोर्ट [Gustav Oppert 1836-1908] a German scholar of Sanskrit who edited the Sabdānuśāsana of Sākaṭāyana.

ओम् See ओंकार above—. ओम् consists of $2\frac{1}{2}$ mātras, cf. अर्धतृतीयमात्र एके बुवते T. Pr 18. 1; शैत्यायन says that ओम् has any one of the three accents, while कौण्डिन्य says it has प्रचय or एकश्रुति i. e. absence of any accent.

আনৈত্ব a scholar of grammar of the nineteenth century who wrote a Vrtti on Pāṇini sutras called पাণিনি- মুন্নানি. He has written many works on the Pūrvamimānsā and other Sāstras.

आष्ठ lit. lip; the place of origin (स्थान) of the labial letters called उपध्मानीय वर्ण i. e the vowels उ, ऊ, the consonants प्, फ्, ब्, मं, म् and the उपध्मानीय letter; cf. ऊप्पध्मानीयानामोष्ठी Sid. Kau. on तुल्यास्प्रथयनं सवर्णम् P.I.1.9, also उवोपोपध्मा ओष्ठे V. Pr. I.70.

ओष्ट्रच lit. produced upon the lip; a letter of the labial class; letters उ, ऊ, ओ, औ, प, फ्, ब, म, म and ब are given as ओष्ट्रच letters in the Rk Prātisākhya, cf. R. Pr. I. 20. See the word ओष्ट above. For the utterance of the letter ब tips of the teeth are also employed; hence the letter ब

is said to have दन्तौष्ठ as its स्थान.. ओस् the case affix ओस् of the gen. and the loc. dual.

ओ

औं (1) the vowel ओ; diphthong vowel made up of आ and ओ; (2) the substitute औ for the final letter उ of the word मनु before the fem. affix ई; cf मनो: स्त्री मनायी, मनायी, मनायी, मन्दा Kās. on P. IV. 1. 38; (3) case ending of the nom. and acc. dual called औड़ also.

आहे a term used by ancient grammarians for the affix औ of the nom. and the acc. dual. The vowel है (शी) is substituted for औ in the case of nouns of the feminine and neuter genders; cf. औड: शी P. VII. 1.18, 19.

औद the case ending औ of the acc. dual; cf. P. IV. 1. 2.

आँणादिक an affix mentioned in the class of affixes called उणादि in treatises of Pāṇini and other grammarians; cf.नमुचि: । मुचेरौणादिकः किप्रत्यथः Kāś. on P. VI. 3. 75; भिडभिड्डी औणादिको प्रत्यथो M.Bh. on Siva Sūtra 2. See the word उणादि above.

आैणादिकपदार्णच a collection of words called औणादिक; a name given to his work by पेदुभह of the 18th century.

औत् (1) the letter भे included in the वृद्धि vowels आ, ऐ and भे, and hence called वृद्धि in Pāṇini's grammar, (2) substitute for the caseending इ (कि) in Pāṇini's grammar; cf. P. VII. 3.118, 119.

औत्तरपदिक pertaining to the ulterior member of a compound; cf. औत्तरपदिक हस्वत्वे (P. VI. 3.61) कृते तुक् प्राप्नोति M. Bh. on I. 1.62.

औरव the substitution of the vowel औ; cf. P. VII. 3,117-119.

आरेसार्गिक an affix or an operation resulting from the general rule (उत्सर्ग); cf. अपत्ये कुस्सिते मृढे मनौरो-त्सार्गिक: स्मृत: M. Bh. on IV. 1.161; cf. also एवमप्यौत्सार्गिकाणां तद्विषयता न प्राप्तोति M. Bh. on IV. 2.66.

आदेवाजि an ancient sage and scholar of Vedic Grammar who is believed to have revised the original text of the कक्तन्त्रप्रातिशाख्य of the Sāma-Veda. cf. Śab. Kaus. I. 1.8.

आँदुम्बरायण an ancient sage whose doctrine of 'evanescence of words' (lit. existence as long as its cognition is had by the sense organs) is seen quoted in the Nirukta; cf. इन्द्रियनित्यं वचनमोदुम्बरा-यणस्तत्र चतुष्ट्यं नोपपद्यते Nir. I. 1.

औहें शिक enumerated; actually stated; उद्देशतः प्रोक्तम् आँदेशिकम् cf. न तु आँदेशिकांमिय Nir. I. 4.

औपचारिक resulting from उपचार or लक्षणा; metonymical.

औपदेशिक mentioned in the original statement; cf. अन्तप्रहण आपदेशिकार्थम्। Kāś. on ध्णान्ता घट् P. I. 1,24; cf. also आपदेशिकप्रायोगिकयोगेपदेशिकस्यय प्रह-णम् Par. Sek. Pari. 120.

औपमन्यच name of an ancient etymologist referred to by Yāska in his Nirukta possibly as a commentator on निवण्ड; cf. निगन्तव एव सन्तो निगमनानिवण्टव उच्यन्ते इत्योपमन्यवः Nir. I. line 4.

आँपिमिक figurative; metaphorical application or statement; cf. (विराद्) पिपीलिकमध्या इत्यापिमकम् Nir. VII. 13.

सौपन्छेषिक resulting from immediate contact; immediately or closely connected; one of the three types of अधिकरण or location which is given as the sense of the locative case; cf. अधिकरण नाम त्रिप्रकारं—व्यापकम् औपश्ठाधिकम्, वैषयिकमिति ... इको यणाचि। अचि उपान्छिष्टस्येति। M. Bh. VI. 1.72.

औपसंख्यानिक subsequently stated by way of addition or modification as done by the Vārttikakāras; cf. औपसंख्यानिकस्य णस्यापवादः । आरण्यंको मनुष्यः Kāś. on P. IV. 2. 129; cf. also Kāś. on V.1.29 and VI.3.41.

अोरस produced from the chest; the Visarjanīya and h (इकार) are looked upon as ओरस and not कण्य by some ancient phoneticians; cf. केचि-दाचार्या: एतो हकारिक्सर्जनीयो उर:स्थानाविच्छ-नित com. on R. Pr. I. 18; cf. also हकार पञ्चमेप्रैक्तमन्तस्थाभिश्च संयुत्तम् । उरस्यं तं विजानीयात्कण्यमाहुरसंयुतम् ॥ Pān. Sikṣā. 16.

औरस्य produced from the chest. See औरस.

और substitute औ for the nom. and acc. case endings applied to the numeral अष्टन; cf. अष्टाभ्य और् P. VII. 1.21.

भौष्णिह beginning with a stanza of the Uspih metre; cf. उष्णिहापूर्वः सतो- बृहत्यन्तः प्रगाथः औष्णिह इत्युच्यते । यथा-यमा- दित्यासो अहुहः Uvaṭa on R.Pr.XVIII.5.

🕹 (अनुस्वार)

→ अनुस्वार or nasal (1) looked upon as a phonetic element, independent, no doubt, but incapable of being pronounced without a vowel preceding it. Hence, it is shown in writing with अ although its form in writing is only a dot above the line; cf. अं इत्यनुस्वार:।अकार इह उचारणार्थ इति बिन्दुमात्रो वर्णोनुस्वारको भवति Kāt. Vyāk. I.1.19; (2) anusvāra, showing or signifying Vikāra i.e. आगम and used as a technical term for the second विभक्ति or the accusative case. See the word अं above on page 1.

: (विसर्ग)

ः विसर्जनीय or विसर्ग; lit. letting out

breath from the mouth; sound or utterance caused by breath escaping from the mouth; breathing. The Visarjanīya, just like the anusvāra, is incapable of being independently uttered. Hence, it is written for convenience as अः although its form for writing purposes is only two dots after the vowel preceding it; cf. अः इति विसर्जनीयः। अकार इह उच्चारणार्थः इति कुमारी-स्तन्युगाकृतिविणी विसर्जनीयसंजो भवति। Kāt. Vyāk. I. 1.16. See अः above on page 2:

💢 (जिह्वामूळीय)

ত্ৰী মুক্তীয়, a phonetical element or unit called Jihvāmūliya, produced at the root of the tongue, which is optionally substituted in the place of the Visarga (left out breath) directly preceding the utterance of the letter ক or অ্ and hence shown as ≍ ক. See অ≍ক্ above on page 2.

७ (उपध्मानीय)

७ उपध्मानीय lit. blowing; a term applied to the visarga when followed by the consonant q or q. The upadhmānīya is looked upon as a letter or phonetic element, which is always connected with the preceding vowel. upadhmānīya is an optional substitute for the visarga before the letter q or \u03c4, when, in writing, is to be shown instead of the visarga, it is shown O, or as ∞, or even as × just as the Jihvāmūlīya; cf. उपभायते शब्दायते इति. उप समीपे ध्मायते शब्दाते इति वा com. on Kāt. I:; cf. also कपाभ्यां प्रागर्धविसर्गसहशौ जिह्नामूलीयोपध्मानीयौ: S.K.on P.VIII.2.1.

॰ (नासिक्य)

ँ नासिक्य, a nasal letter or utterance included among the अयोगवाह letters analogous to anusvāra and yama letters. It is mentioned in the Vājasanevi Prātiśākhya as គី इति नासिक्यः on which Uvvata makes the remark अयमकशाखायां प्रसिद्ध:. The Rk-Pratisakhya mentions नासिक्य, यम and अनुस्वार as नासिक्य or nasal letters, while Uvvata defines नासिक्य as a letter produced only by the nose; cf. केवलनासिकया उच्चार्यमाणा वर्णा नासिक्यः Uvvata on R. Pr. I. 20. The Taittirīya Prātiśākhya calls the letter g as nāsikya when it is followed by the consonant न or प् or म् and gives अह्नाम्, अपराह्ने and The Paniniya শহা as instances. Siksā does not mention नासिक्य as a letter. The Mahabhasya mentions नासिक्य as one of the six ayogavāha letters; cf. के पुनरयो-गवाहाः । विसर्जनीयजिह्वामूलीयोपध्मानीयानु-स्वाराननासिक्ययमाः M. Bh. on Sivasntra 5 Vart. 5, where some manuscripts read नासिक्य for आनुना-सिक्य while in some other manuscripts there is neither the word आनुनासिक्य nor नासिक्य. It is likely that the anunasika-colouring given to the vowel preceding the consonant & substituted for the consonants म, न and others by P. VIII. 3.2. to 12, was looked upon as a separate phonetic unit and called नासिक्य as for instance in संस्कर्ता, मा हि सी:, संशिशाधि etc.

५ (यम)

भ्रम, a letter called यम which is uttered partly through the nose. A class consonant excepting the fifth, when followed by the fifth viz. इ. ज्, ण्, न् or म्, gets doubled

in the Vedic recital, when the second of the doubled consonant which is coloured by the following nasal consonant is called यम. This यम letter is not independent. It necessarily depends upon the following nasal consonant hence it is called अयोगवाह. nasalization is shown in script as ~ followed by the consonant; e. g. पलिक् ^४की, अग् के, etc. The pronunciation of this yama or twin letter is seen in the Vedic recital only; cf. पलिकक्नी ... कम्ब्रगधेभ्यः परे तत्सहशा एव यमाः S. K. on P. VIII. 2. 1. cf. कुँ खुँ गुँ बुँ इति यमाः विश्वति-संख्याका भवन्ति V. Pr. VIII. 24.

क

- ক্ (1) the consonant ক্; the first consonant of the consonant group as also of the guttural group; (2) substitute ক্ for consonants q and ৱ before the consonant q;cf.V.P.2.41. For the elision (লাম) of ক্ on account of its being termed হ্ল see P.I.3.3 and 8.
- 隔 (1) tad.affix 事 applied to the words of the ऋश्य group in the four senses called चातुर्रार्थक e. g. ऋस्यक:, अनइस्क:, बेणुक: etc., cf. P.IV. 2.80; (2) tad. affix 事 applied to nouns in the sense of diminution, censure, pity etc. e. g. अधक:, उर्क:, पुत्रक:, cf. P.V. 3.70-87;(3) tad. affix 表 in the very sense of the word itself (स्वार्थे) e.g. अविकः, यावकः, कालकः; cf. P.V. 4.28-33; (4) Uṇādi affix क e.g. कर्क, वृक, राका, एक, भेक, काक, पाक, शस्क etc. by Unadi sutras III. 40-48 before which the angment zz is prohibited by P. VII. 2.9; (5) krt affix 本 (अ) where ক is dropped by P. I. 3.8, applied, in the sense of agent, to certain roots mentioned P.III.1.135, 136, 144, III. 2.3 to

7, III.2.77 and III.3.83 e.g. बुध:, प्रस्थ:, गृहम्, कम्बलदः, द्विप:, मूलविभुजः, सामगः, सुराप: etc.; (6) substitute क for the word किम before a case affix, cf. P.VII.2.103; (7) the Samāsānta affix कप् (क) at the end of Bahuvrīhi eompounds as prescribed by P. V. 4.151-160.

ककार the consonant क; cf. वर्णात्कार: P. III.3.108 Vart. 3.

कंसविजयगणि a Jain grammarian who wrote a commentary by name शब्दचन्द्रिकोद्धार on the सारस्वतव्याकरण.

कक्योदि a class of words headed by the word कर्की, the word प्रस्थ after which in a compound, does not have the acute accent on its first vowel. e. g. कर्कीप्रस्थ; cf. P. VI.2.87.

কভ্নাই a class of words headed by কভ্ন to which the taddhita affix অণ্ is added in the miscellaneous (ইাদিক) senses, provided the word, to which the affix অণ্ is to be added, is the name of a country; e.g. ক্ষমিক্ষ জাল: আর্থিক:; similarly মাহিদিক:, ট্হলাক:; cf. Kāś. on P.IV.2.133.

करु tad. cāturarthika affix क (1) by P. IV. 2.80 after words headed by बराह, e.g. बराहक:, पलाशक:; (2) by P.IV.4.21, after the word अपमित्य e.g. आपमित्यक:

कञ् kṛt, affix (अ) affixed to the root हश् preceded by त्यर्, तद् etc. by P. IV. 2.60 e.g. ताहशः, याहशः etc., fem. ताहशी by P. IV.1.15.

कटच् tad.affix कट affixed to सं, प्र, उद् and अब by P.V.2.29, 30; e.g. संकट, प्रकट etc.

कट्यच् tad. affix कटय affixed to the word रथ in the sense of collection by P.IV.2.51 e.g. रथकटया.

कडारादि a class of words headed by the word कडार which, although adjectival, are optionally placed first in the Karmadhāraya compound, e.g. कडारजैमिनि: जैमिनिकडार:; cf. Kāś. on II.2.38.

कर्णादि (1) a class of words headed by कर्ण to which the taddhita affix आयन (फिल्ल) is applied in the four senses given in P. IV.2.67-70; e.g. कार्णायनिः वासिष्ठायनिः etc.; cf. Kāś. on P. IV.2.80; (2) a class of words headed by कर्ण to which the taddhita affix जाह (जाह्ल) is added in the sense of a 'root' e.g. कर्णजाहम्; cf. Kāś. on P.V.2.24.

মত্বমীদ্ধাৰ name of a commentary on Nāgeśa's Paribhāṣenduśekhara by Mannudeva, known also as Mantudeva or Manyudeva, who was a pupil of Pāyaguṇḍe in the latter half of the 18th century.

कण्ड glottis; cavity in the throat holding vocal cords; the place of the production of the sounds अ, आ and ह; cf. अहविसर्जनीया: कण्डे V, Pr.I. 71; cf, also कण्डयोऽकार: प्रथमपञ्चमी च R.Pr.I.18.

कण्डतालच्य gutturo-palatal. The diphthongs ए and ए are called Kanthatālavya, as they are produced in the Kanthatālu-sthāna.

कण्डोक्त formally mentioned; directly mentioned.

কত্তীষ্টৰ, কত্তীষ্টৰ gutturo-labial, the diphthongs জা and জা are called Kanthosthya as they are produced at both the Kantha and the Ostha Sthanas.

कण्ड्य produced at the throat or at the glottis: the vowel अ, visarga and the consonant ह् are called कण्डयं in the Prātiśākhyas, while later grammarians include the guttural consonants क्, ख्, ग्, च् and ङ् among the Kanthya letters; cf. अकुह्विसर्जनीयानां कण्डः Sid. Kau. on तुल्यास्यप्रयस्नं सवर्णम् P. I. 1. 9. See कण्ड.

कण्ड्वादि a group of words which are headed by the word कण्डू and which are either nouns or roots or both, to which the affix यक् is added to arrive at the secondary roots. e. g. कण्डूयति, कण्डूयते; हणीयति, हणीयते, महीयते cf. धातुप्रकरणाद्धातुः कस्य चासञ्जनादि । आह चायमिमं दिन्ने मन्ये धातुर्विभाषितः।। Kāś. on P. III.1.27.

कण्वादि a class of words forming a portion of the class of words called गर्गादि, and headed by the word कण्व, to the derivatives of which, formed by the affix यन by the rule गर्गादिस्यो यन् (P.IV.1.105), the affix अण् is added in the miscellaneous senses; e.g. काण्वा: छात्राः; similarly गौकक्षाः, आकळाः, अगस्तयः, कुण्डिनाः etc; cf. P.IV.2.111 and II. 4.70.

कत्यादि a class of words headed by the word किन्न to which the tad. affix एयक (ढकञ्) is applied in the miscellaneous senses: e.g. कानेयक:, प्रामेयक;, कौलेयक: (from कुल्या); cf. P. IV.2,75.

कथादि a class of words headed by the word कथा to which the affix इक (उक्) is added in the sense of 'good therein' (तत्र साधु:); e.g. काथिक:, वैतिण्डिक:, गाणिक:, आयुर्वेदिक:; cf. P.IV. 4.102.

कध्ये, कध्येन krt affix अध्य of the infinitive in Vedic Literature: cf. तुमथें सेते...कध्येकध्येन त्रेन: P.III.4.9.

कन् (1) uṇādi affix as in the words एक, भेक, शब्क etc; (2) tad.affix क as given by Pāṇini sūtras IV.2.131, IV.3.32, 65, 147, IV.4.21; V.1.22, 23, 51, 90, V.2. 64, 65, 66, 68-75, 77-82, V.3.51, 52, 75,81,82,87, 95, 96, 97. V.4.3,4,6, 29-33.

क्ष् (1) krt affix क prescribed after the root दुई e. g. कामदुना; cf. P.III.2. 70;(2) the Samāsānta अ at the end of Bahuvrihi compounds e.g. ब्यूहो-रस्कः, बहुदण्डिका, बहुकुमारीकः, बहुकतृकः, cf. P. V.4.151-154. For its prohibition, see P. V.4.155-160.

कर्माणिपाद name given by Sîradeva and other grammarians to the second pāda of the third adhyāya of Pāṇini's Aṣṭādhyāyī, which begins with the sūtra कर्मण्यम् P. III. 2.1.

कमुळ् krt. assix अम् in Vedic Literature in the sense of the infinitive, e.g. विभाजं in आर्थ वे देवा विभाजं नाशक्तुवन्; cf. P.III.4.12.

कम्प vibration of the larynx which produces the sound.

क्रम्पन a fault in uttering an accented vowel especially a vowel with the circumflex accent which is not properly uttered by the Southerners as remarked by Uvvața; cf. कम्पनं नाम स्वराधितपाठदोष: । स च प्रायेण दाक्षिणात्यानां भवति । स च वज्येः । Uvvața on R. Pr. III.18.

किम्पत the same as कम्पन. See कम्पन above.

कम्बोजादि a class of words headed by the word कम्बोज, the affix अज् placed after which is elided, provided the words कम्बोज and others are names of countries; e.g. कम्बोज: चोल:, केरल:, शक:, यवन: etc. cf. P. IV. 1.175.

करण (1) lit. instrument; the term signifies the most efficient means for accomplishing an act; प्रकृशोपकारकं कियासि**ड**ो यत् विवक्षित तत्साधकतभं कारकं करणसंत्रं भवति, Kas. P. I. 4.42, साधकतमं करणम् e. g. दात्रेण in दात्रेण लुनाति; (2) effort inside the mouth (आभ्यन्तर-प्रयत्न) to produce sound; e.g. touching of the particular place (स्थान) inside the mouth for uttering consonants; cf. स्पृष्टं स्पर्शानां करणम् M. Bh. on P. I. 1.10 Vart. 3; (3) disposition of the organ which produces the sound; cf. श्वासनादो-भयानां विशेषः करणमित्युच्यते । एतच्च पाणिनि-संमताभ्यन्तरप्रयत्न इति भाति । Com. on R. Pr. XIII.3:cf also स्थानकरणानप्रदानानि M. Bh. on I. 2. 32; cf. अनुप्रदानात्संसर्गात् स्थानात् करणविन्ययात् । जायते वर्णवैशेष्यं परीमाणाच्च पञ्चमात T. Pr. XXIII. 2 where karana is described to be of five kinds अनुप्रदान (i.e. नाद or resonance), संसर्ग (contact), स्थान, करणविन्यय and परिमाण; cf. अकारस्य तावत्—अनुप्रदानं नादः, संसर्गः कण्ठे, स्थानं हुनू, करणविन्ययः ओष्टी, परिमाणं मात्राकालः । अनुप्रदानादिभिः पञ्चभिः करणेर्वणीनां वैशेष्यं जायते Com. on Tai. Pr. XXIII. 2. The Vājasaneyi Prātisākhya mentions two karaṇas संवृत and विवृत; cf. द्वे करणे संवृतविवृताख्ये वायोभवतः V. Pr. I. 11; (4) use of a word e.g. इतिकरणं, वत्करणम्; cf. किमुपस्थितं नाम । अनाषे इतिकरण: M.Bh.on. P.VI.1.129.

करविणी or कविणी name of a svarabhakti i. e. behaviour like the vowel ल, noticed in the case of the consonant ल when followed by the sibilant हू; cf. करेणू रहयोयोंने कविणी लहकारयोः । हरिणी रशसानां च हारिता लशकारयोः ॥ करेणुः बर्हिः । काविणी मलहाः Com. on T. Pr. XXI. 15. See स्वरमक्ति.

करिणी name of a svarabhakti i. e. behaviour like the vowel क noticed in the case of the consonant र when it is followed by इ e. g. बरहि: करिणी is named करेण also.

करिष्यत् करिष्यन्ती ancient technical terms for the future tense; the word करिष्यन्ती is more frequently used.

कर्णमूळीय produced at the root of the ear; the utterance of a circumflex vowel is described as Karṇamūlīya.

करी agent of an action, subject; name of a kāraka or instrument in general, of an action, which produces the fruit or result of an action without depending on any other instrument; cf. स्वतन्त्रः कर्ता P. I. 4.54, explained as अगुणीभूतो यः क्रियाप्रसिद्धो स्वातन्त्र्यण विवश्यते तत्कारकं कर्तृ-संग्रं भवति in the Kasikā on P. I. 4. 54. This agent, or rather, the word standing for the agent, is put in the nominative case in the active voice (cf. P. I.4.54), in the instrumental case in the passive voice (cf P. II. 3.18), and in the genitive case when it is connected with a noun of action or verbal derivative noun, (cf. P. II. 3.65).

कतृंयक् the affix य of the passive voice where the object functions as the subject; e. g. यक् in द्रयते केदार: स्वयमेव; cf. अचः कर्तृयकि P. VI. 1.95 and the Kāśikā thereon.

कर्तवेदना experience (of something) by the agent himself; cf. सुखादिभ्यः कर्तृवेदनायाम् P. III. 1.18.

कर्तृसाधन (an affix) applied in the sense of the agent of an activity; भवतीति भावः। कर्तृसाधनश्चायं प्रत्ययः M. Bh. on P. I. 3.1. Vārt. 7.

कर्तस्थिकिय (a root) whose activity is found functioning in the subject; cf. यत्र क्रियाञ्चतिबेशेषदर्शनं कर्तिर Kaiyaṭa on P. III. 1.87 Vārt. 3. Such roots, although transitive do not have any Karmakartari construction by the rule कर्मवस्कर्मणा तुल्यक्रियः P. III. 1.87 as e.g. ग्रामं गच्छित देवदत्तः has no कर्मकर्तिर construction; cf. कर्मस्थमावकानां कर्मस्थिकियाणां वा कर्ता कर्मवद् मवतीति वक्तव्यम् । कर्तृस्थमावकानां कर्तृस्थिकियाणां वा कर्ता कर्मवन्मा मूदिति M. Bh. on III. 1.87. Vārt. 3.

कर्तस्थभावक (a root) whose action or happening is noticed functioning in the subject; e.g. the root स्मृ. cf. कर्तस्थभावकश्चार्य (स्मरति:) M. Bh. on I. 3.67, कर्त्रस्थभावकश्च होति: (शीषातु:) M. Bh. on V. 3.55.

The word

कत्रीभेप्राय meant for the agent of the action. The word is used in connection with the fruit or result of an action; when the result is for the agent, having both the Padas get the terminations; Ātmanepada स्वरित्रञितः कर्त्रभिष्राये क्रियापले P. I. 3.72. कमेकते object of the transitive verb which functions as the subject when there is a marked facility of action; e.g.ओदन is karmakartariobject, functioning as subject.

कर्मकर्त is used also for the कर्मकर्तार

प्रयोग where the object, on which

the verb-activity is found, is

turned into a subject and the

verb which is transitive is turned

into intransitive as a result.

in पन्यते ओदनः स्वयमेवः

कर्मधारय name technically given to a compound-formation of two words in apposition i.e. used in the same case, technically called समानाधिकरण showing the same substratum; cf. तत्पुरुषः समानाधिकरणः कर्म-धारय: I 2.42. The karmadhāraya compound is looked upon as a variety of the tatpurusa compound. There is no satisfactory explanation of the reason such a compound is termed कर्म-धारय. Sākatāyana defines Karmadhāraya as विदेशियां व्यभिचारि एकार्थ कर्मधारयश्च where the word विशेषण is explained as ब्यावर्तक or भदक (distinguishing attribute) showing that the word कर्म may mean भेदककिया. The word कर्मधारय in that could mean 'कर्म भेदककिया, तां धारयति असौ कर्मधारयः' a compound which gives a specification of the thing in hand.

कर्मन् (1) object of a transitive verb, defined as 'something which the agent or the doer of an action wants primarily to achieve. The main feature of कर्मन् is that it is put in the accusative case; cf. कर्तुरीप्सित्तमं कर्म, कर्मणि द्वितीया; P. I. 4.49; II.3.2. Pānini has made 奉护 a technical term and called all such words 'karman' as are connected with a verbal activity and used in the कत्रीप्सिततमं accusative case; cf. कर्म: तथायक्तं चानीप्सितम: अकथितं च and गतिबद्धिप्रत्यवसानार्थशब्दकर्माकमकाणामणि कर्ता स णौ P.I.4.49-52;cf. also यत् क्रियंत तत् कर्म Kāt. II.4.13, कर्जाप्यम् Jain I. 2. 120 and कर्तव्याप्यं कर्म Hem. II. 2. 3. Sometimes a kāraka, related to the activity (किया) as sampradana, apādāna or adhikarana is also treated as karma, if it is not meant or desired as apādāna, sampradāna etc. It is termed अकथितकर्म in scuh cases; cf. अपादानादिविदेशक्यशामिरविवाधितमकथितम on I.4.51. See the word अकथित above. Karman or object is to be achieved by an activity or क्रिया: it is always syntactically connected with a verb or a verbal derivative. When connected with verbs or verbal derivatives indeclinables or words ending with the affixes उक, क्त, क्तवतु, तृन्, etc, it is put in the accusative case. It is put in the genitive case when it is connected with affixes other than those mentioned above; cf. P. II. 3.65, 69. When, however, the karman is expressed (अभिहित) hy a verbal termination (রিহু), or a verbal noun termination (到刊), or a nounaffix (तद्धित), or a compound, it is put in the nominative case. e.g. कट: कियते, कट: कृत:, शस्य:, प्राप्तोदक: प्राम: etc. It is called अभिहित in such cases;cf.P.II.3.1. See the word প্ৰন-भिहित above. The object or Karman which is ईप्सिततम is described to be of three kinds with reference to the way in which it is obtained

from the activity. It is called विकार्य when a transformation or a change is noticed in the object as a result of the verbal activity, e. g. काष्टानि भरमीकरोति, घटं मिनात्त ete. It is called प्राप्य when no change is seen to result from the action, the object only coming into contact with the subject, e. g. ग्रामं गच्छति, आदित्यं पश्यति etc. It is calledनिवेर्त्यwhen the object is brought into being under a specific name: e.g. घटं करोति. ओदनं पचति: cf. निर्वर्त्यं च विकार्यं च प्राप्यं चेति त्रिधा मतम् । तत्रेप्सिततमम् Padamañjarī on I. 4. 49; cf. also Vākyapadīya III.7.45 as also Nyāsa on 1.4.49. The object which is not ईप्सिततम is also subdivided into four kinds e.g. (a) अनीप्सित (ग्रामं गच्छन्) व्याघ्रं पञ्चति, (b) औदासीन्येन प्राप्य or इतरत or अनुभय e. g. (ग्रामं गच्छन्) वृक्षमूलानि उपसपेंति, (c) अनाख्यात or अकथित e.g. बालें in बालें याचते वसुधाम् (d) अन्यपूर्वक e.g अक्षान् दीन्यति, ग्राममभिनिविशते; cf. Padamañjarī on I.4 49. The commentator Abhayanandin on Jainendra Vyākaraņa mentions seven kinds प्राप्य, विषयभूत, निर्वर्त्य, विकियात्मक, ईंप्सित, अनीप्सित and इतरत्, defining कमें as कर्त्रा क्रियया यद् आप्य तत् कारकं कर्म; cf. कर्त्राप्यम् Jain. Vy. I.2.120 com. thereon. जैनेन्द्रमधीते is given therein as an instance of विषयभूत. (2) The word कर्मन् is also used in the sense of किया or verbal activity; cf. उदोनूर्ध्वकर्मणि P. I. 3.24; आदिकर्मणि क्तः कर्तरि च P.III.4.71, कर्तरि कर्मव्यतिहारे P. I.3.14. (3) It is also used in the sense of activity in general, as for instance, the sense of a word; e. g. नामाख्यातयोस्तु कर्मोपसंयोग-द्योतका भवन्ति Nir. I. 3.4, where Durgācārya explains karman as 'sense' (अर्थे).

कर्मनामन् lit. noun showing action, participle.

कर्मप्रवचनीय a technical term used in

connection with a preposition which showed a verbal activity formerly, although for the present time it does not show it; the word is used as a technical term in grammar in connection with prefixes or उपसर्गंड which are not used along with a root, but without it; cf. कर्म प्रोक्तवन्त: कर्मप्रवचनीया: इति M.Bh. on P. I. 4.83; e.g. शाकल्यस्य संहितामनु प्रावर्षत्, अन्वर्जुनं योद्वारः, आ कुमारं यश: पाणिने:; cf. Kāś. on P. I.4.83 to 98.

कमेवद्भाव the activity of the agent or karta of an action represented as object or karman of that very action, for the sake of grammatical operations; e. g. भिद्यते काष्ठं स्वयमेव; करिष्यते कटः स्वयमेव. To show facility of a verbal activity on the object, when the agent or kartā is dispensed with, and the object is looked upon as the agent, and used also as an agent, the verbal terminations ति, तः etc. are not applied in the sense of an agent, but they are applied in the sense of an object; consequently the sign of the voice is not অ (হাৰু), but य (यक्) and the verbal terminations are a. आताम् etc. (तङ्) instead of ति. तस् etc. In popular language the use of an expression of this type is called Karmakartari-Prayoga. For details see M. Bh. on कर्मवत्कर्मणा तल्यक्रिय: P. III. 1.87. Only such roots as are कर्मस्थिकियक or कर्मस्थभावक i. e. roots whose verbal activity is noticed in the object and not in the subject can have this Karmakartari-Prayoga.

कर्मन्यतिहार exchange of verbal activity; reciprocity of action; कर्मन्यतिहार means कियान्यतिहार or कियानिनमय; cf. कर्तरि कर्मन्यतिहारे P. I. 3.14.; also कर्मन्यतिहारे णच् स्त्रियाम् । न्यानकोशी, न्यासुक्षी Kas. on P. III. 3.43.

The roots having their agents characterized by a reciprocity of action take the Atmanepada terminations; cf. P. I. 3.14.

कमेसाधन prescribed in the sense of an object; a term used in the sense Mahābhāsya in the in the sense affixes used 'object' as contrasted with कत्साधन or भावसाधन; e. g. the affix कि in the word विधि, explained as विधीयते इति विधि: or in the word भाव explained as भाज्यते यः स भावः; cf. क्रिया चेव हि भाव्यते, स्वभावसिद्धं तु द्रव्यम् M.Bh. on P. I. 3.1. See similarly the words समाहार M.Bh. on II. 1.51 and उपधि M.Bh. on V. 1.13.

कर्मस्थिकिय (roots) having their verbal activity situated in the object; e.g. the root अव + रुघु in अवस्णिद्ध गाम् or the root क्र in करोति कटम्; cf. कर्मस्थमा-वकानां कर्मस्थिकियाणां च P.III. 1.87 Vart. 3.

कर्मस्थभावक (roots) having their verbal action or happening noticed in the object; e. g. the root आम् and शां in बालमासयित शाययित where the function of the root bears effect in the object boy and not in the movements of the object as in the sentence बालमवरणित्व. See कर्मस्थिकिय above as also M.Bh. on III. 1.87 and Kaiyata on the same.

कर्मादि lit. karman and others; a term often used in the Mahābhāṣya for kārakas or words connected with a verbal activity which have the object or karmakāraka mentioned first; सुपां कर्मादयोप्यर्था; संख्या चैव तथा तिङाम् M.Bh. on I. 4.21.

कर्मापदिष्ट operations prescribed specifically for objects i. e. prescribed in the case of objects which are described to be functioning as the subject to show facility of the verbal action; e.g. the vikaraṇa

यक् or the affix निण्; cf. कर्मापदिश विधयः कर्मस्थमावकानां कर्मस्थिक्रयाणां वा भवन्ति । कर्नस्थमावकाश्च दीपादयः M.Bh.on I.1.44.

कविणी A kind of svarabhakti. See करनिणी.

कर्षण extension; protraction, defined as kālaviprakarṣa by commentators; a peculiarity in the recital as noticed in the pronunciation of ट्र when followed by च्, or ड्र when followed by च e.g. बर्च; षड्जात. cf. Nār. Śik. I.7.19.

कल a fault of pronunciation consequent upon directing the tongue to a place in the mouth which is not the proper one, for the utterance of a vowel; a vowel so pronounced; cf. संवृतः कलो ध्मातः... रामश इति। cf.also निवृत्तकलादिकामवर्णस्य प्रत्यापत्तिं वश्यामि M.Bh. Ahnika 1.

कलाप (कलाप-ब्याकरण) alternative name given to the treatise on grammar written by Sarvavarman who is believd to have lived in the days of the Sātavāhana kings. The treatise is popularly known by the name Katantra Vyakarana. The available treatisc, viz. Kalāpasütras, is much similar to the Katantra Sūtras having a few changes and additions only here and there. It is rather risky to say that Kalapa was an ancient system of grammar which is referred to in the Panini Sūtra कलापिनोण P. IV. 3, 108. For details see कातन्त्र.

कलापरन a commentary on the kāraka portion of the Kalāpa grammar ascribed to the famous commentator Durgasimha.

कलापसंत्रह a commentary on the Kalāpa Sūtras.

কন্তাণিব the author of the work referred to as Kālāpa in the Mahābhāṣya which perhaps was a work on grammar as the word কান্তাণ is mentioned with the word महावार्तिकम् in the Mahābhāṣya, cf. M.Bh. on कलापिनोऽण् P. IV. 3. 108. Kalāpin is mentioned as a pupil of Vaisampāyana in the Mahābhāṣya; cf. वैशम्पायनान्तवासी कलापी M.Bh. on P. IV.3. 104.

कल्प the tad. affix कल्प् added to any substantive in the sense of slightly inferior, or almost complete; e.g. पटुकल्प:, मृदुकल्प:; cf. P. V. 3. 67 and Kāśikā thereon.

करपन, करपना supposition, assumption; cf. गुणकरपनया च भिक्षुनदस्त्रयोश्छन्दस्त्वम् Kāś. on P. IV.3. 110; cf. also अनेकिंक्ष्रकरपनापेक्षया अस्या उचितत्वात् Pari.Sek. on. Pari. 94.

কল্পনাভাষৰ brevity of thought; brevity of expression; minimum assumption. See the word ভাষৰ.

कल्पप् tad. affix कल्प. See कल्प.

कल्पलता name of a commentary on Bhattoji's Praudhamanoramā by Kṛṣṇamiśra.

करमन् the same as karman or object of an action especially when it is not fully entitled to be called karman, but looked upon as karman only for the sake of being used in the accusative case; subordinate karman, as for instance the cow in गां पयो दोग्धि. The term was used by ancient grammarians; cf. विपरीतं तु यस्कर्म तत् कस्म कवयो विदु: M.Bh. on P.I. 4. 51. See कर्मन.

कल्याणमञ्ज author of the commentary Sabdaratnadipa on the Sabdaratna of Hari Dikṣita.

कल्याणसरस्वती author of the Laghusārasvata, a small grammar work. He lived in the 18th century A. D.

कल्याणसागर author of the Haimalingānuśāsana-vivaraṇa, a commentary on the Linigānuśāsana chapter of Hemacandra's grammar. He lived in the 16 th century A. D.

कल्याण्यादि a class of words headed by the word इत्याणी to which the taddhita affix एय (दक्) is added, in the sense of 'offspring' and, side by side, the ending इन् (इनङ्) is substituted for the last letter of those words; e.g. काल्याणिनयः, सौभागिनयः; cf. Kas. on P. IV. 1.126.

कवर्ग the class of guttural consonants consisting of the five consonants क्, ल, ग, व् ङ्

कविकल्पद्धम a treatise on roots written by Bopadeva, the son of Kesava and the pupil of Dhanesa who lived in the time of Hemādri, the Yādava King of Devagiri in the thirteenth century. He has written a short grammar work named Mugdhabodha which has been very popular in Bengal being studied in many Tols or Pāṭhaśālās.

कविकल्पद्धमदीका a commentary on the Kavikalpadruma, written by the author (बोपदेव) himself. It is known by the name Kāvyakāmadhenu; (2) a commentary on Kavikalpadruma by Rāmatarkavāgiša.

कविचन्द्र author of a small treatise on grammar called Sārasatvarī. He lived in the seventeenth century A.D. He was a resident of Darbhangā. Jayakṛṣṇa is also given as the name of the author of the Sārasatvarī grammar and it is possible that Jayakṛṣṇa was given the title, or another name, Kavicandra.

कर्यप name of a writer on the Candra Vyakarana.

कसुन krt affix अस found in Vedic Literature, in the sense of the infinitive; e. g. ईश्वरो विलिख: (विलि- खितुम्) cf. P. III. 4.13, 17. The word ending in this बंसुन becomes an indeclinable; cf. बत्वातोसुन्कसुन: P. I. 1.40.

कसेन krt affix असे in the sense of the infinitive in Vedic Literature; e. g. प्रेषे, श्रियसे; cf. Kās. on P. III. 4.9.

करकादि a class of compound-words headed by करक in which the visarga occurring at the end of the first member is noticed as changed into स against the usual rules; e. g. करकः, कौतस्कृतः भ्रातुष्पुत्रः, सद्यस्कालः, धनुष्कपालम् and others; cf. P. VIII. 3.48. As this करकादिगण is said to be आगृतिगण, similar words can be said to be in the करकादिगण although they are not actually mentioned in the गणपाठ.

का a technical term used in the Jainendra Vyākaraņa for the term पञ्जमी used in Paṇini's grammar.

काण्ड tad. affix काण्ड prescribed after words like दूर्वा, तृण, कर्म in the sense of समूह; cf. दूर्वादिभ्य: (v. l. पूर्वादिभ्य:) काण्ड;; Kāś. on P.IV. 2.51.

काण्डमायन name of an ancient writer of a Prātisākhya work who held that Visarga before the consonant स is dropped only when स is followed by a surd consonant; cf. Tai.Pr. IX. 1.

कातन्त्र name of an important small treatise on grammar which appears like a systematic abridgment of the Astadhyayi of Panini. It ignores many unimportant rules of Panini, adjusts many, and altogether omits the Vedic portion and the accent chapter of Pāṇini. It lays down the Sutras in an order different from that of Pānini dividing the work into four adhyāyas dealing with technical terms, samdhi rules. declension, syntax, compounds noun-affixes (taddhita affixes) conjugation, voice, and verbal derivatives in an order. The total number of rules is 1412 supplemented by many subordinate rules or Vārttikas. The treatise is believed to have been written by Sarvavarman, called Sarvavarman or Sarva or Sarva, who is said to have lived in the reign of the Satavahana kings. belief that Pāṇini refers to a work of Kalāpin in his rules 3.108 and IV. 3.48 and Patanjali's words - कालापम माहावार्तिकम् support it, has much strength. The work was very popular especially among those who wanted to study spoken Sanskrit with ease and attained for several years a very prominent place among text-books on grammar especially in Behar, Bengal and Gujarat. It has got a large number of glosses and commentary works, many which are in a manuscript form at present. Its last chapter (Caturtha-Adhyāya) is ascribed to Vara-As the arrangement of topics is entirely different from Panini's order, inspite of considerable resemblance of Sutras and their wording, it is probable that the work was based on Pānini but composed on the models of ancient grammarians viz. Indra. Sākatāyana and others works, although not available now, were available to the author. The grammar Kātantra is called Kālāpa. A comparison of the Kātantra Sūtras and Sūtras shows that Kālāpa one is a different version of The Kātantra Gramthe other.

107

mar is also called Kaumāra as it is said that the original instructions for the grammar were received by the author from Kumāra or Kārttikeya. For details see Vol. VII Pātanjala Mahābhāṣya published by the D. E. Society, Poona, page 375.

कातन्त्रकोसुदी (i) a commentary on the Kātantra Sūtras written by Govardhana in the 12th century. A. D.; (2) a commentary on the Kātantra Sūtras ascribed to Gangeśaśarman.

कातन्त्रचन्द्रिका a gloss on the commentary of Vararuci on the कातन्त्रसूत्र ascribed to Hari Dīkṣita of the 17th century if this Hari Dīkṣita is the same as the author of the Sabdaratna.

कातन्त्रधातुत्रुत्ति ascribed to Durgasimha, the famous commentator of the Katantra Sutras who lived in the nineth or the tenth century.

कातन्त्रधातुत्र्वात्तिस्तिः a commentary ascribed to Ramanatha and called Manorama on the Katantra-dhatuvṛtti of Durgasimha. See कातन्त्रधातुत्रति above.

कातन्त्रपञ्जिका a name usually given to a compendium of the type of Vivarana or gloss written on the Katantra Sūtras. The gloss written by Durgasimha on the famous commentary on the Katantra Sutras by Durgasimha (the same as famous Durgasimha another of the same name) known as दौगसिंही वृत्ति is called Kātantra Panjika or Kātantravivaraņa. A scholar of Kātantra grammar by name Kusala has written a Panjika on दुर्गसिंह's वृत्ति which is named प्रदीप. Another scholar, Trivikrama has written a gloss named Uddyota.

কানের্থাই সাধাণাত name given to a text consisting of Paribhāṣāsūtras, believed to have been written by the Sūtrakāra himself as a supplementary portion to the main grammar. Many such lists of Paribhāṣāsūtras are available, mostly in manuscript form, containing more than a hundred Sūtras divided into two main groups—the Paribhāṣāsūtras and the Balābalasūtras. See परिभाषासंग्रह ed. by B.O. R. I. Poona.

कातन्त्रपरिभाषावृत्ति (1) name of a gloss on the Paribhasapatha written by Bhāvamiśra, probably a Maithila Pandit whose date is not known. He has explained (2 Paribhāsās deriving many of them from the Kātantra Sūtras. The work seems to be based on the Paribhāsā works by Vyadi and others on the system of Pāṇini, suitable changes having been made by the writer with a view to present the work as belonging to the Kātantra school; (2) name of a gloss on the Paribhāsāpātha of the Kātantra school explaining 65 Paribhāsās. No name of the author is found in the Poona manuscript. The India Office Library copy has given Durgasimha as the author's name; but it is doubtful whether Durgasimha was the author of it. See परिभाषासंग्रह ed. by B. O. R. I. Poona.

कातन्त्रपरिशिष्ट ascribed to Sripatidatta, whose date is not known; from a number of glosses written on this work, it appears that the work was once very popular among students of the Katantra School.

कातन्त्रपरिशिष्टचन्द्रिका a gloss on the Kātantra-Parišista ascribed to a scholar named Rāmadāsa-cakrayartin who has written another... work also named Kātantravyākhyāsāra.

कातन्त्रपरिशिष्टीका a gloss on the Kātantra-Parisista written by a Kātantra scholar Puṇḍarīkākṣa.

कातन्त्रपरिशिष्टप्रद्योत a gloss on the Kātantrapariśiṣṭa by Goyicandra in the twelfth century.

कातन्त्रपरिशिष्टसिद्धान्तरत्नाङ्कुर a gloss on the Kātantra-parisista by Siva-rāmendra, who is believed to have written a gloss on the Sūtras of Pānini also.

कातन्त्रप्रक्रिया a name given to the Kātantra Sūtras which were written in the original form as a Prakrīyāgrantha or a work discussing the various topics such as alphabet, euphonic rules, declension, derivatives from nouns, syntax, conjugation derivatives from roots etc. etc.

कातन्त्रभदीप a grammar work written by a scholar named Kusala on the Kātantrasūtravṛtti by Durgasiṇha. See कातन्त्रपञ्जिका.

कातन्त्रवास्त्रवेधिनी a short explanatory gloss on the Kātantra Sūtras by Jagaddhara of Kashmir who lived in the fourteenth century and who wrote a work on grammar called Apasabdanirākarana.

कातन्त्ररहस्य a work on the Kātantra Sūtras ascribed to Ramānātha Vidyāvācaspati of the sixteenth century A. D.

कातन्त्ररूपमाला a work, explaining the various forms of nouns and verbs according to the rules of the Kātantra grammar, ascribed to Bhāvasena of the fifteenth century.

कातन्त्रलघुन्नाति a short gloss on the Kātantra Sūtras ascribed to a scholar named Chucchukabhatta.

कातन्त्रविवरण a commentary on the

Kātantravistara of Vardhamāna by Pṛthvīdhara who lived in the fifteenth century A. D.

कातन्त्रविस्तर a famous work on the Kātantra Grammar written by Vardhamāna a Jain Scholar of the twelfth century who is believed to be the same as the author of the well-known work Gaṇaratnamahodadhi.

कातन्त्रवासे name of the earliest commentary on the Kātantra Sūtras ascribed to Durgasimha. The commentary was once very popular as is shown by a number of explanatory commentaries written upon it, one of which is believed to have been written by Durgasimha himself. See Durgasimha.

कातन्त्रश्चात्तिटिप्पणी a gloss on दौर्गसिंहोश्चित्ति written by Gunakirti in the four-teenth century A.D.

कातन्त्रवृत्तिटीका a commentary on Durgasimha's Kātantravṛtti by Mokṣeśvara in the fifteenth century A.D.

कातन्त्रवृत्तिव्याख्या named Astamañgala on Durgasimha's Katantravrtti written by Rāmakiśora Cakravartin who is believed to have written a grammatical work शान्दबो-धपकाशिका.

कातन्त्रव्याख्यासार a work of the type of a summary written by Rāmadāsa Cakravartin of the twelfth century.

कातन्त्रसूत्रवृत्ति an old Vitti on the Katantra Sutras ascribed to Vararuci who is, of course, different from Vararuci Katyayana. The Vitti appears to have been occupying a position similar to that of Durgasimha.

कातन्त्रोत्तर a treatise on the Katantra Grammar believed to have been written by Vidyananda. कात्थक्य an ancient writer of Nirukta quoted by Yaska in his Nirukta.

कात्य (1) another name sometimes given to Kātyāyana to whom is ascribed the composition of the Vārttikas on Pāņini-sūtras: (2) an ancient writer Katya quoted as a lexicographer by Ksīrasvāmin, Hemacandra and other writers.

कात्यायन the well-known author of the Vārttikas on the sūtras of Pānini. He is also believed to be the author of the Vajasaneyi Pratiśākhya and many sūtra works named after him. He is believed to be a resident of South India on the strength of the remark प्रियतद्विता दाक्षिणात्याः made by Patanjali in connection with the statement 'यथा लोकिकवैदिकेषु'which is looked upon as Kātyāyana's Vārttika. Some scholars say that Vararuci was also another name given to him, in which case the Värttikakära Vararuci Kātyāyana has to be looked upon as different from the subsequent writer named Vararuci to whom some works on Prakrit and Katantra grammar are ascribed. details see Mahābhāsya Vol. VII. pages 193-223 published by the D. E. Society, Poona. See also वार्तिकपाठ below.

कानच् affix आन forming perfect participles which are mostly seen in Vedic Literature. The affix कानच is technically a substitute for the लिट affix. Nouns ending in कानच् govern the accusative case of the nouns connected with them; e.g. सोमं सुष्वाण:; cf. P. III. 3.106 and P. II. 3.69.

काम augment आम् applied to त्रणीम् just as अकच् is applied, e,g.; आसितव्यं किल तृष्णीकाम् M. Bh. on V.3.72.

कामचार option; permission to do as

desired; liberty of applying any of the rules of grammar that present themselves; cf. तत्र कामचारो गृह्यमाणेन वा विभक्तिं विशेषायतं अडेन वा M. Bh. on P.I.1.27 Vārt. 6.

कारक

कामधेनु abridgment of कान्यकामधेनु of Bopadeva; the word is also used as a short form for कान्यकामधेन.

कामधेनुसुघारस a commentary on the Kāvyakāmadhenu by Ananta, son of Cintamani who lived in the sixteenth century A. D.

कामम् optionally; at will; cf. काममति-दिक्यतां वा M. Bh. on I.1.57.

काम्यच् affix in the sense of 'desiring for oneself' applied to nouns to form denominative roots; e. g. पुत्रकाम्यति; cf. काम्यच P. III, 1. 9.

कार an affix, given in the Pratisakhya works and, by Kātyāyana also in his Vārtlika, which is added to a letter or a phonetic element for convenience of mention; e.g. इकारः, उकारः; cf. वर्ण: कारोत्तरो वर्णाख्याः वर्णकारौ निर्देशकौ Tai. Pra.I. 16: XXII.4.:cf. also V. Pr. 1.37. It is also applied to syllables or words in a similar way to indicate the phonetic element of the word as apart from the sense of the word; e.g. यत एवकारस्तती-न्यत्रावधारणम् Vyāk. Paribhāṣā; cf. also the words चकार:, हिंकार:: (2) additional purpose served by a word such as an adhikara word; cf. अधिकः कारः । पूर्वविप्रतिषेधा न पठितन्या ਮਰ-ਿਰ M. Bh. on P. I. 3.11.

कारक lit. doer of an action. The word is used in the technical sense of 'instrument of action'; cf. कारक-शब्दश्च निभित्तपर्यायः । कारकं हेतुरिति नाथो-न्तरम् । कस्य हेतु: । क्रियाया: Kas. on P. I. 4.23; cf. also कारक इति संज्ञानिदेश: I साधकं निर्वतंकं कारकसंज्ञं भवति | M.Bh. on P. I. 4.23. The word 'kāraka' in short, means 'the capacity in which a thing becomes instrumental in

bringing about an action'. This capacity is looked upon as the sense of the case-affixes which express it. There are six karakas given in all grammar treatises. अपादान, संप्रदान, अधिकरण, करण, कमेन् and कर्त to express which the case affixes or Vibhaktis पञ्चमी, चतुर्थी, सतमी, तृतीया, द्वितीया and प्रथमा are respectively used which, hence, are called Kārakavibhaktis as contrasted with Upapadavibhaktis, which show a relation between two substantives and hence are looked upon as weaker than the Kārakavibhaktis: cf. उपपद्विभक्ते: कारकविभक्तिर्वळीयसी Pari. Sek. Pari.94. The topic explaining Kārakavibhaktis is looked upon as a very important and difficult chapter in treatises of grammar and there are several small compendiums written by scholars dealing with kārakas only. For the topic of Karakas see P. I. 4.23 to 55. Kat. II. 4.8-42, Vyākaraņa Mahābhāṣya Vol. VII. pp.262-264 published by the D. E. Society, Poona.

কাৰেকাৰিকা possibly another name for the treatise on Kārakas known as কাৰেক্স written by Purusottamadeva the reputed grammarian of Bengal who lived in the latter half of the twelfth century A. D. See কাৰেক্স.

कारकजोमुदी a work on the Kātantra grammar discussing the Kāraka portion.

कारकखण्डनमण्डन also called ज्रकारक-खण्डनमण्डन which is a portion of the author's bigger work named त्रिला-चनचन्द्रिका. The work is a discourse on the six kārakas written by Maṇikaṇṭha, a grammarian of the Kātantra school. He has also written another treatise named Kārakavicāra, কাংকবন্ধ (1) written by Purusottamadeva a reputed grammariar of Bengal who wrote many works on grammar of which the Bhāṣā. vṛtti, the Paribhāṣāvṛtti and Jñāpakasamueccya deserve a special mention. The verse portion of the Kārakacakra of which the prose portion appears like a commentary might be bearing the name Kārakakaumudī.

कारकटोका a work on Kārakas ascribed to Bhairava.

কাৰেকৰে a treatise on the topic of Kārakas written by Cākrapānīśeṣa, belonging to the famous Śeṣa family of grammarians, who lived in the seventeenth century A. D.

कारकनिर्णय a work discussing various Kārakas from the Naiyāyika view-point written by the well-known Naiyāyika, Gadādhara Chakravartin of Bengal, who was a pupil of Jagadisa and who flourished in the 16th century A. D. He is looked upon as one of the greatest scholars of Nyāyaśāstra. His main literary work was in the field of Nyāyaśāstra on which he has written several treatises.

कारकपरिच्छेद a work dealing with Kārakas ascribed to Rudrabhatta,

कारकपाद name given by Sivadeva and other grammarians to the fourth pāda of the first adhyāya of Pāṇini's Aṣṭādhyāyī which begins with the Sūtra कारके I. 4. 1 and which deals with the Kārakas or auxiliaries of action.

कारकवाद (1) a treative discussing the several Kārakas, written by Kṛṣṇaśāstri Ārade a famous Nai-yāyīka of Benares who lived in the eighteenth century A. D; (2)

a treatise on syntax written by Jayarāmabhaṭṭācārya which is called कारकविवेक also, which see below.

कारकविचार a work on Kārakas ascribed to Maṇikaṇtha, See Kārakakhaṇḍanamaṇḍana above.

कारकविभक्ति case affix governed by a verb or verbal derivative as contrasted with उपपद्विभक्ति a case affix governed by a noun, not possessing any verbal activity. See the word कारक above. See also the word उपपद्विभक्ति.

कारकविभक्तिबलीयस्त्व the dictum that a Kāraka case is stronger than an Upapada case, e.g. the accusative case as required by the word नमस्कृत्य, which is stronger than the dative case as required by the word नमः. Hence the word मुनित्रयं has to be used in the sentence मुनित्रयं नमस्कृत्य and not the word मुनित्रयं नमस्कृत्य and not the word मुनित्रयं नमस्कृत्य and not the word मुनित्रयं नमस्कृत्य and so the word मुनित्रयं नमस्कृत्य कर्यं क

कारकाविछास an anonymous elementary work on syntax explaining the nature and function of the six Kārakas.

कारकविवेक known as कारकवाद also; a short work on the meaning and relation of words written by Jayarāmabhatṭācārya who lived in the beginning of the eighteenth century. The work forms the concluding portion of a larger work called कारकविवेक which was written by शिरोमणिमझचार्य. The work कारकवाद has a short commentary written by the author himself.

कारकव्याख्या the same as कारकवादव्याख्या written by जयरामभद्याचार्य. See कारकविवेक.

कारिका a verse or a line or lines in metrical form giving the gist of the explanation of a topic; cf. संक्षितस्त्रबहुर्थस्चकः स्रोकः कारिका Padavyavasthāsūtrakārikā of Udayakīrti.

कारित (1) ancient term for the causal Vikaraṇa, (णिच in Pāṇini's grammar and इन् in Kātantra); (2) causal or causative as applied to roots ending in णिच or words derived from such roots called also 'ṇyanta' by the followers of Pāṇini's grammar; cf. इन् कारितं घात्वधें Kāt. III. 2.9, explained as घात्वधिकयानाम्न इन् परा भवति घात्वधें स च कारितसंज्ञक; ।

कार्तकोजपादि a class of words headed by the word कार्तकोजप, which are all dvandva compounds, and which have their first member retaining its own accent; e. g. कार्तकोजपो, आवन्त्यस्मका: etc. cf. Kāś. on P. VI. 2.37.

कार्तिकेय the original instructor of the Kātantra or Kālāpa Grammar, to S'arvavarman who composed the Sūtras according to inspiration received by him. The Kātantra, hence, has also got the name Kaumāra Vyākaraņa.

कार्मनामिक the word is found used in Yāska's Nirukta as an adjective to the word संस्कार where it means 'belonging to nouns derived from roots (कर्मनाम)'like पाचक,कर्षक etc. The changes undergone by the roots in the formation of such words i. e. words showing action are termed कार्मनामिकसंस्कार; cf. कर्मकृतं नाम कर्मनाम। तस्मिन भवः कार्मनामिक: Durgavitti on Nir. I.13.

कार्य (1) brought into existence by activity (कियया निर्वृत्तं कार्यम्) as opposed to नित्य eternal; cf. एके वर्णाञ्च साक्षतिकान् न कार्यान् R.Pr. XIII.4; cf. also ननु च यस्यापि कार्याः (शब्दाः) तस्यापि पूजार्थम् M. Bh. on I. 1.44 Vart. 17;(2) which should be done, used

in connection with a grammatical operation; cf. कार्य एत्वे सयमीकारमाहु: । अभैष्म इत्येतस्य स्थाने अभयोष्मिति। R. Pr. XIV.16; cf. also विप्रतिषय परं कार्यम् P. I.4.2; (3) a grammatical operation as for instance in the phrases द्विकार्ययोगे, त्रिकार्ययोगे etc.; cf. also गौणमुख्ययोर्मुख्ये कार्यसप्तस्यय: Par. Sek. Pari. 15; (4) object of a transitive verb; cf. शेष: कार्ये Sak.

कार्यकाल along wi h the operation; cf. कार्यकाल संज्ञापरिमा म, rules laying down technical terms and regulating rules are to be interpreted along with the rules that prescribe or enjoin operations (provided the technical terms occur in those rules, or, the regulating rules concern those rules). See Pari. Sek. Pari 3.

कार्यकाळपरिभाषा one of the important Paribhāṣās, regarding the application of the Paribhāṣā rules. See कार्यकाल. For details see Par. Sek. Pari. 3.

कार्यातिदेश looking upon the substitute as the very original for the sake of operations that are caused by the presence of the original; the word is used in contrast with रूपातिदेश where actually the original is restored in the place of the substitute on certain conditions. For details see Mahābhāṣya on द्विवेचेनीच P. 1.1.59.

कार्यिन the word or wording that undergoes the operation; cf. सतो हि कार्यिण: कार्येण मिवतन्यम् M. Bh. on I.1. 1. Vārt. 7, also कार्यमनुभवन् .हि कार्यो निमित्तत्या नाश्रीयते Par. Sek. Pari. 10.

দান্ত notion of time created by different contacts made by a thing with other things one after another. Time required for the utterance of a short vowel is taken as a unit of time which is called মানা or

कालमात्रा, lit. measurement of time; (2) degree of a vowel, the vowels being looked upon as possessed of three degrees हस्व,दोंवे,& प्लूत measured respectively by one, two and three mātrās; cf. ऊकालाऽझस्वदीर्धेप्टत: P.V. 2.27; (3) time notion in general, expressed in connection with an activity in three ways past (मृत), present (वर्तमान), and future (भविष्यत) to show which the terms भूता, वर्तमाना and भविष्यन्ती were used by ancient grammarians; cf. the words पूर्वकाल, उत्तरकाल; also cf. पाणि-न्युपज्ञमकालकं व्याकरणम् Kāś. on P. II. 4.21; (4) place of recital (पाठदेश) depending on the time of recital, cf. न परकाल: पूर्वकाले पुन: (V.Pr.III. 3) a dictum similar to Panini's পুৰ্বসা-सिद्धम् P. VIII. 2.1.

কান্তব্র a word not sanctioned by rules of grammar. The word probably refers to the corruption taking place in connection with the use of a word on account of lapse of time; cf. কান্তব্রা স্বাহার: Durgh. Vr. on II.2.6.

काळिनिद्र्शक signifying time; cf. काळिनिद्र्शकाः प्रत्यया एते छुट् छिट् छट् इत्यादयः

कालभेद difference in the time of utterance; cf. किमुच्यत विवारभेदादिति। न पुनः कालभेदादिप। M. Bh. on Siva Sutra 1.

कालञ्यवाय interval of time; cf. आन्य-भाव्यं तु कालशब्दव्यवायात् । कालञ्यवायात् । दण्ड अग्रम् । M. Bh. on Siva Sūtra 1.

कालसामान्य time in general; unspecified time; cf. वर्तमाने लडुक्त: कालसामान्ये न प्राप्तोति Kāś. on P.III.3.142.

कान्यकामधेनु name of the commentary by Bopadeva on his own work कविकस्पद्रम. See कविकस्पद्रम.

কাহাহনেৰে (1) an ancient grammarian and philosopher referred to in the Mahābhāṣya; (2) the work on grammar by Kāśakṛtsna; cf.पाणिनिना प्रोक्तं पाणिनीयम् । आपिशलम् । काशकृत्स्नम् । M.Bh. on I.1. Ahnika 1.

काशादि a class of words headed by the word काश to which the taddhita affix इल is affixed in the four senses stated in P.IV.2.67-70 e.g. काशिलम्, कदीमलम् etc.; cf. Kas. on P.IV.2.80.

काशिका (1)name given to the reputed gloss (शृति) on the Sūtras of Pānini written by the joint authors Jayaditya and Vāmana in the 7th century A.D. Nothing definitely can be said as to which portion was written by Jayaditya and which by Vāmana, or the whole work was jointly written. Some scholars believe that the work was called Kāśikā as it was written in the city of Kāśī and that the gloss on the first five Adhyayas was written by Jayaditya and that on the last three by Vāmana. Although it is written in a scholarly way, the work forms an excellent help to beginners to understand the sense of the pithy Sūtras of Pāniņi. The work has not only deserved but obtained and maintained a very prominent position among students and scholars of Pāṇini's grammar in spite of other works like the Bhāsāvrtti, the Prakriyā Kaumudī, the Siddhanta Kaumudi and others written by equally learned scholars. Its wording is based almost on the Mahabhasya which it has followed. avoiding, of course, the scholarly disquisitions occurring here and there in the Mahabhasya. It appears that many commentary works were written on it, the wellknown among them being the Kāśikāvivaraņa panījikā or Nyāsa written by Jinendrabuddhi and the Padamanjarī by Haradatta. For details see Vyākaraņamahābhāsya Vol. VII pp 286-87 published by the D. E. Society, Poona. (2) The name Kāślikā is sometimes found given to their commentaries on standard works of Sanskrit Grammar by scholars, as possibly they were written at Kāśi; as for instance, (a) Kāsikā on Vaiyākaraṇabhūṣanasāra by Hari Dīkṣita, and (b) Kāsikā on Paribhāṣenduśekhara by Vaidyanātha Pāyaguṇḍe.

काशिकाविवरणपञ्जिका also called Nyāsa, the well-known commentary written by Jinendrabuddhi on the Kāśikā of Jayāditya and Vāmana. See Kāśikā above.

काशिकावृत्तिसार a commentary on the Kāśikāvṛtti named अमृतसूति by Vāraṇāvateśa-śāstrin.

নাহ্যা name of an ancient grammarian quoted by Pāṇini, possibly an author of some Prātiśākhya work now lost.

कारयपीवृत्ति name of a gloss on the Candra Vyakarana.

काश्यादि a class of words headed by the words काशि, चेदि and others to which the taddhita affixes ठच् and ञिठ are added in the miscellaneous senses; e. g. काशिकी, काशिका; वैदिकी, वैदिका etc.; cf. Kāś. on P. IV. 2.116. The fem. affix ई is applied when the affix ठच् is added to the word काशि; cf. P. IV. 1.15.

काष्ट्रादि a class of words headed by the word काष्ट्र after which a word standing as a second member in a compound gets the grave accent for it, e. g. काष्ट्राध्यापक:, परमाध्यापक: etc. cf. P. VIII. 1.67.

কি (1) kṛt affix হ prescribed after ঘু
roots with a prefix attached;e.g.সবি:
স্থি: cf. P.III.3.92, 93; (2) kṛt affix হ
looked upon as a perfect termination and, hence, causing reduplication and accusative case of the
noun connected, found in Vedic

Literature added to roots ending in आ, the root क, and the roots गम, इन and जन; e. g. पि: सोंम, जगुरि:, जिम्म: etc., cf. P. III. 2.171; (2) a term used in the Jainendra Vyākaraṇa for the term संबद्धि.

किंवृत्त a form derived from the pronoun किम्; cf. किमो वृत्तं किंवृत्तम् । किंवृत्त-प्रहणेन तद्विभक्त्यन्तं प्रतीयाङ्कृतरद्यतमौ च । Kas. on P. VIII 1.48.

ৰিয়ুভনাই a class of words headed by the word কিয়ুভন, which get their final vowel lengthened when the word गিং is placed after them as a second member of a compound, provided the word so formed is used as a proper noun; e. g. কিয়ুভ-কাণিং:, অব্বনাগিং:; cf. Kāś. on P. VI. 3.117.

कित् (1) marked with the mute letter which is applied by Panini to affixes, for preventing guna and vrddhi substitutes to the preceding इक् vowel (इ, उ, क or ल); cf.विङति च, Pān. I.1.5; (2) considered or looked upon as marked with mute indicatory 委 for preventing guna; cf. असंयोगाहिट कित and the following P. I. 2.5 etc. The affixes of the first type are for instance बत, बत्वा, बितन and others. The affixes of the second type are given mainly in the second pada of the first Adhyāya by Pānini. Besides the prevention of guna and vrddhi, affixes marked with & or affixes called कित्, cause Samprasarana (see P. VI. 1.15,16), elision of the penultimate π (P. VI.4.24), elision of the penultimate vowel (P. VI. 4.98,100), lengthening of the vowel (VI. 4.15), substitution of 35 (VI. 4.19.21), elision of the final nasal (VI. 4.37), substitution of आ (VI.4.42). The taddhita affixes which are marked with

mute & cause the Vrddhi substitute for the first vowel in the word to which they are added.

क्रिकरण marking with the mute letter क्, or looking upon as marked with mute क् for purposes mentioned above; (see कित् above). The word is often used in the Mahābhāsya; see M.Bh. on I. 1. 3, 5, 46; I. 2. 5. etc.

কিব krt affix ছ prescribed along with कि. See कि above. The affix কিব্ causes the acute accent on the first vowel of the word ending with it, while the affix ki (इ) has itself the acute accent on its vowel इ.

किरादि a class of roots headed by the root कू, viz. the five roots कू, गू, ह, घृ and प्रच्छ after which the desiderative sign, i.e. the affix सन, gets the augment इ (इट्); e. g. चिकरिषति, पिप्राच्छपति; cf. Kas. on P.VII.2.75.

किशरादि, किसरादि a class of words headed by किसर meaning some kind of scent, which get the taddhita affix इक (एन्) applied to them when the word so formed means 'a dealer of that thing; 'e.g. किशरिक:, किशरिकी; cf; Kāś. on P. IV. 4.53.

कील्हाने Kielhorn F., a sound scholar of Sanskrit Grammar who brought out excellent editions of the Pātañjala Mahābhāṣya and the Paribhāṣenduśekhara and wrote an essay on the Vārttikas of Kātyāyana. For details see Pātañjala Mahābhāṣya Vol VII.p.40, D. E society edition, Poona.

(1) guttural class of consonants, i. e. the consonants क्, ख़, ग्, ग्, ग्, इ. ह. The vowel उ added to क्, signifies the class of क्. e. g. चजो: कु विण्यता, VII. 3. 52, कुहोश्च; VII. 4.62, चो: कु:

VIII.2.30, किन्प्रत्ययस्य दु:; VIII.2.62; cf. अणुदित्सवर्णस्य चाप्रत्ययः P.I.1. 69; (2) substitute क for किम् cf. P. VII. 2. 104.

- कुक् augment क् (1) added to क् at the end of a word before a sibilant letter; e. g प्राक्त्रोत; cf. P.VIII. 3. 28; (2) added to the words वात and अतीसार before the affix इन्, cf. P. V. 2. 129; (3) added to words of the नड group before the tad. affix छ (ईच), e. g. नडकीयम्, प्रक्षकीयम्; cf. P. IV. 2. 91.
- ক্ত**ন্ত্ৰনাৰিকাহা** a commentary by Sivabhatṭa on Jinendrabuddhi's Kāśikāvivaraṇapañjikā which is known popularly as Nyāsa.
- ক্রভিন্তকা (1) a commentary on Nāgeśa's Laghūmañjūṣā by Kṛṣṇamiś'ra; (2) a commentary on Nāgeśa's Paribhāṣenduśekhara by Durbalācārya.
- কুজাবি a class of words headed by দুল্ল to which the taddhita affix আঘন (ক্ষ্মু) is applied in the sense of गोत्र i. e. grandchildren etc. e. g. কীলো- যনা:; cf. Kāś. on P. IV. 1.9'.
- कुटादि a group of roots headed by the root दुट् of the VIth conjugation after which an affix which is neither ञित् nor णित् becomes डित्, and as a result prevents the substitution of गुण or बृद्धि for the preceding vowel; e. g. दुटिता, कुटितुम्। टूर्टा. गाङ्कुटादिम्योऽञ्जिन्डित् I. 2. 1.
- कुटादिपाद name given by Sīradeva and later grammarians to the second pāda of the first adhyāya of Pāṇini's Aṣṭādhyāyī, as the pāda begins with the Sūtra गाङ्कुटादिम्यो जिलन्डित् P. I. 2. 1.
- कुँटारच् tad. affix कुटार added to अव, e.g. अवकुटारम्; cf. P. V. 2. 30.
- **कुणप्** tad. affix कुण added to words of पोछ group in the sense of 'ripen-

- ed condition';e.g.पीलुकुण:=पीलूनां पाकः; cf. P.V.2.24.
- कुणरवाड्य name of an ancient grammarian who lived possibly after Pāṇini and before Patañjali and who is referred to in the Mahābhāṣya as giving an alternative form for the standard form of certain words; cf. दुणरवाडवस्त्वाह नेषा शंकरा शंगरेषा M.Bh. on III. 2.14; cf. also कुणरवाडवस्त्वाह नेष वहीनर: । कस्ताहिं । विद्यानर एष; M. Bh. on VII.3.1.
- ক্রাণি name of an ancient Vṛttikāra on the Sūtras of Pāṇini, mentioned in their works by Kaiyaṭa and Haradatta; cf. Kaiyaṭa's Pradīpa on P. I.1.74, also Padamañjarī on I.1.1.
- कुत्व substitution of the consonants of the क् class or guttural consonants.
- কুণ্ডুহ্যান্থিৰ a famous grammarian of the eighteenth century who wrote some works on grammar of which the দ্বিদাগাদাকো is an independent treatise on Paribhāṣās.
- कुमत् a word containing a guttural letter in it; cf. दुमति च P. VIII. 4. 13.
- कुमार (1) Kārtikeya who is believed to have given inspiration to the Kātantra-sūtrakāra to write the Kātantra-Sūtras; (2) named Visnumitra who wrote a commentary on the ऋक्प्रातिशाख्य.
- कुमारीस्तनयुगाकृति a phrase used in the gloss on the कातन्त्र by Durgasimha to give along with the definition of विसर्जनीय or विसर्ग a graphic description of it as shown in script; cf. Kāt. I.1.16 com.
- कुमुदादि a class of words (1) consisting of कुमुद, शर्करा, न्यप्रोध etc. to which the taddhita affix ठच् is applied in the four senses given in P.IV 2.67-70; e.g.कुमुदिकम्, शर्करिकम् etc.;(2) consisting of कुमुद गोमय, रथकार etc. to which

the taddhita affix इक (ठक्) is applied in the senses referred to in (1); e.g. कौमुदिकम्, राथकास्किम् etc.; cf. Kāś. on P.IV.2.80.

कुम्भपद्यादि a class of words headed by कुम्भपदी in which the word पाद at the end of the compound is changed into पाद and further changed into पद before the feminine affix ई; e.g. कुम्भपदी, रातपदी, हुपदी, पञ्चपदी etc.; cf. Kaś. on P. V.4. 138, 139.

कुरच् kṛt. affix उर applied to the roots विद्, भिद् and छिद्; e.g. विदुर: । भिदुरम् । छिदुरम् । cf. Kāś. on P.III.2.162.

कुर्वत a term found in the Brāhmaṇa works and used by ancient grammarians for 'the present tense'.

कुर्वदूप effective or efficient, as opposed to dormant, as applied toनिमित्त (cause); cf.निमित्तराब्दोयमस्ति योग्यतामात्रे । कुस्लस्थेष्यपि बीजेषु वक्तारो भवन्त अङ्कुरनि-मित्तान्येतानीति । अस्ति च कुर्वदूपे । Padamañjarī on P.VII.2.36.

कुर्वादि a class of words headed by the word कुर to which the taddhita affix य (ण्य) is added in the sense of अपत्य or descendant; e.g. कौरव्य: गार्ग्य: etc.; cf. Kāś. on P.IV.1.151.

कुर्विणी a kind of svarabhakti; see कविणी.

চুন্তানেই a class of words headed by the word কুন্তান্ত to which the taddhita affix অক (নুস্) is applied in the sense of 'made by', provided the word so formed is used as a proper noun; e g.কীন্তান্তকম, বাহত্তকম; cf. Kaś. on P.IV.3.118.

कुव्यवाय intervention by a letter of the guttural class; cf. कुव्यवाय हादेशेषु प्रतिषघो वक्तव्यः। प्रयोजनं वृत्रज्ञः, ख्रुज्ञः प्राघानीति, P.VIII.4,2 Vart. 4,5.

ক্ত্ত্বান্ত name of a grammarian who wrote a commentary on the Kātantra Vyākarana; see কার-স্বাধীকা.

कुज् (1) root क in the general sense of activity; (2) pratyāhāra or short form for the three roots कृ, म् and अस्, cf. कुत्र चानुप्रयुज्यते लिटि P.III.1.40.

कृत lit. activity; a term used in the grammars of Panini and others for affixes applied to roots to form verbal derivatives; cf. कृदतिङ् । घातो: (३।१।९१) इत्यधिकारे तिङ्वार्जितः प्रत्ययः कत् स्यात । Kāś. on III.1.93, The kṛt affixes are given exhaustively by Pāṇini in Sūtras III.1.91 to III.4. 117. कृत and तिद्धत appear to be the ancient Pre-Paninian terms used in the Nirukta and the Prātiśākhya works in the respective senses of root-born and noun-born words (क्रदन्त and ताद्वितान्त according to Pāṇini's terminology), and not in the sense of mere affixes; सन्त्यस्पप्रयोगाः कृतोप्येकपदिकाः Nir. I.14; अथापि माधिकेभ्यो घातुभ्यो नैगमाः कृतो माष्यन्ते Nir. II.2; तिङ्कृत्तद्धितसमासाः शन्दमयम् V.Pr. I.27; also cf. V.Pr. VI.4. Patañjali and later grammarians have used the word कृत in the sense of कृदन्त: cf. गतिकारकोपपदानां कृद्धिः सह समासवचनं प्राकृ सुवृत्पत्ते:Pari.Sck.Pari.75. The krt affixes are given by Pānini in the senses of the different Karakas अपादान, संप्रदान, करण, अधिकरण, कर्म and कर्त, stating in general terms that if no other sense is assigned to a krt affix it should be understood that कर्ता or the agent of the verbal activity is the sense; cf. कर्तरि कृत्। येष्वर्थेनिर्देशो नारित तत्रेदमुपतिष्ठते Kās. on III.4.67. The activity element possessed by the root lies generally dormant in the verbal derivative nouns; cf. कुद्मिहितो भावो द्रव्यवद्भवति, क्रियावदिष । M.Bh.on V.4.19 and VI. 2.139.

कृत (1) a term used by ancient grammarians in the sense of 'past tense';(2)effected, done. The word

is mostly used in this sense in grammar works; e.g. किं तेन कृतं स्थात; नानुबन्धकृतमनेकाल्त्वम् Par. Sek. Pari. 6.

कताकृतप्रसङ्गि a definition of the term नित्य in the sense of a rule which occurs after certain another rule is applied, as well as before that rule is applied; cf. कृताकृतप्रसङ्गि नित्यम् । तद्विपरीतमनित्यम् । Pari. Sek. Pari. 42; cf. also कथं पुनर्यं नित्यः । कृताकृतप्रसङ्गित्वात् । M. Bh. on VI. 4. 62.

क्रतादि a class of words such as कृत, मित, मत, मृत, उक्त and others with which the words श्रेण, एक, पूग, कुण्ड, राशि and others are compounded, provided both the words forming the compourd are in the same case; e. g. श्रेणिकृता:, एककृता:, कुण्डम्ता: etc. cf. Kas. on P. II. 1.59.

हतार्थ lit. which has got its purpose served; a term used in connection with a rule that has been possible to be applied (without clash with another rule) in the case of certain instances, although it comes into conflict in the case of other instances: cf. तत्र कृतार्थत्वाद् दिक्राब्दपक्ष परेण ठञ्जती स्थाताम् Kās. on P. IV. 3. 5. The word चरितार्थ is used almost in the same sense.

চাৰে lit. that which should be done; the word কুন্ম is used as a technical term in grammar in the sense of kṛt affixes which possess the sense 'should be done.' Pāṇini has not defined the term কুন্ম, but he has introduced a topic (অধিকার) by the name কুন্ম (P. III. 1.95), and mentioned kṛt affixes therein which are to be called কুন্ম right on upto the mention of the affix তুলু. in P. III. 1.133; cf. কুন্মা: মাছু তুলুন্ন: P. III. 1.95. The kṛtya affixes, common-

ly found in use, are तन्य, अनीय and य (यत्, वयम् and ण्यत्).

क्रिनिम artificial; technical, as opposed to derivative. In grammar, the term कृत्रिम means 'technical sense', as contrasted with अकृत्रिम 'ordinary sense'; cf. कृत्रिमाकृत्रिमयो: कृत्रिमे कार्यसंप्रत्यय: Par. Sek. Pari. 9.

क्रिनाकृत्रिमपरिभाषा a term popularly used by grammarians for the परिभाषा or maxim that out of the two senses, the technical and the derived ones, the technical sense should be preferred; in rare cases, the other too, is preferred; cf. Pari. Sek. Pari.9.

कृत्वसुच् tad. affix वृत्वम् applied to numerals to convey the sense of repetition, e. g. पञ्चकृत्वः दराकृत्वः cf. संख्यायाः क्रियाम्या वृत्तिगणने वृत्यसुच् P. V. 4.17.

इत्वे form of the tad. affix कृत्वस् in Vedic Literature. See कृत्वसूच्.

कृत्स्वर the same as कृदुत्तरपदप्रकृतिस्वर, the retention of its accent by the second member of a tatpurusa compound, if the first member is a word termed Gati or Kāraka, by the rule गतिकारकोपपदात् कृत् P.VI.2. 139; cf. अन्ययस्वरस्य कृत्स्वरः M.Bh. on VI.2.52; cf.विभक्तीवरस्वरात्कृत्स्वरः M.Bh. VI.2.52 Vārt. 6.

क्रदन्त the word ending with a kṛt affix; the term कृत् is found used in the sūtras of Pānini for कृदन्त; cf. कृतद्वितसमासञ्च P. I.2.46. The term कृदन्त for root-nouns, or nouns derived from roots, is found in the Atharvaprātisākhya (I.1.10, II.3.8, III.2.4), the Mahābhāṣya and all the later works on grammar. See the word कृत्.

कृद्भिहित expressed by a kṛt affix;cf. कृदभिहितो भावो द्रव्यवद्भवति M.Bh. on P. II.2.19, III.1.67, IV.13, VI.2.139,

स्याहण mention of a krt i.e. of a word ending with a krt affix. The word mainly occurs in the Paribhāṣā झृद्ग्रहणे गतिकारकपूर्वस्थापि ग्रहणम् which occurs first as an expression of the Vārttikakāra (P.I.4.13 Vārt. 9) and has been later on given as a Paribhāṣā by later grammarians (Pari. Sek.. Pari.28). The Paribhāṣā is referred to as कृद्ग्रहणपरिभाषा in later grammar works especially commentary works.

कृद्ग्रहणपारिभाषा a short term used by the grammarians for the maxim कृद्ग्रहणे गतिकारकपूर्वस्थापि ग्रहणम्. Par. Sek. Pari. 28. See कृद्ग्रहण.

हत्वाचे a short treatise by a grammarian named मोक्षेधर who lived in the fifteenth century. The work deals with verbal derivatives.

क्रल्डुक् the elision of a krt affix; the word is found used along with the words प्रकृतिप्रत्यापत्तिः, and प्रकृतिवत् कारकं भवति in the Varttika आख्यानात्कृतस्त-दाचं इति कृल्डुक् प्रकृतिप्रत्यापत्तिः प्रकृतिवच्च कारकम् by means of which the phrase कंसं वातयति is formed for the sentence कंसव्यमाचं है.

कहोप the dropping or removal of the verbal noun(कृदन्त)after the words प्र, परा etc., when they are compounded with the following noun; e.g. the dropping of गत from the expression निर्गत; कौदाम्ब्या: when it is compounded into निष्कोद्याम्बः। cf. कुछोपे निष्कौद्याम्बः, निर्वाराणिसः M.Bh. on P.I.4.1. Vart. 18.

চ্ছমাপ্ৰাই a class of words headed by the word হুমাপ্ত to which the taddhita affix ইব (হুল্) is applied in the four senses given in P.IV.2. 67-70. e.g. কার্যাপ্রায:, আফ্রিয:; cf. Kāś. on P.IV.2.80.

रुष्ट also कुष्ट the foremost of the seven Yamas; cf. कुष्टप्रथमद्वितीयतृतीयचतुर्थ-मन्द्राति स्वा्यीः Tai. Pr. XXIII.14. क्रण्णिकंकरश्रक्तिया an alternative name for the well-known grammar-work प्राक्तियाकौमुदी written by Rāmacandra Seṣa. See प्रक्तियाकौमुदी.

ক্রজাব্যন্তির called also হাগকুলা, a scholar of Sanskrit Vyākaraņa who wrote গুৱেমাৰবিস্থানি, a commentary on the Prakriyā-Kaumudī of Rāmacandra Śeṣa.

कृष्णमित्र a scholar of grammar and nyāya of the 17th century A.D. who wrote many commentary works some of which are (1) a commentary called Ratnārṇava on the Siddhānta-Kaumudī, (2) a commentary named Kalpalatā on Bhaṭṭoji's Praudhamanoramā, (3) a commentary named Bhāvadīpa on Bhaṭṭoji's Śabdakaustubha, (4) a commentary on Nagojibhaṭṭa's Laghumañjūṣā by name Kuñcikā and (5) a commentary on Vaiyākaraṇabhūṣaṇa.

कृष्णमिश्र an alternative name of कृष्ण-भित्र. See कृष्णभित्र.

क्राणमोनिन् son of Govardhana and surnamed Maunī, who wrote a commentary named सुबोधिनी on the Siddhānta-Kaumudī at the end of the 17th century A.D.

हाणाळीळाशुक्तमुनि author of a commentary named Puruşakāra on Bhoja's Sarasvatīkanthābharana.

कृष्णशास्त्रिन (आरडे) a famous grammarian and logician of the 18th century who wrote Ākhyātaviveka and Kārakavāda. See आरडे.

क्रम्णद्दोष a famous grammarian of the Śeṣa family who wrote a commentary named the Gūḍhabhāvavivṛti on the Prakriyā Kaumudī of Rāmacandra Śeṣa. See कृष्णपण्डित.

केन krt. affix ए in the sense of इत्य (pot.pass.part.) found in Vedic Literature; e.g. नावगाहे = नावगाहितन्यम् cf. Kāś. on P.III.4.14.

केन्य krt. affix एन्य in the sense of झत्य in Vedic Literature; e.g. दिद्दक्षेण्य: । शुक्रूषेण्य:; cf. Kās. on P.III.4.14.

केलिमर् krt. affix एलिम in the sense of कृत्य; e. g. पचेलिमा माषाः; cf. केलिमर उपसंख्यानम् P. III. I. 96 Vārt

केवल isolated; a term applied to a letter or a word when it is not combined with another letter or another word in a compound; cf. धर्मादनिच् केवलात्। केवलात पदसमुदायात् Kāś. on P. V. 4.124; (2) simple (word) without an affix added; cf. अर्थवत्ता नोपपद्यते केवलेन अवचनात्। P. I. 2.45 Vart. 7, also कृत्तद्धितान्तं चैवार्थवत्। न केवलाः कृतस्तद्धिता वा M.Bh.on P.I.4.14.

কাৰ writer of a commentary named সকাৰা on the Siksa of Panini. He lived in the 17th century.

केशवद्त्त writer of the commentary named दुर्घेटोद्धाट on the grammar संक्षितसार written by Goyicandra.

के kit affix पे used in Vedic Literature as noticed in the forms प्रये रोहिच्ये and अन्यथिच्ये; cf. P. III.4.10.

कैमर्थक्य lit. position of questioning the utility; absence of any apparent utility; cf. कैमर्थक्यानियमो भवति विधेयं नास्तीति कृत्वा M. Bh. on I. 4.3, III. 1.46; III. 2.127, III. 3.19; VI. 4.49, VII. 2.26, and VIII. 4.32.

कैयट name of the renowned commentator on the Mahābhāsya, who lived in the 11th century. He was a resident of Kashmir and his father's name was Jaiyaṭa. The commentary on the Mahābhāsya was named महामाध्यप्रदीप by him, which is believed by later grammarians to have really acted as प्रदीप or light, as without it, the Mahābhāsya of Patañjali

would have remained unlit, that is unintelligible, at several places. Later grammarians attached to प्रदीप almost the same importance as they did to the Mahabhasva and the expression तद्कं भाष्य-कैयटया: has been often used by commentators. Many commentary works were written on the Pradipa out of which Nagesa's Uddyota is the most popular. The word कैयट came to be used for the word महाभाष्यप्रदीप which was the work of Kaiyata.For details see Vyākarana Mahābhāsya published by the D. E. Society, Poona, Vol. VII. pp. 389-390.

केयदप्रकाश a commentary on the Mahābhāṣyapradīpa of Kaiyaṭa written by Nīlakaṇṭha of the Draviḍa country. Nīlakaṇṭha lived in the 17th century and wrote works on various subjects.

कैयटप्रकाशिका a commentary on the Mahābhāṣyapradīpa of Kaiyaṭa written by Pravartakopādhyāya.

कैयटविवरण (1) a commentary on the Mahabhāṣyapradīpa of Kaiyaṭa written by Iśvarānanda, in the 16th century; (2) a commentary on Kaiyaṭa's Pradīpa by Rāmacandra-Sarasvatī, who lived in the 16th century.

कोटरादि a class of words headed by the word कोटर which get their final vowel lengthened when the word वन is placed after them as a second member of a compound, provided the word so formed is used as a proper noun; e.g. कोटरावणम्, मिश्रकावणम्, cf. Kāś. on P, VI. 3.117.

কাতভ্ৰমন্থ a reputed grammarian who wrote an extensive explanatory gloss by name Vaiyākaraṇabhūṣana on the Vaiyākaraṇasiddhāntakārikā of Bhaṭṭojī Dīkṣita. Another

Vaiyākaranabhūşanasāra. work which is in a way an abridgment of the Bhūsana, was also written Kondabhatta lived in the beginning of the 17th century. He was the son of Rangoji and nephew of Bhattoji Diksita. was one of the few writers on the Arthavicāra in the Vyākaraņasāstra and his Bhūsaņasāra ranks next to the Vākyapadīya of Bhartrhari. Besides the Bhūsana and Bhūsana-Kondabhaita wrote two independent works viz. Vaiyākaranasiddhäntadīpikā and Sphotavāda.

कोद्ण्डराम a scholar of Sanskrit Vyākaraṇa who composed शन्दसिद्धान्त-मञ्जरी a small treatise dealing with the declension of nouns.

कोणिडस्य an ancient grammarian referred to in the Taittirīya Prātiśākhya (T. Pr. V. 38) and Pāṇini's Aṣṭādhyāyī. (P.II.4.70).

कोमार, कोमारन्याकरण (1) an alternative name of the Kātantra Vyākaraṇa given to it on the strength of the traditional belief that the original inspiration for writing it was received by Sarvavarman from Kumāra or Kārtikeya; (2) small treatises bearing the name Kaumāravyākaraṇa written by Munipungava and Bhāvasena. The latter has written Kātantrarūpamālā also.

কীহন্তীযুত্ৰ an ancient grammarian referred to in the Taittirīya Prātiśākhya; cf. T.Pr. XVIII.2.

कत krt affix त in various senses, called by the name निष्ठा in Pāṇini's grammar along with the affix क्तवत of. क्तक्तवत् निष्ठा P.I.1.26. The various senses in which क्त is prescribed can be noticed below: (1) the general sense of something done

in the past time as past pass.participle e. g. कृत:, भुक्तम् etc.; cf. P. III. 2.102; (2) the sense of the beginning of an activity when it is used actively; e. g. प्रकृत: कटं देवदत्त:, cf. P. III.2.102 Vart. 3; (3) the sense of activity of the present tense applied to roots withe mute झ as also to roots in the sense of desire, knowledge and worship; e.g. मिन्न:, क्ष्विण्ण:, धृष्ट: as also राज्ञां मतः, राज्ञामिष्टः, राज्ञां बुद्धः; cf. P.III.2.187, 88; (4) the sense of mere verbal activity (भाव) e.g. इसितम्, सहितम्, जिस्पतम्, (used always in the neuter gender); cf. P.III.3. 114; (5) the sense of benediction when the word ending in कत is used as a technical term, e.g.देवदत्तः in the sense देवा एनं देवासः. The kit affix क्तिन is also used similarly e.g. साति: भृति: मन्ति:; cf. Kāś. on P. III.3.174

कवतु kit affix तवत् which also is called निष्ठा. It is prescribed in the active sense of somebody who has done a thing sometime in the past. A word ending in it is equivalent to the past active participle; e.g. भुक्तवान् ब्राह्मणः; cf. P.I.1.26. The fem. affix हीप् (ई) is added to nouns ending in क्तवतु to form feminine bases; cf. P. IV. 1.6.

क्तान्त a noun base ending in the kṛt affix क्त; past passive participle; cf. क्षेप सप्तम्यन्तं क्तान्तेन सह समस्यते। अवतप्तेनकुलस्थितं त एतत् M. Bh.on II.2. 47.

क्तार्थ sense of क्त i.e. sense of the past pass. participle; cf. उपसर्गाः कार्थ, प्राद्यः क्तार्थे (समस्यन्ते), P. II. 2. 18, Vart. 4.

क्तिच् kit affix ति added to roots in the benedictive sense to form संज्ञाशब्द or nouns in a technical sense; e.g. तन्तिः in the sense of तनुतात्; cf. Kas. on III.3.174. क्त is also added in the same way. See क्त.

क्तिन् krt affix ति added to roots to form nouns in the sense of verbaction; e.g. कृति:, स्थिति:, मितः etc.;cf. P.III.3.94-97.

किन्न kṛt affix त्रि added to the roots marked with the syllable डु by Pāṇ-inī in his Dhatupāṭha; after this affix त्रि, the tad. affix म (मप्) in the sense of निर्वृत्तम् (accomplished) is necessarily added, e. g. पिन्नमम्, कृत्रिमम्; cf. P. III. 3.88. and P. IV. 4.20.

क्त्वा krt. affix त्वा added to roots (1) in the sense of prohibition conveyed by the word अন্ত or স্বন্ত preceding the root, e.g. अलं कृत्वा, खलु कृत्वा; cf. P. III. 4.18; (2) in the sense of exchange in the case of the root HI. e. g. अपामित्य याचते;; cf. P. III. 4. 19; (3) to show an activity of the past time along with a verb or noun of action showing comparatively a later time, provided the agent of the former and the latter activities is the same;e.g. भुक्त्वा त्रजति, स्नात्वा पीत्वा भक्त्वा त्रजति: cf. P. III. 4. 21. This krt affix is always added to roots when they are without any prefix; when there is a prefix the indeclinable, ending in त्वा, is always compounded with the prefix and त्वा is changed into य (ल्यप्), e.g. प्रकृत्य, प्रहृत्य; cf. समासेऽनञ्जूर्वे क्त्वो स्यप् P. VII. 1.37. The substitution of य is at will in Vedic Literature; e. g. কুণা वासो यजमानं परिधापयित्वा (instead of परिघाप्य), cf. P. VII. 1.38, while sometimes, य is added after खा as an augment e.g. दत्वाय सविता धिय: cf. P. VII. 1. 47, as also sometimes त्वी or त्वीनम् is substituted for त्वा e. g. इश्वीनं देवान्, स्नात्वी मलादिव, cf. P. VII. 1.48, 49.

क्तवान्त gerund; a mid-way derivative

of a verbal root which does not leave its verbal nature on the one hand although it takes the form of a substantive on the other hand.

क्तु kit affix नु added to the roots त्रस्, गृध्, धृष् and क्षिप् in the sense of habituated etc. as given in the rule आ कारतच्छीलतद्वर्मत्तरसाधुकारिषु P.III.2.134; e.g. त्रस्तु:, गृथ्नु: etc. cf. P.III. 2.140.

कमरच् k!t affix मर added in the sense of habituated etc. to the roots स, घस and अद्; e. g. समरः, घस्मरः, अझरः cf. P.III. 2.134 and 160.

क्य common term for the Vikaraṇas क्यन् , क्यङ् and क्यत् ; cf. नः क्ये P. I. 4.15, also cf. P. III. 2.170, VI. 4.50.

क्यङ् affix य taking Atmanepada terminations after it, added in the sense of similar behaviour to a substantive. The substantive to which this affix य is added, becomes a denominative root; e. g. काकः स्येनां-यते, कुमुदं पुष्करायते, cf. Kāś. on P. III. 1.11-12, also on P. III. 1.14-18.

क्यच् denominative affix (विकरण) in the sense of desiring for oneself, added to nouns to form denomitive roots; e.g. पुत्रीयित; क्यच् is also added to nouns that are upamānas or standards of comparison in the sense of (similar) behaviour; e.g. पुत्रीयित च्छात्रम्; cf. Kāś. on P. III.1.8, 10. It is also added in the sense of 'doing' to the words नमस्, विस्य and चित्र; e.g. नमस्यित देवान, विश्वस्यति गुरून, चित्रीयते; cf. Kāś. on P. III. 1.19.

क्यप् krt affix य applied to the roots त्रज् and यज् in the sense of 'verbal activity' and to the roots अज् with सम्, अद् with नि etc. to form proper nouns e. g. त्रज्या, इच्या, समज्या,निअन्ना etc.,cf. P. III. 3.98 and 99; (2) krtya affix य in the sense of 'should be done' applied to the

roots वर्, मू and हन (when preceded by certain words put as upapada), as also to roots with penultimate क and the roots मृज्, इ, स्तु and others; e.g. ब्रह्मोचम्, ब्रह्मभूयम्, इत्यम्, स्तुत्यम् ete. cf. Kāś. on P. III. 1. 106,121.

क्या affix य added to certain nouns like छे। हित and others to form denominative roots after which terminations of both the padas are placed e. g. छ। हितायति, छोहितायते; cf. Kāś. on P. III. 1.13.

प्यु, प्युन् Uṇādi affixes अन.

करवादि a class of words headed by the word ऋतु, which have their first vowel accented acute in a Bahuvrihi dompound, provided the first member of the compound is the word सु; e.g. सुऋतु:, सुप्र्तिः etc.; cf. Kas. on P. VI.2.118.

क्रम (1) serial order or succession as contrasted with यौगपद्य or simultaneity. The difference between ऋम and यौगपद्य is given by मर्तृहरि in the line कमे विभिद्यते रूपं योगपद्ये न भिद्यते Vāk. Pad. II. 470. In order to form a word by the application of several rules of grammar, a particular order is generally followed in accordance with the general principle laid down in the Paribhāsā पूर्वपरिनत्यान्तरङ्गापवादानाम् तरोत्तरं वलीय:. as also according to what is stated in the sutras असिद्धवदत्रामात्, पूर्वत्रासिद्धम् etc.; (2) succession, or being placed after, specifically with reference to indeclinables like एव, च etc. which are placed after a noun with which they are connected. When indcan clinable is not so connected. it is called भिन्नकम; cf. परिपन्थं च तिष्ठति (P. IV. 4.36), चकारो भिन्नकमः प्रत्ययार्थे समुच्चिनाति, Kāś. on P. IV. 4.36; also ईंडजनोध्वें च । चशब्दो भिनकमः ईश: (VII. 2.77) अनुकर्षणार्थी विज्ञायते Kāś.on P.IV.2.78; (3) succession of consonant the same brought about; doubling; reduplication: क्रम is used in this way in the Rk Prātiśākhya as a synonym of dvitva prescribed by Pāņini; e. g. आ त्वा रथं becomes आ त्वा रथम्; सोमानं स्वरणम् becomes सोमानं स्त्वरणम्; cf. स्वरानस्वारोपहितो द्विरुच्यंत संयोगादिः स कमोऽविकमे सन् । etc, R. Pr. VI. 1 to 4: cf. also स एष द्विभीवरूपो विधि: क्रमसंज्ञो वेदितब्य: Uvvata on R. Pr. VI. 1. The root 新 IA. several times used in the Pratiśākhya works for द्विभैवन, cf. also T. Pr.XXI.5; XXIV. 5; (4) repetition of a word in the recital of Vedic passages, the recital by such a repetition being called कमपाठ, which is learnt and taught with a view to understanding the original forms of words combined in the Samhitā by euphonic substitution of letters such as that of ण for न, or of ब for न, as also the separate words of a compound word (सामासिकदाब्द); e.g. पर्जन्याय प्र । प्र गायत । गायत दिव: । दिव-रपुत्राय । पुत्राय मीळहुपे । मीळहुप इति मीळहुषे । cf. कमो द्वाभ्यामतिकम्य प्रत्यादायो-त्तरं तयोः उत्तरेणोपसंदध्यात् तथाई चें समापयेत् ॥ R. Pr. X. 1. For details and special features, cf. R. Pr. ch. X and XI; cf. also V. Pr. IV. 182-190; T. Pr. XXIII. 20, XXIV. 6.

क्रमण doubling. Irregular doubling is looked upon as a fault; cf. क्रमण वा अयथोक्तम् R. Pr. XIV. 25.

क्रमदिश्वर author of a grammar named संक्षितसार who lived at the end of the 13 th century.

क्रमपाट recital of the Vedic Samhitā by means of separate groups of two words, repeating each word except the first of the Vedic verseline; see क्रम above. The various

rules and exceptions are given in detail in Patalas ten and eleven of the Rk Prātiśākhya. Vedic Samhitā or Samhitāpātha is supposed to be the original one and the Padapatha prepared later on, with a view to preserving the Vedic text without any change or modification of a letter, or accent; cf. न लक्षणेन पदकारा अनुवर्त्या: ! पदकारैनीम लक्षणमन्वर्त्यम M. Bh. on III. 1.109, VI. 1.207 and VIII. 2.16, where Patanjali clearly says that grammar-rules are not to follow the Padapatha, but, the writer of the Padapatha is to follow the rules already laid down. The Jatapatha, the Ghanapatha and the other recitals are later developments of the Padapatha as they are not mentioned in the Prātisākhya works.

क्रमादि a class of words headed by the word कम to which the taddhita affix अक (बुज्) is added in the sense of 'one who studies and understands'; e. g. क्रमक:, पदक:, मीमांसक:, शिक्षक: etc. cf. Kāś. on IV. 2.61.

क्रम्य a consonant which is subjected to doubling cf. कम्यो वर्ण: पूर्वमक्षरं भजते R. Pr. XVIII. 18.

किया action, verbal activity; cf. किया-बचनो धातु: M. Bh. on I. 3.1; cf. also कियाबाचकमाख्यातम् R. Pr. XII. 8. quoted by Uvvata in his Bhāṣya on V. Pr. VIII. 50; cf. also उपसर्गा: कियायोगे P. I. 4.59, लक्षणहेत्वोः कियाया: P. III. 2.126; cf. also यत्तिई तदिक्षितं चिष्टितं निभिषतं स शब्दः । नित्याह किया नाम सा M. Bh. Ahnika 1. The word भाव many times is used in the same sense as kriyā or verbal activity in the sūtras of Pāṇini. cf. P.I.2.21; I.3.13; III. 1. 66.etc;cf. also कृदभिहितो भावो द्रव्यवद्भवति a statement made frequently by the Mahābhāsyakāra. Some scholars draw a nice distinction between किया and मान, किया meaning dynamic activity and मान meaning static activity; cf. अपरिस्पन्दन-सावनसाध्यो धात्वयों भानः । सपरिस्पन्दन-सावनसाध्यो धात्वयों भानः । सपरिस्पन्दन-सावनसाध्यो किया Kaiyata's Pradipa on M. Bh. III. 1.87. Philosophically किया is defined as सत्ता appearing in temporal sequence in various things. When सत्ता does not so appear it is called सत्त्व.

कियाकलाप a grammatical. work on the conjugation of roots written by Vijayānanda.

कियागुप्तक a grammar work quoted by वर्धमान in his गणरत्नमहोद्धि.

कियातिपत्ति lit. over-extension or excess of action; the word is, however, used in grammar in the sense of non-happening of an expected action especially when it forms a condition of the conditional mood (लूड्); cf. दुताश्चहेगुण्यादनभिनिर्शित्तः कियायाः कियातिपात्तिः Kāś. on P. III. 3.139; cf. also नान्तरेण साधनं कियायाः प्रवृत्तिरस्तीति साधनातिपात्तिश्चोत्कियातिपत्तिरपि भवति M. Bh. on III. 3.139.

कियाफल intended fruit of a verbal activity; cf. स्वरिताञ्चतः कर्त्रभिप्राये कियाफले. P.I.3.72.

क्रियायोग association with a verbal activity; cf उपसर्गाः क्रियायोगे P.I.4.59. क्रियाथे (adj. to क्रिया) lit. meant or intended for another action; e. g. भोक्तुं बजित where गमनिक्रया is intended for भोजनिक्रया; cf. तुमुन्ण्बुली क्रियायां क्रियार्थायाम् P.III.3. 10.

क्रियावचन meaning or expressing a verbal activity; a term generally applied to dhātus or roots, or even to verbs. The term is also applied to denominative affixes like क्यच् which produce a sort of verbal.

activity in the noun to which they are added; cf. क्रियावचनाः क्यजादयः M.Bh. on III.1 19.

कियाविशेषण determinant or modifier of a verbal activity; cf. कियाविशेषणं चेति वक्तब्यम्। सुष्ठु पचति तुष्ठु पचति M.Bh.on II.1.1; nouns used as Kriyāviśeṣaṇa are put in the neuter gender, and in the nom. or the acc. case in the sing. number; cf. कियाविशेषणानां कर्मस्यं न्युंसकछिद्भता च Pari. Bhāśkara Pari. 56.

कियासमभिद्वार repetition or intensity of a verbal activity; cf. समिमहार: पौन: पुन्यं भृशार्थों वा, Kāś. on P.I.4.2.

कु krt affix ह applied to the root भी, e.g. भीह, cf. P.III.2.174.

कुकन् kṛt affix रक; e.g. भीरक:; cf.(भियः) कुकन्नपि वस्तब्य: P.III.2.174 Vārttika.

क्रेयादिक a root belonging to the class of roots which are headed by की and which are popularly known as roots of the ninth conjugation; cf. यथा तु वार्तिकं तथा कैयादिकस्याप्यत्र महणसिष्यते Padamanjari on VII.2.48.

कोडादि a class of words headed by the word कोड to which the taddhita affix य (ध्यङ्) is added in the sense of a female descendant; e.g. कोड्या, आपिशस्या, गोकश्या etc; cf. Kāś. on P.IV.1.80.

कोष्ट्रीय an ancient school of grammarians who are believed to have written rules or Vārttikas on some rules of Pāṇini to modify them; the कोष्ट्रीय school is quoted in the Mahābhāṣya; cf. परिभाषान्तरामिति च मत्वा कोष्ट्रीयाः पठन्ति । M. Bh. on P. I.1.3.

क्रोडियादि a class of words headed by the word काँडि which do not take the feminine affix ई when they stand at the end of a compound; e.g. कल्याणकोडा, सुभगा, पृथुजघना etc.; cf. Kāś. on P.IV.1.56.

ऋचादिगण a class of roots headed by

the root ক্লা (ভুকাসূ) to which the conjugational sign না (প্লা) is added; roots of the ninth conjugation.

क्रीबत्व a word used in the sense of 'neuter gender' by grammarians later than पतज्ञाले and the Vartti-kakāra; cf. समभागे क्रीविलज्जमधंमेकदे-शिना समस्यते Bhāṣā Vr. on P.II.2.2; पक्षे हि क्रीबल्वम् Kaiyata's Pr. on II.1.51; समाहारद्वन्द्वे क्रीबल्वप्रसङ्गात् Durgh.Vr. on P.II.4.17.

चलुकन kṛt affix लुक added to the root भी; e.g. भीलुक; cf. P. III.2. 174.

कनिए kit affix चन् in the sense of agent added to (1) a root preceded by an Upasarga or a Subanta Upapada or sometimes even without any preceding word; e.g. प्रतिस्वा, धीवा, पीवा; (2) to the root हश्, preceded by an Upapada which is the object of the root हश्, e.g. पारहश्वा; (3) to roots युध् and इन् having राजन as their object, e.g. राजयुष्वा, राजकृत्वा; cf. Pāṇini III.2.94-96.

करप् kit affix बर, taking the affix ई (डीप्) in the feminine gender, added to the roots इ, नश्, जि etc.; इत्वरी, नश्ररः, जिल्बरी, गत्वरी; cf. P.III. 2.163-164.

क्ब सु krt affix ब्स्, taking the fem. affix ई (डीप्) in the feminine gender, prescribed in the sense of perfect tense, which is mostly found in Vedic Literature and added to some roots only such as सद्, वस्, श्रु etc. in the spoken language; e.g. जक्षिवान पापिवान उपसेदिवान कोत्सः पाणिनिम्; cf. Kāś. on P.III. 2.107-109.

कि a common term to signify kit affixes किन and कि both; cf. P. III. 2.134, VI. 3.115, VI.4.40; VIII.3. 25, VI.4.15, VI.4.97.

किन् krt zero affix, i.e. an affix of which every letter is dropped and nothing remains, added to the roots स्पृश्, यज्, स्ज्, दृश्, etc. under certain conditions; e.g. घृतस्पृक्, कंत्विक्, याद्र्, ताद्दक्; cf. Kāś. on P.III.2.58-60.

किए (1) kit affix zero, added to the roots सद्, सू, द्विष् and others with a preceding word as upapada or with a prefix or sometimes even without any word, as also to the root हन preceded by the words ন্ত্রন্, মূল and হুস, and to the root ক preceded by सु, कर्मन् etc., and to the roots सु, and चि under certain conditions e.g. उपसत् , सू:, प्रसू:, पर्णंध्वत् , ब्रह्महा, वृत्रहा, सोमसुत् , आग्निचित् ; cf.P.III. 2.61, 76, 77, 87-92; 177-179; (2) the denominative affix zero applied to any substantive in the sense of behaviour अश्वति, गर्दभति etc.; cf. M.Bh. and Kāś, on P.III.1.11.

किवन्त a substantive ending with the krt affix किए (zero affix) added to a root to form a noun in the sense of the verbal action (भाव). The words ending with this affix having got the sense of verbal activity in them quite suppressed, get the nounterminations सु, औ, जस् etc. and not ति, तः etc. placed after them; cf. कुदिभाहेते। भावो द्रव्यवद् भवति. However, at the same time, words undergo certain operations peculiar to roots simply because the krt affix entirely disappears and the word formed, appears like a root; cf. किबन्ता धातत्वं न जहति. Kaiyata's Prad. on VII.1.70.

क्ष्मणक a Jain grammarian quoted in the well-known stanza धन्यन्तिर: अपणकोमरसिंहराङ्कुo which enumerates the seven gems of the court of Vikramāditya, on the strength of which some scholars believe that he was a famous grammarian of the first century B.C.

क्षमामाणिक्य a Jain grammarian who wrote a small grammar work known as Anițkārikāvivaraņa.

হিনীয়াব্দক্ক (ব্ৰুক্নাৰ্নিন্) or K. C. CHAT-TERJI a scholar of Sanskrit grammar who has written a work on technical terms in Sanskrit, who has edited several grammar works and is at present editing the Cāndra Vyākaraņa and conducting the Sanskrit journal named Manjūsa at Calcutta.

क्षिप्र lit. rapid, accelerated, a short; name given in the a Prātiśākhya works to a Samdhi or euphonic combination of the vowels হ, ত. ক্র ਲ with a following dissimilar vowel; cf. Uvvata Bhāsya on R.Pr. III.10; cf. also इको यणिव P.VI.1.77. The name Ksipra is given to this Samdhi possibly because the vowel, short or long, which is turned into a consonant by this samdhi becomes very short (i.e. shorter than a short vowel i.e. a semi-vowel). The word क्षेत्र is also used in this sense referring to the Ksiprasamdhi.

क्षीरतरिङ्गणी a kind of commentary on the Dhātupāṭha of Pāṇini written by Kṣīrasvāmin.

क्षीरतराङ्गिणीसंकेत an abridgment of श्रीरतराङ्गिणी by the author himself. See श्रीरतराङ्गिणी

क्षीरस्वामिन a grammarian of Kashmir of the 8th century who wrote the famous commentary शीरतरिङ्गणी on the Amarakośa and a commentary on the Nirukta of Yaska.

भुभा, तृष्तु and the like in which the consonant न is not changed into ण although the consonant न is preceded by क, ऋ, र or ब and intervened by letters which are admissible; e. g. भुभाति, तृष्नोति, तृतमतः etc. cf. Kas. on P. VIII. 4, 39. This class (भुभादिगण) is styled as आञ्चतिगण.

क्षेमंकर author of a commentary on सारस्वतप्रक्रिया.

ह्मेप (1) another name of the क्षिप्रसंधि-See the word क्षिप्र above; (2) name given to the Svarita accent borne by the vowel following the semivowel which results from the Ksiprasamdhi; cf R. Pr. II. 8; III. 7,10; VIII. 22; cf. इवर्णोकारयोधिवकारमावे क्षेप्र उदात्तयो: V. Pr. XX. 1; cf. also युवर्णों यवी क्षेप्र: V. Pr I. 115; उदात्तस्वरितयोर्थण: स्वरितोनुदात्तस्य P. VIII. 2. 4.

६वेडन hissing or whizzing sound given as a fault in the utterance of sibilants; cf. ६चेडनमधिको वर्णस्य सहपा खिन: 1 com. on R. Pr. XIV. 6.

कस (1) aorist vikaraņa affix substituted for च्छि; cf. P. III. 1. 45, 46; e. g. अहक्षत, आश्चिक्षत, अधुक्षत cf. Kāś. on P. III. 1. 45, 46; (2) kṛt affix स applied to the root ह्या preceded by a pronoun such as त्यद्, तद् etc. e.g. याहक्षः, ताहक्षः etc. cf. हशेः क्सश्च वक्तव्यः P. III. 2. 60 Vārttika. (3) affix स applied to the root गाह् or ख्या or कच् to form the noun कक्ष; cf. कक्षो गाहतेः क्स हति आसकरणः ख्यातेर्वा कषतेर्वा Nir. II. 2.

क्सर्त Uṇādi affix सर; cf. तन्यृशिभ्यां क्सरन् Uṇādi III. 75.

विस Uṇādi affix सि; cf. हुाषेकुषिशुषिभ्यः विस: Uṇādi III. 155.

क्से krt affix से in the sense of तुमुन in Vedic Literature; e. g. प्रेषे (भगाय) Kās. on III. 4. 9.

ख

ख् second consonant of the guttural class of consonants possessed of धारानुप्रदान, अयोष and विवार qualities.

स्व tad. affix, always changed into ईन, (1) applied to the word कुल in the sense of a descendant, e. g. कुलीन:, आब्कुलीन:; cf. P. IV. 1.139;

(2) applied to the words अवार, पार, पारावार and अवारपार in the Saisika senses, e. g. अवारीण:, पारीण: etc.; cf. P. IV.2.93 and Varttikas 2, 3 on it: (3) applied to words ending in the word वर्ग (which does not mean 'sound' or 'letter') in the sense of 'present there,' e.g. वासुदेववर्गींण:, युधिष्ठिरवर्गींण:; cf. P. IV. 3.64; (4) applied to the words सर्वधुर and एकधुर in the sense of 'bearing,' and to ओजस्, वेशोभग, यशोभग and पूर्व, e. g. ओजसीन: etc., cf. P. IV. 4.78, 79, 130, 132, 133; (5) applied in the sense of 'favourable to' to the words आत्मन् , विश्वजन, etc. (P. V. 1.9), to विंशातिक, (32) to आढक, आचित, पात्र and others (53-55), to समा (85-86), to रात्रि, अहन्, संवत्सर and वर्ष (87-88) and संवत्सर and परिवत्सर (92); e. g. आत्मनीनः, आढकीनः पात्रीणः, समीनः, संवत्स-रीण: etc.; (6) to the words सबैचमन्, यथामुख etc. e. g. सर्वच्चर्मीण: cf. P. V. 2.5 to 17; (7) to the words अध्दक्ष, आशितंगु etc. cf. P. V. 4.7, 8. e. g. अषडक्षीण:. (8) ख is also a technical term in the sense of elision or लोप in the Jainendra Grammar cf. Jain I. 1.61. (9) The word ख is used in the sense of 'glottis' or the hole of the throat (गलबिल) in the ancient Pratisakhya works.

खकार the consonant ख ; see ख.

खब् krt affix अ in the sense of 'agent' applied to the roots बद्, ताप्, and यम् when preceded by certain उपपद words standing as objects. Before this affix अन्, the augment मुम् (म्) is added to the preceding उपपद if it is not an indeclinable. e. g. प्रियंतदः, वर्शवदः, द्विषंतपः परंतपः वाचयमः etc. cf. P. III. 2.38-47.

खा tad. affix ईन, applied to महाकुल in the sense of a descendant; e. g. माहाकुलीन: cf. P. IV. 1.141, to श्राम (P. IV. 2.94), to युष्मद् and असमद् in the Saisika senses (P. IV. 3.1), to प्रतिजन, इदयुग etc. (P. IV. 4.99), to माणव and चरक (P. V. 1.11), to क्रत्विज् (P. IV. 3.71), to मास (P. IV. 3.81), to words meaning corn in the sense of 'a field producing corn' (P.V.2.1), to सर्वचर्मन् (P.V.2.5), and to the words गोष्ठ, अस्, ज्ञाला etc. in some specified senses (P. V. 3.18-23). A viddhi vowel (आ, पे or औ) is substituted for the first vowel of the word to which this affix खन्न is applied, as ज्ञ् is the mute letter applied in the affix खन्न.

खण्ड tad. affix applied to कमल, अम्भोज etc. in the sense of समूह, e. g. कमललण्डम, अम्भोजलण्डम, also to the words दृक्ष and its synonyms, e. g. वृक्षलण्डा, तहलण्डा etc.; cf. Kās on P. IV. 2.38, 51.

खण्डिकादि a class of words headed by the word खण्डिका to which the affix अञ् is added in the sense of collection; e. g. खाण्डिकम्, वाडवम्, भेशुकम्; cf. Kāś. on P. IV. 2.45.

खमुञ् kṛt affix अम् applied to the root क when preceded by a word standing as the object of the root, provided an abuse is meant, e.g. चोरंकारं आक्रोशित; cf. P. III. 4.25.

ख्य the pratyāhāra ख्यू standing for the first and second consonants of the five classes; cf. रार्म्बा: ख्य: P. VII. 4.6; also cf. P. VIII. 3.6, VIII. 4.54.

खर the pratyāhāra खर् standing for hard consonants viz. the first and second letters of the five classes and the sibilants, before which, स् at the end of a word becomes विसर्ग, and soft consonants i. e. the third and fourth consonants of the five classes become hard; cf. खरबसानयोर्विसर्जनीय; P. VIII. 3.15, and खरि च P. VIII. 4.55.

बर्ख krt affix अ added to any root preceded by the word ईघड, दुस or सु, and to the roots मू and क preceded by an upadada word forming either the subject or the object of the roots, e. g. ईघटकर: कटो मक्ता, ईघदादयंभव मक्ता; cf. P. III. 3.126, 127.

खश् krt affix added to the roots यज् (causal), ध्मा,धे, रुज, वहु, लिह, पच, हशू, तप्, मन् etc. preceded by certain specified upapada words. root undergoes all the operations such as the addition of the conjugational sign etc. before this खर्on account of the mute letter হা which makes ৰেহা a Sārvadhātuka affix, and the augment म् is added to the preceding उपपद if it is not an indeclinable on account of the mute letter ख; e. g. जनमेजयः, स्तनंधयः, नाडिंधमः, असूर्ये. पस्यः पण्डितंमन्यः etc.; cf. Pān. III-2,28-37, 83.

खन characterized by the mute letter ख, applied to kit affixes which, by reason of their being खित्, cause (a) the addition of the augment मुस् (स्) to the preceding words अरुस्, हिषद् and words ending in a vowel, and (b) the shortening of the long vowel of the preceding word if it is not an indeclinable; cf. P. VI. 3.66-68.

खिलपाठ a supplementary recital or enunciation which is taken along with the original enunciation or upadesa generally in the form of the sūtras. The word is used in the Kāsikā in the senseof one of the texts forming a part of the original text which is called upadesa; cf. Kāsikā उपदिस्यते अनेनेत्युपदेश: शास्त्रवाक्यानि सूत्रपाठ: खिलपाठश्च (on P.I.3.2); cf. also खिलपाठो घातुपाठ: प्रातिपदिकपाठो वाक्यपाठश्च Padamanjarī on Kāsikā I. 3.2.

बिष्णुच् kṛt affix इणु in the sense of an agent added to the root भू, e. g. अह्यंभविष्णुः, स्थूलंभविष्णुः; cf. P. III. 2.57.

सुकञ् krt affix उक in the sense of an agent added to the root भ, e. g. आल्ब्राभावुकः, सुमर्गभावुकः; cf. P. III. 2.57. See खिण्णुच्-

हिंगुन krt affix अन applied to the root क in the sense of an instrument when preceded by the words आड्य, सुमग, स्थूल etc. provided the whole word is similar in sense to cvi-formation (ब्ब्यर्थ), e.g. आड्यं करणम्, सुभगंकरणम्; cf. P. III. 2.56; fem. आड्यंकरणी, cf. नञ्दनजीकक्ख्युंसरण-तद्धनानामुपसंख्यानम् P.IV.1.15.Varttika.

ग

मं third letter of the guttural class of consonants, possessed of the properties घोष, संद्रत, नाद and अल्पप्राणः some grammarians look upon the word किन्द्रत् (P.I.1.5) as made up of क्, ग and क् and say that the Guna and Vrddhi substitutes do not take place in the vowels इ, उ, क, and ल if an affix or so, marked by the mute letter ग follows.

गङ्गाधर [GANGADHARA SHASTRI TELANG (1) a stalwart grammand Sanskrit scholar of repute who was a pupil of Balasarasvatī of Vārāņasi and prepared in the last century a host of Sanskrit scholars in Banaras among whom a special mention could be made of Dr. Thebaut, Dr. Venis and Dr. Ganganatha Jha. He was given by Government of India the titles Mahāmahopādhyāya and C. I.E.His surname was Manavalli but he was often known as গঙ্গাঘ্যোস্প্ৰী तेल्ड. For details, see Mahabhasya, D.E. Society Ed.Poona p.p.33, 34; (2) an old scholar of Vyākaraṇa who is believed to have written a commentary on Vikṛtavallī of Vyāḍi; (3) a comparatively modern scholar who is said to have written a commentary named Induprakāsa on the Sabdenduśekhara;(4) author of the Vyākaraṇadīpaprabhā, a short commentary on the Vyākaraṇa work of Cidrūpāśramin. See चिद्रपाश्मिन.

শক্ত্রাহার্মী writer of Kātantra-kaumudī possibly different from the reputed Gaṅgeśa Upādhyāa who is looked upon as the founder of the Navyanyāya school of modern Naiyāyikas, and who lived in the twelfth century A. D.

गजकुम्भारुति a graphic description of the Jihvāmūlīya letter as found in script, given by Durgasimha; cf. गजकुम्भारुतिवर्णे उपध्मानीयसंज्ञा भवति Durgasimha's com. on Kāt. I.l. 18. see 🖰 (उपधानीय).

गण a class of words, as found in the sutras of Pāṇini by the mention of the first word followed by the word इति; e.g. स्वरादि, सर्वादि, ऊर्यादि, स्वादि, अदादि, गर्गादि etc. The ten gaṇas or classes of roots given by Pāṇini in his dhātupāṭha are given the name Daśagaṇī by later grammarians.

the several words forming a class or gaṇa, named after the first word said to have been written by Pāṇini himself as a supplementary work to his great grammar called Asṭaka or Aṣṭādhyāyī, the Śikṣā, the Dhātupāṭha and the Lingānusāsana being the other ones. Other grammarians such as আক্রাম্বান, সাণিয়াই and others have their own gaṇapāṭhās. The gaṇapaṭha is traditionally ascribed to Pāṇini; the issue is question-

ed, however, by modern scholars. The text of the gaṇapāṭha is metrically arranged by some scholars. The most scholarly and authoritative treatise on gaṇapāṭha is the Gaṇaratnamahodadhi of Vardhamāna.

गणरत्नमहोदाध a grammar work, consisting of a metrical enumeration of the words in the Gaṇapāṭha of Pāṇini, written by Vardhamāna, a Jain grammarian of the 12th century, who is believed to have been one of the six gems at the court of Lakṣmaṇasena of Bengal. Vardhamāna has written a commentary also, on his Gaṇaratnamahodadhi. Besides Vardhamāna's commentary, there are other commentaries written by गोवर्धन and गङ्गाधर.

गणरत्नमहोद्धिदीका also called गणरत्न-महोदिधिश्चित, a commentary on the गणरत्नमहोद्धि of Vardhamāna written by the author himself. See गणरत्नमहोद्धि.

गणरत्नमहोद्ध्यवचूरि a metrical commentary on Vardhamāna's Gaņaratnamahodadhi. The name of the author is not available.

गणसूत्र a statement of the type of a Sutra in the Gaṇapātha of Pāṇini where mention of a word or words in the Gaṇapātha is made along with certain conditions; e.g. पूर्वपरावर, स्वमज्ञातिधनाख्यायाम्, in the सर्वोदिगण, and क्लातोसुन्कसुनः, तसिलादयः प्राक्पाश्यः in the स्वरादिगण. Some of the gaṇasūtras are found incorporated in the Sūtrapātha itself. Many later grammarians have appended their own gaṇapātha to their Sūtrapātha.

गणसूत्रविचार a commentary on the Gaṇapāṭha of Pāṇini written by Mannudeva who flourished in the nineteenth century.

गांते (1) lit. motion; stretching out, lengthening of a syllable. The word is explained in the Prātiśākhya works which define it lengthening of a Stobha vowel with the utterance of the vowel ξ or \Im after it, e.g. हाइ or हायि for हा; similarly आ— इ or आ — यि ; (2) a technical term used by Pānini in connection with prefixes and certain indeclinables which are called गति. cf. P.I.4.60-79. The words called gati can be compounded with the following word provided the latter is not a verb, the compound being named tatpurusa e.g. प्रकृतम् , ऊरीकृत्य cf. P.II.2.18; the word गति is used by Pāṇini in the masculine gender as seen in the Sūtra गतिरनन्तर: P.VI. 2.49 and hence explained as formed by the addition of the affix किन to गम्, the word being used as a technical term by the rule किन्की च संज्ञायाम P.III.3.174; (3) realization, understanding; cf उभयगतिरिह भवति Par. Sek. Pari.9;सांप्रतिकाभावे भूतपूर्वगितिः Par. Sek. Pari 76; अगत्या हि परिभाषा आश्रीयते Purusottamadeva Pātha 119.

गातिकारकपरिभाषा a popular name given to the maxim गतिकारकोपपदानां कृद्धि: सह समासवचनं प्राक् सुबुत्पेत्तः; cf. Par. Sek. Pari. 75.

गतिनिघात the grave (अनुदात्त) accent of the गति word before a verb with an acute (उदात्त) accent; cf. तिङि चोदात्तवति P. VIII.1.71.

गातिसमास a compound with the preceding gati word prescribed by the rule कुगतिप्रादयः P.II. 2.18; cf. गति-समास । निष्कौशाम्बः, निर्वाराणसिः M.Bh. on II. 4, 26.

गत्यर्थे a root denoting motion; the word frequently occurs in the

Sūtras of Pāṇini and the Mahābhā-sya in connection with some special operations prescribed for roots which are गत्यर्थ. There is also a conventional expression सर्वे गत्यर्था ज्ञानार्था: meaning 'roots denoting motion denote also knowledge'; cf. Hem. Pari, 121.

গৰা a popular name given to the scholarly commentary written by Vaidyanātha Pāyaguṇḍe on the Paribhāṣenduśekhara. The commentary is called ন্ধাইন্ধা also, as it was written in the town of Kāśī (Vārāṇasī).

गदाधरचक्रवार्तेच the reprited Naiyāyika who wrote numerous works on the Navyanyaya; he has written a few works like ब्युत्पत्तिवाद, उपसर्ग-विचार, कारकनिर्णय, सर्वनामविचार, प्रत्ययविचार on Vyākaraṇa themes although the treatment, as also the style, is logical.

गन्तच्य that which should be understood; the word is used in the sense of अवगन्तब्य; cf. तत्र संवन्धादेतद्र-न्तब्यम् M. Bh. on I.1.9.

गमक capable of conveying the sense; intelligible; the word is often used in grammatical works; cf. सोवक्षत्वेपि गमकत्वात्समासः; cf. also अवस्यं कस्याचित्रज्य-मासस्य असमर्थसमासस्य गमकस्य साधुत्थं वक्तव्यम् । अस्यपित्यानि मुखानि M. Bh. on II. 1. 1.

गम्य to be understood, not expressed; cf. यस्यार्थों गम्यते न च शब्दः प्रयुख्यते स गम्यः। com. on Hem. II. 2. 62.

गम्यादि a class of words headed by the word गमी which are formed by the application of uṇādi affixes in the sense of future time; e. g. गमी प्रामम्, आगामी, प्रस्थायी etc. cf. Kāś. on P. III. 3. 3.

गरीयस् involving a special effort. The word is frequently used by the Varttikakara and old grammari-

ans in connection with something, which involves greater effort and longer expression and, hence, not commendable in rules of the Shastra works where brevity is the soul of 'wit'; cf. पदगौरवाद्योगविभागो गरीयान Par. Sek. Pari. 121. The word गुरु is also sometimes used in a similar sense; cf. तद् गुरु भवति M. Bh. I.1 Ahn. 1 Vārt. 2.

गरीयस्त्व greater effort or prolixity of expression which is looked upon as a fault in connection with grammar-works of the sutra type where every care is taken to make the expression as brief as possible; cf. अर्धमात्रालाववेन पुत्रोत्सव मन्यन्ते वैयाकरणाः Par. Sek. Pari. 122. The word गौरव is often used for गरीयस्त्व.

गर्गोदिगण a class of words headed by गर्म to which the affix यज्ञ, (य) causing Viddhi to the first vowel of the word, is added in the sense of a descendant barring the son or daughter; cf. गर्गोदिस्यो यज्ञ P. IV. 1 105 and the instances गार्थः, वास्यः, वैयात्रपदाः, पोलस्यः cf. Kās. on P. IV. 1. 105.

गर्भवत् lit. just like a foctus. The word is used in connection with affixes that are placed like a foetus in the midst of a word in spite of the rule that affixes are to be placed after; cf. परश्च P. III. 1. 2. The affixes अकच्, टाप् etc. are of this kind; cf. गर्भवहाबादयो भवन्ति । यथा मध्ये गर्भस्तथा टाबादयः स्त्रीप्रस्थाः प्रातिपदि-कस्वाद्योमध्ये भवन्ति Sīradeva Par. V.. Pari. 91.

बिक्रेन्य the word occurs in the Prātisākhya works in connection with the definition of संत्रम, in the kramapātha. The word संत्रम means bringing together two words when they are combined according to rules

of Samdhi. (See the word संक्रम). the Kramapātha, where each word occurs twice by repetition, a word occurring twice in a hymn or a sentence is not to be repeated for Kramapātha, but it is to be passed over. The word which is passed over in Kramapātha is called गलत्पद; e. g. दिशां च पतये नमो नमो वृक्षेम्यो हरिकेशेम्यः पश्रुनां पतये नमो नम: सस्पिञ्जराय त्विषीमते पथीनां पतये नमः । In the Kramapātha पत्ये नमः and नमः are passed over and पश्चनां is to be connected with सस्पिञ्जराय. The words पत्ये नमः and नमः are called galatpada; cf. गलत्पदमतिक्रम्य अगलता सह संघानं संक्रमः V. Pr. IV. 197. There is no गललद in पदपाठ.

गवादि a class of words headed by the word गो to which the affix यत् is affixed in the senses mentioned in rules from P. V. 1. 5. to V. 1. 36; e. g. गज्यम्, ह्विष्यम् युग्यम्, मेध्यम् etc.; cf. Kās. on P. V. 1.2.

गवाश्वप्रभृति the dvandva compound words गवाश्च, गवाविक गवेडक, अजाविक, खुञ्जमाणवक, पुत्रपीत्र मांसशोणित and others which are to be declined in the neuter gender and singular number; cf. P. II. 4.11.

गहादि a class of words headed by the word गह to which the taddhita affix ह्य (छ) is added in the Saisika or miscellaneous senses; e. g. गहीयम्, अन्तस्थीयम्; this class called 'gahīya' is looked upon as आकृतिगण, and hence the words वैणुकीयम् वैत्रकीयम् and the like could be explained as correct; cf. Kās. on P. IV. 2.138.

गार्थे an ancient reputed grammarian and possibly a writer of a Nirukta work, whose views, especially in connection with accents are given in the Prātisākhya works, the Nirukta and Pāṇini's Astādhyāyī. Although belonging to the Nirukta school, he upheld the view of the Vaiyākaraṇas that all words cannot be derived, but only some of them; cf. Nir. I. 12.3 cf. also V. Pr. IV. 167, Nir. I. 3.5, III. 14.22; R. Pr. I. 13; XIII. 12; P. VII. 3.99, VIII. 3.20, VIII. 4.69.

गांडच an ancient grammarian and niruktakāra quoted by Pāṇini; cf. P. VI 3.60, VII. I.74, VII. 3,99, VIII. 4.67, cf. also Nir. IV. 3.

गान a technical term for the term आज्ञ (pertaining to the base in the grammar of Pāṇini); cf. नाणांत् गान क्लीय: Kāt. Pari. 72.

गि a conventional term for उपसर्ग in the Jeinendra Vyākaraṇa.

गित् marked with the mute letter ग्; affixes that are गित् prevent guṇa or vṛddhi in the preceding word; cf. क्विङ्ति च P. I. 1.5; cf. also M. Bh. I. 3.10; III. 2.139; cf. also गकारोप्यत्र चर्ल्यून्तो निर्दिश्यते Kāś. on P. I. 1.5.

गिरिधर writer of विभक्तयर्थीनर्णय, a work on syntax.

गीर्वाणपद्मञ्जरी a grammatical work written by वरदराज, pupil of Bhattoji Dīkṣita in the 17th century who wrote many works on grammar such as मध्यकौसुदी, लघुकौसुदी etc.

गुडादि a class of words headed by the word गुड to which the taddhita affix इक (ठज्) is added in the sense of 'good therein'; e.g. गौडिकः इक्षः, कौल्माषिको मुद्रः; cf. Kāś. on P. IV. 4.103.

degree, the second out of the three degrees of a vowel viz. primary

degree, guna degree and vrddhi degree e.g. इ, ए and ऐ or उ, ओ and औ. अ is given as a guna of अ; but regarding a also, three degrees can be stated अ, अ and आ. In the Prätiśākhya and Nirukta U is called गुण or even गुणागम but no definition is given; cf. गुणागमादतन-भावि चेतन R.Pr.XI.6; रोवम् इति विभाषि-तगण:। शेवमित्यपि भवति Nir.X.17; (2) the properties of phonetic elements or letters such as श्वास,नाद etc.; cf.R. Pr. Ch.XIII; (3) secondary, subordinate; cf. शेष:, अङ्गं, गणः इति समानार्थाः Durgācārya on Nir. I.12; (4) properties residing in a substance just as whiteness, etc. in a garment which are different from the sub-The word गुण is stance (द्रब्य). explained by quotations ancient grammarians in the Mahabhasya as सत्त्वे निविशतेऽपैति पृथग्जातिष दृश्यते । आध्यश्चाकियाजश्च सोऽसत्त्वप्रकृ तेराणः ॥ अपर आह। उपैत्यन्यज्जहात्यन्यद दृष्टो द्रव्यान्तरेष्वि। वाचकः सर्विकिङ्गानां द्रव्यादन्यो गुणः स्मृतः; M. Bh. on IV.1.44;cf. also शब्दस्पर्श-रूपरसगन्धा गुणास्ततोन्यद् द्रव्यम् , $\mathbf{M.Bh.on}$ V.1.119; (5) properties of letters like उदात्तल, अनुदात्तल, स्वरितला, ह्रस्व-त्व, दोघेत्व, प्छतत्व, आनुनासिक्य etc.; cf. भेदकलाद् गुणस्य। आनुनासिक्यं नाम गुणः M. Bh. on I.1.1. Vart. 13; (6) determinant; cf.भवति बहुत्रीही तद्गुणस्वि-ज्ञानमपि M. Bh. on P. I. 1.27; (7) technical term in Panini's grammar standing for the vowels अ, ए and ओ; cf. अदेङ् गुण: P.I.1.2. For the various shades of the meaning of the word गुण, see Mahābhāsya on V.1.119. " गुणशन्दोयं बह्वर्थ: । अरत्येव समेष्वययवेषु वर्तते । चचौगुणांश्च ।

गुणकर्मन् a term used by the ancient grammarians for the गोणकर्मन् or indirect object of a verb having two objects. The word is found quoted in the Mahābhā- sya; cf. कथिते छादयश्चेत्युः वश्चे कुर्योत्तदा

गुणे । गुणे गुणकर्मणि । cf. also गुणकर्मणि लादिविधि: सपरे M.Bh. on I. 4.51.

गुणकीतिं a Jain writer of the thirteenth century who wrote a commentary named कातन्त्रवृत्तिव्यिणी on दुर्गसिंहवृत्ति.

गुणभाविन् a vowel, liable to take the guna substitute e. g. इ, उ, क, लृ and the penultimate अ; cf. यत्र किङ्त्यनन्तरो गुणभान्यस्ति तत्रैव स्यात् । चितम् । स्तुतम् । इह तु न स्याद्भितः भित्रवानिति । M. Bh. on I. 1.5.

गुणभेद difference in properties; cf. एकोयमात्मा उदकं नाम तस्य गुणभेदादन्यत्वं भवति । अन्यदिदं शीतमन्यदिदमुण्णामिति । M. Bh. on I, 1.2.

गुणवचन lit. expressing quality; words expressing quality such as शुक्क, नील, etc.; cf. गुणवचनन्नाहाणादिम्यः कर्मणि च P.V.I.124. See page 369 Vyākaraņa Mahābhāṣya Vol. VII. D.E. Society edition, Poona.

गुणादि a class of words headed by the word गुण, which, when preceded by the word बहु in a Bahuvrihi compound, do not have their last vowel acute; e. g. बहुगुणा रुज्ज:; बहुक्षरं पदम्, etc. This class of गुणादि words is considered as आकृतिगण; cf. Kāś. on P. VI. 2.176.

गुणिन् possessed of a quality; cf. इह कदाचिद् गुणा गुणिविशेपका भवति । तद्यथा पट: गुक्क इति । कदाचित्र गुणिना गुणो न्यपदिश्यते । पटस्य गुक्क इति । M. Bh. on I.4.21.

मुणीभूत subordinate, lit. which has become subordinated, which has become submerged, and therefore has formed an integral part of another; e. g. an augment (आगम) with respect to the word to which it has been added; cf. यदागमास्तद्गुणीभ्रतास्तद्ग्रहणेन यहान्ते। M. Bh. I. 1.20 Vart. 5; Par. Sek. Pari. 11.

गुरु (1) possessed of a special effort as opposed to लघु; cf. तद् गुरु भवति M. Bh. Ahnika 1. (2) heavy, a technical term including दोर्च (long) vowel as also a हुन्च (short) vowel when it is followed by a conjunct consonant, (cf. संयोगे गुर । दोर्च च। P. I. 4.11, 12) or a consonant after which the word terminates or when it (the vowel) is nasalized; cf. Tai. Pr. XXII. 14, cf. also R. Pr. I. 5.

गुरुमत् a word containing a गुरु vowel in it; cf. इजादेश्च गुरुमतोनुन्छः P.III.1.36.

गुरूलघुता consideration of prolixity and brevity of expression; cf. तत्राप्ययं नावस्यं गुरुलघुतामेवोपलक्षायेतुमहीति । M. Bh. on I. 1.1.

गुरुलाघव the same as गुरुलघुता which see above; cf. पर्यायशब्दानां गुरुलाघवन्वर्चा नाद्रियते Sīradeva Pari. 125.

गूढ held up or caught between two words with which it is connected; e. g. the word असि in इयं ते राट् यन्ता असि यमन: ध्रुव: घरण: । cf. V. Pr. IV. 176.

युद्धफिकाप्रकाश a short gloss on the Siddhāntakaumudī of Bhaṭṭojī Dīkṣita, by Indradatta.

गुढभावन्नि a commentary on Rāmacandra's Prakriyā Kaumudī by Kṛṣṇaśeṣa of the famous Śeṣa family of grammarians. The date of this Kṛṣṇaśeṣa is the middle of the sixteenth century. For details about Kṛṣṇaśeṣa and the Śeṣa family see introduction to Prakriyākaumudi B. S. S. No. 78.

युदार्थदीपिनी a commentary (द्याते) on the sūtras of Pāṇini by Sadāśiva Mīśra who lived in the seventeenth century.

पूढार्थप्रकाश a commentary on the Laghusabdendusekhara by M. M. Vasudeva Shastri Abhyankar (1863-1942).

गृष्ट्यादि a class of words headed by the word गृष्टि to which the taddhita

affix एय (ढज्) is affixed in the sense of 'an offspring' (अपत्य); eg. गाउँच:, हाल्य: etc.; cf. Kāś. on P. IV.1.136.

गृहीत included; cf. भ्राजादिस्त्र एव गृहीतत्वात् Kāś. on P. III. 2,178.

गोणिकापुत्र a grammarian whose view in connection with the correctness of the expressions नेताश्वस्य झुझं and नेताश्वस्य सुझस्य is given by the Mahābhāṣyakāra in the words 'both expressions are justified' (उभयथा गोणिकापुत्रः). Nāgeśa has observed that गोणिकापुत्र is nobody else but the Mahābhāṣyakāra himself; cf. गोणिकापुत्रः भाष्यकार इत्याहुः। Nāgeśa's Uddyota on Mahābhāṣyapradīpa on P. I. 4.51.

गोत्र lit. family. The word is used by Pāṇini in the technical sense of a descendant except the son or a daughter; cf. अपत्यं पौत्रप्रसृति गोत्रम् P. IV. 1.162. The word गोत्रापत्य is also used in the same sense. The affix, which is found many times in the sense of gotra, barring the usual अण्, is यज्ञ ; cf. गगीदिस्यो यज्ञ P. IV. 1.105.

गोत्रप्रत्यय affix in the sense of गोत्र; cf. यश्चासौ गोत्रप्रत्य: प्राप्नोति स एक: स्यात् M. Bh. on IV. 1.93.

गोनदीय lit. inhabitant of Gonarda which was the name of a district. in the province of Oudh in the Mahābhāsyakāra of the according to some scholars. Others believe that Gonarda was of the district named Gonda at present. The expression गोनदीय आह occurs four times in the Mahabhasya where it refers to a scholar of grammar in Patanjali's time; cf. M.Bh. on I. 1.21; I. 1.29; III. 1.92; VII. 2.101. As Kaiyata paraphrases the words गोनदीयस्वाह as भाष्यकारस्त्वाह, scholars say that गोनदीय was the name taken by the Mahābhāṣyakāra himself who was a resident of Gonarda. Hari Dīkṣita, however holds that गोनदींच was the term used for the author of the Vārttikas; cf. Bṛhacchabdaratna.

गोपननादि a class of eight words headed by the word गोपनन, the taddhita affix in the sense of गान (i. e. a descendant excepting a son or a daughter) such as the affix यून or अन after which, is not elided in the plural number; e. g. गोपननाः, शैमनाः etc.; cf. Kōś. on P. II. 4.67.

गोपाल (देव) known more by the nickname of मनुदेव or मन्तुदेव who · lived in the eighteenth century and wrote several commentary works on well-known grammatical treatises such as the Vaiyākaraņabhūsaņasāra, Laghuśabdenduśekhara, Paribhāsenduśekhara etc. He is believed to have written a treatise on Ganasūtras also; (2) La grammarian different from the ्above मन्तुदेव who has written an explanatory work on the Pratiśākhyas; (3) a scholar of grammar, different from the above who is believed to have written a gloss named Visamārthadīpikā on the Sārasvata Vyākaraņa at the end of the sixteenth century.

गोपीचन्द्र known also by the name गोपीचन्द्र who has written several commentary works on the grammatical treatises of the Samksiptasāra or Jaumāra school of Vyākarana founded by Kramdīsvara and Jumaranandin in the 12th century, the well-known among them being the संस्थास्त्रीका, संस्थित-सार्पिभात्रासूत्रटीका and तद्धितपरिशिट्टीका. He is believed to have lived in the thirteenth century A. D.

गोपीनाथ a Bengali scholar of Katantra Grammar who is believed to have written Katantraparisistapraddyota.

गोयीचन्द्र see गोपीचन्द्र.

गोयुगच् a tad. affix applied to nouns like अध, उड़, etc. in the sense of a pair e. g. उड़गोयुगम्, अध्ययेयुगम्; cf. दित्वे गोयुगच् Kāś. on P. V. 2.29.

गोरइस्ट्यूकर a well known German scholar who made a sound study of Pāṇini's Sanskrit Vyākaraṇa and wrote a very informative treatise entitled 'Pāṇini, his place in Sanskrit Literature.' He lived in the latter half of the 19th century.

गोवर्धन a grammarian who has written a work on Kātantra Grammar called कातन्त्रकोमुदी and also a commentary on the Ganaratnamahodadhi of Vardhamāna. A gloss on the Unādisūtras is also assigned to Govardhana who is likely to be the same as above.

गोविन्द writer of a commentary known as अध्याक्त्री by reason of that work beginning with the stanza अभ्या क्त्रीo, on the Paribhāsendušekhara of Nāgesa.

गोविन्द (चक्रवर्तिन्) writer of Samāsavāda, a short treatise on the sense conveyed by compound words.

गोविन्दराम writer of 'Sabdadīpikā,' a commentary on the Mugdhabodha Vyākarana of Bopadeva.

गोषदादि a class of words to which the taddhita affix अक (बुन्) is added in the sense of possession provided the word so formed refers to a chapter (अध्याय) or a section (अनुवाक); c. देवामुर:, वेमुक्त: etc.; cf. Kāś. on P. V. 2.62.

गोष्ठच् a tad.affix applied to words like गो and others in the sense of 'a place'; cf. गोष्ठजादयः स्थानादिषु पश्चनामा पश्चनामादिम्य उपसंख्यानम्। गवां स्थानं गोगोष्ठम्, अक्षगोष्टम्; महिंबीगोष्टम् Kās. on P.V.2.29:

It is very likely that words like গান্ত, বন and others were treated as pratyayas by Pāṇini and kātyāyana who followed Pāṇini, because they were found always associated with a noun preceding them and never independently.

मोण (1) a word subordinate in syntax or sense to another; adjectival; उपसर्जनीभूत; (2) possessing a secondary sense, e. g. the word गा in the sense of 'a dull man'; cf. गौणमुख्ययोर्मुख्ये कार्यसंप्रत्ययः, M. Bh. on I.1.15, I.4. 108, VI.3. 46. See also Par. Sek. Pari. 15; (3) secondary, as opposed to primary; cf. गौण कमीण दुझादेः प्रथाने नीहकृष्यहाम्।

गौणमुख्यस्याय the maxim that the primary sense occurs to the mind earlier than the secondary sense, and hence words used in the primary sense should be always taken for grammatical operations in preference to words in a secondary sense. See the word गोण.

गौतम an ancient sage referred to in the Prātiśākhya works as a Prātiśākhyakāra; cf. T.Pr. V.38.

गौरव greatness of effort; prolixity as opposed to लाघन; cf. पर्यायशब्दानां लाघनगारवचर्चा नाद्रियते Par.Sek.Par.115; cf. also पदगौरवाचोगविभागो गरीयान् Par.Sek. Pari. 121.

गौरादि a class of words to which the affix ई (ङोज्) is added to form the feminine base; e.g. गौरी, मत्सी, ह्यी, हिरिणी; the class contains a large number of words exceeding 150; for details see Kāsikā on P.IV.l. 41; (2) a small class of eleven words, headed by the word गौर which do not have the acute accent on the last syllable in a tatpurusa compound when they are placed after the preposition उप; cf. P. VI.2.194.

गिमन् tad. affix in the sense of possession; cf. वाचो गिमनि:। वाग्मी। P.I.2.124.

प्रस्त a fault of pronunciation due to the utterance of a letter hindered or held back at the throat; cf. जिह्नामूळनिग्रहे ग्रत्समेतत् R.Pr.XIV.3; cf. also ग्रस्त निरस्तमवलम्बतम्। प्रस्तः जिह्नामूळ गृहीतः। अञ्चक्त इत्यपरे। Pradipa on M. Bh. Āhnika 1.

प्रहण (1) technical term for a word or प्रातिपदिक in Veda; cf. प्रहणस्य च। गृह्मते इति प्रहण वेदस्थः शब्दः। तत् त्रिविधम्। कार्यभाक्, निमित्तम्, उपवन्ध इति। तस्यपि स्वरूपपूर्वकः अकारः आख्या भवति। Com. on T.Pr.I.22; (2) citing, quoting; cf. प्रहणवता प्रातिपदिकेन न तदन्तिविधः Par.Sek. Pari. 31; cf. also गृह्णनति प्रहणानि Com. on T.Pr.I.24. (3) mention, inclusion; (4) employment in a rule of grammar; cf. प्रातिपदिक्रमहणे छिङ्गविशिष्टस्यापि प्रहणम्. Par. Sek. Pari.71.

प्रहणक citing or instructing the inclusion (प्रहण) of certain other things by the mention of a particular thing; e. g. the rule अणुदित्सवर्णस्य चाप्रत्ययः is a प्रहणक rule as it advises that the citing of the letters अ, इ, क etc. includes the long and protracted forms of अ, इ, उ etc; cf. also प्रहणकशास्त्रस्य सावर्ण्यविधिनिषधाभ्यां प्रागनिष्पत्तः Sid. Kau. on अकः सवर्णे दीर्घः V1.1.101.

प्रहणवत् specifically mentioned in a rule, individually mentioned; cf. प्रहणवता प्रातिपदिकेन तदन्तविधनीस्ति । Par. Sek.Pari.31. See the word प्रहण.

श्रहादि a class of roots headed by the root मह to which the affix इन् (णिनि), causing viddhi to the preceding vowel of the root, is added in the sense of an agent; e.g. प्राही, उत्साही, साथी, मन्त्री etc.; cf. Kāś. on P.III. 1.134.

त्रास a fault in the utterance of a letter which makes it indistinct by being held up at the throat. Seeग्रस्त.

म्सु krt affix स्तु applied to the roots छै, जि and स्था in the sense of an agent; cf. म्ह्राजिस्थक्ष क्स्तु: P.III.1.139.

ट

घ् (1) fourth consonant of the guthaving tural class of consonants properties कण्डसंत्रतत्व. नादानुप्रदानत्व and महाप्राणत्य; (2)the consonant व at the beginning of a tad. afflx which is always changed into इय; cf. P. VII. 1. 9; substitute for & at the end of roots beginning with s,as also of the root नह under certain conditions; cf. P. VIII.2.32,33,34; (4) substitute for the consonant व of मतुर् placed after the pronouns किम् and इदम् which again is changed into इय by VII.1.9; e.g. कियान्, इयान्; cf. P.V. 2.40.

ঘ (1) consonant ঘু, স্ব being added at the end for facility of pronunciation; cf.Tai. Pr.I.21; (2) technical term for the tad. affixes तर्प and तमप्, cf. P.I.1.22, causing the shortening of \(\frac{1}{2}\) at the end of bases before it, under certain conditions, cf. P. VI. 3.43-45, and liable to be changed into तराम and तमाम् after किम्, verbs ending in ए, and indeclinables; cf. P.V.4.11; (3) tad. affix ঘ (হ্য) in the sense of 'a descendant' applied to ধ্বৰ, and in the sense of having that as a deity' applied to अपोनप्तृ, अपानप्तृ and also to महेन्द्र and to the words राष्ट्र etc., e.g. क्षत्रियः, अपोनन्त्रियः, अपानन्त्रियः, महेन्द्रियम्, राष्ट्रियः etc.; cf. P. IV.1.138, IV.2.27, 29, 93; (4) tad. affix \(\text{q}\), applied to अप्र, समुद्र and अभ्र in the sense of 'present there', to सहस्र in the sense of 'possession', to নধ্ৰৰ without any change of sense, and to यज्ञ and ऋत्विज in the sense of 'deserving'; cf. P.IV.4.117,118,135, 136,141, V.1.71; (5) krt affix a when the word to which it has been applied becomes a proper noun i.e.a noun in a specific sense or a technical term; cf. III.3.118, 119,125.

ঘকাৰ the consonant ঘ; see ঘ্.

घच् tad. affix इय, as found in the word क्षेत्रिय; cf. क्षेत्रियच् परक्षेत्रे चिकित्स्य: P.V.2.92 and Kāśikā thereon.

घन् kṛt affix अ causing the substitution of vṛddhi for the preceding vowel applied in various senses as specified in P.III.3. 16-42, III.3. 45-55, III.3.120-125, e.g. पाद:, रोग:, आय:, भाव:, अवप्राह: प्रावार:, अवतार:, लेख: राग: etc.

ঘন tad. affix স্ব applied to the words গ্রহ্ম, ব্রহ্ম, থাস, and to multisyllabic words in specified senses, causing the acute accent on the first vowel of the word so formed; cf.IV.2.26, IV.4. 115, V.1.68, V.3.79, 80.

धन a variety of the क्रमपाठ or recital of the Vedic hymns to show the serial order of words there; one of the eight vikṛtis of the padapāṭha.

घस tad. affix इय, occurring in Vedic Literature, applied to the word ऋतु, e.g. अयं ते योनिर्कत्वियः; cf. Kāś. on P. V.1.106.

ঘি (1) a tech. term applied to noun bases or Prātipadikas ending in ছ and ও excepting the words ধৰি and দিন and those which are termed নবী; cf. P. I. 4.79; (2) a conventional term for ভদ্ত (a short vowel) found used in the Jainendra Vyākaraņa.

घित affixes having the mute letter मु, as for instance, घन म, घन etc. which cause the substitution of a guttural in the place of the palatal letter च or ज before it; e.g. त्यागः सगः cf. P.VII.3.52.

चितुण् kit affix इन् causing the sulstitution of Viddhi for the preceding vowel, as also to the penultimate vowel अ, applied to the eight roots शम्, तम्, दम् etc., as also to सपृत्, अनुरुष् etc. and कस्, लघ् लप्, etc. e. g. शमी, तमी, दमी, संपकी, संज्वारी, प्रलापी etc.; cf. P. III.2,141-145.

धिसंज्ञ (noun bases or Prātipadikas) called or termed थि. See थि.

यु a tech. term applied to the roots दा and धा, as also to those like दे or दो which become दा by the substitution of आ for the final diphthong vowel, barring the root दाप् (to cut) and देप् (to purify); cf. दाधा ध्वदापु P.I. 1.20.

घुट a conventional term for the first five case-affixes; cf. घुटि च Kāt. II. 1.68. The term घुट् is used in the Kātantra Vyākaraņa and corresponds to the term सर्वनामस्थान of Pāṇini.

घुरच् kit affix उर applied to the roots मञ्ज् ,मास and भिद् in the sense of habit; e.g. भङ्गुरं काष्ट्रम, भासुरं ज्योति:, भेदुर: पग्नः; cf. Kās. on P.III.2.161.

घोष an external effort in the pronunciation of a sonant or a soft consonant which causes depth of the tone; cf. अन्ये तु घोषाः स्यु: संवृताः etc., Sid. Kau. on VIII. 2.1.

घोषवत् a consonant characterized by the property घोष at the time of its utterance; cf. तृतीयचतुर्थाः संवृतकण्डाः नादानुप्रदाना घोषवन्तः M.Bh. on P.I.1.9.

13

र् (1) fifth letter of the guttural class of consonants having the properties कण्ठसंत्रतत्व, घोष, नादानुप्रदान, अल्पप्राणत्व and आनुनासिक्य; (2) the consonant ङ् getting the letter क as an aug-

ment added to it, if standing at the end of a word and followed by a sibilant, e. g. प्राङ्क्शेत cf. ङ्णोः दुक् दुक् शिर P. VIII. 3. 28; (3) the consonant ङ् which, standing at the end of a word and preceded by a short vowel, causes the vowel following it to get the augment ङ् prefixed to it; e. g, प्रत्यङ्डास्ते; cf. ङमो हस्वादिच ङम्ण नित्यम P. VIII.3.32.

জ (1) fifth consonant of the guttural class of consonants which is a nasal (অনুনাধিক) consonant; the vowel অ being added at the end for facility of pronunciation; cf. T. Pr. I.21; (2) a conventional term used for all the nasal consonants in the Jainendra Vyākaraņa.

জন a short term or Pratyāhāra standing for the letters ङ्, ण्, न्, झ, and भू, casually mentioned in the Mahābhāṣya; cf. एतदप्यस्तु अकारेण ভুজो हुस्वादचि ভুজুण्नित्यमिति। M. Bh. on Māheśvara Sutras 8, 9.

ङम् a short term or Pratyāhāra for the consonants इ, ग, and न. See इ (3).

ङमुद् augment ङम् i.e. ङ्, ण् or न् prefixed to a vowel at the beginning of a word provided that vowel is preceded by ङ, ण् or न standing at the end of the preceding word. See ङ् (3).

डस् ending of the genitive case singular; स्व is substituted for डस् after bases ending in अ; cf. P. IV. 1. 2 and VII. 1. 12.

ङसि case-ending of the ablative case, changed into आत after bases ending in अ and into स्मात् after pronouns; cf.P.IV.1.2,VII.1.12,15.

stanged into (a) आम after bases termed Nadī, fem. bases ending in आ and the word नी, (b) into औ after bases ending in इ and उ, and (c) into सिन् after bases of pronouns; cf.

P.IV. 1. 2, VII. 3. 116, 117, 118, 119 and VII. 1. 15, 16.

ভিন (1) affixes with the mute letter ু attached to them either before or after, with a view to preventing the guna and vrddhi substitutes for the preceding इ, उ, क, or लू, as for example, the affixes ৰম্ভ, অন্ত and others; (2) affixes conventionally called दित after certain bases under certain conditions; cf. गाङ्क्टादिभ्यो जिणन्डित P. I. 2. 1-4; (3) roots marked with the mute letter signifying the application of the Atmanepada terminations to them; (4) substitutes marked with mute which are put in the place of the last letter of the word for which they are prescribed as substitutes; (5) case affixes marked with mute letter & which cause the substitution of guna to the last vowel इ or उ of words termed वि. ड़ी common term for the fem. affix ई, mentioned as डीप, डीब or डीन by

Panini; cf. P. IV. 1. 5-8; IV. 1. 15-39, 40-65 and IV. 1. 73.

डीन fem. affix ई added to words in the class headed by আর্ন্ন্ব; cf. P. IV. 1. 73. Words ending with this affix डीन् have their first vowel accented acute.

ङ्कीप् fem. affix ई which is anudātta (grave) added (a) to words ending in the vowel = or the consonant न (cf.P.IV.1.5), (b) to words ending with affixes marked with mute 3. F or ਲ; cf. P.IV.1.6, (c) to words ending with affixes marked with mute ट् as also ending with the affixes द. अण्, अञ्, इयसच् दघ्नच्, मात्रच्, तयप् , ठक्, ठञ्, कन् and करप (cf. P.IV.1.15) and to certain other words under certain conditions; cf. P. IV. 1.16-24.

कीष sem. affix ई, which is udātta, applied to words in the class of

words headed by गौर, as also to bases ending in affixes marked with mute g, as also to words mentioned in the class headed by बह; cf. P.IV.1.41-46. It is also added in the sense of 'wife of' to any word denoting a male person; cf. P. IV. 1. 48, together with the augment স্থানক (आन्) to the words इन्द्र, वरुण etc. e.g. इन्द्राणी, वरुणानी, यत्रनानी meaning the script of the Yavanas' cf. P. IV. 1.49. It is also added to words ending in कीत and words ending in क and also to words expressive of 'limbs of the body' under certain conditions; cf. P. IV. 1. 50-59 and IV. 1.61-65.

डुद augment इ mentioned as इट्, in Kāśikā, added to the vowel following the consonant & at the end of a word. See ङमुट्.

ক dative case termination changed . into a after bases ending in short अ and into समे after pronouns; cf. P. IV. 1.2, VII. 1.13, 14.

ভয়নৰ noun bases ending with the fem. affix ङो (ङीप्, ङीप्, or ङीन्); cf. ङचन्तादित्येवं भविष्यति M.Bh. on P. I. 1.89 Vart. 16.

ङ्यापाद a popular name given by grammarians to the first pada of the fourth adhyaya of Panini's Astādhyāyī as the pāda begins with the rule ड्याप्प्रातिपदिकात् IV. I.1.

ङ्बानेप् kit affix वन् in the sense of an agent referring to an activity of past time, added to the roots & and यज् ; e. g. मुत्वा, मुत्वानी ;यज्वा यज्वानी cf. P. III 2.103.

च् first consonant of the palatal class of consonants, possessed of the properties, श्वास, अवोष, अल्पप्राण and कण्ठिववृत्तल. च् at the beginning of an affix is mute e.g. च्फ्ड्र, cf. चुद्द P. I. 3.7; words, having the mute letter च् (dropped), have their last vowel accented acute e.g. मङ्गुरम्। मासुरम्। cf. चित: VI. 1.163.

चि (1) the letter च, the vowel अ being added for facility of utterance, cf. T. Pr. I. 21; (2) a Pratyāhāra or short term standing for the palatal class of consonants च, छ, जू, झ and जु; cf इचरोयास्ताला V. Pr. I. 66; (3) indeclinable = called Nipāta by Pānini; cf. चादयोऽसन्त्वे P. I. 4.57. \(\) possesses four senses समुचय, अन्वाचय, इतरेतरयोग and समाहार cf. Kāś. on II. 2.29. See also M. Bh. on II. 2.29 Vart. 15 for a detailed explanation of the four senses. The indeclinable ৰ is sometimes used in the sense of 'a determined mention' or avadhāraṇa; cf. Kāś. on II. 1.48 and It is also used for the purpose of अनुवृत्ति or अनुकर्षण i. e. drawing a word from the previous rule to the next rule; (cf. M. Bh. on P. VI. 1.90) with a convention that a word drawn thus, does not proceed to the next rule; cf. चानकृष्टं नोत्तरत्र Par. Sek Pari. 78; (4) a conventional term for अभ्यास (reduplicative syllable) used in Vyākaraņa; cf. the Jainendra चिवकारेषु अपवादा उत्सगान बाधन्ते Kat. Pari. 75.

eant the consonant ব্, the vowel আ being added for facility of utterance and কাৰ as an affix to show that only the consonant ব is meant there; cf. T. Pr. I. 16, 21.

चकोर a grammarian who wrote a commentary on the 'Sabdalin-gārthacandrikā' of Sujanapandita.

चक्कनशर्मा a grammarian who is said to have written a work named Dhātusamgraha.

चक्रक a kind of fault in the application of operations, resulting in confusion; a fault in which one returns to the same place not immediately as in Anavasthā but after several steps; cf. पुनर्केन्छिमावः पुनराट इति चक्रकमञ्चवस्था प्राप्ताति । M. Bh. on I. 3.60 Vārt 5.

चন্ধনাংক known by the name কাংক-লক্ষ also, a small work on syntax attributed to বংকবি.

चक्रपाणि (शेष) a grammarian of the Sesa family of the latter half of the 17th century who held views against Bhattojī Dīkṣita and wrote प्रौडमनोरमाखण्डन, कारकतस्व and कारकविचार...

चिक्रिन् a grammarian who has written a small disquisition on the correctness of the form जाप्रहीता. See जाप्रहीतीतिवाद.

ৰক্ত a Vikarana affix of the aorist substituted for ভিন্ত after roots ending in the causal sign গি, as also after the roots প্লি, হু and others; this বহু causes reduplication of the preceding root form; cf. P. III 1.48-50. e. g. অবুযুক্, অহিপ্সিয়ন; cf. also P. VII. 4.93.

चङ्गदास a grammarian who has written a work on the topic of the five vṛttis. The work is named ভঙ্গবৃথ্যি.

चङ्गद्वात a short treatise written by चङ्गदास, dealing with the topic of the five compact expressions or Vrttis viz. इत, तद्धित, समास, एकशेष, and सनादिघातु.

चङ्गुदास or चाङ्गुदास a scholar of grammar who has written an independent work on Sanskrit Vyākaraņa called वैयाकरणजीवातु. The treatise is also known as चाङ्गुसूत्र or चाङ्गु-ब्याकरण.

चण् the indeclinable च (with ण् as a mute letter added to it which of course disappears) possessing the sense of चत् or condition. e. g. अयं च मरिष्यति cf. Kāś. on P. VIII. 1.30.

चणप् tad. affix चण in the sense of वित्त (known by) applied to a word which refers to that thing by which a person is known. e. g. विद्याचणः, कशचणः; cf. P. V. 2.26.

चण्डपाण्डित writer of a Prākṛta grammar. He was known also as चन्द्र and hence identified by some with Candragomin.

ৰব্ৰথ a term used by ancient grammarians for the fourth consonants which are sonant aspirates, termed ক্ষম by Pāṇini; cf. R. Pr. IV. 2. T. Pr. I. 18, V. Pr. 154. R. T. 176.

चतुर्थी a term used by ancient grammarians for the dative case; cf. उतो त्वस्मै तन्वं विससे इति चतुर्थ्याम्; Nir. I. 9.3.

चतुर्थीसमास the tatpurusa compound with the first word in the dative case in its dissolution; cf. चतुर्थीसमासे सित पूर्वपद्भक्षतिस्वरत्वेन भवितन्यम् M. Bh. on II. 1.36.

चतुर्मात्र consisting of four mātrās or moras, a short vowel consisting of one mātrā, a long vowel of two mātrās, and a protracted vowel of three mātrās; cf. आन्तर्यतस्त्रिमात्र-चतुर्मात्राणां स्थानिनां त्रिमात्रचतुर्मात्रा आदेशा मा भूवितिति। M. Bh. on Siva sūtra 3.4.

grammarian whose grammar existing in the Tibetan script, is now available in the Devanagari script. The work consists of six chapters or Adhyayas in which no technical terms or satisfias like

दि, बु are found. There is no section on Vedic Grammar and accents. The work is based on Pāṇini's grammar and is believed to have been written by Candra or Candragomin in the 5th century A. D. Bhartrhari in his Vākyapadīya refers to him; cf. स नीता बहुशाखत्वं चन्द्राचार्यादिभिः पुनः Vākyapadīya II. 489. A summary of the work is found in the Agnipurāṇa, ch. 248-258.

মানুহার called also কলা, a well-known commentary on Nāgeśa's Laghuśabdenduśekhara by Bhairavamiśra who lived in the latter half of the 18th century and the first half of the nineteenth century.

चन्द्रकीर्ति a Jain grammarian of the twelfth century A.D. who has written a commentary named Subodhinī on the Sārasvata Vyākaraṇa.

चन्द्रगोमिन named also चन्द्र, a Buddhist scholar who has written an easy Sanskrit Grammar based on the Asṭādhyāyī of Pāṇini. He is believed to have lived in North India in the fifth century A.D. See चन्द्र.

चन्द्राचार्य a grammarian mentioned by Bhartrhari in his Väkyapadīya as one who took a leading part in restoring the traditional explanation of Pāṇini's Vyākaraṇa which, by the spread of rival easy treatises on grammar, had become almost lost; cf. यः पतञ्जलिशिष्यम्या भृष्टी व्याकरणागमः । काले स दाक्षिणात्येषु प्रन्थमात्रे व्याकरणागमः । काले स दाक्षिणात्येषु प्रन्थमात्रे व्याक्ष्याः ॥ पर्वतादागमं लब्धा भाष्यवीजानुसारिभः । स नीता बहुशाख्यः चन्द्राचार्यादिभिः पुनः ॥ Vākyapadīya II. 488-489. See चन्द्र and चन्द्रगोमिन.

चय् a short term (Pratyāhāra) for the first letters (क्, च्, ट्त, and प्) of the five classes. Sometimes as opined by पौष्करसादि, second letters are substituted for these if a sibilant follows them, e.g. अभ्सराः, वश्सरः । cf. चयो द्वितीयाः द्यारे पौष्करसादे रिति वाच्यम् cf. S.K. on ङ्णोः कुक्टुक् शरि P. VIII.3.28.

चर् a short term (Pratyāhāra) for the hard unaspirated surds and इ, ब्, स्. The change of the second, third and fourth letters into the first is called चर्नी; cf. अभ्यासे चर्च । खरि च। वावसाने । Pān. VIII.4.54-56.

चरद् tad. affix चर in the sense of 'being (so and so) in the past'. e.g. आड्यचर:, fem. आड्यचरी; cf. भूतपूर्वे चरद् P.V.3.53.

बरण explained as a synonym of the word যানো which means a branch or a school of Vedic Learning; cf. चरा- হাল্বা: कठकलापादय: Kāś. on P.IV.?.46.

चरिताकेय having kriyā or activity hidden in it. The term is used by Bhartrhari in connection with a solitary noun-word or a substantive having the force of a sentence, and hence which can be termed a sentence on account of the verbal activity dormant in it. e.g. पिण्डीम्; c. वाक्यं तदपि मन्यन्ते यत्पदं चरितिकियम् Vākyapad.II. 326, and चरिता गर्भीकृता आख्याताक्रिया यस्य तद्गर्भीकृताकि-यापदं नामपदं वाक्यं प्रयुक्तते। Com. on Vākyapadīya II.326.

बरितार्थे which has got already a scope of application; the term is used by commentators in connection with a rule or a word forming a part of a rule which applies in the case of some instances and hence which cannot be said to be ज्यर्थ (superfluous) or without any utility and as a result cannot be said to be capable of allowing some conclusion to be drawn from it according to the dictum ज्यर्थ सन्ज्ञापयति।

cf. अपवादो यद्यन्यत्र चरितार्थस्तर्द्धन्तरङ्गेण बाध्यते Par. Sek. Pari. 65.

चकरोत a term used by the ancient grammarians in connection with a secondary root in the sense of frequency; the term यङ्ख्यान्त is used by comparatively modern grammarians in the same sense. The বর্ম-रीत roots are treated as roots of the adadi class or second conjugation and hence the general Vikarana अ (হাব) is omitted after them. The word is based on the 3rd pers. sing form चकरोति from the root क in the sense of frequency; e.g. चर्करीति, चर्कति; बाभवीति बाभोति; cf. चर्क-रीतंच a gana-sutra in the named 'adādi' given by Pāṇini in connection with अदिप्रभृतिभ्यः Pān. II.4.72; cf. also चर्करीतमिति यङ्कुक: प्रान्तां संज्ञा Bhasa Vr. on P. II. 4.72. The word चेकीयित is similarly used for the frequentative when the sign of the frequentative viz. य (यङ्) is not elided. See चेक्रीयित.

चर्करीतवृत्त a form of the frequentative or intensive. e.g. आपनीपणत्, चोष्क्यमाणः। cf. आपनीपणदिति पणतेश्चर्करी-तवृत्तम्। Nir. II. 28; चोष्क्यमाण इति चेष्क्यतेश्चर्करीतवृत्तम् Nir.VI.22. See the word चर्करीत.

चर्चा (1) splitting up of a word into its component parts, which is generally shown in the Padapītha by अवग्रह (s). The word, hence means पदपाठ or recital by showing separately the constitutent words of the Samhitā or the running text of the Veda. The word is used almost in the same sense in the Mahābhāṣya in respect of showing the words of a sūtra separately; cf. न केवलान चर्चापदानि व्याख्यानं शुद्धिः आत् ऐजिति। किं तर्हि। उदाहरणं प्रस्पुदाहरणं वाक्याध्याहारः इस्थितसमुदितं व्याख्यानं भवति M.Bh. on Māhesvara Sūtra 1 Vārt. 61; (2) a

repeated word; cf. इतिकरणात् पुरतो यत् पुनः पदवचनं तत् चर्चाशब्देनोच्यते. Uvvata on V. Pr. III.20; (3) a discussion or a debate where consideration is given to each single word; cf. प्यायशब्दानां लाघवगौरवचची नाद्रियते Par. Sek. Pari. 115.

चर्चागण repetition of a word in the पदपाठ, ऋमपाठ, जटापाठ etc. where the several Pathas appear to be called चर्चा.In the परपाठ a word in a compound is repeated twice, in the क्रमपाठ every word is repeated twice, in the जटापाट, six times.

चचापद component words of a running text or of a compound word.

चत्वे substitution of a hard consonant or হা, ুর, ল, for soft consonants and aspirates. See the word चर्.

चर्मशिरस् name of a Nirukta writer quoted by Yāska; cf. Nir.III.15.

चवगे the group of consonants of the palatal class, viz. च, হু, ज, झ and স্. The word a is used in the same sense in the Prātiśākhya works. See the word 7.

चाक्रवर्मण an ancient grammarian whose view is quoted by Pāṇini in his Sūtra ई 3 चाकवर्मणस्य P.VI.1.130.

चाङ्गुदास the same as चङ्ग or चाङ्ग or चङ्गुदास, a grammarian who composed a compendium on grammar called वैयाकरणजीवातु and also a commentary on it.

चाङ्गुसूत्र a treatise on the grammar written by चाडगुदास in the Sütra form, which was named वैयाकरणजीवात by him.

चाङ्गुक्याकरण the same as चाङ्गस्त्र.

चातुःस्वाये the view that there are four accents-the udatta, the anudatta, the svarita and pracaya-held by the Khandikiya and the Aukhīya Schools.

four senses तदस्मिन्नस्ति, तेन निर्वृत्तम्, तस्य निवासः and अद्रभवः mentioned by Pāṇini in IV.2.67-70; cf.अपत्यादि-भ्यश्चात्ररर्थपर्यन्तेभ्यः येन्येर्थाः स शेवः M.Bh. on IV.2.92.

चातर्थिक the affixes prescribed in the four senses mentioned in P. IV.2.67-70. These taddhita affixes are given in the Sūtras IV.2.71 to IV.2.91. The term चातुर्रार्थिक used for these affixes by commentators on Pāņini sūtras.

चात्रवंण्योदि words mentioned in the class headed by चातुर्वेण्य where the tad. affix অস্ is applied although the words चतुर्वेण, चतुर्वेद and others are not गुणवचन words to which চ্যস্ is regularly applied by P. V.1.124. cf. ब्राह्मणादिषु चातुर्वर्ण्यादीनामुप-संख्यानम् P. V.1. 124 Vārt. 1.

चादि a class of words headed by च which are termed निपात by Panini e.g. च, वा, ह, एवम् नूनम्, चेत्, माङ् etc.; cf. चादयोऽसत्वे. P. I.4.57. For the meaning of the word असस्य see p.370 Vyākaraņamahābhāṣya. Vol. VII. published by the D. E. Society, Poona.

चानश kit affix आन applied to a root, to signify habit, age or strength; e. g. आत्मानं भूषयमाणाः । कवन्त्रं विभ्राणाः । যাসুন্নিদানা:। cf. P. III. 2. 129.

चान्द्र name of a treatise on grammar written by Candra, who is believed to have been the same as Candragomin. The Grammar is based upon that of Panini, but it does not treat Vedic forms and accents. See the word चन्द्र above. For details see pp. 375- 376 Patanjali Mahābhāsya. Vol. VII, D. E. Society's Edition.

चान्द्रव्याकरणपद्धति name of a commentary on the चान्द्रव्याकरण written by आनन्ददत्त.

चातुरथे a tad. affix prescribed in the | चाप् the fem. affix आ, applied to

words ending in the tad. affixes ज्यङ् and ष्यङ्; e. g. कौसल्या, वाराह्या, गौकक्ष्या; cf. Kāś. on P. IV. 1. 74.

चारायण an ancient grammarian referred to by Patañjali in the Mahābhāṣya as a scholar who had a line of pupils named after him; cf. कम्बलचारायणीयाः M. Bh. on P. I. 1.73.

चारितार्थ्य fulfilment of the object or the purpose. The word is used in connection with a rule of grammar. See चरितार्थ.

चार्थ the meaning of the indeclinable च to convey which, as existing in different individuals, the dvandva compound is prescribed. Out of the four senses possessed by the indeclinable च, the Dvandva compound is prescribed in two senses viz. इतरेतरयोग and समाहार out of the four समुख्य, अन्वाचय, इतरेतरयोग and समाहार; cf. क: पुनश्चेन इतोर्थ: । समुख्योन्वाचय इतरेतरयोगः समाहार इति M. Bh. on P. II.2.29; cf. also Cāndra Vyākaraņa II.2.48.

चालु tad. affix (आलु) applied to the word हृदय, in the sense of possession, optionally along with the affixes बत् इन and इन. e. g. हृदयालु:, हृदयबान, हृदयी and हृदयिक:; cf. Kāś. on V.2. 122.

चिकीर्षित desiderative formation; a term used by ancient grammarians for the term सन्नत्त of Pāṇini on the analogy of the terms भवन्ती, वर्तमाना etc. cf. आ इत्याकार उपसर्गः पुरस्तात, चिका- र्षितज उत्तरः, आग्रु शोचयतीति आग्रुगुक्षणिः Nir. VI. 1.

चिकीषिंतज in the sense of the desiderative; cf. चिकीर्षितादथीण्जातः सत्रन्तादित्यर्थै: Durgācārya on Nir. VI.1.

विच्चिन्द्रका name of a commentary on the Paribhāṣenduśekhara writren by Vishnu Shastri Bhat, in reply to the treatise named বুলকবৌ-ক্লব. See বিচ্ছায়ান্তিন. For details see pp. 39, 40 of Vyākaraņa Mahābhāṣya Vol. VII. published by the D.E. Society, Poona.

चिए substitute इ causing vrddhi, in the place of the aorist vikaraṇa affix चित्र, prescribed in the case of all roots in the passive voice and in the case of the roots पद, दीप, जन् etc. in the active voice before the affix त of the third pers. sing. in the Atmanepada, which in its turn is elided by P. VI. 4. 104. cf. P. III. 1,60-66.

चিत् affixes or substitutes or bases marked with the mute letter হ signifying the acute accent for the last vowel; e. g. অথুহ, ধ্ৰুংহু, ক্যুডিনহু etc. cf. P. VI. 1. 163, 164.

चित्करण marking with the mute letter च, signifying the acute accent of the last vowel; cf. चापि चित्करणसाम-र्थ्यादन्तोदात्तत्वं भविष्यति; M. Bh. on P. III, 1.3 Vārt. 16.

चित्प्रभा name of a commentary on the Paribhāṣenduśekhara by ब्रह्मानन्दसरस्वती.

चिद्स्थिमाळा name of a commentary on the Laghuśabdenduśekhara by Vaidyanātha Pāyaguṇḍe,one of the distinguished disciples of Nāgeśabhatta.

चिद्र्पाश्रय named also चिद्र्पाश्रम who wrote a learned commentary named विषमी on the Paribhāṣenduśekhara of Nāgeśabhaṭṭa

चिन्ता (1) view; theory. e.g. बाध्यसामान्य-चिन्ता, बाध्यविदेशिचन्ता cf. इयमेव बाध्य-सामान्यचिन्तेति व्यवाह्थ्यते Par. Sek. Pari. 58; (2) a matter of scrutiny on a suspicion; cf. चिन्ता च—मयतिरिदन्य-तरस्याम् इत्यतोन्यतरस्यांप्रहणस्य सिंहावलोकन-न्यायादनुवृत्ते; Durghaṭa Vṛ. on VI.4.69.

ren by Vishnu Shastri Bhat, in चिन्तामणि name of a commentary

on the Sūtras of the Śākaṭāyana Vyākaraṇa written by यक्षवर्मन्. It is also called लघुत्रति.

चिन्तामणिप्रकाशिका a commentary on the चिन्तामणि of यक्षवर्मन, written by अजितसेन in the twelfth century. See चिन्तामणि

चिन्त्य questionable; contestable; which cannot be easily admitted. The word is used in connection with a statement made by a sound scholar which cannot be easily brushed aside; cf. एतेन यत्केयटे केचि-दित्यादिना अस्यैव वाग्रहणस्य , तदीनत्यत्वज्ञाप-कतोक्ता सापि चिन्त्या. Par. Sekh. Pari. 93. 5.

चु the group of palatal consonants viv. च, छ, ज, झ and ज; cf. चुटू P. I. 3. 7, चो: कु: VIII. 2. 30, कुहोश्च: VII. 4 62.

चुञ्चुप् tad. affix चुञ्च applied to a word in the sense of 'well-known by '; e. g. विद्याचुञ्च:; cs. P. V. 2. 26.

चुरादि a class or group of roots headed by the root चुर्, familiarly known as the tenth conjugation.

चुिक्षभिष्टि a grammarian who is supposed to have written a gloss (वृत्ति) on the Sutras of Pāṇini; cf. तत्र च वृत्तिः पाणिनिप्रणीतानां स्त्राणां विवरणं चुव्हिमहिन्द्सरादि (V. 1. निर्देशादि) विरचितम्, Nyāsa, on the benedictory verse of Kāśikā: वृत्तौ भाष्ये तथा घातुनामपारायणा-दिषु at the very beginning.

খুর্ণি a gloss on the Sūtras of Pāṇini referred to by Itsing and Śrīpatidatta. Some scholars believe that Pataĥjali's Mahābhāṣya is referred to here by the word খুলি, as it fully discusses all the knotty points. Others believe that খুলি, stands for the Vṛtti of লুপ্তিমাই. In Jain Religious Literature there are some brief comments on the Sūtras which are called খুলি and there possibly

was a similar चूर्णि on the sūtras of Pāṇini.

चेकीयित the sign य (यङ् of Pāṇini) of the frequentative or intensive. The word is mostly used in the Kātantra Grammar works: **धातोर्यशब्दश्चेक्रीयतं** कियासमभिहारे, III. 2. 14. The word चेक्रीयित is used in the Mahābhāsya in the sense of यङन्त where Kaiyata remarks यङ: पूर्वाचार्यसंज्ञा चेक्रीयितमिति cf. प्रदीप on M.Bh. on P. IV.1.78 Vartika. The word चेक्रीयितान्त means यङन्त in Pāṇini's terminology meaning a secondary root derived from the primary root in the sense of intensity. The word चर्करीतान्त is used for the frequentative bases in which य, the sign of the frequentative, is omitted. See चर्करीत.

चेन्द्र tad. affix एलु applied to the word हिम in the sense of 'unable to bear' e. g. हिमेलु:, cf. P. V. 2. 122 Vart. 7.

चोक्सनाथ a southern grammarian of the seventeenth century who has composed in 430 stanzas a short list of the important roots with their meaning. The work is called धातुरनावली.

चोदक (1) an objector; the word is common in the Commentary Literature where likely objections to a particular statement are raised, without specific reference to any individual objector, and replies are given, simply with a view to making matters clear; (2) repetition of a word with इति interposed; cf. चोदक: परिग्रह: इत्यनथीन्तरम्. See अष्टष्टवर्ण and परिग्रह.

चोरद् the crude form of the word चार with the mute consonant ट् added to signify the addition of हीए to form the feminine base e.g. चोरी; cf. P. IV. 1.15. चौरादिक a root belonging to the tenth conjugation of roots (चुरादिगण); cf. आम: इति चौरादिकस्य णिचि बृद्धौ सत्यां भवति। Kāś. on P. VII. 3. 34.

च्छ the consonant छ with च prfiexed, for which श is substituted by च्छ्ठी: शुडनुनासिके च P. VI. 4. 19.

হদ্ধন্ tad. affix আয়ন causing a viddhi substitute for the first vowel of the word to which it is added. The affix (হুদ্ৰু) is added in the sense of 'a descendant except the direct son or daughter' to words কুত্ৰ and others; cf. P. IV. 1. 98.

चिल the sign of the aorist (छुङ्) for which generally सिच् and अङ्, क्स, चङ् and चिण् are substituted in specified cases; cf. P. III. 1. 43-66.

चि tad. affix (of which nothing remains) to signify the taking place of something which was not so before; after the word ending in चि the forms of the root क, भू or अस् have to be placed; e.g. ग्रुह्मी-करोति; cf. P. V. 4. 50

च्यर्थ possessing the sense of चित्र. See चित्र cf. P. III. 2. 56 also P. III. 3. 127 Vart. 1.

Ø

च्यू the second consonant of the palatal class of consonants (चवर्ग), which is possessed of the properties श्वास, अधाष, महाप्राण and कण्डविद्यतकारित्व. छू, placed at the beginning of affixes, is mute; while ई्य is substituted for छ standing at the beginning of taddhita affixes; cf. P. I. 3.7 and VII. 1.2. छ at the end of roots has got ष substituted for it; cf. P. VIII. 2.36.

छ tad. affix ईय, added (1) to the words स्वस्, भ्रातृ and to words ending with the tad. affix फिन्; cf. P.

IV. 1.143,144 and 149; (2) to the dvandva compound of words meaning constellations, to the words अपानम्, अपानप्तृ, महेन्द्र, द्यावापृथिवी, शुनासीर etc. as also to शर्करा, उत्कर, नड etc. in certain specified senses, cf. P. IV. 2.6, 28, 29, 32, 48, 84, 90 & 91;(3) to words beginning with the vowel called Vrddhi (আ, ট or औ), to words ending with गर्त, to words of the गह class, and to युष्मद् and अस्मद् in the शैषिक senses, cf. P. IV. 3.114, 137-45 and IV. 3.1; (4) to the words जिह्नामुल, अङ्गुलि, as also to words ending in वर्ग in the sense of 'present there'; cf. P.IV.3.62-64; (5) to the words शिशुकन्द, यमसभ, dvandva compounds, इन्द्रजनन and others in the sense of 'a book composed in respect of', cf. P.IV. 3.88; (6) to words meaning warrior tribes, to words रैवतिक etc., as also आयुध, and अप्र, in some specified senses; cf. P.IV. 3.91, 131, IV. 4.14, 117; (7) to all words barring those given as exceptions in the general senses mentioned in the sec. V.I.1-37; (8) to the words মুন্ন, कडड्कर, दक्षिण, words ending in वत्सर, अनुप्रवचन etc. होत्रा, अभ्यमित्र and कुशाग्र in specified senses; cf. P. V. 1. 40, 69,70,91,92, 111,112,135, V. 2.17, V.3.105; (9) to compound words in the sense of इव; e.g. काकतालीयम्, अजानृ,पाणीयम् etc. cf. V. 3. 106;and (10) to words ending in জানি and स्थान in specified senses; cf. P. V.4, 9,10.

ন্তকাৰ the letter ভ, the word কাৰ being looked upon as an affix added to the consonant ভ which, by the addition of ভা, is made a complete syllable; cf. T. Pr. I. 16, 21.

छण् tad. affix ईय causing the vṛddhi substitute for the first vowel of the word to which it is added. छण् is added (1) to the words पितृष्वस् and

मातृष्वस् in the sense of अपरय; cf. P· IV. 1.132, 134; (2) to the words कृशाक्ष, अरिष्ठ and others as a चातुर्थिक affix; cf. P. IV. 2.80; (3) to the words तिचिर, वरतन्त, खण्डिक and उख in the sense of 'instructed by', cf. P.IV.3.102; and (4) to the word शलातुर in the sense of 'being a national of' or 'having as a domicile.' e. g. शालातुरीय:; cf. P. IV. 3.94.

छन्दस् (1) Vedic Literature in general as found in the rule बहुँछ छन्दसि which has occurred several times in the Sūtrās of Paṇini, cf. छन्दो- वस्त्रज्ञाणि भवन्ति M. Bh. on I.1.1, and I.4.3; cf. also V. Pr. I.1, 4; (2) Vedic Saṃhitā texts as contrasted with the Brāhmaṇa texts; cf. छन्दो- ब्राह्मणानि च तिह्मयाणि P. IV.2.66; (3) metre, metrical portion of the Veda.

छन्दोभाषा Vedic language as contrasted with भाषा (ordinary language in use); cf. गुरुत्वं लघुता साम्यं ह्रस्वदीर्घष्टुतानि च...एतत्सर्व तु विश्वयं छन्दोभाषां विजानता T. Pr. XXIV. 5.

ভদাব a popular name given by grammarians to the first pāda of the fifth Adhyāya of Paṇini's Aṣṭādhyāyī as the pāda begins with the rule সাক্ কীবাল্ড: P. V. 1.1.

छच् a short term or Pratyāhāra standing for হা, হা, মৃ, হু and বা; cf. নুংহু ব্যান্ P. VIII.3.7.

छस् tad. affix इंच added to the word भवत् in the general है। जिस्स senses, e. g. भवदीय:; cf. P. IV.2.115. The mute letter स has been attached to the affix छस् so that the base भवत् before it could be termed pada (cf. सिति च P. I.4.16) and as a result have the consonant त changed into इ by P. VIII.2.39.

छान्द्स found in the Vedic Literature; Vedic; cf. छान्दसा अपि कचिद् भाषायां प्रयुज्यन्ते Bhāṣāvṛtti on P. IV. 4.143; cf. also छान्दसमेतत् । दृष्टानुविधिश्च च्छन्दिस भवति; M. Bh. on I.1.5.

हाया a learned commentary on Nāgeśa's Mahābhāṣyapradīpoddyota written by his pupil बाळभट्ट (possibly the same as, or the son of, वैद्यनाथ पायगुण्डे) who lived in the eighteenth century.

হুক্ত ক্রমন্থ a grammarian who wrote a short gloss called কান-সভ্যুথূানি on the Kātantrasūtras.

ज

ज् third consonant of the palatal class of consonants, possessed of the properties नाद, घोष, अल्पप्राण and कण्ट- संवृत्तकारित्व. ज् at the beginning of affixes is mute in Panini's grammar.

ন the consonant ন with প added to it for facility of pronunciation; cf. T. Pr. I..21. See ন.

जगद्धर a poet and grammarian of Kasmīra of the fourteenth century who wrote a commentary named बालवेशियों on the Katantra Sūtras.

जगन्नाथ (1) the well-known poet and scholar of Vyākaraņa and Alamkāra who wrote many excellent poetical works. He lived in the sixteenth century. He was a pupil of कृष्णशेष and he severely criticised the views of Appaya Diksita and Bhattoji Diksita. He wrote a sort of refutation of Bhattoji's commentary Praudha-Manoramā on the Siddhanta Kaumudi, which he named प्रांढमनारमाखण्डन but which is popularly termed मनोरमाजनमदेन. His famous work is the Rasaganga-Alankārašāstra; dhara on writer of a commentary on the Rk-Prātiśākhya by name Varnakramalaksaņā; (3) writer of Sārapradīpikā, a commentary on the Sārasvata Vyākaraņa.

जटा a kind of Vedic recital wherein each word is repeated six times. जटा is called one of the 8 kinds (अष्टिकृति) of the Kramapāṭha, which in its turn is based on the Padapāṭha; cf. जटा माला शिखा रेखा ध्वजो दण्डो रथा घनः। अष्टो विकृतयः प्रोक्ताः क्रमपूर्वा मनीषिभिः। जटा is defined as अनुलोमविलोमाभ्यां त्रिवारं हि पठेत् क्रमम्। विलोमे पदवत्संधिः अनुलोम यथाक्रमम्। The recital of ओषधयः संवदन्ते सोमेन can be illustrated as ओषधयः सं, समोषधयः, ओषधयः सं, सं वदन्ते, वदन्ते सोमेन। सोमेन वदन्ते, वदन्ते सोमेन।

जयकृष्ण a famous grammarian of the Mauni family who lived in Vārānasī in the seventeenth century. He wrote विभक्त्यर्थनिर्णय, स्फोटचन्द्रिका, a commentary on the Siddhāntakaumudī called मुनोधिनी and a commentary on the Madhya Kaumudī named विलास. He wrote a commentary on the Laghukaumudī also.

जयदेव a grammarian, (of course different from the well-known poet), to whom a small treatise on grammar by name इष्टतन्त्रव्याकरण is attributed.

जयन्त (1) author of तत्त्वचन्द्र a commentary on पाणिनिस्त्रञ्जति written by Vitthala; (2) writer of a commentary named Vādighaṭamudgara on the Sārasvataprakriyā.

जयरामभद्दाचार्य a famous Bengalee scholar of Vyākaraņa and Nyāya who has written a small treatise dealing with syntax. The treatise is named कारकवाद.

जयादित्य one of the famous joint authors (जयादित्य and वामन) of the well-known gloss (वृत्ति) on the Sutras of Pāṇini, popularly called काशिकावृत्ति. As the काशिकावृत्ति is mentioned by It-sing, who has also mentioned Bharthari's Vākya-

padīya, as a grammar treatise written some 40 years before his visit, the time of काशिकाञ्चि is fixed as the middle of the 7th century A.D. Some scholars believe that जयादित्य was the same as जयापिड a king of Kaśmīra and वामन was his minister. For details, see pp. 386—388 of the Vyākaraņa Mahābhāṣya Vol. VII published by the D.E. Society, Poona. See काशिका.

जयानन्द a Jain grammarian of the fourteenth century who wrote a commentary named তত্ত্বাৰ on the ভিন্নান্ত্ৰাৰ of Hemacandra.

जञ् a short term (प्रत्याहार) signifying the soft inaspirate class consonants ज्, ब्, ग्, ड् and द्.

সহবৈ substitution of a জহা consonant prescribed by Pāṇini for any consonant excepting a semi-vowel or a nasal, if followed by any fourth or third consonant out of the class consonants, or if it is at the end of a pāda; cf. P.VIII. 2.39, VIII.4. 53.

जহ**भाव** the same as জহল, which see above.

जस् case termination अस् of the nom. plural; cf.P. IV. 1.2.

जासे case termination अस् of the nom. plural mentioned as जस् by Pāṇini in IV. 1.2, but referred to as जिस by him; cf. P.IV.1.31 and VII.1.50.

जहत्स्वार्था (वृत्ति) a composite expression where the constituent members give up their individual sense. In compound words such as राजपुरुष in the sentence राजपुरुषमान्त्रय the word राजन् gives up its sense inasmuch as he, the king, is not brought; पुरुष also gives up its sense as every man is not brought. It is of course to be noted that although the sense is

given up by each word, it is not completely given up; cf. जहदप्यसा स्वार्थ नात्यन्ताय जहाति; M. Bh. on P. II. 1.1. Vārt. 2. For detailed explanation see Mahābhāṣya on P. II. 1.1. Vārt. 2.

जहस्रमेत्व abandonment or giving up of properties in the case of a word included in a द्वति or composite expression; cf. जहस्रमेत्वाच्छब्दप्रवृत्तेः Durghața Vitti on P. II. 2.6.

जाप्रहीतेतिवाद a short disguisition on the correctness of the word जाप्रहीता, written by a grammarian named Cakrin; cf. भट्टोजिदीक्षितप्राहप्रस्तं माधव-दिग्गजम्। अमूमुचत् सत्यवर्यश्चकी चित्रप्रसादभाक्, colophon.

জান born or produced there or then; one of the senses in which the tad. affixes, called জানাৰ্থক, are prescribed by Pāṇini in the sūtra নুস জান: and the following; cf. P. IV. 3.25-37.

जातबहिरङ्गासिद्धत्व invalidity of a Bahiranga operation that has already taken place by virtue of the Antaranga-paribhāṣā—असिद्धं बहिरङ्गमन्तरङ्गे— that which is 'bahiranga' is regarded as not having taken effect when that which is 'antaranga' is to take effect. For details see Par. Śek. Paribhāṣā 50.

जाताभीयासिद्धत्व invalidity of a grammatical operation prescribed by a rule in the आभीय section (P. VI. 4. 22 upto the end of the fourth pada) which, although it has taken place, is to be looked upon as not having taken place when any other operation in the same section is to take effect. See आभीयासिद्ध.

of generality which is present in the several individual objects of the same kind. The biggest or widest notion of the universal or genus is

सत्ता which, according to the grammarians, exists in every object or substance, and hence, it is the denotation or denoted sense of every substantive or Prātipadika, although on many an occasion vyakti or an individual object is required for daily affairs and is actually referred to in ordinary Inthe Mahābhāsya a learned discussion is held regarding whether जाति is the denotation or ब्यक्ति is the denotation. word जाति is defined in the Mahābhāṣya as follows:— आकृतिप्रहणा जातिलिङ्गानां चन सर्वभाकः । सकुदारयातनि-गोंह्या गोत्रं च चरणैः सह ॥ अपर आह । पादुभीवविनाशाभ्यां सत्त्वस्य युगपद्गुणैः । असर्वे-लिङ्गां बह्वयो तां जातिं कवया विद: M. Bh. on IV. 1.63. For details see Bhartrhari's Vākyapadīya.

জানিম্থ the view that জানি, or genus only, is the denotation of every word. The view was first advocated by Vājapyāyana which was later on held by many, the Mīmāmisakas being the chief supporters of the view. See Mahābhāṣya on P. I. 2.64. See Par. Śek. Pari. 40.

जातिपदार्थवाद see जातिपक्ष.

जातिस्वर the acute accent for the last vowel of a word ending with क्त of the p.p.p. denoting a genus; cf. P. VI. 2.170.

जातीयर् tad. affix जातीय in the sense of प्रकार or variety; e. g. पटुजातीय:, मृदुजातीय:; cf. Kāś. on P. V. 3.69. Originally जातीय was possibly an independent word, but as its use, especially as a noun, was found restricted, it came to be looked upon as an affix on the analogy of the affixes कल्प, देश्य, देशीय and others.

जात्य name of a variety of the Sva-

rita or circumflex accent; the original svarita accent as contrasted with the svarita for the grave which follows upon an acute as prescribed by P. in VIII. 4.67, and which is found in the words इन्द्र:, होता etc. The jātya svarita is noticed in the words स्व:, क, न्यक्, कन्या etc.; cf. उदात्तपूर्व स्वरितमनुदात्तं पंदेसरम् । अतान्यत् स्वरित स्वारं जात्यमाचक्षते पदे ॥ जात्या स्वभावेनैव उदात्तानुदात्तरांगितं विना जातो जात्यः । तं जात्यमाचक्षते ब्याडिप्रभृतयः R. Pr. and com. III. 4.

जामि tautologous, unnecessarily repeated; the word is defined and illustrated by Yāska as;-तद्यत्समान्यामृचि समानाभिन्याहारं भवति तज्जामि भवतीत्येकं मधुमन्तं मधुश्रुतमिति यथा Nir.X.16.2. For other definitions of the word जामि conveying practically the same idea, cf. Nir.X.16.3 and 4.

जाहच् tad. affix added in the sense of 'a root' to the words कर्ण. अक्षि, नख, मुख and others; e.g. कर्णजाहम् cf. P. V.2.24.

जि a conventional term for संप्रसारण used in the Jainendra Vyākaraṇa

जित् (1) lit. affix marked with the mute letter ज़; e. g. जस्, जिस, ज़ुसू. the word जित् is not however found used in this sense; (2) a word supposed to be marked with the mute indicatory letter s.The word is used in this sense by the Varttikakāra saying that such a word does not denote itself but its synonyms; cf. जित् पर्यायवचनस्यैव राजाद्यर्थम् P.I.1.68 Vart. 7. In the Sutra सभा राजामनुष्यपूर्वा P.II. 4. 23, the word राजन् is supposed to be जित् and hence it denotes इन, ईश्वर etc.; but not the word राजन् itself; (3) In the Pratisakhya works जित् means the first two consonants of each class (বর্ग); e.g. ক্, জু, ভু, স্থু. etc. which are terminology; cf. द्वौ द्वौ प्रथमो जित्. V· Pr.I.50;III.13.

নিবৰক author of the Siddhantaratna, a commentary on the Sarasvata Sūtras.

जिनेन्द्रबुद्धि a reputed Buddhist Grammarian of the eighth century who wrote a scholarly commentary on the Kāśikāvṛtti of Jayāditya and Vāmana. The commentary is called न्यास or काशिकाविवरणपञ्जिका and the writer is referred to as न्यासकार in many later grammar works. Some scholars identify him with पूज्यपाददेवनिन्दिन् the writer of the जैनेन्द्र- ब्याकरण, but this is not possible as पूज्यपाददेवनिन्दिन् was a Jain Grammarian who flourished much earlier.

जिन्निर्देश mention as जित; cf. जिन्निर्देश: कर्तव्य: M.Bh. on I.1.68 Vart. 7. See जित.

जिह्ना used in the sense of जिह्नाम, the tip of the tongue.

जिहामूलस्थान (1) having the root of the tongue as the place of its production; the phonetic element or letter called जिह्वामूलीय; (2) name given to that phonetic element into which a visarga is changed when followed by क् or ख़; cf × क इति जिह्वामूलीयः V.Pr.VIII.19. The जिह्वामूलीय letter is called जिह्वय also; see Nyasa on I. 1.9. The Rk. Pratisakhya looks upon क, ल, जिह्वामूलीय, and the guttural letters as जिह्वामूलस्थान.

जिह्नामूळीय produced at the root of the tongue; the same as जिह्नामूलस्थान, which see above.

স্ত্ৰ augment অ্ added to the root আ before the causal sign দিল্ when the root means shaking;cf. বা বিঘূনন লুক্ P. VII. 3.38.

Pratiśākhya works জিন্ means the first two consonants of each class (বৰ্ণ); e.g. ক্, ভ্, ভ্, ভ্, ভং etc. which are the same as অৰ্ letters in Pāṇini's

रसवती on it, which were composed by क्रमदीश्वर in the thirteenth century. The work of जुमरनन्दिन is known as जीमारव्याकरण.

जुस verbal termination उस् substituted for the original झि of the third pers. pl. in certain cases mentioned in P.III. 4.108, 109, 110, 111, and 112.

जुस्भाव the transformation of झि into जुस; the substitution of जुस for झि. The term is often used in the Mahābhāṣya; cf. M. Bh. on I. 1.57, I.1.63, III.1.43 etc. See जुस.

जुहोत्यादिगण the class of roots headed by हु after which the vikarana sap is saided and the root is reduplicated in the four conjugational tenses; third conjugation of roots.

जैनेन्द्रव्याकरण name of a grammar work written by Pūjyapāda Devanandin, also called Siddhanandin, in the fifth century A.D. grammar is based on the Astadhyāyī of Pānini, the section on Vedic accent and the rules of Panini explaining Vedic forms being, of course, neglected. The grammar is called Jainendra Vyākarana or Jainendra Sabdānusāsana. The work is available in two versions, one consisting of 3000 sūtras and the other of 3700 sūtras. It has got many commentaries, of which the Mahavrtti written by Abhayanandin is the principal one. For details Jainendra Vyākaraņa, introduction published by the Bharatiya Jñanapītha Vārāņasī.

जैनेन्द्रव्याकरणमहानृत्ति name of a commentary on the Jainendra Vyākaraņa, written by Abhayanandin in the ninth century A. D. see जैनेन्द्रव्याकरण above.

जोमार (ट्याकरण) a treatise on Vyākaraṇa written by Jumaranandin. See ज्ञमरनन्दिन above. The Jaumāra Vyākaraņa has no Vedic section dealing with Vedic forms or accents, but it has added a section on Prākņita just as the Haima Vyākaraņa.

जौमारपरिशिष्ट a supplement to the Jaumara Vyakaraņa written by Goyicandra. See गोयीचन्द्र.

जीमार संस्करण the revised version by Jumūranandin of the original grammar treatise in verse called संक्षितसार written by Kramadīsvara. The Jaumārasamskaraņa is the same as Jaumāra Vyākaraņa, which see above.

जौहोत्यादिक a root belonging to the जुहोत्यादिगण or the third conjugation.

ज्ञानदीपिका name of a commentary on Amarasiinhā's Amarakosa written by Śrīpati (Chakravartin) in the 14th century.

ল্পাম lit. indirect or implicit revealer; a word very commonly used in the sense of an indicatory statement. The Sūtras, especially those of Pānini, are very laconic and it is believed that not a single word in the Sūtras is devoid of purpose. If it is claimed that a particular word is without any purpose, the object of it being achieved in some other way, the commentators always try to assign some purpose or the other for the use of the word in the Sütra. Such a word or words or sometimes even the whole Sūtra is called ज्ञापक or indicator of a particular thing. Paribhāsās or rules of interpretation are mostly derived by indication(ज्ञापकसिद्ध) from a word or words in a Sūtra which apparently appear to be ज्यथं or without purpose, and which are shown as सार्थक after the particular indication (ज्ञापन) drawn from them. The ज्ञापक is shown to be constituted of four वैयर्थ्य. ज्ञापन, स्वस्मिञ्जारितार्थ्य and अन्यत्रफल. For the instances of Iñāpakas, see Paribhāsenduśekhara. Purusottamadeva in his Jñapakasamuccaya has drawn numerous conclusions of the type of ज्ञापन from the wording of Pānini Sūtras. The word ज्ञापक and ज्ञापन are used many times as synonyms although ज्ञापन sometimes refers to conclusions drawn from a wording which is ज्ञापक or indicator. For instances of নাণ্ক, cf.M.Bh. on Māhesvara Sūtras 1, 3, 5, P. I.1. 3, 11, 18, 23, 51 etc. The word ऊर in the rule বাह জত় is a wellknown ज्ञापक of the अन्तरङ्गपरिभाषा. earliest use of the word जापक in the sense given above, is found in the Paribhāṣāsūcana of Vyādi. Paribhāsā works on other systems of grammar such as the Katantra, the Jainendra and others have drawn similar Jmapakas from the wording of the Sūtras in their systems. Sometimes a Jñāpaka is not regularly constituted of the four parts given above; it is a mere indicator and is called बोधक instead of ज्ञापक.

हापकसमुख्य a work giving a collection of about 400 Jñāpakas or indicatory wordings found in the Sūtras of Pānini and the conclusions drawn from them. It was written by Purusottamadeva, a Buddhist scholar of Pāṇini's grammar in the twelfth century A. D., who was probably the same as the famous great Vaiyākaraṇa patronized by Laksmaṇasena. See पुरुषोत्तम-देव.

হ্বাपकसाध्य realizable, or possible to be drawn, from a wording in the Sūtra of Pāṇini in the manner shown above. See হাণক.

ज्ञापकसिद्ध realized from the ज्ञापक wording; the conclusion drawn from an indicatory word in the form of Paribhāṣās and the like. Such conclusions are not said to be universally valid; cf. ज्ञापकसिद्धं न सर्वत्र Par. Sek. Pari. 110.7.

ज्ञापन a conclusion or inference, drawn from a word or words in a Sūtra, with a view to assign a purpose to that or to those words which otherwise would have been without a purpose. The word is sometimes used in the sense of ज्ञापक, and refers to the word or words supposed to be without any purpose and therefore looked upon as a reason or हेत् for the desired conclusion to be drawn. words किमेतस्य ज्ञापेन प्रयोजनम् occur very frequently in the Mahabhasya: cf, M.Bh. on P. I. 1. 11, 14,19, 55, 68, I. 2.41 etc. etc.

ज्ञापित concluded or proved by means of a ज्ञापक word or wording; cf. इन्ते: पूर्ववित्रतिषेषो वार्तिकेनेव ज्ञापतः M.Bh. on III. 4. 37 Vart. 3.

ज्ञाप्य a conclusion or formula to be drawn from a jñāpaka word or words; cf. the usual expression बानता बिनानुपपत्तिस्तावतो ज्ञाप्यत्वम् stating that only so much, as is absolutely necessary, is to be inferred.

ज्ञाप्यमान indicated or suggested; cf. उत्पातेन ज्ञाप्यमाने (चतुर्थी वाच्या)। वाताय क्षिला विद्युत् etc. M.Bh. on II. 3.13 Vart. 3.

by Rāmacandra possibly belonging to the 18th century on the Vājasaneyi Prātiśākhya; (2) name of a commentary on Nāgeśa's Laghuśabdenduśekhara by Udayamkara Pāthaka of Vārāṇasi in the 18th century.

ज्वालिति standing for ज्वलादि, name of

a class of 30 roots headed by the root ज्वल दितों and given as चल कम्पने, जल घातने etc; cf. ज्वलितिकसन्तेम्यो ण: P. III. 1.140.

झ

- झ् fourth consonant of the palatal class of consonants possessed of the properties नादानुप्रदान, घोष, संवतकण्ठत्व, and महाप्राणत्य; झ at the beginning of an affix in Pāṇini Sūtras is mute; e. g. the affixes झि, झ etc.; cf. चुटूं P. I. 3.7.
- आ a verbal ending of the 3rd pers. Atm. for छ (i.e. छकार); cf P. III.4. 78; for the letter झ, अन्त is substituted; cf. झान्त: P. VIII.1.3, but हरे in the perfect tense; cf. P. III. 4.81 and रन् in the potential and benedictive moods; cf. P. III. 4.85.
- झच् wording of the affix झ (see above) suggested by the Vārttikakāra to have the last vowel of अन्त acute, by चितः (P.VI.1.163) the property चित्त being transferred from the original झ to अन्त; cf. Kāś. तथा च झचश्चित्करणमर्थवद् भवति on P.VII.1.3.
- झ्य a short term (प्रत्याहार) for the fourth, third, second and first consonants of the five classes, after which ह is changed into the cognate of the preceding consonant while श is changed into ऴ optionally; cf. P. VIII. 4.62, 63.
- सर् a short term (प्रत्याहार) for any consonant except semi-vowels, nasals and है; cf. P. VIII.4.65.
- श्रन्थ a short term (प्रत्याहार) for consonants excepting semi-vowels and nasals; cf. P.I.2.9, VI.1.58, VI.4. 15, VII. 1.60, VIII. 2.39, and VIII.4.53.
- स्याहार) for the fourth and the third of the class consonants; cf. P. VIII. 4.53, 54.

- झष् a short term (प्रत्याहार) for the fourth (झ, भ, घ, द and घ) of the class consonants; cf. P.VIII. 2.37, 40.
- हिस (1) verb-ending of the 3rd pers. pl. Parasmaipada, substituted for the उकार of the ten lakāras, changed to जुस in the potential and the benedictive moods, and optionally so in the imperfect and after the sign स of the aorist; cf.P,III. 4. 82, 83, 84, 108, 109, 110, 111, 112; (2) a conventional term for अञ्चल (indeclinable) used in the Jainendra Vyākaraņa.
- इत् a term, meaning 'having झ् as इत्' used by the Vārttikakāra in connection with those words in the rules of Pāṇini which themselves as well as words referring to their special kinds, are liable to undergo the prescribed operation; cf. झित् तस्य च तिंद्रशेषाणां च मत्स्याद्यधम्। पिक्षमत्स्यमृगान् इन्ति । मात्स्यिकः। तिंद्रशेषाणाम्। शाक्षितः शाकुलिकः । M.Bh.on P.I. 1. 68 Vārt. 8.

54

- अ (1) the nasal (fifth consonant) of the palatal class of consonants possessed of the properties नादानुप्रदान, शोष, कण्टसंत्रतल, अरुपपाण and आनुनासिक्य; (2) mute letter, characterized by which an affix signifies दृद्धि for the preceding vowel; ज् of a taddhita affix, however, signifies दृद्धि for the first vowel of the word to which the affix is added; (3) a mute letter added to a root at the end to signify that the root takes verb-endings of both the padas.
- স tad. affix ঝ; cf. P. IV. 2. 58, 106, 107 and IV.4.129.
- जम् a short term (प्रत्याहार) for the five nasal consonants ङ्, ज्, ग्, ग् and म्.

সি a mute syllable prefixed to a root in the Dhātupātha of Pāṇini' signifying the addition of the affix ব (ক) to the root, in the sense of the present time; e. g. ফ্রিল্ডা:, ঘূত: etc.; cf. Kās. on P. III. 2.187.

নিত্র tad. affix হ্ন added to words headed by কার্যা as also to words meaning a village in the Vāhīka country optionally with the affix ঠুজ in the Saiṣika senses;e.g. কায়িকা, কায়িকা, ঝাইকা, ঝাইকা, ঝাইকা, য়ায়নিকা. The affixes ঠুজ and জিঠ are added to the word কাল preceded by आपद as also by some other words; e.g. आपत्कालिका, आपत्कालिका तात्कालिका etc.; cf. P. IV.2. 116,117,118 and Vārttika on IV. 2.116.

जित् (1) an affix marked with the mute letter ज़; causing the substitution of viddhi for the preceding vowel and acute accent for the first vowel of the word to which it is added, but, causing viddhi for the first vowel of the word to which it is added in case the affix is a tad. affix; cf. P.VII.2, 115, 116, 117; (2) a root marked with the consonant ज़, taking verb-endings of both the Parasmaipada and the Atmanepada kinds; e.g. करोति, कुरते, बिभति, बिभते, कीणाति, कीणाते elc.; cf. स्वरितिन्तः कर्नभिप्राये क्रियापळे P.I.3.72.

সীব a root marked with the mute syllable সি prefixed to it, signifying the addition of the affix ক in the present tense. See সি.

ञ्च taddhita affix च signifying the substitution of viddhi as also the acute accent for the first vowel of the word to which it is added. It is added (1) to words headed by प्रगदिन in the four senses termed चंत्रण e.g.प्राग्द्यम्, चारचम् etc.; cf.P.IV. 2.80; (2) to

the word गम्भीर and अब्ययीभाव compounds in the sense of 'present there', e.g. गाम्भीयेम्, पारिमुख्यम् etc. cf. P.IV.3.58, 59; (3) to the word विदूर e.g. वेदुयं; cf. P. IV.3.84; (4) to the words headed by হাণ্ডিক in the sense of 'domicile of', e.g. शाण्डिक्यः; cf. P. IV.3.92; (5) to the words छन्दोग, ओक्थिक, नट etc. sense of duty (ঘন) or scripture (आम्नाय) e. g. छान्दोग्यम् , औविथक्यम् नाट्यम् etc.; cf. P. IV. 3.129; (6) to the word गृहपति in the sense of 'associated with'; e.g. गाईपत्यः (আম:);cf.P.IV.4.90;(7) to the words ऋषभ and उपान्ह; cf. P. V.1.14; (8) to the words अनन्त, आवसथ etc.,cf.P. V.4.23; (9) to the word अतिथि; cf. P.V.4.26; and (10) to the words in the sense of qπ(wandering tribes for earning money), as also to the words meaning त्रात (kinds of tribes) as also to words ending with the affix ৰদুস under certain conditions; cf. P.V.3.112, 113.

ड्यङ् tad. affix in the sense of 'a descendant' added to words beginning with आ, ऐ, औ or ending with इ, as also to the words कांसल and अजाद provided they mean a country and a Kṣatriya too; e.g. सोबीर्य:, आवन्त्य:, कांन्त्य: कौसल्य:, आजाद्य:; cf. P. IV.1.171.

ज्यह् tad. affix य causing बृद्धि to the first vowel of the word to which it is added and the addition of ई (इंप्) in the sense of feminine gender, added to words meaning warrior tribes of the Vāhīka country but not Brāhmaṇas or Kṣatriyas. e.g. श्रोद्रक्यः, श्रोद्रकी etc.; cf. P. V. 3. 114.

ञ्युद् krt affix added to the root वह् in Vedic Literature preceded by the words कन्य, पुरीष, पुरीष्य or हन्य. e.g. कन्यवाहन:, पुरीषवाहन:, हन्यवाहन:; cf. P. III.2.65, 66.

ਣ

₹ the first consonant of the lingual class (टबर्ग) possessed of the properties श्वासानुप्रदान, अधोष, विवृतकण्ठत्व and अल्पप्राणल्व. When prefixed or affixed to an affix as an indicatory letter, it signifies the addition of the fem. affix डीप् (ई); cf. P. IV. 1.15. When added to the conjugational affixes (ভদ্মার) it shows that in the Atmanepada the vowel of the last syllable is changed to U. cf. P. III. 4.79. When added to an augment (आगम), it shows that the augment marked with it is to be prefixed and not to be affixed; e. g. नुट्, तुट् etc.; cf. P. I. 1.46.

ट(1) the consonant ट्र, the vowel अ being added for facility of utterance; cf. अकारो व्यञ्जनानाम्, T. Pr. I. 21; (2) short term, (प्रत्याहार) standing for टब्गे or the lingual class of consonants, found used in the Prātiśākhya works; ct. RT. 13, V. Pr. I. 64, T. Pr. I. 27; (3) tad. affix (31) added to the word पत्ग्नी in the sense 'तत्र जात: 'e. g. म्हगूनी, cf. P. IV. 3.34, Vart. 2; (4) krt affix (अ) added to the root ব্, स and कु under certain conditions; e. g. कुरचर:, अप्रेसर:, यशस्करी (विद्या) दिवाकर:, विभाकरः कमेंकरः etc.; cf. P. 2.16-23.

टक् kit affix अ, not admitting गुण or चृद्धि to the preceding vowel and causing ङीप् in the feminine (by P.IV. 1.15), added to the roots गा, पा and इन् under certain conditions; e. g. सामगः, सुरापः, पतिन्नी etc.; cf. P. IV. 2.8, 52, 53, 54, 55.

टकार the consonant ट्, कार being added for facility of utterance; cf. वर्णास्कार: P. III. 3.108 Vart. 3; cf. also V. Pr. I.17.

टच् the samāsānta affix अ added to certain specified words at the end of the tatpuruṣa and other compounds. e.g. राजसल:, पञ्चगवम्, महानसम्, समक्षम्, अध्यात्मम् etc. cf. P.V.4.91-112.

टवर्ग the class of lingual consonants; the same as टु in Pāṇini.

टा case ending of the third case (तृतीया) sing. number; cf. P. IV.1.2,

टाङ् short term for affixes beginning with टाप् in P. IV. 1.4 and ending with ध्यङ् in P. IV. 1.78; cf. टाङिति प्रत्याहारप्रहणम् । टाप: प्रभृति आ ध्यङो ङकारात् M. Bh. on I. 2.48 V. 2.

হাৰ্ feminine affix সা added to masculine nouns ending in স by the rule সনায়ন্ত্ৰাৰ্ IV. 1.4 excepting those nouns where any other affix prescribed by subsequent rules becomes applicable.

रि the final syllable beginning with a vowel; part of a word consisting of the final vowel in a word and the consonants following the final vowel; cf. अचेल्स्यादि टि P. I. 1.64.

रिटन (1) tad. affix इक added to the words श्राणा, मांस and ओदन in the sense of 'something given as wages' e. g. श्राणिक; श्राणिकी; cf. P. IV. 4.67; (2) tad. affix इक added to कंस and रूप्ते in the आहींय senses e. g. कींसक:, कोंसिकी; cf. P. V.1.25,26.

दित marked or characterized by the mute letter इ. For the significance of the addition of इ, see इ.

दिलोप deletion or elision of the final syllable beginning with a vowel, as prescribed by Pāṇini in certain rules; cf. मस्य टेलीप: VII. 1.88, हे: P. VI. 4.143, 155 नस्तदिते P. VI. 4.144 and अह्नग्रहोरेच P. VI. 4.145.

टीटच् tad. affix टीट added to the preposition अब in the sense of

'lowering of the nose' (नासिकाया: नतम्) e. g. अवटीटम्; cf. P. V. 2.31.

દ (1) mute syllable হু prefixed to roots to signify the addition of the affix স্থান্থ in the sense of verbal activity; e. g. বিষয়:, প্ৰযয়:; cf. P.III. 3.89; (2) the class of lingual consonants হ, হ, হ, হ and ण; cf দ্বহু P. I. 3.7.

ड्रक् augment ट् added to that in connection with which it is prescribed; it is prescribed in connection with ङ and ण followed by a sibilant, e. g. सुगण्+ षष्ट: = सुगण्ट्षप्ट:; cf. P. VIII. 3.28.

देण्यण् tad. affix एण्य added to the word वृक्ष meaning 'a warrior tribe not of a Brāhmaṇa nor of a Kṣatriya caste' in the sense of the word (वृक्ष) itself; e. g. वाकेंण्य:, cf. P. V. 3.115

ट्यण् tad. affix य, causing इद्धि for the initial vowel and the addition of the fem. affix ई, applied to the word सोम in the sense of 'having that as a deity,' e. g. सौम्यं हिंच:, सौमी ऋकु; cf. P. IV. 2.30.

ट्यु tad. affix अन to which the augment त is prefixed, making the affix तन, applicable to the words साय, चिरं, प्राह्व, प्राग and indeclinable words in the Saisika or miscellaneous senses; e. g. सायंतन:, चिरंतन: दिवातनम् etc.; cf. P. IV. 3.23, 24.

ट्युल tad. affix added in the same way as ट्यु above, making only a difference in the accent. When the affix ट्युल is added, the acute accent is given to the last vowel of the word preceding the affix.

हुउ
tad. affix ह, causing viddhi for
the initial vowel of the word to
which it is added and also the
addition of the fem.affix है,applied
to the word शमी in the sense

of 'विकार,' e.g. ज्ञामीली सुक्; cf. Kāś. on P. IV. 3.142.

द्वित having टु as इत्; roots, that have इ as इत् or mute, take the affix अधुच् in the sense of verbal activity. See इ.

7

3 the second consonant of the lingual class possessed of the properties श्वासानुप्रदान, अधोष, विवृतकण्टत्व and महाप्राणल्व. For the syllable ठ at the beginning of taddhita affixes, the syllable হুন্ন is substituted; if however the affix (beginning with ਰ) follows upon a word ending in इस्, उस्, उ, क, ल, and त् then क is added instead of इक; e. g. धानुष्क:, औदश्वित्क: etc.; cf. टस्येक:, इससक्तान्तात् कः, P. VII. 3.50, 51. Some scholars say that इक् and क् are substituted for z by the sūtras quoted above; cf. Kās. on VII. 3.50.

3 (1) tad. affix ঠ; see ঠ above for the substitution of ছক and ক for ঠ. ঠ stands as a common term for ঠক্, ঠক্, ঠক্, ঠক্, and ঠক্ as also for ছল্, ছন্, and ঠক্ (2) the consonant ঠ, the vowel আ being added for facitity of pronunciation, cf. T. Pr. I.21.

उक् a very common tad. affix इक, or क in case it is added to words ending in इस, उस, उ, क, ल and त according to P. VII. 3. 51, causing the substitution of viddhi for the first vowel of the word to which it is added. उस् is added to (1) रेवती and other words in the sense of descendant (अपत्य) e. g. रेवतिकः, दाण्डग्राहिकः, गार्गिकः, भागवित्तिकः यामुन्दायनिकः, cf. P. IV. 1.146–149; (2) to the words लाक्षा, राचना etc. in the sense of 'dyed in', e. g.

लाक्षिकम्, रोचिनिकम् ; cf. P. IV. 2.2; (3) to the words दिध and उद्धित in the sense of संरक्त 'made better', e.g. दाधिकम्, औदश्वित्कम् (क instead of इक substituted for उक्), cf. P. IV. 2. 18, 19; (4) to the words आग्रहायणी, अक्षरथ etc.; cf. P. IV. 2. 22, 23; (5) to words expressive of inanimate objects, to the words हस्त and धेन, as also to the words केश and अध in the sense of 'multitude'; cf. P. IV. 2. 47, 48; '6) to the words कत. उक्य and words ending in स्त्र. वसन्त etc., in the sense of 'students of' (तदधीते तद्देद), cf. P. IV. 2.59, 60, 63; (7) to the words उसद and others as also to शर्करा as a चात्रर्थिक affix; cf. P. IV. 2.80, 84; (8) to the words कन्था, भवत् and वर्षा in the Saisika senses; cf. P. IV. 2.102, 115, IV. 3.18; (9) to the words उपजान and others in the sense 'generally present'; cf. P. IV. 3. 40; (10) to the words consisting of two syllables, and the words 報表, ঙ্গান্ধण etc.in the sense of explanatory literary work; cf. P. IV.3.72; (11) to words meaning 'sources of income 'in the sense of 'accruing from'; cf. P. IV. 3.75; (12) to words denoting inanimate things excepting words showing time or place, in the sense of 'भक्ति', cf. P. IV. 8.96; and (13) to the words इल and सोर in the sense of 'belonging to', cf. P. IV. 3.124. The tad. affix তকু is added as a general termination, excepting in such cases where other affixes are prescribed, in specified senses like 'तेन दीव्यति, ' तेन खनति, ' 'तेन संस्कृतम्' etc.; cf. P. IV. 4.1-75, as also to words हल, सीर, कथा, विकथा, वितण्डा etc. in specified senses, cf. P. IV. 4. 81, 102. তক is also added as a general tad. affix or अधिकारविहितप्रत्यय, in various specified senses, as prescribed by P. V.1.19-63, and to the words उदर, अवःश्रुल, दण्ड, आजिन, अङ्गुली, मण्डल, etc. and to the word एकशाला, in the prescribed senses; cf. P. V. 2.67,76, V. 3.108,109; while, without making any change in sense it is added to अनुगादिन, विनय, समय, उपाय (औपयिक being the word formed), अकरमात, कथन्ति; (cf.आकस्मिक काथाचित्क), समूह,विशेष, अत्यय and others, and to the word वाक् in the sense of 'expressed'; cf. P. V. 4.13, 34, 35. The fem. affix ङीप् (ई) is added to words ending in the affix उक् to form fem. bases.

ठक्पाद a popular name given to the fourth pāda of the fourth adhyāya of Pāṇini's Aṣṭādhyāyī. The pāda begins with the rule प्राग्वहतेष्टक् P.IV.4.1 prescribing the taddhita affix टक् in the senses prescribed in rules beginning with the next rule 'तेन दिव्यति खनति जयति जितम् 'and ending with the rule 'निकट वसति' P.IV.4.73.

उच् tad. affix इक or क (by P.VII.3.51) with the vowel a accented acute applied to (1) सुमुद and others as a Cāturarthika affix; cf. P. IV.2.80; (2) to multisyllabic words and words beginning with 39 which are proper nouns for persons; cf. P. V.3.78, 80; and (3) to the word एकशाला in the sense of इत: cf. P. V.3.109. The base, to which ze is added, retains generally two syllables or sometimes three, the rest being elided before the affix उन् e. g. देविकः, वायुकः, पितृकः दोबलिकः etc. from the words देवदत्त, वायुदत्त, पितृ-दत्त, शेवलदत्त etc.; cf. P. V.3.83, 84.

ठञ् tad. affix इक or क (by P.VII.3.51) causing Vrddhi and acute accent for the first vowel of the word to which it is added, applied (1) to महाराज, प्रोष्टपद and कवचिन् in the specified senses, cf. P. IV.2.35, 41

e. g. माहाराजिक, प्रौष्टपदिक etc.; (2) to words काशि, चेदि, संज्ञा and others, along with ञिठ, e. g. काशिकी, काशिका, also with সিত্ত to words denoting villages in the Vāhīka country e.g. शाक्रिकी शाक्रिका: as also to words ending in 3 forming names of countries in all the Saisika senses cf. P. IV.2.116-120; (3) to compound words having a word showing direction as their first member, to words denoting time, as also to the words शरद्, निशा and प्रदोष in the Saisika senses; cf. P. IV.3.6, 7, 11-15; (4) to the words বুগা (in Vedic Literature), and to हेमन्त and वसन्त in the Saisika senses; cf. P.IV.3.19-21; (5) to संबत्सर, आग्रहायणी, words having अन्त: as the first member, to the word ग्राम preceded by परि or अन्, to multisyllabic words having their last vowel accented acute, to words denoting sacrifices, to words forming names of sages, to words ending in ऋ and to the word महाराज in the specific senses which are mentioned; cf. P. IV.3.50, 60, 61, 67, 68, 69, 78, 79, 97; (6) to the words गोपुच्छ, श्वगण, आक्रन्द, लवण, परश्वघ, compound words having a multisyllabic words as their first member, and to the words ne etc. in the specified senses; cf.P.IV.4.6,11, 38, 52, 58, 64, 103; (7) to any word as a general tad. affix (अधिकारविहित), unless any other affix has been specified in the specified senses 'तेन क्रीतम्' 'तस्य निमित्तम्'... 'तदर्हम्' mentioned in the section of sutras V. 1. 18. to 117; (8) to the words अयःशुल, दण्ड, अजिन, compound words having एक or गा as their first member as also to the words নিজ্ম্যান and निष्कसहस्न; cf. P.V.2.76, 118,119.

ठन् tad. affix इक or क (according to P. VII.3.51), causing the addition of आ, and not ई, for forming the

feminine base, applied (1) to the word नौ and werds with syllables in the sense of 'crossing' or 'swimming' over; cf. P.IV.4. 7; e.g. नायिक: नायिका, बाहक: बाहका; (2) to the words वस, कय, and विकय and optionally with ভ to আমুঘ in the sense of maintaining (तेन जीवति); cf. P. IV. 4.13, 14; (3) to the word प्रतिषथ, words ending with अगार, to the word হার, to words showing completion (प्रणवाचिन्), to the words अर्ध, भाग, वस्न, द्रव्य, षण्मास and. श्राद in specified senses; cf. P. IV 4.42, 70, V. 1.21, 48, 49, 51, 84, V. 2, 85, and 109; (4) to words ending in अ as also to the words headed by ब्रीहि, and optionally with the affix इलच to तुन्द and with the affix a to केशांn the sense of मतुप्(possession); cf. P. V. 2, 115, 116, 117 and 109.

ति marked with the mute letter इ.

There is no affix or word marked with mute इ (at the end) in Pāṇinī's grammar, but to avoid certain technical difficulties, the Mahābhasyakāra has proposed mute इ instead of इ in the case of the affix इट of the first pers. sing. perf. Ātm. and उठ p escribed as Saṃprasāraṇa substitute by P. VI. 4.132 e. g. प्रष्टोह:, प्रश्लेहा; cf. M.Bh. on III.4.79 and VI.4.19.

ਵ

ड् (1) third letter of the lingual class of consonants possessed of the properties नादानुपदान, घोष, संवृतकण्डल, and अल्पप्राण; (2) mute letter applied to affixes by Pāṇini to show the elision of the दि part (cf. P. 1. 1.64.) of the preceding word viz. the penultimate vowel and the consonant or consonants following it; cf. है: (लोप: डिति प्रत्येष परे)

- VI.4.143. The syllable ति of विदाति is also elided before an affix mark-with the mute letter हु.
- ड (1) kṛt affix अ applied to the root गम् preceded by अन्त, अस्यन्त, अस्यन्त स्ट., as also to the roots हन् and जन् under certain conditions; cf. P. III.2,48,49, 50, 97-101 and to the root क्रम् to form the word नक, cf. P. VI. 3.75; (2) tad. affix अ applied to words ending in दशन, words ending in शत् and the word विश्वति in the sense of 'more than' e.g. एकादशं शतम्, एकिनशम्, एकिनशिंगम्, एकि
- ৰ samāsānta (জ) added to a Bahuvrīhi compound meaning a numeral e.g. ওপৰ্যাঃ ওপৰিয়াঃ cf. P.V.4.74.
- डद् tad. affix अ in the sense of पूरण applied to a numeral to form an ordinal numeral; e. g. एकादशः, त्रयोदशः, cf. P.V.2.48.
- डण् tad. affix अ, causing viddhi and टिलेप, applied to त्रिंशत् and चत्वारिंशत् to show the परिमाण i.e. measurement or extent of a Brāhmaṇa work; e. g. त्रेंशानि बाह्मणानि, चात्वारिंशानि cf. P. V. 1.62.
- डतमञ् tad. affix अतम in the sense of determination or selection of one out of many, applied to the pronouns किं, यत् and तत्; e,g. कतमः; cf. P.V.3.93,as also to एक according to Eastern Grammarians; e.g. एकतमो भवतां देवदत्तः; cf. P.V.3.94.
- डतरच् tad. affix अंतर in the sense of 'selection out of two' applied to the words कि, यत् and तत् as also to the word एक; e.g. कतरा भवताः पट्टः cf. P. V. 3.92, एकतरा भवताः विवदत्तः cf. P. V. 3.94.
- हतरादि a class of words headed by the word हतर which stands for हतरान्त i.e. words ending with the affix हतर; similarly the word हतम which follows हतर stands for हतमान्त.

- This class इतरादि is a subdivision of the bigger class called सर्वादि, and it consists of only five words viz. इतरान्त, उतमान्त, अन्य, अन्यतर and इतर; cf P. VII.1.25 and I.1.27.
- डाते tad. affix अति affixed to the word किम् to show number or measurement; e.g. कित बाझणाः, cf. P.V.2.41. The words ending with the affix डित are termed संख्या and षट् for purposes of declension etc.; cf. P.I.1.23,25.
- ভাষা kit affix অং added to the root অন্ in the sense of 'instrument' or 'location' e.g. আফো:, cf. P. III. 3. 125 Vārītika.
- डस् affix अस् applied to the word धतवाह and others at the end of a pada i.e. when the word धतवाह has got the पदसंज्ञा. e. g. धतवा: इन्द्र:। धेतवोम्याम् cf. P.III. 2.71 Vart. 1 and 2.
- ভা (1) verb-ending আ, causing elision of the penultimate vowel as also of the following consonant, substituted for the 3rd pers. sing. affix तिष् of the first future; e.g. করা; cf. P.II.4.85; (2) case ending আ substituted in Vedic Literature for any case affix as noticed in Vedic usages; e.g. নামা দুখিত্যাম; cf. P. VII.1.39.
- ভাৰ্ tad. assix আ applied to dissyllabic words, used as imitation of sounds, or used as onomatopoetic, when connected with the root कु or मु or अम्. The word to which हाच् is applied becomes generally doubled; c. g पटपटाकरोात, पटपटाभवति पटपटास्यात; cf. P.V.4.57. The affix डाच् is also applied to द्वितीय, तृतीय, to compound words formed of a numeral and the word गुण, as also to the words सपत्र, निष्पत्र, मुख, प्रिय etc. when these words are connected with the root कृ;e.g. द्वितीयाकरोति-तृतीया-करोति, द्विगुणाकरोति, सपत्राकरोति, सुखाकरोति etc.; cf. P.V.4. 58 to 67.

- डाप् fem. affix आ added optionally to words ending in मन् and to Bahu-vrihi compounds ending in अन् to show feminine gender, the words remaining as they are when the optional affix डाप् is not applied; e.g. दामा, सीमा, सुपर्वी; cf. P. IV. 1.11, 12, 13.
- डामहच् tad. affix आमह added to the words मान and पिन in the sense of 'father'; e.g. मातामहः, पितामहः; cf. P. IV. 2.36 Vārt. 2.
 - बित् possessed of the mute letter इ added for the purpose of the elision of हि (last vowel and the consonant or consonants after it) of the preceding word, See ड.
 - डिनि (1) tad. affix applied to अवान्तर-दीक्षा, तिलम्त etc. in the sense of चरति (observing); e.g. तिलमती, cf. P. V. 1. 94 Vart 3; (2) applied in the sense of 'having as measurement'applied to numeral words ending in शत् or शिन् and the word विशति; e.g. निशिनो मासा:, विशिनोङ्गिरस;; cf. M. Bh. on P. V. 2.37.
 - डिमच् tad. affix इस applied to the words अग्र, आदि, पश्चात् and अन्त in the Saisika senses; e.g. अग्रिमम्, आदि-मम्, पश्चिमम्, अन्तिम्म; cf. M. Bh. on P.IV.3.23.
 - डियाच् case affix इया for Inst.sing.seen in Vedic Literature; e.g. मुक्षेत्रिया, मुगात्रिया; cf. Kāś. on P.VII.1.39.
 - द्धपञ्च tad affix उप added to the word कृत् in the sense of diminutive; e.g. कृत्य: a small oil-pot (कृत्); cf. V.3. 89.
 - ड्रम्सन Unadi affix उम् added to the root पा to form the word पुंस; cf. पाते ड्रीम्सन् Unadi Sutra IV.177.
 - স্তুত্ত tad. affix ভল in the sense of brother' applied to the word মানু; e.g. মানুল:; cf. P. IV. 2.36 Vart 1.

- डुतुए tad. affix मत् as a चातुर्रार्थेक affix applied to the words कुमुद, नड and वतत; e.g. कुमुद्रान्, नड्बान्, वेतस्वान; cf.P. IV. 2.87.
- ड्य tad. affix य (1) added in the sense of 'Sāma introduced by ' (दर्ध साम) to the word वामदेव; e.g. वामदेव्यं साम; cf. P. IV. 2.9; (2) added to the word स्रोत्स optionally with यत in the sense of 'present there' (तत्र भय:); e.g. स्रोतस्य:, cf. P. IV. 4.113.
- ड्यण् tad. affix य added to the words पाथस् and नदी in the sense of 'present there' (तत्र मन:), e. g. पाथ्यः नान्यः; cf. P. IV. 4.111.
- ड्यत् tad. affix य added along with ड्य to the same words to which the affix ड्य is added as also in the same sense, the vowel अ of ड्यत् being स्वरित. See the word ड्य above.
- ड्या case affix या seen in Vedic Literature e. g. अनुष्ठया उच्च्यावयतात् cf. S. K. on P. VII. 1.39.
- ड्रट् kit affix र with fem. affix ई added to it, applied to the root स्त्यै. e.g. स्त्री cf. संस्त्याने स्त्यायतेर्ड्ट् स्त्री M. Bh. on IV. 1.3.
- ड्रुवलच् tad.affix वल, in the four senses, added to the words नड and शाद; e. g. नड्वलम्, शादलम्; cf. P. IV. 2.88,
- ड्वित a root marked with the mute syllable इ (at the beginning) to signify the application of the kit affix त्रि which is invariably followed by the addition of म (मप्), in the sense of 'achieved by 'e.g. पिन्त्रमम्; कृत्रिमम्; cf. P. III. 3.88 and IV. 4.20.
- डुन, tad. affix अक added to the words विंशति and त्रिंशत् in the tetrad of tad. senses; e. g. विंशक:, त्रिंशक: cf. P. V. 1.24.

3

₹ (1) fourth consonant of the lingual class of consonants possessed of the properties नादानप्रदान, घोष, संवृतकण्ठत्व and महाप्राणत्व; (2) the consonant & which is elided when followed by and the preceding vowel is lengthened; e.g. गादा, cf. P. VIII. 3.13 and VI. 3.111; of a पद, or, if followed by any consonant excepting a semivowel or a nasal excepting in the cases of roots beginning with द or the roots दूह, मुह etc. as also वह and आह cf. P. VIII. 2.31, 32, 33, 34; (4) gat the beginning of a tad. affix which has got एय substituted for it; cf. गाड्नेय:, वैनतेय:; cf. P. V. 3.102.

ट tad. affix ह (1) applied to the word समा in the sense of 'fit for' (तत्र साधु:) in Vedic literature; e. g. समेय:; cf. IV. 4.106; (2) applied to the word शिला in the sense of इतः e. g. शिलेयं दिशः cf. P. V. 3.102; (3) common term (ह) for the affixes हक्, हम् and ह also, after the application of which the affix छीय (है) is added in the sense of feminine gender; cf. P. IV. 1.15.

ढक tad. affix एव causing the substitution of vrddhi for the first vowel of the word to which it is added. दक् is added in the sense of अपत्य (descendant) (1) to words ending in feminine affixes, to words ending in the vowel इ, excepting इ of the tad. affix হুল, to words of the class headed by সুসু, to words मण्डूक, विकर्ण, कुषीतक, भू, कुलटा and to words headed by कड़याणी which get इन substituted for its last vowel;e.g. सापर्णयः, दात्तयः शोभ्रयः, माण्ड्रकेयः, वैकर्णेयः, कौषीतकेय:, भौवेय:, कौळटेय:, काल्याणिनेयः etc.; cf. Kās on P. IV. 1,119-127;

(2) to the words पितृष्वस् and मातृष्वस with the vowel melided and to the word বুদ্দুল, e. g. पितृष्वसेय:, मातृष्वसंयः, दौष्कुलेयः, cf. Kāś. on P. IV. 1.133, 134, 142; (3) to the word कलि in the sense of Sama. to the word आमे in the sense of 'dedicated to a deity' (सास्य देवता) as also to the words नदी. वाराणसी, श्रावस्ती and others in the Saisika senses; e. g. कालेयं साम. आग्नेय:, नादेयम् माहेयम् etc. cf. Kāś. on P. IV. 2.8, 33, 97; (4) to the words त्दी, धुर्, कि, ज्ञाति, बीहि and য়ালি in the specified senses; cf. P. IV. 3.94, IV. 4.77, V. 1.127, V. 2.2.

ढक्स् tad. affix एयक applied (1) to the word कुल optionally along with यत् and ख, when it is not a member of a compound; e. g. कोल्लेयक;, कुल्य:, कुलीन:; cf. P. IV. 1. 140; (2) to the words किन्न and others in the Saisika senses as also to the words कुल, कुक्षि and प्रीना, if the words formed with the affix added, respectively mean dog, sword and ornament; e. g. काल्प्रेयक: कौल्लेयक: (धा), क्रीक्ष्रेयक: (आस:), प्रवेयक: (अलंकार:); cf. Kas. on P.IV 2.95,96.

ढञ् tad. affix एय causing Vrddhi substituted for the first vowel of the base and the addition of the fem. ्रaffix ङीप् (इ), applied (1) to words meaning quadrupeds and words in the class of words headed by যান্ত in the sense of अपत्य; e. g. कामण्ड-लेयः, गार्धेयः, हालेयः, बालेयः etc; cf. P. IV.1.135,136; (2) to the word क्षीर, words of the class headed by साख, the words कोश, हति, कुक्षि, कलशि, अस्ति, अहि,ग्रीत्रा,वर्मती,एणी,पथि,अतिथि,वसति,स्वपति, पुरुष, छदिन, उपधि, बलि, परिखा, वास्त in the various senses mentioned in connection with these words; e, g. क्षेरेय:, साखेयम्, कोशेयम्, दार्त्यम्, काक्षेत्रम् etc, cf. Kāś'. on P. IV. 2. 20, 80, IV. 3. 42, 56, 57, 94, 159, IV.4.104, V.1.10,13,17, V.3.101.

डिनुक् tad. affix एयिन applied to the word छगलिन in the sense of 'students following the text of' e.g. छागलिया: in the sense छगलिना प्रोक्त-मधीयते ते: cf. Kas. on P.IV.3.109.

द्भ tad. affix एर (एय् + र) applied in the sense of offspring to the word गोधा and optionally with ढक् to words meaning persons having a bodily defect or a low social status; e. g. गाँधर:, कांगर: दासर:; कांग्य:, दांसय:. cf. Kāś. on P. IV. 1. 129, 131.

ण

प्(1) fifth consonant of the lingual class of consonants possessed of the properties, नादानुप्रदान, घोष, संवृतक-ण्ठत्व, अल्पप्राण and आनुनासिक्यः (2) the mute letter of indicating the substitution of vrddhī (cf. P. VII. 2. 115-117) when attached to affixes; (3) the consonant η at the beginn. ing of roots which is changed into न; the roots, having ण at the beginning changeable to न्, being called गोपदेश; (4) ण as a substitute for न following the letters ऋ, ऋ, ऱ, and ৰ directly, or with the intervention of consonants of the guttural and labial classes, but occurring in the same word. Such a substitution of ण for न is called णत्व; cf. P.VIII.4. 1-39. For जल in Vedic Literature; cf. R. Pr.V.20-28, T.Pr.VII.1-12. V.Pr.III.84-88; (5) the consonant of added as an augment to a vowel at the beginning of a word when it follows the consonant a at the end of the previous word; cf. P. VIII. 3. 32. In the Vedic Prātiśākhyas this augment of is added to the preceding q and looked upon as a part of the previous word. ण (1) krt affix अ, added optionally to the roots headed by জ্বন্ত and ending with 報明 in the first conjugation (see ज्वलित above) in the sense of agent, and necessarily to the root ३ये, roots ending with आ and the roots ब्यघ्, आहु, संसु, इ with अति. सो with अव, ह with अव, लिह, श्रिष् and ध्स, to the roots द and नी without any prefix and optionally to प्रहु; e. g. ज्वाल: or ज्वल:, अवस्थाय:, दाय:, धायः, ब्याधः, आसावः, संस्नावः, अत्यायः, अवसायः, अवहारः, लेहः, श्लेषः, श्वासः, दावः, नाय:, प्रह: or ब्राह:; in the case of the root प्रह the affix ज is applied by. ब्यवस्थितविभाषा, the word ग्रह: meaning a planet and the word प्राह: meaning a crocodile; cf. on P. III. 1.140-143; (2) krt affix अ in the sense of verbal activity (মাৰ) applied along with the affix अप् to the root अद् with नि; e.g.न्याद: निघस:; cf. P. III.3.60; (3) krt affix Π prescribed by the Vārttikakāra after the roots तन, शील . काम, भश्च and चर with आ; cf. P.III.1.140 Vart 1. and III. 2.1 Vārt. 7; (4) tad. affix अ in the sense of अपत्य added along with za also, to a word referring to a female descendant (गोत्रस्त्री) if the resultant word indicates censure; e. g. गार्ग्य: गार्गिक:; cf. P. IV.1.147, 150; (5) tad. affix \(\frac{1}{2} \) in the sense of अपत्य added also with the affix फिञ्, to the word फाण्टाहृति; (6) tad. affix अ in the sense of 'a game' added to a word meaning 'an instrument in the game'; e.g. दाण्डा, मोहा; cf. P. IV.2.57; (7) tad. affix अ added to the word ন্তন্ম and others in the sense of 'habituated to' e.g. छात्र:, शेक्ष:, पौरोह: चौर:; cf. P.IV. 4.62; (8) tad. affix अ added to the words अन्न, भक्त, सर्वे पथिन, यथाकथाच, प्रज्ञा, श्रद्धा, अर्चा, वृत्तिं and अरण्य in the senses specified with respect to each; e.g. आन्न:

(मनुष्यः) भाक्तः (शाल्ठः), सार्व (सर्वस्मै हितम्), पान्थः, याथाकथाचं (कार्यम्), प्राज्ञः or प्रज्ञावान् , श्राद्धः or श्रद्धावान् , आर्चः or अर्चावान् , धार्तः or वृत्तिमान् and आरण्याः (सुमनसः); cf. Kāś. on P.IV. 4.85, 100, V.1.10, 76, 98, V.2.101 and IV.2.104 Vārttika.

णच् krt affix अ in the sense of reciprocal action, added to any root; the affix णच् is to get necessarily the affix अञ् added to it followed by the fem. affix ई e.g. ब्यावकोशो, ब्यावहासी; cf. Kas. on P.III.3.43 and P. V. 4.14.

णत्व cerebralization; lingualization; the substitution of ण for न under certain conditions; cf. P. VIII.4. 1-39. See ण.

णत्वपाद a popular name given by grammarians to the fourth pada cf. Pāṇini's Aṣṭādhyāyī, as the pāda begins with the rule खाभ्यां नो णः समानपद and mainly gives rules about णत्व i. e. the substitution of the consonant ण for न्.

णम्ळ kit affix अम्, causing viddhi to the final vowel or to the penultimate अ, (1) added to any root in the sense of the infinitive in Vedic Literature when the connected root is शक्; e.g. आग्नं वे देवा विभाजं नाशक्तुवन; cf. Kāś. on P. III. 4.14; (2) added to any root to frequency of a past action, when the root form ending with णम्ल is repeated to convey the sense of frequency; e.g. भोजं भोजं मजित, पार्यभायं नजित, cf. Kāś. on P. III. 4.22; (3) added to a root showing past action and preceded by the word अम्रे, प्रथम or पूर्व, optionally along with the krt affix क्ला; e.g. अग्रेभोजं or अग्रे भुक्त्वा व्रजति; cf. Kāś. on P.III.4.24;(4) added in general to a root specified in P.III.4.25 to 64, showing a subordinate action and having the same subject as the root showing the main provided the root to which जम्ल is added is preceded by an antecedent or connected word, such as स्वादुम् or अन्यथा or एवम् or any other given in Panini's rules; cf. P. III.4.26 to III.4.64; e.g. स्वादुंकारं भुङ्क्ते, अन्यथाकारं मुङ्के, एवंकारं मुङ्के, ब्राह्मणेवंद भोजयति, यावज्जीवमधीते, समूलकाषं कषति, हन्ति, तैलपेषं पिनष्टि, अजकनाशं नष्टः etc.: cf. Kāś. on P.III.4.26-64. णमुल is added to the roots कष्, पिष्, हन् and others mentioned in P. III. 4. 34 to 45, the same root is repeated to show the principal action. The word ending in णमुल has the acute accent (उदात्त) on the first vowel (cf. P.VI.I.194) or on the vowel preceding the affix: cf. P. VI.1.193.

णमुल्तत्पुरुष a term used in connection with the compound of the णमुलन्त with its उपपद which precedes; c. g. अग्रेभोजम्, मूलकोपदंशम्; cf. P. II. 2.20, 21.

णल personal ending अ substituted for तिप् and मिप् in लिट्ट or the perfect, and in the case of निद् and ब्रू in लट्ट or the pres. tense optionally; cf. P. III, 4. 82, 83, 84. The affix पल् on account of being marked by the mute letter ण causes vyddhi to the preceding vowel; the vyddhi is, however, optional in the case of the 1st pers. (भिप्;) cf. P. VII.1.91. औ is substituted for एल after roots ending in आ; cf. P. VII.1.34.

णस् tad. affix अस applied to the word पर्श in the sense of collection. The original Varttika is पर्शाः सण् P. IV. 2. 43 Vart. 3. Some scholars read णम् in the place of सण् in the Varttika which is read as पर्शा णम् वक्तव्यः by them.

णि common term for णिङ् (signifying Atmanepada) and णिचु; cf. गरणा

यस्कर्म • P. I. 3.67, णेरानिट VI. 4.51; cf. also P. I. 3.86, I. 4.52, II.4.46, 51; III. 2.137; VI. 1.31, 48, 54, VI. 4.90; VII. 2.26, VII. 3.36; VII.4.1, VIII. 4.30.

णिङ् affix इ causing viddhi, prescribed after the root कम, the base ending in इ i.e. कामि being called a root; cf. P. III. 1.30, 32. The mute letter इ signifies that the root कामि is to take only the Atmanepada affixes e.g. कामयत, अचीकमत.

णिच् affix इ causing vrddhi (1) . applied to roots of the tenth conjugation (चुरादिगण) such as चुर्, चित् etc. e. g. चोरयति, चोरयते; cf. P. III. 1.25; (2) applied to any root to form a causal base from it, e. g. भावयति from भू, गमयति from गम्; cf. हेत्रमति च P. III. 1.26; (3) applied to the words मुण्ड, भिश्र etc. in the sense of making, doing, practising etc. (करण); e. g. मुण्डं करोति मुण्डयति, न्नतयति (eats something or avoids it as an observance), हलं गृह्णाति इलयति etc.; cf. P. III. 1.21; (4) applied to the words सत्य, पाश, रूप, वीणा, तूल, श्लोक, सेना, लोमन, त्वच, वर्मन्, वर्ण and चूर्ण in the various senses given by the Värttikakära to form denominative roots ending in इ; e. g. सत्यापयित, पाश्चयति etc; cf. P. III.1.25; (5) applied to suitable words in the sense of composing, e.g. स्त्रं करोति सूत्रयति, etc.; (6) applied to a verbal noun (कुदन्त) in the sense of 'narrating' with the omission of the krt affix and the karaka of the verbal activity put in a suitable case; e. g. कंसं घातयति for the sentence कंसवधमाच्छे or बालें बन्धयति for बलिबन्धमाच्छे,or रात्रिं विवासयति, सूर्यमुद्गमयि, पुष्येण योजयति etc.; cf. Kāś. on P. III. 1.26. Roots ending in গিলু (গিলন্त) take the conjugational endings of both the Parasmaipada and the Atmanepada; cf. গিল্প P. I. 3.74. They have perfect forms by the addition of সাম with a suitable form of the perfect tense of the root কু, মু or সম placed after সাম, the word ending with সাম and the verbal form after it being looked upon as separate words e. g. কাৰো লকাৰ কাৰো লকা etc.; cf. P. III.1.35, 40. They have the aorist form, with the substitution of the Vikarana লছ (अ) for ভিল্ল before which the root is reduplicated; e. g. স্বাম্বন, স্বাম্বন etc.; cf. P.III.1.48, VI.1.11 as also VII.4.93-97.

णिजन्त roots ending in শিৰু; the term is generally applied to causal bases of roots. See শিৰু.

णित् (1) an affix with the mute consonant ण added to it to signify the substitution of vrddhi for the preceding vowel or for the penultimate अ or for the first vowel of the word if the affix applied is a taddhita affix; cf. P. VII.2.115-117; e. g. अण, ण, उण, ण etc.; (2) an affix not actually marked with the mute letter ण but looked upon as such for the purpose of vrddhi; e. g. the Sarvanāmasthāna affixes after the words गो and सिंस, cf. P. VII.1.90, 92.

णित्व possession of ण as a mute letter for the purpose of viddhi. See the word णিत्.

णिनि krt affix इन् signifying vrddhi (1) applied to the roots headed by प्रह् (i. e. the roots प्रह्, उद्वस्, स्था etc.) in the sense of an agent; e. g. प्राही, उद्वासी, स्थायी. cf. P. III.1.134; (2) applied to the root हन् preceded by the word कुमार or शीर्ष as उपपद; e. g. कुमारघाती, शीर्षघाती, cf. P. III.2.51; (3) applied to any root preceded by a substantive as upapada in the sense of habit, or when comparison or vow or frequency of action is conveyed, or to the root मन् with a substantive as उपपद e. g. उप्णभोजी, शीतमोजी, उष्ट्रकोशी, ध्वाङ्क्षरावी: स्थाण्डलशायी, अधाद्धभाजी; क्षीरपायिण उशीनराः; पायिणा वाह्वीकाः; दर्शनीयमानी, शोमनीयमानी, cf. P. III.2.78-82; (4) applied to the root यज preceded by a word referring to the ক্লে of থাগদন্ত as also to the root इन preceded by a word forming the object (कमेन) of the root हन, the words so formed referring to the past tense; e. g. अहिटो याजी, पिउड्यवाती, cf. P. III 2,85, 86; (5) applied to a root when the word so formed refers to a kind of necessary activity or to a debtor; cf. अवस्यंकारी, शतंदायी, सहस्रंदायी cf. P. III.4. 169-170; (6) tad-affix इन्, causing viddhi for the first vowel, applied to the words कारयप and कौशिक referring to ancient sages named so, as also to words which are the names of the pupils of कलापि or of वैद्याग्यायन, as also to the words शुनक, वाजसनेय etc. in the sense of 'students learning what has been traditionally spoken by those sages' e. g. कास्यपिन:. ताण्डिन:. हारिद्रविण: शानिकन:, वाजसनेयिन: etc.; cf P. IV.3, 103 101, 106; (7) applied to words forming the names of ancient sages who are the speakers of ancient Brahmana works in the sense of 'pupils studying those works' as also to words forming the names of sages who composed old Kalpa works in the sense of those कल्प works; e. g. भाक्तविनः, ऐतरियणः। पैङ्गी कल्पः अरुणपराजी कल्पः; cf. Kāś. on P. IV. 3.105; (१) applied to the words पाराशर्य and शिला-िल् in the sense of 'students reading the Bhiksusūtras (of पाराज्य) and the Nata sūtras (of शिलालिन्)' respectively; e. g. पाराशरिणो भिक्षवः, शैला-छिनो नटाः; cf. Kāś. on P. IV.3.110.

णिलोप elision of the affix পি (পিনু or পিছ্ see above) before an ardhadhātuka affix withou the augment হ (হুহু) prefixed to it; cf. প্রনিটি P. VI. 4.51, and VI.4.52, 53, 54 also.

णुर् augment ण्, prefixed to the initial vowe! when it follows upon the consonant ण् at the end of the preceding word; e. g. सुगण्णीश; for सुगण् + ईश: cf. P. VIII. 3.32.

णोपदेश a root mentioned in the Dhātupātha by Pāṇini as beginning with म which subsequently is changed to न (by P. VI. 1.65) in all the forms derived from the root; e.g. the roots मम, म and others. In the case of these roots the initial न is again changed into म after a prefix like म or मरा having the letter र in it and having a vowel or a consonant of the guttural or labial class intervening between the letter र and the letter न; e.g. प्रमामति, प्रमायकः etc. cf. Kāś. on P. VIII. 4.14.

णौपाद a popular name given to the fourth pada of the seventh Adhya-ya of Panini's Astadhyayī, which begins with the rule णी चङ्युपधाया हस्त्र: P. VII. 4.1.

ण्य tad. affix य (1) applied in the sense of 'descendant' as also in a few other senses, mentioned in rules from IV. 1. 92 to IV.3.168, applied to words दिति, अदिति. the आदित्य and word: with पति as the उत्तरपद in a compound, c. g. दैत्य:, आदित्य:, प्राजापत्यम् etc. cf.Kas.on P. IV.1 84; (2) applied in the sense of a descendant (अपत्य) applied to the words कुरु,, गर्ग, रथकार, कथि, मति, दर्भ etc., e.g. कीरव्य:, गार्ग्य: etc. cf. Kāś. on P. IV. 1.151; (3) applied in the sense of अपत्य or descendant to words ending in सेना, to the word लक्षण and to words in the sense of artisans, e.g.

कारिषेण्यः, लाक्षण्यः, तान्तुवाय्यः, कौम्भकार्यः; cf. Kāś. on P.IV.1.152; (4) applied in the Catuararthika senses to the words संकाश, काम्पिल्य, कश्मीर etc., e.g. साङ्कास्यम्, काग्पिल्यम् etc.; cf. Kās. on P. IV. 2.80; (5) applied to the word परिषद् and optionally with the affix ठक to the word सेना in the specified senses; e. g. परिषदं समविति, परिषदि साधवी वारिषद्य:, सेनां समविति सैन्य: सीनकी वा; cf. Kās. on P. IV. 44. 45, 101; (6) applied as a tad. affix called 'tadraja', to the word क्र and words beginning with न e. g. कोरब्य: नैषध्य:; cf. Kis. on P. IV. 1.172; कुरव:, निज्ञा: etc. are the nom. pl. forms.

ण्यत् krtya affix य which causes vrddhi and which has the circumflex accent (1) applied to a root ending with 率 or any consonant to form the pot. pass.participle; e. g. कार्यम्, हार्यम्, वाक्यम् etc. cf. Käś. on P. IV. 1.124; (2) applied to a root ending in 3 if a necessity of the activity is to be indicated, e. g. अवस्य जान्यम्, अवस्य-पाब्यम् cf. Käś. on P. IV. 1.125; (3) tad. affix a applied to the word षण्मास optionally with यप् and उञ् affixes; e. g. षाण्मास्य:, षण्मास्य:, षाण्मा-सिक:; cf. Kāś. on P. V. 1.84.

ण्युद krt affix अन in the sense of 'skilled agent' applied (1) to the root में to sing. e. g. गायन:, गायनी, cf. Kāś. on P. III 1.147, also गाथक:, गाथिका by P. III. 1.146; (2) to the root gi (III. P. and III.A. also) if 'rice' or 'time' be the sense conveyed: e. g. हायना बीह्य:, हायनः संवत्सरः cf. Kās. on P. III. 1.148.

णिन krt. affix णिन i. e. zero, causing vrddhi, applied to the root भज् and to सह and वह in Vedic Literature if the root is preceded by | 7 the first consonant

preposition (उपसर्ग) or a substantive as the upapada; e. g. अर्द्धभाक्, प्रभाक्, तुराषाट्, दित्यवाट्; cf. Kāś. on P. III, 2.62, 63, 64.

णिवन krt affix व or zero, seen applied in Vedic Literature to the root वह preceded by धत, to शंस preceded by उक्थ, to दाश preceded by पुरम and to यज preceded by अव. e. g. श्वतवा इन्द्रः, उवथशा यजमानः, पुरोडाः, अवया:; cf. Kāś. on P. III. 2.71, 72.

ण्वच krt affix अक seen always with the fem. affix आ applied to a root when the sense conveyed is 'a turn 'or 'a deserving thing 'or 'debt 'or 'occurrence;' e. g. भवतः शायिका, अहीति भवान् इक्षमिक्षकाम्, ओदनभोजिकां धारयसि, इक्षमक्षिका उदपादि: cf Kāś. on P. III. 3.111.

ण्वुल (1) a very general kit affix अक, causing vrddhi and acute accent to the vowel preceding the affix, applied to a root optionally with तू (i. e. तूच) in the sense of an agent e. g. कारक: हारक: also कर्ता, हर्ता; cf. P. III. 1., 33; (2) krt. affix अक applied optionally with the affix तुम् to a root when it refers to an action for which another action is mentioned by the principal verb; e. g. भोजको नजित or भाक्तुं त्रजीतः cf. Kāś. on तुमुन्ग्वुलौ क्रियायां कियार्थायाम् ?: P. III. 3.10; (3) krt affix अक, necessarily accompanied by the fem. affix आ added to it, applied to a root if the sense given by the wo; d so formed is the name of a disease or a proper noun or a narration or a query; e. g. प्रवाहिका, प्रच्छार्दैका, शालभञ्जिका, तालभिक्षका, कारिका, cf. Kāś. on P. III. 3.108, 109, 110.

of the

dental class of consonants which has got the properties श्वासानुपदान, अद्योष, वित्रतकण्ठत्व and अल्पप्राणत्व. When used as a mute letter by Panini, a signifies the Svarita accent of the vowel of that affix or so, which is marked with it; e. g. कार्यम्, हार्यम्, प्यस्यम् cf. P. VI.1.185. When appied to a vowel at its end, त signifiis only the vowel of that grade only, possessed by such of its varieties which reguire the same time for their utterance as the vowel marked wtih নু, e. g. সানু stands for 31 with any of the three accents as also pure or nasalised; आत does not include अ or अ 3 cf. तपरस्तत्कालस्य P. I. 1. 70. The use of the indicatory mute a for the purpose is seen also in the Pratis ākhya works; cf. V. Pr. I. 114 R. T. 234.

त (1) personal ending of the third pers. sing. Atm; cf. P. III. 4. 78, which is changed to a in the perfect tense and omitted after the substitute चिण् for न्लि in the aorist; cf. P.VI.4.104; (2) personal ending substituted for the affix q of the Paras. 2nd pers. pl. in the imperative, imperfect, potential, benedictive, aorist and conditional for which, तात्, तन wand थन are substituted in Vedic Literature, and also for & in case a repetition of an action is meant; cf. P. III. 4. 85, 101 as also VII. 1. 44, 45 and III. 4.2-5. cf. P. III. 4.85 and III. 4. 101; (3) tad. affix त applied to the words कम् and शम e. g. कन्तः, शन्तः, cf. P. V. 2. 138; (4) tad. affix ন applied to হ্যান্ when दशत् is changed to श; cf. दशानां दशतां शभावः तश्च प्रत्ययः । दश दशतः परिमाणमस्य संघर्य शतम्, Kāś. on P. V. 1. 59; (5) general term for the athx to of the past pass. part. in popular use; (6) a technical term for the past participle affixes (त) क्त and तवत् (क्तवतु) called निष्ठा by Pāṇini; cf. P. I.1.26; the term त is used for निष्ठा in the Jainendra Vyākararņa.

বন্ধা the consonant ন, the vowel अ and the word কা being placed after it for facility in understanding; cf. T. Pr. I. 17, 21.

নক্ষয়িভাৰি a class of words headed by নধায়িভা to which the taddhita affix অ (অস্) is added in the sense of 'a native place or a domicile'. The word so formed has the acute accent on its first vowel; e. g. নাধায়িভ: ৰাম্যান্ত্ৰ্যো:; cf. Kāś. on P. IV. 3.93.

तङ् (1) a short term used for the nine personal endings of the Atmanepada viz. त,आताम...महिङ् which are themselves termed Atmanepada; cf. तङानौ आत्मनपदम् P. 1. 4. 100; (2) the personal-ending त of the 2nd pers. pl. (substituted for a by III.4 101) looked upon as तङ् sometimes, when it is lengthened in the Vedic Literature; cf. तङ्गित थोदेशस्य ङिन्तपक्षे प्रहणम्। भरता जातवेदसम् Kas. on P. VI. 3. 133.

तच्छीछादि the triad of senses तच्छील, तद्धमें and तत्साधुकारिन possessed by the agent of an action, in connection with which the affixes तृन, इण्णुच् etc. are prescribed (cf P.III. 2.184 etc.) which (affixes) hence are called ताच्छीलिक; cf. अयं तच्छीला-दिष्वधेषु तृन् विधीयते, M. Bh. on P. III. 2.146, c. g. कर्तां कटान.

तण् ancient term for संज्ञा and छन्दस् used by the Vārtikakāra; cf. बहुलं तणीति वक्तव्यम् । किमिदं तणीति । संज्ञाछन्दसी- श्रेहणम्, M. Bh. on P. II. 4.54 Vārt. 11; III. 2.8 Vārt. 2; IV. 1.52. Vārt. 3.

বাংকান্ত requiring the same time for utterance as for example one mātrā for short vowels, two for long ones and three for protracted ones, although those vowels are nasalised or pure, or acute, grave or circumflex. See the word ব্ৰহ্

तत्कालमाप्तिक occurring or presenting itself at the same time or simultaneously.

तर्वचन्द्र name of a commentary on Rāmacandra's Prakriyākaumudī.

तत्त्वबोधिनी name of the well-known commentary on Bhattoji's Siddhanta Kaumudī written by his pupil Jmānendrasarasvatī at Benares. Out of the several commnetaries on the Siddhantakaumudī, the Tattvabodhinī is looked upon as the most authoritative and at the same time very scholarly.

तर्विमिशिनी name of a commentary on the Kāśikāvṛtti by a grammarian named Upamanyu in the beginning of the nineteenth century A₄ D.

तरवादशं name of a commentary on the Paribhāsendusekhara written by M. M. Vasudev Shastri Abhyankar in 1889 A. D. The commentary is more critical than explanatory, wherein the auothor has given the purpose and the gist of the important Paribhāṣās and has brought out clearly the differences between the school of Bhattojī and the school of Nāgeśa in several important matters.

নংযুক্ত name of an important kind of compound words similar to the compound word নংযুক্ত i.e. (নংখ যুক্ত:), and hence chosen as the name of such compounds by ancient grammarians before Pāṇini. Pāṇini has not defined the term with a view to including such

compounds as would be covered by the definition. He has mentioned the term त्रपुर्व in II.1.22 as Adhikāra and on its strength directed that all compounds mentioned or prescribed thereafter upto Sūtra II.2.22 be called तस्रहा. No definite number of the sub-divisions of तत्पुरुष is given; but from the nature of compounds included in the तत्पुरुष-अधिकार, the sub-divisions विभक्तितत्पुरुष cf. P.II.1.24 to 48. समानाधिकरणतत्पुरुष cf. P. II.1.49 to 72 (called by the name कर्मधारय; acc.to P.I. 2. 42), संख्यातलुरुष (called द्विग by P.II.1.52), अवयवतलुरुष or एकदेशितत्परुष cf. P.II.2.1-3, व्यधिकरणतत्पुरुष cf. P. II 2.5, नञ्तलुरुष cf. P.II.2.6, उपप-दतत्पुरुष cf. P. II.2.19, प्रादितत्पुरुष cf. P.II.2 18 and णमुल्तत्युरुष cf.P.II.2.20 are found mentioned in the commentary literature on standard classical works. Besides these, a peculiar tatpurusa compound mentioned by Pānini in II.1.72, is popularly called मयुरव्यंसकादिसमास. Pāṇini has defined only two out of these varieties viz. द्विगु as संख्यापूर्वी दित: P.II. 1.23, and कर्मधारय तत्पुरुषः समानाधिकरणः कर्मधारयः P. I.2.42. The Mahābhāsyakāra has described तत्पुरुष as उत्तरपदार्थप्रधानस्तत्पुरुषः; M.Bh. on II.1.6, II.1.20, II.1.49. etc., and as a consequence follows that the gender of tatpurusa compound word is that of the last member of the compound; cf. परवाछिङ्गं द्दन्द्रतत्पुरुषयो: P. II.4. 26; cf. also तसुरवश्चापि कः परविछिङ्गं प्रयोजयति । यः पूर्वपदार्थप्रधानः एकदेशिसमासः अर्धपिप्पलीति । यो ह्युत्तरपदार्थप्रधानो दैवकृतं तस्य परविहाङ्गम् , M. Bh. on II.4.26. Sometimes, the compound gets a gender different from that of the last word; cf. P.II.4.19-31. The tatpurusa compound is optional as generally all compounds are,

depending as they do upon the desire of the speaker. Some tatpurusa compounds such as the प्रादितत्पुरुष or उपपदतत्पुरुष are called नित्य and hence their constitutent words, with the case affixes applied to them, are not noticed separately; cf. P.II.2.18,19. In some cases & as a compound-ending (समासान्त) is added; e.g. राजधुरा, नान्दीपरम ; cf. P. V.4.74; in some cases अनू (अ) is added: cf. P.V.4. 75 to 87; while in some other cases टच (अ) is added, the mute letter z signifying the addition of होप (ई) in the feminine gender; cf. P.V.4. 91-112. For details see p.p. 270-273 Mahābhāsya Vol.VII published by the D. E. Society, Poona.

तद्=तिवाधि a peculiar feature in the interpretation of the rules of Pāṇini, laid down by the author of the Sūtras himself by virtue of which an adjectival word, qualifying its principal word, does not denote itself, but something ending with it also; cf. यन विधिस्तदन्तस्य P.I.1.72. This feature is principally noticed in the case of general words or adhikāras which are put in a particular rule, but which occur in a large number of subsequent rules; for instance, the word प्राति-पदिकात, put in P.IV.1.1, is valid in every rule upto the end chapter V and the words अत:, उतः, यञः etc. mean अदन्ताद , उदन्तात् , यञन्तात etc. Similarly the words धातोः (P.III.1.91) and अङ्गस्य (P.VI. 4.1) occurring in a number of subsequent rules have the adjectival words to them, which are mentioned in subsequent denoting not only those words, but words ending with them. large number of cases this feature of तदन्तिधि is not desirable, as it goes against arriving at the desired forms, and exceptions deduced from Pāṇini's rules are laid down by the Vārttikakāra and later grammarians; cf. Par. Sek. Pari. 16,23, 31; also Mahābhāsya on P.I.1.72.

तदादिविधि a convention similar to the तदन्तिभिध of Pāṇini,laid down by the Vārttikakāra laying down that in case an operation is prescribed for something followed by a single letter, that single letter should be taken to mean a word beginning with that single letter; cf. यारमान्विधि-स्तदादायन्त्रहणे P.I.1.72 Vārt. 29; Par. Sek. Pari. 33.

तदगुणसंविज्ञान lit. connection with what is denoted by the constituent members; the word refers to a Bahuvrihi compound kind of where the object denoted by the compound includes also what is the constituent denoted bv members of the compound; e. g. the compound word सर्वादि in the rule सर्वादीनि सर्वनामानि includes the word सर्व among the words विश्व, उभय and others, which alone form the अन्यपदार्थ or the external thing and not merely the external object as mentioned in Pānini's rule अनेकमन्य-मपदार्थे (P.II. 2. 24); cf. भवति बहुनीही तदगुणसंविज्ञानमपि । तद्यथा । चित्रवाससमानय । लोहितोष्णीषा ऋत्विजः प्रचरन्ति । तद्गुण आनीयते तद्गुणाश्च प्रचरन्ति M.Bh. on I.1.27. For details cf. Mahābhāsya on P.I.1.27 as also Par. Sek. Pari. 77.

तद्गुणीभूत lit. made subordinated to (the principal factor); completely included so as to form a portion. The word is used in connection with augments which, when added to a word are completely included in that word, and, in fact, form a part of the word; cf. यदागमास्तद्गुणी-

भूतास्तद्प्रहणेन गृह्यन्ते Par. Sek. Pari. 11.

तोंद्रत a term of the ancient pre-Pāņinian grammarians used by Pāṇini just like सर्वनामन् or अब्यय without giving any specific definition of it. The term occurs in the Nirukta of Yāska and the Vājasaneyi-Prātisākhya; cf. अथ ताद्ध-तसमासेषु एकप्वसु चानेकपर्वेषु पूर्वे पूर्वमपरमपरं प्रविभज्य निव्वयात् । दण्डयः पुरुषः । दण्डमई-तीति वा, दण्डेन संपद्यते इति वा Nir. II.2; also cf. तिङ्कुत्तद्भितचतुः यसमासाः शब्दमयम् Vāj. Prāti.I. 27. It is to be noted that the word तदित is used by the ancient grammarians in the sense of a word derived from a substantive (प्रातिपादिक) by the application of suffixes like अ, यत् etc., and not in the sense of words derived from roots by affixes like अन, ति etc. which were termed नामकरण, as possibly contrasted with the word ताद्वित used by Yāska in II. 5. Pānini has used the word तिस्त not for words. but for the suffixes which are added to form such words at all places (e.g. in I. 1.38, IV.1.17, 76, VI.1.61 etc.). In fact, he has begun the enumeration of taddhita affixes with the rule ताद्विता: (P.IV.1. 76) by putting the term तद्वित for affixes such as तি, ঘ্যন্ত, अण etc. which are mentioned thereafter. In his rule कृत्तिद्वतसमासाश्च and in the Vārttika समासकत्तद्धिताब्यय०(I.4.1Vārt. 41) which are similar to V.Pr.1. 27 quoted above, the word appears to be actually used for words derived from nouns by secondary affixes, along with the word इत which also means words derived from roots, although commentators have explained there the terms कृत् and तिद्धत for कृदन्त and तिद्वतान्त. The term तिद्वत is evidently echoed in the Sutra तस्मे हितम् which, although it is not the first Sūtra

of the taddhita section, may imply that there were possibly long lists of secondary nouns with the senses of secondary suffixes, and तदित was perhaps the first sense given there. The number of taddhita suffixes mentioned by Pānini is quite a large one; there are in fact IllO rules given in the taddhita section covering almost two Adhvāvas viz. from P. IV. 1.76 to the end of the fifth Adhyaya. The main sub-divisions of taddhita affixes mentioned by commentators are, Apatyadyarthaka (IV.1.92 to 178), Raktādyarthaka (IV.2.1 to 91), Saisika (IV.2. 92 to IV.3.133), Prāgdīvyatīya (IV. 3 134 to 168), Prāgvahatīya (IV.4.1 to IV.4.74), Prāgghitīya (IV.4.75 to IV.4.109), Ārhīya (V.1.1 to 71), Ţhañadhikārastha (V. 1.72 to V. 1.114), Bhāvakarmārthaka (V.1.115 to V.1.136), Pāncamika (V. 2.1 to V. 2.93). Matvarthiya (V. 2.94 to V. 2. 140), Vibhaktisamijaka (V. 3.1 to V. 3.26) and Svārthika (V. 3.27 to V. 4.16₀). The samāsānta affixes (V.4.68 to V.4.160) can be included in the Svärthika affixes.

तिइतकोश a work on the taddhita section written by Siromani Bhattā-cārya, who has also written तिइन्तशिरोमणि.

तद्भाव the essence, also called तस्व; cf. यस्य गुणान्तरेष्विप प्रादुर्भेवत्सु तस्वं न विहन्यते तद् द्रव्यम् । किं पुनस्तस्वम् । तद्भावस्तस्वम् M. Bh. on P.V.1.119.

तद्भावित produced or brought into being by some grammatical operation such as the vowel आ in दाक्षि, कारक, अकार्षीत् etc. by the substitution of वृद्धि, as contrasted with the original आ in प्राम, विधान शाला, माला etc.; cf. कि पुनिरदं तद्धावितप्रहणं वृद्धिरित्यंवं य आकारिकारीकारा भाज्यत्ते तेषां प्रहणमाहो- स्विदादैज्मात्रस्य M.Bh. on I. 1.1.

तद्राज the taddhita affixes अञ्,अण्,ज्यङ्क, ण्य, as also इज् , ह्, ज्युट्, ण्य, टेण्यण् and यज्ञ given in the rules of Pāṇini IV. 1.168-174 and V.3. 112-119. They are called तराज as they are applied to such words as mean both the country and the warrior race or clan (क्षत्त्रिय); cf. तराजमाचक्षाणः तराजः S. K. on P. IV.1.168. The peculiar feature of these tadrāja affixes is that they are omitted when the word to which they have been applied is used in the plural number; e. g. ऐक्शकः, ऐक्शकः, इक्शकः; similarly इक्शक्णम्; cf. P.II.4.62.

तहत् (1) as above, similarly; the words होषं तहत् (the rest as above) are frequently seen used by commentators; (2) the tad. affix चत् in the sense of possession and not in the sense of measure etc. cf. तहति तिहित न्यायंसिहतं चेत् V.Pr.V.8.

तह्नव्यि treatment of something as that which is not that e.g. the treatment of affixes not marked with mute ñ or n as marked with n even though they are not actually marked that way, cf. P. I. 2.1-4; also cf. तह्नव्ितदेशेऽिकिद्धिषप्रसङ्घः P. I. 2.1 Vart 4.

तन (1) personal ending for त of the second pers. pl. Parasmaipada in the imperative in Vedic Literature; e.g. जुजूष्ट्रन for जुषत cf. Kāś. on P. VII. 1.45; (2) tad. affixes ट्यु and ट्युल् i.e. अन which, with the augment त, in effect becomes तन. e.g. सायंतन, चिरंतन, etc.; cf. P. IV. 3.23.

तनप् personal ending for त of the second pers. pl. e.g. दघातन for घत्त. cf. Kāṣ. on P. VII. 1.45. See तन.

নন্দ a word frequently used in the Mahābhāṣya in the sense of 'intended' or বিবাধান. The word is used always in the neuter gender like प्रमाणम्; cf. तन्त्रं तरानिर्देश: M. Bh. on P. I. 2.33, II. 2.34, नात्र निर्देश्यस्तन्त्रम् on P. I. 2.39, III.3.38, III. 4.21,IV.1.92 etc. The word is also explained in the sense of 'important'.

तन्त्रप्रद्रीप name of the learned commentary written by मैत्रेयरक्षित. a famous Buddhist grammarian of the 12th century A. D. on the काशिक।विवरणपञ्जिका (न्यास) of Jinendrabuddhi. The work is available at present only in a manuscript form, and that too in fragments. Many later scholars have copiously quoted from this work. name of the work viz. तन्त्रप्रदीप is rarely mentioned; but the name of the author is mentioned as रक्षित. मैत्रेय or even मैत्रेयरक्षित. There are two commentaries on the तन्त्रप्रदीप named उद्द्यातनप्रभा and आलाक.

तनाई a class of roots headed by the root तन, which is popularly called as the eighth conjugation to which the conjugational sign उ is added; e.g. तनोति, करोति, कुरते; cf. P. II. 4.79; III. 1.79.

तनोत्यादि a class of words which is the same as तनादि; cf. P. VI. 4.37. See तनादि.

तन्नामिकाण् the tad. affix अण् prescribed by the rule अनुद्धाभ्यो नदीमानुषी-भ्यस्तन्नामिकाभ्यः P. IV. 1.113; cf. M. Bh. on P. IV. 1.114.

तप् (1) tad. affix त added to the words पर्वन and मस्त् to form the words पर्वतः and मस्तः; cf. P. V. 2.122 Vart. 10; (2) personal ending in Vedic Literature substituted for त of the impera. sec. pers. pl. e. g. श्रुणोत श्रावाण: cf. Kāś. on P. VII. 1.45.

तपरकरण addition of the mute letter त् after a vowel to signify the inclusion of only such varieties of the vowel as take the same time for their utterance as the vowel marked with π ; cf. P. I. 1.70. See π .

বাদ personal ending বাদ substituted for খান in the impera. imperf. potential, benedictive, aorist and conditional; cf. P. III. 4.85, 101.

तम common term for the tad. affixes तमट् and तमप्.

तमट् tad. affix तम added optionally with the affix डट् (अ) to विंशति, विंशत etc., as also to words ending with them, in the sense of प्रण (completion), and necessarily (नित्यं) to the words शत, सहस्र, ष्रि, सतित etc. e. g. एकविंशतितमः एकविंशः, विंशतमः, विंशत, शततमः, ष्रितमः, विंशी, तिंशी etc.; cf. Kas. on V. 2.56-58.

तमप् tad. affix तम added without a change of sense, i. e. in the sense of the base itself to noun bases possessing the sense of excellence, as also to verbal forms showing excellence; e. g. आढयतमः, दर्शनीयतमः, श्रेष्ठतमः, पचितितमाम् cf. Kāś. on P. V. 3.55-56. The affix तमप् is termed प also; cf. P. I. 1.22.

तय tad. affix तयप् applied to a numeral (संख्या) in the sense of अवयिन or 'possessed of parts'; e.g. पञ्च अवयेन अस्य पञ्चतयम्, दश्तयम्, चतुष्र्यी; cf. Kāś. on P. V. 2.42. अय is substituted for तय optionally after the numerals द्वि and ति and necessarily after उभ; cf. P. V. 2.43-44.

तयप् tad. affix तय. See तय.

तर tad. affix तर्ण added to tases showing excellence (अतिशायन) when the excellence shown is between two persons; e. g. अनयो: सुकुमारतर: सुकुमारतरा, पचतितराम्; cf. Kaś. on P. V.3.57. The affix तर्ण is called च just like तम्ण; cf. P.I. 1.22.

तरप् tad. affix तर. See तर.

तल् tad. affix त (1) added in the sense of collection (समृह) to the words ग्राम, जन, बन्धु and सहाय and गज also, e.g. ग्रामता, जनता etc.; (2) added in the sense of 'the nature of a thing' (भाव) along with the affix ल optionally, as also optionally along with the affixes इमन, ध्यञ् etc. given in P. V. 1.122 to 136; अपतित्वम्, अश्वत्वम्, अश्वता; अपतिता; पृथुत्वम्, पृथुता, प्रथिमा; शुक्रता, गुक्कत्वम्, शौक्ल्यम्, ग्रुक्किमा; etc., cf. Kāś. on P. V. 1,119 to 136. Words ending with the affix রক্ত are always declined in the feminine gender with the sem. assix आ (दाप) added to them: (f. तलन्त: (शब्द: स्त्रियाम्), Lingānuśāsana 17.

तवर्ग the class of dental consonants viz. त्, ध्, इ, ध् and न; cf. विभक्ती तवर्गप्रतिषधोऽतद्विते P.I 3.4 Vart. 1.

तचेड़ krt affix तवे for the infinitive affix तुम in Vedic Literature; e.g. दशमे मासे स्तवे; cf. P.III 4.9.

तवेन kṛt affix तथे for the infinitive affix तुम् in Vedic Literature; e.g. गन्तथे, क्त्वे, ह्त्वे; cf. P.III. 4.9.

तवे (1) kṛt affix तवे for the infinitive affix तुम् in Vedic Literature. The affix तवे has a peculiarity of accent, namely that the word ending in तवे has got both the initial and ending vowels accented acute (उदात); e. g. सोमिन्द्राय पातवे, ह्वंसे दातवा उ; cf. P.III.4.9; and VI. 1.200; (2) kṛtya affix in Vedic Literature, e. g. परिचातवे for परिचातव्यम्; cf. Kāś. on P. III. 4.14.

तन्य kṛtya affix applied to a root to form the pot pass. part. e.g. कर्तन्यम्; cf. Kāś. on P.III.1.96.

तब्यत् krtya affix तब्य applied to a root to form the pot. pass. part.; the affix तब्यत् has the circumflex

accent on the last syllable; e.g. क्तन्यम् cf. Kēś. on P. III. 1. 96.

तस् (1) personal ending of the third pers. dual Parasmaipada substituted technically for ल (लकार); cf P. III.4.78; (2) tad. affix तम् (तिस or तिसल्). See तिस and तिसल्.

तस्ति (1) tad. affix तस् showing direction by means of a thing e.g. बृक्षम्लतः, हिमवत्तः; cf. Kāś. on P.IV.3.114, 115; (2) tad. affix तस् applied in the sense of the abl. case and substituted for the abl. case affix; e g. ग्रामतः आगच्छाते, चोरतो विभेति; sometimes the affix is applied instead of the instrumental or the genitive case also. e.g. बृत्ततः न व्यथते for वृत्तेन न व्यथते; देवा अर्जुनतः अभवन्, for अर्जुनस्य पक्षे अभवन् cf. Kāś. on P.V.4.44-49.

तासिन् (1) tad. affix तस् added to pronouns from सर्व upto द्वि, to the pronoun किम् and after परि and अभि; e.g. कुतः; यतः, ततः, अभितः; cf. Kāś.on P.V.3. 7 to 9.

तासिलादि a class of taddhita affixes headed by the affix तस् (तसिल्) as given by Pāṇini in his sūtras from पञ्चम्यास्तासिल् P. V. 3.7. upto संख्यायाः कियाभ्याद्यातिगणने कृत्वसुच् V.3.17; cf. P. VI.3.35. The words ending with the affixes from तसिल् in P.V.3.7 upto पाराप् in P.V.3.47 (excluding पाराप्) become indeclinables; cf. Kāś. on P.I.1.38.

বা (1) a technical term for the genitive case affix used in the Jainendra Vyākaraṇa; (2) the tad. affix বল্ which is popularly called বা as the nouns ending in বল্ i. e. ব are declined in the fem. gender with the fem. affix আ added to them.

ताच्छड्य (1) use of a word for that word (of which the sense has been conveyed); the expression ताद्य्या-ताच्छच्यम् is often used by grammarians just like a Paribhāṣā; cf. अस्ति

तादर्थ्यात्तान्छव्यम् । बहुत्रीह्यर्थानि पदानि बहुत्रीहि-रिति M. Bh. on P. I.1.29; similarly तृतीयासमासः for तृतीयार्थानि पदानि M.Bh. on P.I.1.30 or समासार्थ शास्त्रं समास: M. Bh. on P.I. 2.43; (2) use of a word for that word of which there is the vicinity; cf. अथवा साहचर्यात ताच्छब्यं भविष्यति । कालसहचरितो वर्णः। वर्णोपि काल एव; M. Bh. on P. I.2.27 where the letter 3 is taken in the sense of time required for its utterance. the reason being that sound and time go together; cf. also M.Bh. on P.I.2. 70, IV. 3. 48, V. 2. 79; (3) use of a word for that which resides there; cf. तालथ्याताच्छव्यं भविष्यति M.Bh. on V. 4.50 Vart. 3. At all the above places, the use of one word for another is by Laksanā.

ताच्छोलिक prescribed in the sense of 'habituated'; a term used in connection with all affixes prescribed in the triad of senses viz. ताच्छील्य, ताद्धम्य, तत्साधुकारित्य in Sūtras from P. III.2. 134 to 180; cf. ताच्छीलिकेषु वासल्पनिधिनारित P. III.2.146 Vart. 3, Par. Sek. Pari. 67.

तात् (1) the same as तातङ् substituted for त and हि of the imperative sec. and third sing. Parasmaipada; cf. P. VII. 1.35; (2) substitute तात् for त of the imperative 2nd pl. in Vedic Literature; e.g. गात्र गात्रमस्यान्न ङ्णुतात् cf. Kāś. on P. VII.1.44.

तातङ् the affix तात्. See तात् (1).

तातिल् tad. affix ताति in the very sense of the word to which it is applied occurring in Vedic Literature after the words सर्व and देव, as also after शिव, शम् and अरिष्ट in the sense of 'bringing about' and in the sense of भाव (presence) after the same words शिव, शम् and अरिष्ट; e.g. सर्वतातिः, देवतातिः, शिवतातिः etc. cf. P.IV.4.142–144.

तात्पर्य (1) repetition of action; cf. तालर्यमाभीकृष्यं पानःपुन्यमासेवा Kāś.on III. 2.81 also तालर्यमासेवा । द्रव्ये व्यातिः, कियावामासेवा । (2) foremost consideration; cf. चतुर्गहणे सति ताल्पर्येण स्यन्दिः संनिधापितो भवति Kāś. on P.VII.2.59; (3) purport (of a sentence), significance, intention; cf. सर्पशास्त्रोपकारक मिति तत्तालर्यम् Par. Sek. Pari. 2, 3.

ताथामान्य name given to the grave (अनुदात्त) vowel which is अवग्रह i.e. which occurs at the end of the first member of a compound and which is placed between two acute vowels i.e. is preceded by and followed by an acute vowel; e.g. तनूडनप्त्रे, तनूडनप'त्: cf. उदाद्यन्तो न्यवग्र-हस्ताथाभाज्य: I V.Pr.I.120. The tathābhāvya vowel is recited as a kampa (कम्प); cf. तथा चोक्तमी-जिजहायनकैर्माध्यन्दिनमतानुसारिभिः— ' अवप्रहो यदा नीच उच्चयोर्मध्यतः क्वचित्। ताथाभाव्यो भवेत्कम्पस्तनूनप्त्रे निदर्शनम् '. Some Vedic scholars hold the view that the ताथाभाग्य vowel is not a grave (अनुदात) vowel, but it is a kind of स्वरित or circumflex vowel. Strictly according to Pāņini "an anudātta following upon an udatta becomes Svarita"; cf. P.VIII. 466, V.Pr. IV. 1.138; cf. also R.Pr.III. 16.

ताद्ध्ये (1) the nature of being meant for another; cf. चतुर्थां भिषाने ताद्ध्यं उपसंख्यानम्। यूपाय दारु M. Bh. on P. II.3.13; (2) meant for another; cf. तद्धं एव ताद्ध्यम्। चातुर्वण्यां दित्वात् ष्यम्। आग्नेदेवताय इदम् अग्निदेवत्यम्। ताद्ध्यं यत्। cf. Kāś. on P. V. 4.24; (3) being possessed of the same sense; cf. ताद्ध्यात्ताच्छन्यम्. See ताच्छन्यः

तादात्म्य possession of the same nature; तत्त्वभावता;; cf. सुवामन्त्रिते पराङ्गवत्त्वरे । तादात्म्यातिदेशोयम् Kāś. on P.II. 1.2.

ताद्धम्ये being possessed of the same property; cf. चतुर्भिः प्रकारैस्तस्मिन्स इस्ये- तद्भवति तास्थ्यात्ताद्धम्यत्तिसामिष्यात्तसाहचर्या-

दिति। M. Bh. on IV. 1.48 Vart. 3. ताड्रप्य restoration to, or resumption of the same form by the rule of Sthānivadbhāva, prescribed in P.I. 1.56, called इपातिदेश as contrasted with आयोतिदेश; cf. नेह ताड्रप्यमतिदिस्ते M. Bh. on VI. 1.85 Vart. 26.

तान one uniform accent or tone, एकश्रुति, as observed at the time of sacrifices in the case of the recital of the hymns; cf. तानलक्षणमेकं स्वरमाहुवेज्ञकभीण V. Pr. I.130; cf. also P. I. 2.34.

तानादिक a root of the tanādi class of roots (8th conjugation).

বাদ personal ending substituted for বল্ of the 3rd pers. dual in the imperative, imperfect, potential, benedictive, aorist and conditional; cf. P. III.4.85, 101.

तार (1) elevated, high; a place for the production of words; cf. T.Pr. XVII. 11; (2) recital in a high tone which is recommended in the evening time; cf. तारं तु विद्यास्मवने तृतीय, शिरोगतं तत्र सदा प्रयोज्यम् com. on T. Pr. XXIII. 12.

तारकादि a class of words headed by the word तारका and containing prominently the words पुष्प, कण्टक, मुकुल, कुसुम, पहान, बुसुझा, ज्यर and many others numbering more than ninety, to which the taddhita affix इत (इतच्) is added in the sense of 'containing'. As this class, called तारकादि, is looked upon as आञ्चतिगण, nouns with इत added at their end, are supposed to be included in it: cf. P. V. 2.36.

तारानाथ called तर्कवाचस्पति; a Bengali modern Sanskrit scholar and grammarian of the nineteenth century who has written a commentary called Saralā on the Siddhānta Kaumudī. He has edited many

important Sanskrit works consisting of many kosas.

तालक्य lit. produced from ताल the part below the tongue; the vowel इ, चवर्ग, य and श् are called तालक्य, palatal letters; cf. इचशेयास्तालो V.Pr. I. 66. These letters are formed upon the palate by the middle part of the tongue; cf. R.Pr. 1.42, R.Pr. II.36.

तास्त्राद् a small class of eight words to which the affix अ (अण्) is added in the sense of 'a product' or 'a part' e.g. तालं धनुः, बाहिणम्, etc.; cf. Kāś, on P. IV. 3. 152.

तालु palate; cf. तालुशब्देन जिह्नाया अधस्तन-प्रदेश उच्यते । स इवर्णस्य स्थानम् । जिह्नामध्यं करणम् । cf. T. Pr. II. 22.

নাৰ্ conjugational sign or Vikaraṇa (নামি) added to a root in the first future before the personal endings which become accented grave (अनुदात्त); cf. P.VI.1.186; it has the augment হ prefixed, if the root, to which it is added, is মূহ. cf. P. VI. 4. 62.

तासि the Vikaraņa ताम्. See तास.

ित (1) personal ending तिपु of the 3rd pers. sing.; (2) common term for the krt affixes क्तिन् and क्तिच् as also for the unadi affix fa; see किन् and किच्; (3) fem. affix ति added to the word युवन्. e. g. युवतिः cf. P. IV. 1.77; (4) tad. affix ति as found in the words पङ्कित and विंशति cf. Kas. on P.V.1.59; (5) tad. affix added to the word पक्ष in the sense of 'a root,' and to the words कम् and राम् in the sense of possession (मलर्थे); e.g. पक्षति:, कन्ति:, शान्ति:, cf. Kāś. on P. V.2.25, 138; (6) a technical term for the term गति in Pāṇini's grammar, cf. उपसर्गाः किया-योगे; गतिश्च P. 1.4.59, 60. The term ति for गति is used in the Jainendra Vyākaraņa.

तिककितवादि a class of compound words headed by the dvandva compound तिककितव in which the taddhita affixes added to the constitutnt members of the compound are dropped when the dvandva eompound is to be used in the plural number; तैकायनयश्च कैत-वायनयश्च तिककितवा:; cf. Kāś. on P. II. 4.68.

तिकन् tad. affix तिक added to the word मृद् in the sense of the word itself (स्वार्थ) e.g. मृत्तिका cf.; P. V. 4.39.

तिकादि a class of words headed by the words तिक, कितव, संज्ञा and others to which the taddhita affix आयनि (फिज्ञ्) causing the substitution of viddhi is added in the sense of 'a descendant'; e.g. तैकायनि:, कैत-वायनि:; cf. Kāś. on P. IV.1.154.

तिङ् (1) a brief term (प्रत्याहार) for the 18 personal endings. Out of these eighteen personal endings, which are common for all tenses and moods, the first nine तिप्, तस् etc. all called Parasmaipada, while the other nine त, आताम etc. are named Ātmanepada and तङ् also; cf. तङानावात्मनेपदम्; (2) a verbal form called also आख्यातक; cf. तिङ् खड आख्यातका भवन्ति। पचित पठति। V. Pr. I. 27.

तिङन्त (1) a word ending in तिङ, a verb; (2) a popular name given to the section which deals with verbs in books on grammar as contrasted with the term सुबन्त which is used for the section dealing with nouns.

तिङन्तिशरोमणि a work dealing with verbal forms written by शिरोमणि-महाचार्यः

तिङ्थं senses possessed by the personal endings of verbs, viz. कारक (कती or कमें) संख्या and काल. For details see Vaiyākaraṇabhūṣaṇasāra.

নিজ্নিয়ান the grave accent for the whole word (सर्वनियात) generally possessed by a verbal form when it is preceded by a word form which is not a verb; cf. নিজনৈজ: P. VIII. 1.28.

तित् an affix to which the mute indicatory letter त is added signifying the circumflex accent of that affix; e. g. the affixes यत्, ण्यत् etc.; cf. P. VI. 1.185.

तित्स्वर the circumflex accent possessed by an affix marked with the mute letter त्. See तित्.

तिथुक् the augment तिथ् added to the words बहु, पूप, गण and संघ when they are followed by the tad. affix अ (ड) e. g. बहुतिथ:; cf. P. V. 2.52.

বিष্ the personal ending of the 3rd pers. sing. substituted for ভ (ভন্না) in the Parasmaipada. For substitutes for বিষ in special cases, see P. VI. 168, III. 4.82, 83, 84.

तिमण्णा a southern grammarian who wrote a short treatise on the pratyāhāras like अण्, हण् etc. in the grammar of Pāṇini.

तिरमञ्ज a southern writer of the commentary named सुमनोरमा on the Siddhanta Kaumudi of Bhattoji Diksita.

तिन्ध् tad. affix ति added in Vedic Literature to the word वृक्क when superior quality is meant, e.g. वृक्कति: cf. P. V. 4.41.

तिष्ठद्भुप्रभृति compound words headed by the word तिष्ठद्ध which are termed as avyayībhāva compounds and treated as indeclinables; e. g. तिष्ठद्ध, वहद्द, असंप्रति, प्राह्णम् etc.; cf. Kāś. on P. II. 1.17.

तीक्ष्ण utterance with a sharp tone characterizing the pronunciation of the Abhinihita kind of circumflex vowel as opposed to the utterance which is called मृदु when the circumflex, called पादवृत्त, is pronounced; cf. सर्वतीक्ष्णोऽभिनिहितः प्राक्षियस्तदनन्तरम्, ततो मृदुतरो स्वारी जात्यक्षे-प्रावुभौ स्मृतौ। ततो मृदुतरः स्वारस्तैरोज्यञ्जन उच्यते। पादवृत्तो मृदुतसस्तेतस्वारयळावळम् Uvvata on V. Pr. I. 125.

तीय tad. affix तीय in the sense of पूरा added to the words द्वि and त्रि before which त्रि is changed into तृ. e, g. द्वितीय:, तृतीय: cf. P. V. 2.54, 55; the tad. affix अन् (अ) is added to the words ending in तीय to mean a section e. g. द्वितीया भागः cf. Kas. on P. V. 3.48.

तीवतर extreme sharpness of the nasalization at the time of pronouncing the anusvāra and the fifth letters recommended by Saityāyana. e. g. अमोद्रस्मुबदः, बञ्चते परिवञ्चते. cf. T. Pr. XVII. 1.

तु (1) short term (प्रत्याहार) for the dental consonants त्, य्, द्, ध् and न् cf. P. I. 1.69; (2) personal-ending substituted for ति in the 2nd pers. imper. sing. Parasmaipada cf. P. III. 4.86; (3) tad. affix तु in the sense of possession added in Vedic Literature to कम् and राम् e. g. कन्तुः, रान्तुः cf. P. V. 2.138; (4) uṇādi affix तु (तुन्) prescribed by the rule सिन्निगमिमसिसन्यविधाञ्कु शिम्यस्तुन् (Uṇādi Sūtra I.69), before which the augment इ is not added e. g. सेतुः सक्तुः etc. cf. P. VII. 2.9.

तुक् augment त् added (1) to the root चि in the form चित्य, the pot. pass. part. of चि cf. P. III. 1.132; (2) to the short vowel at the end of a root before a kṛt affix marked with the mute letter प् e.g. अभिचित, प्रहत्य cf. P. VI. 1.71; (3) to a short vowel before छ if there be close proximity (संहिता) between the

two e. g. इच्छति, गच्छति; cf. P. VI. 1.73; (4) to the indeclinables आ and मा as also to a long vowel before छ, e. g. अन्डादयित, विचाच्छाद्येतः cf. P. VI. 1.74, 75; (5) to a long vowel optionally, if it is at the end of a word, e. g. लक्ष्मीच्छाया, लक्ष्मीछाया, cf. P. VI. 1.76; (7) to the letter न् at the end of a word before इ. e.g. भवाञ्च्छेतं, cf. P. VIII. 3.31.

तुष्विधि a rule prescribing the addition of the augment त्; e.g. नलेापः सुप्त्वरसंज्ञातुष्विधिषु इति P. VIII. 2.2 See तुकृ.

तुजादि roots such as the root तुज् and the like, which have their vowel of the reduplicative syllable lengthened as seen mostly in Vedic Literature; e. g. तुतुजान:, सामहान:, दाधार etc.; cf. Kas. on P. VI.1.7.

तुद augment त् (1) added to the affix अन substituted for the यु of ट्यु and ट्युल्; e. g. चिरंतनः, सायंतनः, cf. P. IV. 3.23; (2) added to the tadaffix इक (उक्) applied to the word अस् in the Saisika senses; e.g. शौव-रितकः cf. P. IV. 315.

ব্ৰাই a class of roots headed by the root বুহ্ which take the conjugational sign অ (হা) and which are popularly called roots of the sixth conjugation; cf. P. III.1.77.

तुन् uṇādi affix तु, added to the roots सि, तन्, गम् etc. See तु (4).

तुन्दादि a very small class of words headed by the word तुन्द to which the taddhita affix इल (इलच्) is added in the sense of possession (मस्तर्थ). The affix इल is optional and the other affixes इन्, इक and मत् are also added; e.g. तुन्दिल, तुन्दी, तुन्दिकः, तुन्दवान्; similarly उदिरलः 'etc.; cf. Kāś. on P.V.2.117.

तुम् kṛt affix तुम् of the infinitive (1) added to a root optionally with

ण्वल when the root refers to an action for the purpose of which another action is mentioned by the principal verb ; e.g. भोक्तुं त्रजति or भोजको वजित; cf. Kāś. on P.III.3.11: (2) added to a root connected with another root in the sense of desire provided both have the same subject; e.g.. इच्छति भोक्तुम् ; cf. P. III. 3.158; (3) added to a root connected with the words काल, समय or वेला: e.g. कालो भोक्तुम् etc. c.f. P.III.3.167; (4) added to any root which is connected with the roots হাক, খুবু, शा, की, घट, रम, लम्, कम्, सहू, अई and असू or its synonym, as also with अलम्, or its synonym ; e.g. शक्नोति भोक्तुम्, भवति भोक्तुम्, वेला भोक्तुम् , अलं भोक्तुम् , पर्यातः कर्तुम्: cf. Kas. on P. III. 4. 65, 66.

तुल्य similar in articulation; savarņa; cf. R. T. 168.

तुल्याधिकरण having got the same substratum; denoting ultimately the same object; expressed in the same case; the same as samānādhikaraņa in the grammnr of Pāṇīni. cf. Kāt. II.5.5.

त् (1) substitute prescribed for the last vowel of the word अर्चन् so as to make it declinable like words marked with the mute letter मः (2) common term for the kṛt affixes तृन and तृन् prescribed in the sense of the agent of a verbal activity; the tad. affixes ईयस, and इष्ठ are seen placed after words ending in तृ in Vedic Literature before which the affix तृ is elided; e. g. करिष्ठः, दोहीयसी; cf. Kāś. on P. V. 3.59.

বৃষ্ tad. affix বৃ, taking the fem. affix ई (ভীষু), (1) added to a root optionally with অক (ত্ৰুত্) in the sense of the agent of a verbal activity, the word so form-

तृन्

ed having the last vowel acute; e.g. कर्ता कारकः; हर्ता हारकः; cf. P. III. 1.133; (2) prescribed in the sense of 'deserving one' optionally along with the pot. pass. part. affixes; e.g. भवान खल्ज कन्याया चोढा, भवान कन्यां बहेत, भवता खल्ज कन्या वोढन्या, वाह्या, वहनीया वा; cf. Kāś. on P. III. 3.169.

राजन्त a word ending in the affix तृच् and hence getting the guṇa vowel (i. e. अ) substituted for the final vowel क before the Sarvanāmasthāna (i. e. the first five) case affixes; cf. तृजन्त आदेशो भविष्यति, M. Bh. on VII. 1.96.

तुष्वद्भाव treatment of a word as ending with the affix तृच् although, in fact, it does not so end; e. g. the word कोष्टु; cf. तृष्वत्कोष्टु:, P. VII. 1.95; cf. also तृष्वद्भावस्थावकाराः, कोष्ट्रा कोष्ट्रना; M.Bh, on VII. 1.95 Vart. 10.

तुणादि a class of words to which the taddhita affix दा is added in the four senses given in P. IV. 2.67 to 70; e. g. तृणदा:, नडदा:, पणदा: etc.; cf. Kāś. on P. IV. 3.80.

त्तीय the third consonants out of the class consonants; वर्गतृतीय; viz. ग्, ज्, इ, द and वृ; cf. यथा तृतीयास्तथा पञ्चमा आनुनासिक्यवर्जम् M. Bh. on P. I. 1.9.

रतीया the third case; affixes of the third case (instrumental case or तृतीयाविभक्ति) which are placed (l) after nouns in the sense of an instrument or an agent provided the agent is not expressed by the personal-ending of the root; e. g. देवदत्तेन कृतम्, परगुना छिन्तिः cf. P. III. 3.18; (2) after nouns connected with सह, nouns meaning defective limbs, nouns forming the object of ज्ञा with सम् as also nouns meaning हेतु or a thing capable of producing a result; e. g. पुत्नेण सहागतः, अक्षा

काणः, मात्रा संजानीते, विद्यया यशः; cf. Kāś. on P. II.3.19,23; (3) optionally with the ablative after nouns meaning quality, and optionally with the genitive after pronouns in the sense of Ed, when the word हेतु is actually used e. g. पाण्डित्येन मक्तः or पाण्डित्यानमक्तः; केन हेतुना or कस्य हेतोर्वसित; it is observed by the Vārttikakāra that when the word हेतू or its synonym is used in a sentence, a pronoun is put in any case in apposition to that word i.e. हेतु or its synonym e. g. केन निमित्तेन, किं निमित्तम् etc.; cf. Kāś. on P. II. 3. 25, 27; (4) optionally after nouns connected with the words पृथक, विना, नाना, after the words स्तोक, अल्प, as also after दूर, अन्तिक and their synonyms; e.g. पृथग्देवदत्तेन etc. स्तोकेन मुक्तः, दूरेण ग्रामस्य, केशेः प्रसितः; cf. Kās.on P.II.3. 32, 33,35, 44; (5) optionally with the locative case after nouns meaning constellation when the tad. affix after them has been elided; e.g. पुष्येण संप्रयातोस्मि श्रवण पनरागत: Mahābhārata; cf. P.II.3.45; (6) optionally with the genitive case after words connected with तुल्य or its synonyms; e.g.तुल्यो देवदत्तेन, तुल्या देवदत्तस्य; cf. P. II.3.72.

तृतीयासमास called also तृतीयातसुरुषसमास as prescribed by P. II. 1. 30-35; e.g. तृतीयासमासे P.I. 1.30 and the Mahābhāsya thereon.

त्व (1) krt affix त with the acute accent on the first vowel of the word formed by its application, applied to any root in the sense of 'an agent' provided the agent is habituated to do a thing, or has his nature to do it, or does it well; e.g. बदिता जनापबादान, मुण्डियतार श्राविष्ठायना भवन्ति वधूमूदाम्, कर्ता कटम्; cf. Kāś. on P. III.2.135; words ending with तृन govern the noun connected with them in the accusative case;

(2) the term तृन्, used as a short term (प्रस्महार) standing for kit affixes beginning with those prescribed by the rule लटः शतृशानची। (P.III.2.124) and ending with the affix तृन् (in P.III.3.69); cf. Kāś. on P.III.4.69.

तैत्तिरीयप्रातिशाख्य called also कृष्णयज्ञ:-प्रातिशाख्य and hence representing possibly all the different branches or Sākhās of the कृष्णयञ्जवेद, which is not attributed definitely to a particular author but is supposed to have been revised from time to time and taught by various acaryas who were the followers of the Taittirīya Šākhā. The work is divided into two main parts, each of which is further divided into twelve sections called adhyayas, and discusses the various topics such as letters and their properties, accents, euphonic changes and the like, just as the other Pratisakhya works. It is believed that Vararuci. Māhiseya and Ātreya wrote Bhāsyas on the Taittiriya Prātisākhya, but at present, only two important commentary works on it are available- (a) the 'Tribhāsyaratna', based upon the three Bhāṣyas mentioned above as the title shows. written by Somayārya and (b) the 'Vaidikābharana' written Gopālayajvan. For details see Introduction to 'Taittirīya Prātiśākhya' ed. Govt Oriental Library Series, Mysore.

तैरोविराम a kind of स्वरित, or a vowel with a circumflex accent which follows an acute-accented vowel characterized by avagraha i. e. coming at the end of the first member of a compound; e. g गोप-ताविति गोऽपती यज्ञपतिमिति यज्ञऽपति. Here the vowel अ of q following upon

the avagraha is called तैरोविरामस्वरित; cf. उदवप्रहस्तरोविराम: V. Pr. I. 118,

तैरोव्यञ्जन a kind of svarita or circumflex-accented vowel which follows an acute-accented vowel, with the intervention of a consonant between the acute accented vowel and the circumflex vowel which (vowel) originally was grave. e. g. इंडे, रन्ते, इन्ये, काम्ये; here the vowel ए is तैरोज्यज्ञनस्वरित; cf. स्वरो न्यञ्जनयुतस्तैरो-ज्यञ्जन:, V. Pr. I. 117.

तैल्ज्य् tad. affix तैल applied in the sense of oil to a word meaning the substance from which oil is extracted; e. g. तिलतैलं सर्पवतैलम्; cf. विकार स्नेहने तैलन्, Kāś. on P. V. 2. 29.

तोलपदाक्षित a southern grammarian who has written a gloss called प्रकाश on the Siddhantakaumudi of Bhattoji Diksita.

तोसुन krt affix तोन in the sense of the infinitive (तुम्) seen in Vedie Literature; e. g. ईश्वरोभिचरितो:. The word ending with तोसुन् becomes an indeclinable.

तौदादिक a root belonging to the तुदादि class of roots (sixth conjugation) which take the vikaraṇa अ (श) causing no guṇa or vṛddhi substitute for the vowel of the root.

तौच्बल्यादि a class of words headed by the word तौच्बल्ल, the taddhita affix in the sense of युवन (grandchild) placed after which is not elided by P. II. 4. 60; e. g. तौच्बल्ल: पिता, तौच्बलायन: पुत्र:; cf. Kāś. on P.II. 4.61.

हन tad. affix हन added to the words चिर, परंत् and परि showing time, as also to the word प्रग in Vedic Literature; e. g. चिरत्नम्, परंत्नम्, परंत्तम्, परंत्तमम्, परंत्तमम्नम्, परंत्तमम्, परंत्तमम्नम्, परंत्तमम्, परंतम्यम्, परंत्तमम्, परंत्तमम्, परंत्तमम्, परंत्तमम्नम्नम्नम्तम्।

रनप् tad. affix त्न, added to the word नव optionally with the affixes तनप् and स्त्र before which नव is changed to न्; e. g. नृत्नम्, नृत्नम्, नवीनम्; cf. P. V. 4, 30 Vārt.6.

त्य (1) tad affix त्य standing for त्यक् and त्यम् which see below; (2) a technical term for मत्यय (a suffix or a termination) in the Jainendra Vyākaraņa.

त्यक् tad. affix त्य added in the Saisika senses to the words दक्षिणा, पश्चात् and पुरस्; e. g. दाक्षिणात्यः,पाश्चात्यः, पीरस्त्यः, दाक्षिणात्यका cf. P. IV 2. 98.

त्यक्त tad. affix त्यक added to the words उप and अधि in the senses 'near' and 'above' respectively; cf. पर्वतस्थासन्नमुपत्यका, तस्यैवारूढमधित्यका, cf. Kāś. on P. V. 2.34.

त्यदादि a term used for the class of pronouns headed by त्यद् which are eight viz. त्यद्, तद्, यद्, एतद्, अदस्, इदम्, एक and द्वि; cf.P.I.1.74,I.2.72, III. 2. 60, VII. 2. 102.

त्यदादिविधि a specific operation prescribed for the pronouns headed by त्यद् e. g. the substitution of अ for the final letter; cf. त्यदादिविधौ च प्रयोजनम्, M. Bh. on P. I. 1. 27 Vart. 6.

ह्यप् tad. affix त्य (1) added to a few specified indeclinables in the Saisika senses; e. g. अमात्य:, इहत्य: etc.; cf. Kāś. on IV. 2. 104; (2) added to the indeclinables एषमस्, ह्यस् and श्वस् optionally along with ट्यु and ठन्: e. g. श्वस्त्यम्, श्वस्तनम्, शौवस्तिकम्; cf. Kāś. on P. IV. 2. 105.

ৰ a common term for the krt affixes ছুন্ and হুন্ন (P.III. 2. 181–186) in case the vowel হ of হুন্ন is looked upon as equivalent to an augment, as also for the uṇādi affix ছুন্ and the tad. affixes ন and সূত্ৰ (P. IV. 2.51 and V.3.10); the tad. affix ন is added in the sense of समृह or collection to the word गो, e.g. गोत्रा; cf. Kāś. on P.IV.2.51.

ষন্ত tad. affix termed Vibhakti added to pronouns excepting দ্ধি and others, and to the words बहु and কিন্ when they end with the loc. case termination; e.g. মুদ্দ, নদ, মহুদ etc.; cf. Kaś. on P.V. 1.10, 14.

त्रा tad. affix त्रा in the sense of something donated, as also to the words देव, मनुष्य, पुरुष,पुरु and मत्ये ending in the accusative or the locative case; e. g. बाह्मणत्रा करोति, देवत्रा वसति: cf. Kāś. on P. V.4.55,56. There is avagraha before the tad. affix त्रा. देवत्रीत देवडता;cf. V.Pr. V.9.

त्रि (1) kṛt affix वित्र, always having the tad. affix मप् (म) added to it, applied to the roots marked with the mute syllable इ prefixed to them in the Dhātupāṭha; e.g. इात्रेमम्, पवित्रमम्; (2) a term signifying the plural number; cf. ना नौ मे मदथें त्रिद्धेयेकेषु V.Pr.II.3.

त्रिक lit. triad; a term used in the Mahābhāṣya in connection with the Vibhakti affixes i.e. case endings and personal endings which are in groups of three; cf. त्रिकं पुनर्विभक्तिसंज्ञम् M.Bh. on P.I.1,38; cf. also कस्यचिंदेव त्रिकस्य प्रथमसंज्ञा स्यात् M.Bh. on P.I.4.101; cf. also M.Bh. on II.2.23, V.1.52, V.1.58.

त्रिपथगा name of a commentary on the Paribhāṣenduśekhara written by Rāghavendrācārya Gajendragadkar, a resident of Sātārā and a pupil of Nīlakaṇthaśāstri Thatte. He lived in the second half of the eighteenth and first half of the nineteenth century and wrote comentaries on important grammar works.

त्रिपद made up of a collection of three padas or words; the word is used in connection with a Rk or a portion of the kramapātha; cf. य्योक्तं पुनस्कं त्रिपद्मभृति T.Pr.I.61. The word

is found used in connection with a bahuvrīhi compound made up of three words; cf. the term त्रिपद-बहुनीहि.

शिपादी a term usually used in connection with the last three Pādas (ch. VIII. 2, VIII. 3 and VIII. 4) of Pāṇini's Aṣṭādhyāyī, the rules in which are not valid by convention to rules in the first seven chapters and a quarter, as also a later rule in which (the Tripādi) is not valid to an earlier one; cf. पूर्वशासिद्धम् P. VIII.2.1; (2) name of a critical treatise on Pāṇini's grammar ("The Tripādi") written by Dr. H. E. Buiskool recently.

त्रिभाष्यरत्न name of a commentary on the Taittirīya Prātiśākhya written by Somayārya. The commentary is said to have been based on the three Bhāṣya works attributed to the three ancient Vedic scholars— Vararuci, Māhiṣeya and Ātreya.

ষিমান consisting of three moras or mātrās. The protracted or জুৱ vowels are said to consist of three mātrās as contrasted with the short and long vowels which respectively consist of one and two mātrās; cf. Kāś. on P.I.2.27.

त्रिमुनि (1) the famous three ancient grammarians Pāṇini (the author of the Sūtras), Kātyāyana (the author of the Vārttikas), and Pataājali (the author of the Mahābhāṣya;) (2) the grammar of Pāṇini, called so, being the contribution of the reputed triad of Grammarians.

সৈতক repeated thrice, occurring thrice; a term used in the Pratisākhya works in respect of a word which is repeated in the krama and other artificial recitations.

त्रिलोकनाथ son of Vaidyanātha who wrote a small treatise on kārakas

called पट्कारकनिरूपण.

त्रिक्षोत्रन a scholar of grammar who has written a small work named অৱ্যুখ্যান্ত্রানি on the uses of indeclinables.

जिविकम pupil of Vardhamāna who wrote a gloss called 'पञ्जिकोहयोत'. on the Kātantra—vṛtti

निशिखा name of a commentary on the Paribhāṣenduśekhara written by Lakṣminṛsimha in the 18th century.

त्रैकाल्य all the three times, past, present and future; cf. त्रयः कालाः समाहृताः त्रिकालम्, त्रिकालमेव त्रैकाल्यम् । स्वार्थे ध्यञ् Uvvaṭabhāṣya on V. Pr. I. I5.

त्रेपादिक a rule or an operation prescribed by Pāṇini in the last three quarters of his Aṣṭādhyāyī. See त्रिपादी above.

त्रेशब्द्य a collection of three words (to express the same sense); cf. अपि च त्रेशब्द्यं न प्रकल्पते । अस्पृक्षत् अस्पाक्षींत् अस्प्राक्षींदिति M. Bh. on III. 1.44; cf. also M. Bh. on P. I. 4.74, IV. 1.88, IV. 2.60 etc.

त्रैस्वर्य (1) use of the three accents acute, grave and circumflex at the time of the recital of the Veda; त्रयः खरा एव त्रैस्वर्यम्; cf. चातुर्वण्यांदीनां स्वार्थे उपसंख्यानम् । त्रेलोवयम् , त्रैस्वर्यम् Kāś, on P. V. 1. 124. cf. also यद्येव त्रैस्वर्ये न प्रकल्पते तत्र को दोषः । त्रेस्वर्येणाधीमेहे इत्येतत्रोपपद्यते । M. Bh. on P. I. 2.31.

ज्यक्षर (a word) having three vowels or syllables in it; ज्यच् or ज्यन्क; cf. हाक्षरज्यक्षरेभ्य इति वक्तज्यम् cf. M. Bh. on VIII 4.6.

ज्यम्बक a grammarian of the nineteenth century, who resided at Wai in Sātārā District and wrote a commentary on the Paribhāsendusekhara which is named ज्यम्बकी after the writer. ज्यस्वकी a commentary on the Paribhāṣenduśekhae by स्वज्यक: see ज्यस्वक.

रच tad. affix त्व in the sense of duty, nature or essence, prescribed optionally with the affix तल् (ता); e.g. अश्वत्वम, गोत्वम, अश्वता, गोता; cf. तस्य भावस्त्वतले P. V. 1.119, also cf. त्वतले तुंणवचनस्य P. VI. 3. 35 Vart.10.

स्वत् krt affix त्व in the sense of the potential pass. part. in Vedic Literature; e. g. कर्त्व हवि: । कर्तव्यम्; also cf. Kāś. on P.III. 4.14;cf. also हतानि या च कर्त्वा R. V. 1X. 47.2.

हबन tad. affix ल before which there is observed the caesura or avagraha in the recital of the Padapātha. e. g. देवल्वमिति देवडलम् । cf. V. Pr. V. 9.

थ

- श् (1) second consonant of the dental class of consonants possessed of the properties श्वासानुप्रदान, अशोष, विवृत-कण्डल and महाप्राणल्व; (2) augment स् (शुक्) added to the words षष्, कित, कित्रिय and चतुर before the Purana affix डट्. e. g. पण्णां पूरणः षष्टः, कित्यः, चतुर्थः; cf. Kāś. on P. V. 2.51; (3) substitute for the consonant ह of आह before any consonant except a nasal, and a semivowel as also for the consonant स् of स्था preceded by the preposition डद्; cf. P. VIII. 2.35, VIII. 4.61.
- थ (1) personal-ending of the 2nd pers. pl. Parasmaipada, substituted for the छ of the ten lakāra affixes; (2) substitute (थल्) for the 2nd pers. sing. personal ending सिप् in the perfect tense; (3) uṇādi affix (थक्) added to the roots पा, तृ, तुद् etc. e. g. पीथा, तीथा, etc.; cf. uṇādi sūtra II. 7; (4) uṇādi affix (व्यन्)

added to the roots हन, सुष्, ती etc.; e. g. हथ:, सुष्ठं, तीथ: etc. cf. uṇādi sūtra II. 2: (5) uṇādi affix (थन्) added to the roots उष्, सुष्ठ, गा and क. e. g. ओष्ठः, कोष्ठम् etc. cf. uṇādi sūtra II. 4; (6) a technical term for the term अम्यस्त or the reduplicated wording of Pāṇini (cf. उमे अम्यस्तम्) P. VI. 1. 5, used in the Jainendra Vyākaraņa.

थकर krt affix यक added to the root में 'to sing,' in the sense of agent provided he is skilled; e. g. गाथक:; cf. P. III. 1.146.

थद् tad. affix थ added to numerals ending in न in Vedic Literature; e. g. पञ्चथः, सप्तथः, पर्णमयानि पञ्चथानि मनन्ति; cf. P. V. 2.50.

थन personal-ending यन substituted for त of the 2nd pers. pl. of the imperative Parasmaipada in Vedic Literature, e. g. यदिष्ठन for यदिच्छय; cf. Kās. on P. VII. 1.45.

थमु tad. affix थम् in the sense of प्रकार (manner) added to the pronouns इदम्, and किम्, the words ending in थम् becoming indeclinables; e. g. इत्थम्, कथम् cf. P. V. 3.24, 25.

थल personal ending य substituted for सिप् of the 2nd pers. sing. Parasmaipada in the perfect tense as also in the present tense in specific cases; cf. P. III. 4.82, 83,84.

थस् personal ending of the 2nd pers. dual Parasmaipada, which is substituted for छ of the lakāra affixes; cf. P. III 4. 78.

था (1) tad. affix या in the sense of question or reason (हेतु) added to the pronoun किम् in Vedic Literature; e.g. कथा देवा आसन्; cf. Kāś. on P.V.3.26; (2) tad. affix था (थाल according to Pāṇini) which gets caesura or avagraha after प्रतन, पूर्व, विश्व, इम and क्यु; e.g. प्रत्नथेति प्रतन्त्रथा,

पर्वथेति पर्वेऽथा etc.; cf. Vai. Pr.V.12; (3) tad. affix খাত in the sense of इव added to the words प्रतन, पूर्व, विश्व and इम in Vedic Literature, e.g. तं प्रत्नथा पूर्वथा विश्वथेमथा; cf. Kāś. on P. V.3.111; (4) tad. affix थाल in the sense of mannar (प्रकार) added to किन्, pronouns excepting those headed by दि, and the word बहु; e.g. सर्वथा, cf. P V 3.23.

थाल tad. affix थाल. See था.

थास् personal ending of the pers. sing. Atmanepada, substituted for of the lakara affixes.

थीम (THIEME, PAUL) a sound scholar of the present day, well versed in Sanskrit Grammar and Vedic Literature, who has written a critical treatise named "Panini and the Veda."

थुक (1) augment य added to the words षष्, कति, कतिपय and चतुर; see थ above; (2) augment थ् added to the root अस of the fourth conjugation Paras. before the affixes of the aorist. e.g. आस्थत्; cf. P.VII.4.17.

थ्यन tad. affix ध्य in the sense of 'favourable for' (तस्मै हितम्) added' to the words अज and अवि; e.g. -अजथ्या यूथि: । अविथ्या । cf. Kāś. on P. V.1.8.

द

द third consonant of the dental class of consonants possessed of the properties नादानुप्रदान, बोष, संवृतकण्ठत्व and अल्पप्राणता;(2) consonant द substituted for the final letter of nouns ending with the affix वस् as also for the final letter of संस्, ध्वंस् and अनडुड् provided the final letter is at the end of a pada; e.g. विद्यद्भयाम् etc.; cf. Kāś. on P, VIII. 2.72; (3) consonant & substituted for the final स of roots excepting the root अस, before the दिन्तोष्ठ्य also दन्त्योष्ठ्य or दन्त्योष्ठ्य

personal ending faq of the third pers. sing.; e. g. अचकाद् भवान् ; cf. P. VIII. 3.93.

द् (1) the consonant द्, the vowel अ being added for facility of utterance or use; (2) a technical term used in the Jainendra Vyakarana for the term आत्मनेपद in the grammar of Panini.

द्ग्ध a fault of pronunciation where the letters are uttered indistinct (अस्पष्ट).

ব্য়ক tad. affix ব্ল prescribed optionally with द्रयस and मात्र in the sense of measure (प्रमाण), with ङीप् (ई) to be added further to form the fem. base, e. g. जानुदन्नम्, जानुद्रयसम्, जानुमात्रम् , जातुदन्नी, cf. P. V. 2.37 and IV.1.15; दब्रच is added optionally along with अण as also with द्रयस and मात्र to the words पुरुष and हस्तिन् e.g. पुरुषद्वयसम्, पौरुषम् पुरुषदन्नम्, पुरुषमात्रम्; cf. P. V. 2.38.

दण्ड one of the eight artificial Vedie recitations.

द्ण्डादि a class of words headed by the word दण्ड to which the taddhita affix य, is added in the sense of 'deserving'; cf. दण्डमहीत दण्डचः Kās. on P. V. 1.66

दिधपयआदि a class of compound words headed by the word दिधपयस् which are not compounded as समाहारद्वन्द्र which ends in the neuter gender and singular number; e.g. द्धिपयसी, शिववैश्रवणी, श्रद्धातपसी etc.; cf. Kāś. on P.II. 4.14.

दन्त place where the utterance of dental letters originates;cf. ल्रुत्लसानां दन्ताः S. K. on P. I. 1.9.

दन्तमूळीय the letters त्, य् द्, ध् and नः; cf. दन्तमूलीयस्तु तकारवर्गः R. Pr. I. 19. The Rk. Prātišākhya calls (飞) also as दन्तमूलीय.

dentolabial letter ब्; cf. ओष्टान्ताभ्यां दन्तैर्वकार । दन्तैरिति स्थानिदेश्तः । ओष्टान्ताभ्याम् इति करणनिर्देशः Com. on T.Pr.II. 43.

इन्त्य produced at the teeth, dental; formed at the teeth by the tip of the tongue; e.g. the letters ल ल, स, and तवगे; cf. ललीसता दन्ते V.Pr.I.69. According to Pāṇini's grammar ल (long) does not exist. According to Taittirīya Prātisākhya इ is partly dental and partly lingual; cf. T.Pr.II.41, while व is partly dental and partly labial; cf. T.Pr. II.43; cf. दन्त्या जिह्नाप्रकरणाः V. Pr.I. 76; cf. लुग्वा दुहिदहलिहगुहामात्मनेपदे दन्त्ये P. VII. 3..73.

द्यानन्द्सरस्त्र ती a brilliant Vedic scholar of the nineteenth century belonging to North India who established on a sound footing the study of the Vedas and Vyākaraṇa and encouraged the study of Kāśikāvṛtti. He has written many books on Vedic studies.

द्यापाल a Jain writer who wrote a treatise named रूपसिद्धिः

द्यारत्न a Jain scholar who has written a grammar treatise on the Sarasvata Grammar called सारस्त्रतपरिभाषा.

द्याराम writer of a commentary on the Mugdhabodha Vyākaraņa of Bopadeva.

द्र्णेण name of a commentary on Kondabhaṭṭa's Vaiyākaraṇabhūṣaṇasāra, written by a grammarian named Harivallabha.

द्र्भेणा name of a commentary on the Śabdakaustubha, written by Mannudeva or Mantudeva of the nineteenth century.

द्शक a name given to the treatise on grammar written by व्यात्रपाद which consisted of 10 chapters; cf. दशकं वैयात्रपदीयम् Kāś. on P. V. 1.58. The

word also means students reading the work दशक; cf. दशका वैयाघ्रपदीयाः, Kāś. on P. IV.2.65.

হ্যানতী (1) a section of grammatical treatises dealing with the ten conjugations of roots. e.g. the first section of the second part (ভ্রমেষ্) of the Siddhānta Kaumudī; (2) name of the dhātupāṭha of Pāṇini which gives ten classes of roots; cf. মুবাহ্যা হ্যানতীদিবিতিনা ব্যান্ত Nyāsa on I.3.1.

द्शभुष्करण the ten classes or conjugations of roots; धुष् was a term for धातु (root) in some ancient grammar works.

হ্যাৰন্তকাৰিকা a short treatise on the roots belonging to more than one conjugation; the name of the author is not given.

दा tad. affix named 'vibhakti' applied to the words सर्व, एक, अन्य, किं, यत्,तत् and इदम् in the locative case; e.g. सर्वदा, एकदा, कदा; cf. Kāś. on P. V. 3.15,19,20,21.

दाक्षायण name, by which ज्याडि, the author of the grammar work संप्रह is referred to. The word दाक्षायण <u>ब्याडि</u> was indicates that descendant of दक्ष, and, as Pāṇini called दाक्षीपुत्र, critics and Vyādi Pāņini that relatives; cf. शोभना खब्ब दाक्षायणस्य दाक्षायणेन वा संग्रहस्य कृति: M. Bh. on P. II.3.66.

दाक्षीपुत्र lit. son of a female descendant of दक्ष; name given to Pāṇini who was the son of दाक्षी a female descendant of दक्ष; cf. शंकर: शांकरीं प्रादाहाक्षीपुत्राय धीमते Pāṇ. Sik. 56; cf. also सर्वे सर्वपदादेशा दाक्षीपुत्रस्य पाणिने: M.Bh. on P. I. 1.20; VII.1.27.

दानविजय a Jain grammarian, who wrote a small grammar treatise named शब्दभूषण.

वैयाव्रपदीयम् Kāś. on P. V. 1.58. The दानीम् tad. affix called विभक्ति, applied

to तद् and इदम् in the sense of the locative case. e.g. तदानीम्, इदानीम्; cf. P. V.3.18, 19.

दामन्यादि a class of words headed by the word दामनि to which the taddhita affix छ is added without any change of sense; e.g. दामनीयः, औलपीयः cf. Kāś. on P. V. 3.116.

दारुण्य explained by the commentators on the Prātiśākhya works as हडत्व (firmness) or कठिनता (hardness,) and given as a characteristic of the acute or उदात्त tone; cf. आयामी दारुण्यमणुता खस्येत्युचै:कराणि शब्दस्य, T. Pr. XXII.9, quoted in the Mahābhāṣya on P.I. 2.29, where दारुण्य is explained as खरस्य दारुणता रूक्षता।

दासीभारादि a class of words headed by the word दासीभार which, although they are tatpurusa compounds, retain the accents of the first member of the compound; cf. P. VI.2.42.

ৰি a technical term in the Jainendra Vyākaraņa for the term সমূহ্য used by Pāṇini.

दिक्शाञ्द a word denoting a direction such as पूर्व, उत्तर and the like, used as a substantive, e. g. पूर्वो प्रामात्, or showing the direction of another thing being its adjective, e. g. इयमस्याः पूर्वा; cf. Kāś. on P. II.3.29.

दिक्समास the bahuvrihi compound prescribed by the rule दिङ्नामान्यन्तरांछ, e.g. पूर्वोत्तरा (north-east) or उत्तरपश्चिमा (north-west); cf. दिक्समासः दिगुपदिष्टः समासः, Kāś. on P.I. 1.28.

दिगादि a class of words headed by the word दिक् to which the tad. affix य (यत्) is added in the sense of 'produced therein' (तत्र भव:), e.g. ग्रिशि भवं दिस्यम्, similarly वर्ण्यम्, गण्यः etc.; cf. Kāś. on P.IV.3.54.

दिनण् tad. affix added to the word मध्य, before which मध्य is changed to मध्यम्; e. g. माध्यन्दिन उद्गायति;cf. मध्य मध्य दिनण् चास्मात् M.Bh. on IV. 3.60.

दिचादि a class of roots of the fourth conjugation, headed by the root दिव (दीन्यति), called also दीन्यत्यादि cf. P. I. 2.27.

दी a technical term in the Jainendra Vyākaraņa for दाेर्च (long vowel) in Pāṇini's grammar.

दीपप्रभा a commentary on वारक्चसंप्रह by नारायण

दीसि explained as स्कृति or throbbing in utterance. Out of the seven svaras or yamas क्रुष्ट, प्रथम, द्वितीय, तृतीय, चतुर्थ, सन्द्र and आतिस्वाय, the throbbing (दीति) of the latter and latter tone leads to the perception of the former and former one; cf. तेषां दीतिजापलिंब: T. Pr. XXIII. 15.

द्रीर्घ long; a term used in connection with the lengthened tone of a vowel described to be dvimātra as contrasted with हरन having one mātrā and जुत having three mātras; cf. द्विस्तानान् दिर्घ: V. Pr. I. 35, V. Pr. I. 57, also जकालोब्झस्वदीर्घन्द्वतः P. I.2.27.

ব্যথিবিধি a grammatical operation where a short vowel is turned into a long one; a rule of grammar prescribing the lengthening of a short vowel.

डु a technical term în the Jainendra Vyākarana for the term वृद्ध which is used in Pāṇini's grammar and which is defined by Pāṇini in the rule बुद्धियस्याचामादिस्तद बुद्धम् P. I. 1.73.

दुःश्किष्ट a word, or words whose case affixes can be syntactically connected only with some difficulty; cf. बहुत्रीहौ सक्थ्यक्ष्णोः स्वाङ्गात् षच्। स्वाङ्गवाची यः सिक्थ्यक्वः आक्षराब्दश्च तदन्ताद् बहुन्नीहैः षच् मवति । सूत्रे तु दुःश्चिश्विभक्तानि पदानि । Kās. on P. V. 4.113.

दुःस्पृष्ट produced by an incomplete contact of the करण; the term is applied to the phonetic element ळ which is due to the incomplete contact of the organ at the production of the letter छ; cf. दु:स्पृष्ट- श्रेति विशेय:; Pāṇ. Sīkṣā 5.

दुगेसिंह the famous commentator of the Katantra sutras, whose Vrtti on the sūtras is the most popular It is called कातन्त्रसूत्रवृत्ति or कातन्तवृत्ति or दौर्गसिंहीवृत्ति also. work on Paribhasas named परिभाषा-द्वति, in which Paribhisas are explained and established as based the Kātantra Vyakarana sūtras, is attributed to Durga-It is doubtful whether this commentator Durgasimha is Durgācārya, the same as famous commentator of Yāska's There is a legend that Nirukta. Durgasimha was the brother of Vikramāditya, the founder of the Vikrama Era. Besides the gloss on the Katantra sutras, some grammar works such as a gloss on the uṇādi sūtras, a gloss (वृत्ति) on Kālāpa-Vyākaraņa Sūtras, a commentary on Karakas named অনুকা-Nāmalingānusāsana Paribhāsāvītti are ascribed Durgasimha. Some scholars believe that the term अमरसिंह was only a title given to Durgasimha for his profound scholarship, and it was Durgasimha who was the author of the well-known work Amarakosa.

दुर्गोदास a grammarian who wrote (a) a gloss on Bopadeva's Mugdhabodha, (b) a gloss named घातु-दीपिका on Kavikalpadruma and (c) Sabdārṇavakosa.

दुगात्तम a grammarian who wrote a work on genders called लिङ्गान्-शासन and also a commentary on it. हुर्घटगुनि name of a grammar work explaining words which are difficult to derive according to rules of Pāṇini. The work is written in the style of a running commentary on select sūtras of Pāṇini, devoted mainly to explain difficult formations. The author of it, Śaraṇadeva, was an eastern grammarian who, as is evident from the number of quotations in his work, was a great scholar of the 12th or the 13th century.

दुर्घटवृत्तिसंस्करण a grammar work on the formation of difficult words attributed to शर्वरक्षित or सर्वरक्षित.

दुर्घटोद्धार name of a commentary by Kesavadatta-Sarman on the grammar work named पंक्षितसार.

दुर्वेलाचार्य a grammarian who wrote a treatise on grammar दुर्वेलीयव्याकरण, named after him. Besides this treatise, he has written commentaries on Nāgesa's Laghumanjūṣā and Paribhāsendusckhara.

दुस्स्पृष्ट see दुःस्पृष्ट.

on the Paribhāṣenduśekhara of Nāgeśa, believed to have been written by Gopālācārya Karhādkar, a grammarian of the 19th century and attributed to Bhīmācārya. This commentary, which was written to criticize the commentary written by Viṣṇuśāstrī Bhat, was again criticized in reply by Viṣṇuśāstrī Bhat in his Ciccandrikā. (चिचन्द्रिका). See विष्णुशास्त्री भट.

is used in connection; the word is used in connection with a fault found with, or objection raised against an argument advanced by a writer, by his opponent or by the writer himself who replies it to make his argument well establis-

hed; cf.नित्यवादी कार्यपक्षे द्षणमाह-कार्येष्विति . Mahā. Prad. on P.I. 1.44 Vārt.!6.

दूस tad. affix prescribed after the word अनि in the sense of milk(दुग्ध) along with the affixes साद and मरीस optionally, by the Varttikakāra; e. g. अनिद्सम्। अनिसोहम्। अनिमरीसम्; cf. Kāś. on M. Bh. IV. 2. 36.

दृढािद a class of words headed by इंढ to which the tad. affix य (ध्यञ्) or इमन् (इमिन्च्) is added in the sense of nature (भाव); त्व and तल् (ता) can, of course, be added optionally; e.g. दाढ्यम्, द्रिष्टमा इढत्वम्, इढता. See also लावण्य श्रेत्य, औष्ण्य, जाड्य, पाण्डित्य, मौर्ष्य etc.; cf. Kāś. on P. V. 1. 123.

হয় seen in use in Vedic Literature, or Classical Literature, or in the talk of cultured people; said in connection with words which a grammarian tries to explain; cf. হুগানুবিঘিশ্য-বেধি মন্বিনি Vyāḍi Pari. Pāṭha 68.

दशन्तिचि taking place of an operation, or application of a rule of grammar in accordance with the words seen in use. See इष्ट.

हष्टान्त similar instance, generally quoted to explain effectively some rules or conventions laid down; cf. नतु चायमप्यस्ति हथान्तः समुदाये वाक्यपरिसमाप्ति-रिति । तद्यथा गर्गाः शतं दण्ड्यन्तामिति M.Bh. on P.I. 1.7.

द्यापचार discrepant, characterized by discrepancy; cf. यद्यपि तावदयं पराशब्दो द्यापचार उपसर्गश्चानुपसर्गश्च अयं तु खळ विशब्दोऽद्रष्टापचार उपसर्ग एवः M. Bh. on P. 1. 3. 19.

देवताइन्द्र a compound word called इन्द्र whose members are names of deities; the peculiarities of this Dvandva compound are (a) that generally there are changes at the end of the first member, by virtue of which it appears similar to a word ending in the dual number, and (b) that both the words retain their original accents. e. g. इन्द्रासोमी, सामापूषणा, अभीषोमाभ्यां, मित्रावरणाभ्याम्; for changes, cf. P. VI.3.25-31; for accent, cf. देवताद्वन्द्वानि चानामन्त्रितानि (द्विरुदात्तानि)। इन्द्रावृहस्पतिभ्याम्, इन्द्रावृहस्पती इति त्रीणि V. Pr. II.48, 49; cf. also देवताद्वन्द्वे च P. VI. 2.141.

देवनान्दिन called also पुज्यपाद or पुज्यपाद-देवनन्दिन believed to have lived in the fifth century A.D. and written the treatise on grammar, of course based on Pāṇīni Sūtras, which is known as जैनेन्द्र–ब्याकरण or जैनेन्द्र-शब्दानशासन. The writer of this grammar is possibly mentioned as जैनेन्द्र in the usually quoted verse of Bopadeva :- इन्द्रश्चन्द्रः काराक्रत्सापिराली शाकटायनः पाणिन्यमरजैनेन्द्रा जयन्त्यशदिशा-ब्दिका: देवनन्दिन was a great Jain saint and scholar who wrote many works on Jain Agamas of which सर्वार्थासिद्धि, the commentary on the तत्त्वार्थोधिगमसूत्र, is well-known.

देवपथादि a class of words headed by the word देवपथ, the affix कन applied to which in the sense of a statue, or applied for the formation of a proper noun, is dropped देवपथ:, हंसपथ:, शिव:, विष्णु: etc.; cf.Kāś. on P. V. 3.100.

देवदार्भन् a grammarian who has written a disquisition on the philosophy of Vyākaraṇa in verse, and added a commentary of his own on it which he has named as समन्वयप्रदीपसंकेत.

देवानान्दिन a Jain grammarian of the eighth century who is believed to have written a grammar work, called सिद्धान्तसारस्वत-शब्दानुशासन. It is likely that देवानान्दिन् is the same as देवनान्दि-पूज्यपाद and the grammar work is the same as जैनेन्द्रशब्दानुशासन for which see देवनान्दिन्.

देविकापाद a popular name given to the third pāda of the seventh adhyāya of Pāṇini's Astādhyāyī as the pāda begins with the Sūtra देविकाशिंशणादित्यवाट्दार्धसत्त्रश्रेयसामात् P.VII 3.1.

देवीदीन a modern grammarian of the 19th century who has written a gloss on the Astādhyāyī of Pāṇini.

देवेन्द्र a Jain grammarian of the 13th century who has written a commentary named लघुन्यास on the घान्दानुशासन of Hemacandra. He has written many works on the Jain Agamas, of which a commentary on the Uttaradhyanasūtra can be specially mentioned. He is called देवेन्द्रस्रो also.

देश lit. place; (1) original place of articulation; cf. अदेशे वा वचनं व्यञ्जनस्य, R. Pr. XIV. 5; (2) place of origin; उचारणस्थान; (3) place of inferential establishment of a Paribhāṣā etc. परिभाषादेश: उद्देश: Par. Sek. pari. 2,3; (4) passage of the Samhitā text, cf. T. Pr. I. 59.

देशीयर् tad. affix देशीय in the sense of slightly less, or almost similar, optionally prescribed with the affixes कल्प and देश्य e.g. मृदुकल्पः, मृदुदेश्यः मृदुदेशीयः cf.Kāś. on P.V.3.67.

देश्य (1) tad. affix in the sense of almost similar; see देशीयर् above; (2) (words) current in popular use or language, although not sanctioned by rules of grammar; cf. देश्याः स्त्रानियन्धाः कियन्त M.Bh. on P. V. 3.55; cf. देश्या देष्टच्याः साञ्चलेन प्रतिपाद्याः, Kaiyata on V. 3.55; probably Kaiyata had a difficulty in explaining the word देश्य in the old way meaning 'current in use', as many words called bad words, introduced from other languages were current at his time which he was reluctant to term as देश्य.

दैव name of a system of grammar or a work on grammar the peculiarity of which is the omission of the एकरोब topic; cf. अनेकरोबं दैवं स्थात्.

दैनादिक a root belonging to the fourth conjugation of roots (दिवा- दिगण); cf. जमु ताडने इति चुरादी पठ्यते तस्यदं ग्रहणं, न देवादिकस्य, Kās. on P. II 3.56.

दैनेन्द्र name given to a work on grammar, presumably the same as जैनेद्र-शब्दानुशासन written by पूज्यपाद-देवनान्दन्. See जैनन्द्रज्याकरण.

दोष (1) a fault of pronunciation; cf. एता: स्वरदोषभावनाः अतोन्ये व्यञ्जनदोषाः M.Bh. on I. 1.1 Vārt.18; (2) defect shown in connection with an expression or explanation.

दोषोद्धरण name of a commentary on Nāgeśa's Paribhāṣenduśekhara written by मनुदेव of the eighteenth century.

दोषोद्धार name of a commentary on Nāgesa's Laghusabdendusekhara written by मञ्जदेव of the eighteenth century.

च tad. affix च, applid to इदम् in the sense of 'a day', when इदम् is changed into अ (अहा); e. g. अच, cf. P.V. 3.22 Vārt. 5.

चस् tad. affix द्यस्, applied to the word समान when समान is changed into स; e.g. सद्य:, cf. सद्य: परत्परावेषम: P. V.3.22; cf. also समानस्य समावो द्यश्चाहान P. V. 3.22. Vart. 1

ঘ a technical term in the Jainendra Vyākaraņa for the term ভন্মৰ (the latter or the second member of a compound word) which is used in Pāṇini's grammar.

युतादि a class of roots headed by the root द्युत्, the aorist sign िन्न after which gets (अ) अङ् substituted for it; e.g. अग्रुतत्, अश्वितत्; cf. Kās. on P. III.1.55. and I.3.91. द्युस् tad. affix द्युस् applied to the word उभय in the sense of a day; e.g. उभयद्य: cf. P. V. 3.22 Vārt. 7.

द्योतक indicative, suggestive; directly capable of expressing the sense by denotation; the nipatas and upasargas are said to be 'dyotaka' and not 'vācaka' by standard grammarians headed by the Vārttikakāra: cf. निपातस्यानर्थकस्यापि प्रातिपदिकत्वम् P.I.2.45 Vārttīka 12; cf. Kaiyata also on the above; cf. also निपाता द्योतकाः केचित्प्रथगथाभिधायिनः Vākyapadīya II. 194; गतिवाचकत्वमपि तस्य (स्थाधातोः) व्यवस्थाप्यते, उपसर्गस्त तहचो-तक एव com. on Vākyapadīya II. 190; cf. पश्चाच्छोतर्बोधाय द्योतकोपसर्गसंबन्धः Par. Sek. on Pari. 50; cf. also হুই स्वरादयो वाचकाः चादयो द्योतका इति भेदः Bhāṣā Vr. on P.I.1.37. The Karmapravacaniyas are definitely laid down as dyotaka, cf. कियाया द्योतको नायं न संबन्धस्य वाचकः। नापि क्रियापदाक्षेपी संबन्धस्य तु भेदकः Vākyapadīya II.206; the case affixes are said to be any way, 'vācaka' or 'dyotaka'; cf. वाचिका द्योतिका वा स्युद्धिंत्वादीनां विभक्तयः Vakyapadīya II. 165.

चोतन conveyance of sense indirectly or by suggestion, and not directly. See चोतक above.

चोत्य (sense) conveyed by suggestion indirectly and not directly expressed, as in the case of karma-pravacaniyas, the krt affixes and the tad. affixes; cf. अनुशन्दो लक्षणे होत्ये कमंत्रवन्वनीयसंज्ञो भवति Kāś. on P. I. 4.84.

द्भव्य substance, as opposed to गुण property and क्रिया action which exist on dravya. The word सन्त is used by Yāska, Pāṇini and other grammarians in a very general sense as something in completed formation or existence as opposed to 'bhāva' or kriyā or verbal activity,

and the word हृज्य is used by old grammarians as synchymous with सच्च; cf. चादयोऽसच्चे । चादयो निपातसंज्ञा भगन्त न चेत्सचे वर्तन्ते, cf. Kās on P. I. 4.57; cf. S. K. also on P. I. 4.57. (2) The word हृज्य is also found used in the sense of an individual object, as opposed to the genus or generic notion (आकृति); cf. हृज्याभिषानं ज्याडि:, M. Bh. on P. I. 2. 64. Vārt. 45. (3) The word हृज्य is found used in the sense of Sādhana or means in Tait. Prāti. cf. तत्र शब्द हृज्याण्युदाहरिष्याम:। शब्द हृज्याणि साधनानि वर्णविष्याम: Таі, Pr. XXII. 8.

द्रव्यपदार्थिक a grammarian who maintains that 'dravya' or 'individual object' is the sense of words; cf. न ह्याकृतिपदार्थिकस्य द्रव्यं न पदार्थी, द्रव्यपदार्थिकस्य वाकृतिर्न पदार्थी:। M. Bh. on I.2.64 Vart. 53. See द्रव्य.

द्रव्यवचन expressive of substance as their sense as opposed to गुणवचन; cf. उभयवचना होते शुक्रादयः द्रव्यं चाहुर्गुणं च। M. Bh. on P. V.1.119.

द्रव्यवद्भाव behaviour like a dravya as noticed in the case of the bhāva or kriyā found in a root after a kṛt affix is added to it; cf. कृदभिहितो भागो द्रव्यवद्भवति. M. Bh. on II.2.19, III.1.67 etc.

द्रव्याभिधान denotation of द्रव्य or individual object as the sense of words as opposed to आइत्यभिधान i.e. denotation of the general form possessed by objects of the same class; of द्रव्याभिधानं व्यादि: P. I.2.64 Vart. 45. See द्रव्य.

द्भुत lit. rapid; the vice of rapidity in utterance; a fault of speech especially in connection with the utterance of vowels in Vedic recital when on account of haste the utterance of letters becomes indistinct. cf. सहक्षमणीकृतमधंत्र दुतं विकिणिमता: स्वरद्रोषमान्वनाः। M. Bh. Āhnika 1 Vārt. 18.

हुतबोध name of a treatise on grammar written for beginners by Bharatasena or Bharatamalla of Bengal in the sixteenth century.

द्वता one of the three Vittis or styles of utterance mentioned in the Prātiśākhya works and quoted in the Mahābhāsya; cf. तिलो वृत्तीरुपदिशन्ति वाचो विलम्बितां मध्यमां च दृतां च । अभ्यासार्थे हुतां वृत्तिं प्रयोगार्थे तु मध्यमाम् । शिष्याणा-मुपदेशार्थे कुर्योद् वृत्ति विलम्बिताम् । R. Pr. XIII. 18, 19; cf. ये हि दूतायां वृत्ती वर्णा-स्त्रिभागाधिकास्ते मध्यमायां, ये वर्णास्त्रिभागाधिकास्ते विलम्बितायाम् । M. Bh. on P. I.1.70, Vart. 4. The utterance of a letter takes \frac{1}{3} rd time more in the मध्यमवृत्ति than in the हुतवृत्ति, while in the विलभितवृत्ति it takes $\frac{1}{3}$ rd more than in मध्यमवृत्ति. In short, the utterance of the same letter takes in three vittis, Druta, Vilambita and Madhyama the quantity of time in the proportion of 9:12:16 respectively.

ইাতিকা a kind of the position of the tongue at the time of pronouncing the letter ছ.

इन्द्र name of a compound, formed or two or more words used in the same case, showing their collection together; cf. चार्थे द्वन्द्व: P. II.2.29. Out of the four meanings of the indeclinable ਚ, viz. सम्चय, अन्वाचय, इतरेतरयोग and समाहार, dvandva compound is sanctioned in the last two senses only called इतरेतरद्वन्द्व (as in प्लक्षन्यग्रोधौ etc.) and समाहारद्वन्द्र (as in वाक्तवचम् etc.) respectively. For details see Mahabhasya on II.2.29. The dvandva compound takes place only when the speaker intends mentioning the several objects together i.e. when there is, in short, सहविवक्षा orयुगपद्ध-करणवचनता; cf. अनुस्यूतेव भेदाभ्यां एका प्रस्थापजायते । यस्यां सहविवक्षां तामाहुर्द्वन्द्वे-करोषयो: ॥ ईर. Pr. II. The gender of a word in the द्वन्द्वसमास is that of the last word in the case of the इतरेत-रद्वन्द्व, while it is the neuter gender in the case of the समाहारद्वन्द्व.

ह्रयसच् tad. affix इयस, in the sense of measure, prescribed optionally along with the affixes दझ and मात्र; cf. ऊलः प्रमाणमस्य ऊरह्रयसम्; Kāś. on P. V. 2.37; fem. ऊरह्रयसम्, cf.P.IV.1.15.

द्वारादि a class of words headed by the word द्वार् which get the augment ऐच् (i.e. ऐ or ओ) placed before the letter च or च in them, instead of the substitution of viddhi, when a taddhita affix marked with the mute letter ज्, ण or क् is added to them; e. g. दौवारिकः सौवस्तिकः, शौवम्, शौवनम् etc.; cf. Kāś. on P. VII.3.4.

हि a term used for the dual number in the Prātisākhya works; cf. नो नौ मे मदथें त्रिद्धेकेषु V. Pr. II. 3 where Uvvaṭa has explained the words त्रि, द्वि and एक as बहुबचन, द्विबचन and एकबचन respectively.

(a) doubled; the term is used in connection with reduplication in the Kātantra and Haima grammars cf. Hem. IV.1.1, Kat.III 8. 10.

द्धि:प्रयोग doubling, putting a word or word element twice; the words द्वित्व and द्विचन are used in the same sense.

द्धिःस्पृष्ठ a word used many times synonymously with दुःस्पृष्ठ; the letters ळ,ळ्ह, and upadhmānīya (ध्पृ) are termed द्धिःस्पृष्ठ or दुःस्पृष्ट.

द्विकमेक a term used in connection with roots governing two objects or two words in the accusative case, e.g. दुह in गां दोग्धि पय:; the term कमें according to the strict

definition of the term कर्त्तरीप्सिततमं कर्म or आप्यं कर्म applies to one of the two, which is called the प्रधानकमें or the direct object, the other one, which, in fact, is related to the verbal activity by relation of any other kāraka or instrument is taken as karmakāraka and hence put in the accusative case. For details see Mahābhāsya and Kāśikā on P.I.4.51. Some roots in their causal formation govern two objects out of which one object is the actual one while the other is the subject of the primitive root. e.g. गमयति माणवकं प्रामम्; वोधयति माणवकं धमेम: cf. Kāś. on P.I.4.52. See for details Mahābhāsya on P. I. 4.52.

कार्ययोग simultaneous occurrence of two grammatical operations resulting into a conflict and creating a doubt as to which of the two should take place first; cf. द्विकार्ययोगी हि विप्रतिषेघ: M.Bh. on P.I.1.3 Vart. 6; I.1.12; etc. The term विप्रतिषेघ occurring in the rule विप्रतिषेघ परं क. यंग् P. I.4.2 is evidently defined in this way by the word दिकार्ययोग in the Mahābhāsya.

হিৰুত্ত a compound expression or word separated into two by avagraha in the Padapāṭha; the word is misstated as বুৰুত্ত by some Vedic reciters.

बिसु name of a compound with a numeral as the first member. The compound is looked upon as a subdivision of the Tatpurusa compound. The dvigu compound, having collection as its general sense, is declined in the neuter gender and singular number; when it ends in अ the fem. affix को is added generally, e. g. पञ्चपात्रम्, त्रिमुबनम्, पञ्चमूळो. The Dvigu compound also takes place when a

karmadharaya compound, having a word denoting a direction or a numeral as its first member, (a) has a tad. affix added to it e. g. पञ्चकपाछ: (पुरोडाशः), or (b) has got a word placed after it in a compound e. g. पञ्चपवमनः or (c) has a collective sense e. g. पञ्चपूळा; cf. ताद्धे-ताथाँतरपदसमाहारे चं (P. II. 1.51) also cf. Kāś. and S. K. on P.II.1.51,52.

द्विगुपाद a popular name given by grammarians to the fourth quarter of the second Adhyāya of Pāṇini's Aṣṭādhyāyi which begins with the sūtra द्विगुरेकवचनम् II. 4.1.

द्वितीय the second consonant in the five groups of consonants, surd aspirate, cf. T. Pr. I. 11; V. Pr. I. 54, R. Pr. VI. 15; it is called द्वितीयस्पद्यों also.

द्वितीयद्विवेचन the reduplication of a root beginning with a vowel prescribed by the rule अजादेद्वितीयस्य P. VI. 1.2.

द्वितीया the second case; the accusative case, mainly prescribed for a word which is related as a karmakāraka to the activity in the sentence; cf. P. II. 3.2 to 5.

द्वित्व doubling, reduplication prescribed for (1) a root in the perfect tense excepting the cases where the affix आम is added to the root before the personal ending; e.g. बभूव, चकार, ऊणुंनाव etc. cf. P. VI. 1.1, 2; (2) a root before the Vikarana affixes सन्, यङ्, श्लु and चङ् e. g. बुभ्षति, चेक्रीयते, चक्रेरीति, जुहोति, अचीकरत् etc. cf. P. VI. 1.9-11; (3) a word ending in अम्. (প্রভূ) in the sense of repetition, e. g. स्मारं स्मारं वक्ष्ये, भोजं भोजं वजित cf. आमीक्ष्ण्ये द्वे भवतः P. VIII. 1.12 Vārt. 7; (4) any word (a) in the sense of constant or frequent action, (b) in the sense of repetition, (c) showing

reproach, or scorn, or quality in the sense of its incomplete possession, or (d) in the vocative case at the beginning of a sentence in some specified senses; reduplication is also prescribed for the prepositions परि, प्र, सम्, उप, उद्, उपरि, अधि, अधस् some specified senses A letter ex-P. VIII, 1.1 to 15. cepting ₹ and ₹, is also repeated, if so desired, when (a) it occurs after the letter gor which is preceded by a vowel e. g. अक: अद्भम् etc. cf. VIII. 4.46; or when (b) it is preceded by a vowel and followed by a consonant e. g. दद्धयत्र, मद्भवत्र cf. P. VIII. 4.47. For details see Kāś. on VIII. 4.46-52. The word दिल्ल is sometimes used in the sense of the dual number: cf. Kāś. on P. I. 2.51. The words द्वित्व, द्विवचन and द्विरुक्त are generally used as synonyms. Pānini generally uses the word दे. For द्विल्व in Vedic Literature cf. R. Pr. VI. 1.4; T. Pr. XIV. 1-8 V. Pr. IV. 101-118.

दिएण्ड्यादि a class of words, which are headed by the word दिएण्ड and which are all bahuvrtīhi compounds, to which the affix इ is found added as a Samāsānta affix e. g. दिदण्ड:, सपदि etc.; cf. Kāś. on P. V. 4.128.

द्विरुक्ति repetition of a word, or of a letter or of a root. See द्वित्व.

द्विरुचारण phonemic utterance a second time; see द्विल.

द्विरूपवत् phonemically repeated; see दिल.

द्विर्मान repetition, reduplication. See द्वित्व.

द्विचंचन see द्वित्व and द्विशक्ति; the word is very frequently used in the Mahābhāṣya instead of द्वित्व. cf. M. Bh. on I. l. Āhnika 1, I. 1.7, 10, 57, 59. etc. etc.

हिचचन a case affix of the dual number; dual number; a word in the dual number; cf. M. Bh. on I. 1.11, I. 4.21 etc.; cf. ह्योरथ्योर्वचनं द्विचचनम् Kāś. on P. V. 3.57.

द्वितचस् a word in the dual number; cf. षष्टादयश्च द्विवचोन्तभाज: R. Pr. I. 28 where the word द्विवचस् is explained as द्विवचनाभिधायिन: by Uvvata.

হিবন a syllable consisting of two consonants; cf. R. T. 245.

द्विचर्ण (1) a repeated consonant; cf. द्विचर्णसेकवर्णवत्, V. Pr. IV.144; (2) doubling, repetition; cf. हस्वपूर्वो ङकारो द्विचर्णम् T. Pr. IX. 18; cf. also T. Pr. XIV. 1. R. Pr. IX. 18.

is frequently used in connection with doubling of consonants or words in the Prātišākhya Literature as also in the Kātantra, Sākatāyana and Haima grammars cf. R. Pr. VI. 1, XV. 5, V. Pr. IV. 101, R. T. 264; cf. also Kāt. III. 8.10, Sāk. IV. 1.43; Hem. IV. 1.1.

द्विसन्धि a kind of विवृत्ति or interval of time in the pronunciation of two consecutive vowels, which as a result of two euphonic changes has a vowel preceded by a vowel and followed also by a vowel; e. g. अमृदुमा उ अंशवे, R. Pr. II. 44.

द्विस्वर possessed of two vowels, dissyllabic; cf. न पदे द्विस्वरे नित्यम् T. Pr. XVI. 17.

दिस्स्पृष्ट a term used for an upadhmānīya letter or a phonetic element resulting from a visarga followed by the letter प् or फ्. See उपध्यानीय. The word is also used sometimes for the pronunciation ळ of इ. and ळह् of इ. See दुःस्पृष्ट.

द्विहल possessed of two consecutive consonants; cf.तस्मानुङ द्विहल:, P. VII. 4. 71; cf. also M. Bh. on VI. 1.68.

हैभ्रम् used adverbially for द्विधा in the sense of 'optionally' or ' in two ways'; cf. द्वैधं शब्दानामप्रतिपत्तिः M. Bh. on P. I. 1. 44 Vart. 15.

हैपद group of two words; an expression consisting of two words; cf. प्र वीचं न: सुमना द्वैपदाश्च R. Pr. VIII. 2. 10; X. 3; XI. 37 etc.

हाच् a word possessed of two vowels in it; dissyllabic words; the word is frequently used in Pāṇini's Aṣṭādhyāyi and Patañjali's Mahābhāṣya, Kāśikā Vṛṭṭi and other works on Pāṇini's grammar.

ह्यादि a class of pronouns headed by the pronoun दि to which the taddhita affixes called विभक्ति, as prescribed by the rules of Pāṇini in the rule पञ्चम्यास्तासेल् and the following ones, are not added. cf. P. V. 3. 2.

ह्यूष्मन् name of a Samdhi made up of two spirants, or resulting in the presence of two spirants or Usman letters e.g. निष्प्रिकारी;, स्वस्ताता; cf. R. Pr. XI. 22.

ध

ध् (1) fourth letter of the dental class(तवर्ग) possessed of the properties नादानुप्रदान, घोष, कण्डसंत्रृतत्व and महाप्राण; (2) substitute ध् for the ह of नह् before a 'jhal' consonant or at the end of a word e. g. नद्धम्, उपानत; cf. P. VIII. 2. 34; (3) substitute ध् for the letters त् and ध् placed after a fourth letter, e. g. छञ्चम्, दोग्धा etc. cf. P. VIII. 2. 40.

ध a technical term in the Jainendra Vyākarāṇa for the term सर्व-नामस्थान of Pāṇini used for the first five case affixes सु, औ, अस्, अम्, औ and इ (nom. and acc. pl. neuter gender); cf. P. I. 1. 42, 43. धनजित् name of the author of a short metrical treatise on roots named धातुकल्पलतिका.

धमुञ् tad. affix optionally substituted in the place of the tad. affix धा after the words द्वि and त्रि; e. g. द्विधा, द्वेधम्, त्रिधा, त्रैधम्; cf. P. V. 3.45.

धरणीघर a grammarian of the sixteenth century at the court of Udayasimha who wrote a commentary on the sūtras of Pāṇini which was named वैयाकरणसर्वस्व as also a commentary on the Sikṣā of Pāṇini.

धमे defined as ऋषिसंप्रदाय, the traditional practices laid down by the sages for posterity; cf. केवलम् विसंप्रदाया धर्म इति कृत्वा याज्ञिकाः शास्त्रेण अनुविद्धते M. Bh. I. 1. Ahnika 1; cf. also धर्मशास्त्र in एवं च कृत्वा धर्मशास्त्रं प्रवृत्तम्, M. Bh. on P. I. 2. 64, as also धर्मसूत्रकारा: in नेवेश्वर आज्ञापयति नापि धर्मसूत्रकाराः पठन्ति अपवादैरुत्सर्गा वाध्यन्तामिति M. Bh. on I. 1.47; (2) religious merit, cf. धर्मोपदे-शनमिदं शास्त्रमारमन्नवयवेन शास्त्रायः संप्रतीयते. M. Bh. on P. VI. 1. 84, cf also ज्ञाने धर्म इति चेत्तथाऽधर्मः M. Bh. I. 1. Ahnika 1; 3) property possessed by a thing or a letter or a word. e. g. वर्णधर्म; cf. Kāś. on P. 2.29; cf. also Kāś. on P. II. 1, 55, II. 3.33, VIII. 1. 4. cf. also R. Pr. III. 8, 13 XIV. 1 etc.; (4) the characteristic of being in a substance; in the phrase अयं घट: the dharma viz.घटल is predicated of this (इदम्) or, in other words the designation pot (घटसंज्ञा) is the predication; the explanation in short, can be given as घटत्ववान इदं-पदार्थः or घटाभिन्नः इदंपदार्थः

धर्मकीर्ति a Jain scholar called by the name कीर्ति also, who was the author of धातुप्रस्थयपिक्षका and रूपावतार a well-known treatise on roots; cf. बीपदेशमहाग्राह्मस्तो वामनिदग्गजः। कीर्तिरेव प्रसङ्गेन माधवेन समुद्धृतः॥ He is believed

to have been the first grammarian who arranged the sūtras of Pāṇini according to the subject matter.

धार्मेन् (1)a thing possessed of properties, द्रव्यः cf. धर्मशब्देन धर्मी भण्यते Kas. on P.III.3.77;cf. also the common expression धर्मिग्राहकमानात् Par. Sek. on Pari. 55, 66, 79, 82; (2) the same as dharma in rare cases according to the dictum धर्मधार्मिणोरभेदोपचारः e. g. वर्णेकं देहि, पुराणैकं देहि; cf. Durghata Vr. on P, II. 1. 49.

भा tad.affix (1) applied to a numeral in the sense of a kind (प्रकार) or a division of time, e.g.एकघा, द्विधा, त्रिधा etc.; cf. P.V.3.42, 43; (2) applied to बहु to show divisions of a short time; e.g. बहुधा दिवसस्य सुङ्क्ते and बहुधा मासस्य सुङ्क्ते; cf. Kāś. on P.V.4.20.

धातु a root; the basic word of a verbal form, defined by the Bhasyakāra as क्रियावचनो धातुः or even as भाववचना घातुः, a word denoting a verbal activity. Pānini not defined the term as such. but he has given a long list of rosts under ten groups, named dasagani, which includes 2200 roots which can be called primary roots as contrasted with secondary roots. The secondary roots can be divided main two groups (1) roots derived from roots (धातुजधातव:) and (2) roots derived from nouns The roots derived (नामधातवः). from roots can further be classified into three main subdivisions: (a) causative roots or णिजन्त, (b) desiderative roots or सत्रन्त, (c) intensive roots or यङन्त and यङ्खुगन्त; while roots derived from nouns or denominative roots can further be divided into क्यजन्त, काम्यजन्त, क्यङन्त, क्यषन्त, णिङन्त, क्षित्रन्त and the miscellaneous ones (प्रकीण) as derived from nouns like কण्डू (কण्डादि) by the application of the affix यक् or from nouns like सत्य,वेद, पादा, मुण्ड, मिश्र, etc. by the application of affix णिच्. Besides these, there a few roots formed by the application of the affix आय and ईय (ईयङ्). All these roots can further be classified into Parasmaipadin or Parasmaibhāsa, Atmanepadin or Atmanebhása and Ubhayapadin. Roots possessed of a mute grave (अनुदात्त) vowel or of the mute consonant & added to the root in the Dhatupatha or ending in the affixes यङ्, क्यङ् etc. as also roots in the passive voice are termed Atmanepadin; while roots ending with the affix िच as also roots possessed of a mute circumflex vowel or a mute consonant স্applied to them are termed Ubhaya-All the rest are termed padin. Parasmaipadin. There are some other mute letters or syllables applied by Pāṇini to the roots in his Dhatupatha for specific purposes; e.g. at the end to signify prohibition of vrddhi to the penultimate अ in the aorist, e.g. अक्लीत् cf. P. VII.2.5; इर to signify the optional substitution of স or স্ভু for the affix for of the agrist, e.g. अभिदत्, अभैत्तित् ; cf. P.III.1.57; उ to signify the optional application of the augment इ (इट्) before क्ला e.g. शमित्वा, शान्त्वा; cf. P.VII. 2. 56; ऊ to signify the optional application of the augment इ (इट्) e.g. गोता, गोपिता, cf. P.VII.2.44; आ to signify the prohibition of the augment इट in the case of the past pass. part. e.g. क्ष्विण:, स्वित्र:, cf. P. VII.2.16; \(\xi\) to signify the addition of a nasal after the last vowel e. g. निन्दित from निदि, cf. P. VII.1.58; ऋ to signify the prohibition of हरन to the penultimate long vowel before णिचू, e. g. अशशासत्, cf. P.VII. 4.2; ल to signify the substitution of अङ् for िल in the aorist, e.g. अगमत्, cf. P. III.1.55; ओ to signify the substitution of q for q of the past pass.part. e.g. लग्न:, आपीन:, सून:, दून: etc.; cf. P. VIII. 2.45. Besides these, the mute syllables त्रि, दु and डु are prefixed for specific purposes; cf. P. III.2.187, III.3.89 and III. 3.88. The term घात is a sufficiently old one which is taken by Pānini from ancient grammarians and which is found used in the Prātiśākhya Nirukta and the works, signifying the 'elemental (radical)base' for nouns which are all derivable from roots according to the writers of the Nirukta works and the grammarian Sakatayana; cf. नाम च धातुजमाह निरुक्ते ब्याकरणे शकटस्य च तोकम् M. Bh. on P. III.3.1. Some scholars have divided roots into six categories; cl. तत्र घातवः षोढा (a) परिपाठिताः भूबादयः, (b) अपरिपाठिता आन्दोलयत्यादयः, (c) परिपठितापरिपठिताः (सत्रपठिताः) स्कृत्कम्भस्तम्भेत्यादयः, (d) प्रत्ययधातवः सनाद्यन्ताः, (e) नामघातवः कण्ड्रादयः, (f) प्रत्ययनामधातवः होडगल्मह्ली-बप्रमृतयः; cf. Sringāra Prak. I. For details see M.Bh. on P.I.3.1 as also pp 255, 256 Vol. VII Vyākarana-Mahabhasya published by the D.E. Society, Poona.

धातुकल्पलिका a short treatise on the roots of the different conjugations written by a grammarian named Dhanañjaya.

धातुकारिकावळी a grammatical work in verse written by Varadarāja, the pupil of Bhattojī Dīkṣita who lived in the 17th century. Besides Kārikāvalī, Varadarāja wrote তদুকীদুহা and मध्यकौमुदा also.

धातुद्गिका (1) name of a commentary on the Kavikalpadruma of Bopadeva by Rāmālaṁkāra; (2) name of a commentary on the Kavikalpadruma by Durgādāsa who wrote a commentary on the Mugdhabodha also.

ধার্ণাত (1) name given in general to the several collections of roots given generally with their meanings by grammarians belonging to the various different schools of grammar. These collections are given as necessary appendices named বিভ to their grammars by the well known grammarians of Sanskrit such as Pāṇini, Sākaṭāyana, and others: (2) a small treatise on roots written by Bhīmasena of the 14th century.

धातुपाठबृत्ति a commentary on the Dhātupāṭha by Nāgeśa.

घातुपारायण a grammatical treatise dealing with roots written as a su pplementary work by Jumaranandin to his grammar work called Rasavatī, which itself was a thoroughly revised and enlarged edition of the रचनती a commentary written by Kramadīśvara on his own grammar named संशितसार. Jumaranandin is believed to have been a Jain writer who lived in the fifteenth century A.D.

খানুসকাৰ a work dealing with roots written as a supplementary work by Balarāma-Pancānana to his own grammar named Prabodha-Prakāśa.

धातुप्रत्ययपश्चिका a work dealing with verbal forms written by Dharma-kīrti, a Jain grammarian of the eighth century.

धातुमदीप a work dealing with verbal forms written by Maitreya Raksita, a Buddhist writer and a famous grammarian belonging to the eastern part of India who lived in the middle of the twelfth century. He is believed to have written many scholarly works in connection with Pāṇini's grammar out of which the Tantrapradīpa is the most important one. The work Dhātupradīpa is quoted by Saraṇadeva, who was a contemporary of Maitreya Rakṣita, in his Durghatavṛtti on P. II. 4. 52.

धातुमञ्जरी called also धातुसंग्रह attributed to a grammarian named Kāśīnātha.

খান্ত্রমান্তা a work on roots in verseform attributed to a grammarian named Iśvarak inta.

धातुरत्नमञ्जरी a treatise dealing with roots believed to have been written by Rāmasimhavarman.

খানুংনোকং a work dealing with roots believed to have been written by Nārāyaṇa who was given the title বৃল্য. He lived in the seventeenth century; a work named ধাৰোন্তি-ত্যাক্ষণ is also believed to have been written by him.

धातुरत्नावली a short list of the important roots from the Dhātupāṭha of Pāṇini, given in verse by ভাল্লনাথ a grammarian of the 17th century.

धातुलोप an elision of a portion of a root; cf. न घातुलोप आर्धघातुके, P.I.1 4.

धातुवात्त a general term applied to a treatise discussing roots, but specifically used in connection with the scholarly commentary written by Madhavacarya, the reputed scholar and politician at the court of the Vijayānagara kings in the fourteenth century, on the Dhatupatha of Panini. The work is generally referred to as माधवीया-धात्रशति to distinguish it from ordinary commentary works called also ঘারুহবি written by grammarians like Vijayānanda and others.

धातुः याकरण a grammar dealing with verbs believed to have been written by Vangasena.

धातुसंबन्धपाद conventional name given to the fourth pāda of Pānini's Aṣṭādhyāyī which begins with the Sūtra धातसंबन्धे प्रत्यया: P. III.4.1

धातूपदेश enumeration or recital of roots in the Dhātupāṭha;cf. पकृत्युप-पदापाधयश्चोपदिशः। क्ष। धात्पदेश प्रातिपदिको-पदेश च। M. Bh. on P. III. 1. 1.

धात्वर्थे lit. meaning of a root, the verbal activity, named किया or भाव: cf. धात्वर्थ: किया; M. Bh. on III.2. 84, III.2.115. The verbal activity is described generally to be made up of a series of continuous subordinate activities carried on by the different karakas or agents and instruments of verbal activity helping the process of the main activity. When the process of the verbal activity is complete, the completed activity is looked upon as a substantive or dravya and a word denoting it, such as पाक, or याग does not get conjugational affixes, but it is regularly declined like a noun Just as स्वार्थ, द्रब्य, लिङ्ग, संख्या, and कारक are given as प्रातिपदिकार्थ, in the same manner দ্বিয়া, কান্ত, ৭ুম্ব, वचन or संख्या, and कारक are given as चात्वर्थ, as they are shown by 'a verbal form, although strictly speaking verbal activity (क्रियां भाव) alone is the sense of a root, as stated in the Mahabhasya. details see Vaiyāk.Bh.Sāra, where it is said that fruit (4.78) and effort (ब्यापार) are expressed by a root. cf. फलब्यापारयोधांतु:. The five senses given above are in fact conveyed not by a root, but by a verb or आख्यात or तिङन्त.

धान्यपाद a popular name given to the

second pāda of the fifth adhyāya of Pāṇini's Aṣṭādhyāyī possibly because the pāda begins with the Sūtra धान्यानां भवने क्षेत्र खञ्, P. V.2.1.

धारण (1) suppression of a consonant, out of two successive consonants which is looked upon fault of recital; e.g. ह्वयामि when recited as वयामि; ef. धारणमनुपलब्धः Uvvața on R.Pr.XIV. 6; (2) repetition of a consonant which is also a fault; e.g. ज्ज्योतिष्कृत् for ज्योतिष्कृतः cf. Uvvata on XIV.6;cf. also घारयन्त; परक्रमं etc. explained by Uvvata as सान्तस्थस्य संयोगस्य आदी रक्तं धारयन्तो विलम्बमानाः परक्रमं कुर्वन्ति where धारयन्तः means 'lengthening' or 'prolonging' cf. R.Pr. on XIV.23; (3) the pecullar position of the mouth (मुखसं-धारणम्) by which a double consonant is recited as a single one, cf. द्विवर्णमेकवर्णवत् (एकप्रयत्ननिवत्ये) धारणात् e.g. ब्यात्तम् , कुक्कुट:, cf. V.Pr. IV.144.

খি (1) a technical term used for sonant consonants in the Prātišākhya and old grammar works; cf. ঘি হালঃ V. Pr. I.53, explained by Uvvata as বৰ্গাणা ওব্যক্তমন্ত্ৰ: যুক্তমনুষ্ঠা ঘি: V Pr. I.53; the term ঘি corresponds to হ্য of Pāṇini; (2) personal ending ঘি substituted for হি of the impera. 2nd sing. e.g. ভুহুছি, ভিন্তি, মিন্তি, স্থুছি, যুগেল etc.; cf. P.V.4.101-103.

ষ্ট a technical term in the Jainendra Vyākaraņa for খান্ত (a root) which is used freely by the ancient grammarians and Pāṇini.

धर (1) the augment घू prefixed to the consonant स् following upon the consonant ह or न occurring at the end of a word; e.g. श्रुल्सिये, महान्त्साये etc.; cf. P. VIII.3.29; (2) technical short term for घातु (root); the technical term is धुष्, but the nom. sing. used is धुट्; (3) a technical term standing for con-

sonants excepting semi-vowels and nasals; cf. ঘুতন্ত ঘুটি Kāt. III.6.51. The term is used in the Kātantra Vyākaraṇa. It corresponds to the term ল্লাব্ of Pāṇini.

धुना tad. affix called Vibhakti tad. affix, applied to the word इदम् when इदम् is changed into अ; cf. इदम: अश्माव: धुना च प्रत्यय: Kāś. on P. V. 3.17.

খুমাই a class of words headed by the word ঘুম to which the tad.affix সক (নুস্) is added in the miscellaneous (মাজিক) senses; e. g. ঘামক: আড্ক: etc.; cf Kās. on P.IV.2.127.

भृत or भृतप्रचय a kind of original grave vowel turned into a circumflex one which is called प्रचय unless followed by another acute or circumflex vowel. The Taittirīya Prātiśākhya has mentioned seven varieties of this 'pracaya' out of which भृतप्रचय or भृत is one. For details see Bhāsya on भृत: प्रचय: कौण्डिन्यस्य, T.Pr.XVIII.3.

ध्य tad. affix ध्य applied to the words भाग, इप and नाम in the same sense as those words possess;e.g.भागध्यम्, cf. Kāś. on P. V.4.25.

ध्मात name of a fault in the pronunciation of a vowel when on account of fullness of breath it appears as uttered long (दोषे), although really it is short; cf. श्वासभूयिष्ठतया हुस्वोपि दीने इव लक्ष्यते, Kaiyaṭa on I. I. Āhnika 1. Vārt. 18.

ध्यम् tad. affix ध्यमुञ् substituted for धा optionally after the word एक e. g. ऐकध्यम्, एकधा; cf. P. V. 3.44.

ध्ये krt affix ध्ये seen in Vedic Literature, substituted for त्या optionally; e. g. साढ्ये, साढ्वा; cf. P. VI. 3.113. भुव (1) fixed, stationary, as contrasted with moving (द्वन) which is termed अपादान and hence put in the ablative case; cf. द्वनमपायेऽपादानम् P. I. 4.24; (2) repeated sound (नाद) of a third or a fourth consonant of the class consonants when it occurs at the end of the first word of a split up compound word; cf. R. Pr. VI. 11 and XI. 24.

भ्रोट्य fixed; of a stationary nature; of क्तोऽधिकरणे च श्रोड्यगांतिप्रत्यवसानार्थेभ्यः P. III. 4.76.

ध्विन (1) sound; cf. ध्विन कुवैनेवमुच्यते— शब्द कुरु शब्दं मा कार्षी: M. Bh. I. 1. Ahnika 1; cf. also Vāk. Pad. I. 77; cf. also स्फोट: शब्द:, ध्विन: शब्दगुण:, M.Bh. on I. 1.70 Vārt. 5. ध्विन or sound is said to be the indicator (स्चक or ब्यञ्जक) of स्फोट the eternal sound.

ध्वनित suggested, as opposed to उक्त expressed; the word is found frequently used in the Paribhāṣenduśekhara and other works in connection with such dictums as are not actually made, but indicated in the Mahābhāsya.

ভবান personal-ending of the sec. pers. pl. Ātmanepada, substituted for ভূ of the 10 lakārəs.

ध्वात personal-ending in Vedic Literature, substituted for ध्वम् of the sec. pers. pl. Atmanepada; e. g. वारयध्वात् for वारयध्वम् cf. P. VII. 1.42.

ध्वान the second out of the seven positions of voice in the Veda recital which are—उपांग्र, ध्वान, निमद, उपाब्दमत्, मन्द्र, मध्यम and तार.

pl. Atmanepada in the present and perfect tenses.

न

न fifth consonant of the dental class of consonants which is possessed of the properties घोष, नादानुप्रदान, अल्पप्राणत्व, संवृतकण्ठत्व and आनुनासिक्य. In Pāṇini's grammar the nasal consonant न् (a) is added as an augment prescribed नुद् or नुम् which originally is en as न, but afterwards changed into अनुस्वार or प्रसवर्ण as required, as for example in प्यांसि, यशाँभि, निन्दति, वन्दति etc.; cf. P. VII. 1.58-73, VII. 1.79-83; VIII. 3.24; (b) is changed into m when it directly follows upon 来, 泵, ¿ or ą or even vowel, intervened by а semivowel except ऌ, a guttural a labial consonant. consonant or an anusvāra; cf. P. 4.1.1-31. (c) is substituted for the final म of a root, e.g. प्रशान, प्रतान् cf. P. VIII. 2.64, 65.

न (1) the consonant न (see न above) with the vowel added to it for facility of utterance, cf. T. Pr. I. 21; (2) tad. affix न added to words headed by पामन् in the sense of possession; e.g. पामन:, हेमन; etc., cf. P. V. 2.100; (3) tad. affix = as found in the word ज्योलना derived from ज्योतिष्, cf P. V. 2.114; (4) unādi affix न as found in the word स्योन:; cf. Kāś. on P. VI. 4.19; (5) the krt affix नङ् as also नन् prescribed after the roots यज्, याचु, यत्, विच्छ्, प्रच्छ्, रक्ष् and स्वप्, e g. यज्ञ:, याच्या, प्रश्न: etc., cf. P. III. 3.90, 91; (6) the negative particle न given by Pāṇini as नज् and referred to in the same way, which (i.e. न.) when compounded with a following word, is changed into अ or अन् or retained in rare cases as for instance in नम्राट्, नासत्यो, नक्षत्रम् etc. cf.P.VI.3.73-75;(7) tad.affix ন (নজ্) applied to the words स्त्री and पुंस् in senses given from P. IV. 1.92 to V. 2.1 e. g. क्लेंग, पंस्तम् cf. IV. 1.87.

नकार the consonant न to which the vowel अ and the affix कार are added for facility of utterance; e.g. तथा नकार उदय नकार R. Pr. IV. -; cf. V. Pr. I. 17, 21.

नङ् krt affix न applied to the roots यज्, याच्, यत् and others in the sense of verbal activity; e. g. यज्ञ; याच्ञा, यत्न: etc. cf. P. 1II. 3.90, 91. See न (5).

নজিক্ kit. affix নল্ applied to the roots লেণ্, নূল্ and খুলু in the sense of 'habituated' e. g. লেমক্ খুল্পাক্; see Kāś. on P. III. 2.172.

नम् the negative particle (नजू)
which possesses the six senses
which are sketched as साहस्यं तदमावश्च
तदन्यत्वं तदस्यता । अप्राशस्त्यं विरोधश्च नजर्थाः
षट् प्रकीतिंताः and which are respectively illustrated by the
examples अनिक्षः शरः, भूतले घटो नास्ति,
अघटः पटः, अनुदरसुदरं तरुण्याः, अश्राह्मणो
चार्धुविकः and असुरः दैत्यः। See न (6).

নহনদ্বেত a compound with ন as its first member which is changed into জ or জন, or remains unchanged, the indeclinable ন (ন জ্) possessing any one of the six senses given above under ন (6); e. g জনাৱন, জনস্ব:, নদানি: etc.; cf. P. VI. 3. 73-77.

as its first member; the term is found used in the Mahābhāṣya for both the नञ्तसुहष as well as the नञ्बहुनीहि compounds; cf. M. Bh. on P.I.4.1 Vart, 19, also on P.II.1.1.

नञ्स्वर्वलीयस्त्व the superiority, or strength of the accent caused by नञ्समास which sets aside the accent caused by the case affix; cf. विभक्तिस्वराजञ्चरे वलीयान् P. VI, 2.158 Vart. 13,

नहादि (1) a class of words headed by the word नह to which the tad. affix आयन (पक्) is added in the sense of गोत्र (grandchild and further descendants); e. g, नाहायनः, चारायणः; cf. Kāś. on P. IV.1. 99; (2) a class of words headed by नह to which the affix ईप (छ) is added, together with the augment क placed after the word and before the affix, in the four senses prescribed in P. IV.2. 67-70; e.g. नहकीयम्, प्रक्षकीयम्; cf. Kāś. on P. IV. 2. 91.

नत cerebralized; changed into ण्.
The change of the consonant न्
into ण् is called नित in the old
Prātiśākhya works; cf. स्परो वोष्मणि
चानते R. Pr. IV. 11.

नाति lit. inclination, bending down; the word is used generally in the technical sense of 'cerebralization' but applied to the change of न into ण as also that of स into घु; cf. दन्त्यस्य मूर्धन्यापत्तिर्नेति:, V. Pr.I. 42. The root नम् is used in the sense of 'cerebralizing ' or 'being cerebralized very frequently in the Prātisākhya works; e. g. the word नम्यते is used in the sense of 'is cerebralized '; नमयति in the sense of 'cerebralizes' and नामिन् in the sense of 'causing cerebralization'; cf. ऋकारादयो दश नामिनः स्वराः, पूर्वो नन्ता नित्य नम्यमुत्तरम् R. Pr. I. 27.

नदीं a technical term applied in Pāṇini's grammar to words in the feminine gender ending in ई and ऊ excepting a few like स्त्री, श्री, श्रू and others; it is optionally applied to words ending in इ and उ, of course in the fem. gender, before case affixes of the dative, ablative, genitive and locative sing. The term was probably in use before Pāṇini and was taken from the fem. word नदी which was taken as a model. Very

probably there was a long list of words like नद (नदर्) चोर (चोरर्) etc. which were given as ending in र and to which the affix ई (डीप्) was added for forming the feminine base; the first word नदी so formed, was taken as a model and all words in the list and similar others were called नदी; cf. P. I. 4. 3-6.

नद्ध a fault of pronunciation when a letter, although distinctly pronounced inside the mouth, does not become audible, being held up (वद्ध) by the lips or the like. The fault is similar to अम्बूकृत; cf. ओडा-भ्यामम्बूकृतमाह नद्धम् R.Pr.XIV.2.

नदादि a class of words headed by नदी, मही and other fem. nouns to which the taddhita affix एय (ढक्) is added in the miscellaneous (शैषिक) senses; e.g. नादेयम्, मोह्यम्, वाराणसेयम्, श्रावस्तयम् etc.; cf. Kāś. on P.IV.2.97.

नन् kit affix न applied to the root स्त्रप् to show verbal activity; e.g. स्वप्नः cf.P.III.3,91.

नन्तु one that causes cerebralization; cf. पूर्वो नन्ता नितंषु नम्यमुत्तरम् R.Pr.I.27. See नित.

नन्द् सुन्द्र a Jain grammarian who wrote a gloss (अव चूरि) on the हैमशब्दानुशासनवृत्ति.

निद्केश्वर an ancient grammarian who has written a short work in verses on grammar in general, which is named निद्केश्वरकारिकासूत्र. There is a scholarly commentary upon it written by उपमन्य.

निद्केश्वरकारिका a short treatise of 28 stanzas, attributed to an ancient grammarian निद्केश्वर, which gives a philosophical interpretation of the fourteen sūtras attributed to God Śiva. The authorship of the treatise is assigned traditionally to

the Divine Bull of God Siva. See नन्दिकेश्वर. The treatise is also named नन्दिकेश्वरकारिकास्त्र.

निद्केश्वरकारिकाविवरण called also निद्केश्वरकारिकाटीका a gloss written by Upamanyu on निद्केश्वरकारिका. See निद्केश्वरकारिका.

नन्धादि name given to the class of roots beginning with the root नन्द्, which includes the roots वाश्, मद, दूत् वृष्, शुभ् and others as given in the Ganapatha. These roots have the affix ल्यु i.e. अन added to them in the sense of agent. e.g. नन्दनः, वाशनः, मदनः, वर्षनः शाभनः, रमणः, दर्पणः, जनादनः, यवनः etc.; cf. P.III.1.134.

नपुंसक lit. a word which is neither in the masculine nor in the feminine gender; a word in the neuter gender; cf. R.Pr.XIII.7, V. Pr. II. 32; III.138; cf. P. VI.3.75, on which the Siddhanta Kaumudi observes न स्त्री पुमान नपुंसकम्। स्त्रीपुंसयोः पुसकमावो निपातनात्।

नपुंसकस्वर the special accent viz. the acute accent for the first vowel for nouns in the neuter gender excepting those that end in इन्, as prescribed by निव्यवस्थानिसन्तस्य Phitsūtra 11; cf. नपुंसकस्वरो मा भूत् M.Bh. on P.VII.1.77.

नम्य capable of being cerebralized. See नति

नर person; personal ending; the term is used in connection with (the affixes of) the three persons प्रथम, मध्यम, and उत्तम which are promiscuously seen sometimes in the Vedic Literature; cf. सुतिङ्कपग्रहिलङ्कनराणां ... ब्यत्ययमिन्छति ... M. Bh. on III.1.85.

नरेन्द्रस्रि an old grammarian believed to have been the original writer of the Sārasvata Vyākaraṇa, on the strength of references to him in the commentary on the Sārasvata Vyākaraņa written by क्षेमेन्द्र as also references in the commentary on the Prakriyākaumudī by Vitthaleśa. He is believed to have lived in the tenth century A;D.

नरेन्द्राचार्य the same as नरेन्द्रसूरि. See नरेन्द्रसूरि.

नलोप elision of न्, which in Pāṇini's grammar is sometimes taken as valid for certain grammatical operations, and otherwise for other operations; cf. नलोप: सुप्स्वरसंज्ञातुन्विधिषु कृति P.VIII.2.2.

नवगणी a term used in connection with the first nine ganas or conjugations given by Pāṇini in his Dhātupāṭha, the tenth conjugation being looked upon as a secondary conjugation.

নিমারিকা name given to the first nine Ahnikas or lessons of the Mahābhāṣya which are written in explanation of only the first pāda of the first Adhyāya of Pāṇini's Aṣṭādhyāyī and which contain almost all the important theories, statements and problems newly introduced by Patañjali.

नव्यमत a term used for the differentiation in views and explanations held by the comparatively new school of Bhaṭṭojī Dīkṣita, as contrasted with those held by Kāśikā-kāra and Kaiyaṭa; the term is sometimes applied to the differences of opinion expressed by Nageśabhaṭṭa in contrast with Bhaṭṭojī Dikṣita. For details see p.p. 23-24 Vol.VII of the Pātañ-jala Mahābhāṣya ed. D.E. Society, Poona.

as a synonym of 'lupta'in some commentaries.

नष्टस्पा name given to an anustup verse which has nine, ten and eleven syllables respectively for the first, second and third feet; e.g. विपृच्छाभि पाक्यान् देवान् R.V.I.120.4; cf. R.Pr. XVI. 29. The verse has got 32 syllables, but it has only three feet instead of four.

ना (1) tad. affix ना as also नाज् prescribed respectively after वि and नज् (negative particle न) in the sense of separation; e. g. विना, नाना; (2) case ending ना substituted for the ins. sing. affix टा (called also आइ in ancient grammars) in the masculine gender after words called वि i.e. words ending in इ or उ excepting such as are called नदी.

नागेश the most reputed modern scholar of Panini's grammar, who was well-versed in other Sastras also, who lived in Benares in the latter half of the seventeenth and the first half of the eighteenth century. He wrote many masterly commentaries known by the words शेखर and उहयोत on the authoritative old works in different Sastras, the total list of his small and big works together well nigh exceeding a hundred. He was a bright pupil of Hari Diksita, the grandson of Bhattoji He was a renowned teacher also, and many of the famous scholars of grammar in Benares and outside at present are his spiritual descendants. was a Mahārāstrīya Brāhmaņa of Tāsgaon in Sātārā District, who received his education in Benares. For some years he stayed under the patronage of Rāma, the king of Sringibera at his time. He was very clever in leading debates in the various Sastras and won the title of Sabhāpati. Out of his numerous works, the Uddyota on Kaiyaṭa's Mahābhāṣyapradīpa, the Laghuśabdenduśekhara on the Siddhānta Kaumudī and the Paribhāṣenduśekhara are quite well-known and studied by every one who wishes to get proficiency in Pāṇini's grammar. For details see pp. 21-24 and 401-403, Vol. VII of the Pāṭañjala Mahābhāṣya ed. D. E. Society, Poona.

नाञ् see नाः

नाटच् tad. affix नाट applied to the prefix अन optionally with the affixes टीटच् and भटच्; e. g. अननाटम्, अनटीटम्, अनभ्रटम्; cf. Kāś. on P. V. 2.31.

नाद् (1) voice; resonance; tone; the sound caused by the vibration of the vocal chords in the open glottis when the air passes through them; cf. वर्णोत्परयननारमानी अनुरणनरूपः शब्दः नादः Uddyota on M. Bh. on P. I. 1.9; cf. also संद्रते कण्ठे यः शब्दः कियते स नादसंज्ञो मनति T. Pr. II. 4; (2) sound, articulate sound generally without sense, which is momentary; (3) the highest sound. See परा.

नादानुप्रदान having voice (नाद) as their main cause; a term used in connection with vowels and sonant consonants which are caused by नाद: cf. नाद: अनुप्रदानं स्वरघोष्ठवस्म । अनुप्रदीयते अनेन वर्ण: इति अनुप्रदानं मूळ-कारणम्, com. on T. Pr. II. 8.

नादि (a root) beginning with न in the Dhātupātha as contrasted with one beginning with ण् (णादि) whose ण् is, of course, changed into न् when conjugational and other forms are arrived at; cf. सर्वे नादयो णोपदेशा रातिनान्दनार्दनाञ्चनाष्ट्रनाथ्चनाधृनुवर्जम् M.Bh. on VI. 1.65.

नादिन possessed of नाद; sonorous, resonant. See नाद.

नानापद different words as opposed to समानपद or a single word;cf.V.Pr. III. 80; T.Pr. XXIV. 3, XX. 3.

नान्तरीयक absolutely necessary; being, in a way, inseparable; cf. कश्चि-दन्नार्थी शालिकलापं सतुषं सपलालमाहरति नान्तरीयकत्वात् M. Bh. on P. III. 3.18 on which Kaiyaṭa observes अन्तरशब्दो विनार्थे । अन्तर भवमन्तरीयम् । तत्र नञ्समास कृते पृषोदरादित्वाद्धाष्यकारवचन-प्रामाण्याद्वा नलापामावः ।

नापुंसक the same as नपुंसकालिङ्ग or neuter gender; cf. नापुंसकं भवेत्तास्मन् । नपुंसके भवं नापुंसकम् M. Bh. on IV. 1.3.

नाम् the genitive affix आम् together with the augment न prefixed to it; cf. नामि P. VI. 4. 3.

নামর a word or noun derived from a noun, as opposed to ধারুর a word derived from a root.

नामधातु a denominative root; the term सुङ्घातु is also used for नामधातु; cf. सुङ्घातुर्नीमधातुरिभधीयते Nyāsa on P. VI. 1.3. See the word धातु.

नामन noun, substantive; one of the four categories of words given in the Nirukta and other ancient grammer works; cf. चत्वारि पदजातानि नामाख्याते चोपसर्गनिपाताश्च, Nir. I.1. The word is defined as सत्त्वप्रधानानि नामानि by standard grammarians; cf. Nir. I. 1.; cf. also सत्त्वाभिधायकं नाम, R. Pr. XIII.8; V. Pr. VIII. 49 and com. thereon. Pāņini divides words into two categories only, viz. सुबन्त and तिङन्त and includes नामन् , उपसर्गे and निपात under सुबन्त. The Singaraprakasa defines नामन as follows-अनपेक्षितशब्दब्युत्पत्तीनि सत्त्व-भूताथों भिधायों नि नामानि । तानि द्विविधानि । आविष्टलिङ्गानि अनाविष्टलिङ्गानि च । The word नामन at the end of a sasthitatpurusa compound signifies a name or Samija e. g. सर्वनामन, दिङ्-नामन्, छन्दोनामन्; cf. also. Bhasavitti on संज्ञायां कल्थाशीनरेषु P. II.4. 20 and संज्ञायां भृतू • P. III. 2.46 where the author of the work explains the word संज्ञायां as नाम्नि. The word is used in the sense of 'a collection of words' in the Nirukta, cf. अन्ति-रिक्षनामानि, अपत्यनामानि, ईश्वरनामानि, उदकनामानि, etc.

नामिलङ्गानुशासन a treatise in which words with their genders are given. The term is usually used in connection with the great dictionary by अमरसिंह which is called नामिलङ्गानुशासन or अमरकोष.

नामिन् (vowels) which cause cerebralization; the ten vowels क, ऋ, इ, ई, उ, ऊ, ए, ओ, ऐ, ओ; cf. ककारा-द्यो दश नामिनः स्वराः R. Pr. I. 27. cf. also R.T. 94. See the word नति. The word मिन् is used for नामिन् in the Vājasaneyi Prātis'ākhya; cf. अकण्ठयो मानी V. Pr. I. 46; cf. also नामिपरो रम् Kāt. I.5.12.

नारायण (1) name of a grammarian who wrote a commentary on the Mahābhāṣya-Pradīpa; (2) a grammarian who is said to have written a gloss named Śabdabhūṣaṇa on the Sūtras of Pāṇini as also some minor works named चाब्दमञ्जरी, राब्दभेदानिहपग, etc.

নাংখেতাব্যন্ত্য a grammarian of the seventeenth century who wrote a treatise on grammar named Sārāvalī, and a treatise on roots named Dhātupārāyaṇa.

नाज्यवधान necessary intervention; cf. येन नाज्यवधानं तेन ज्यवाहितेषि वचनप्रामाण्यात्, a statement which is looked upon as a general statement of the nature of Paribhāṣā occurring in the Mahābhāsya on P. VII. 2.3.

নাহা elision, the word is used in grammar as a synonym of lopa.'

नासिकास्थान a place in the nose where a nasal letter such as इ, ज़, ज, न or म् and anusvara get a tinge of nasalization while passing through it. The yama letters e.g. the nasal क्, ख्, ग्, घृ get nasalization in the utterance of the words पलिनियनः, चाल्यनतुः, अभियः, ध्वन्तिः, cf. यमा नाम वर्णः प्रातिशारन्य प्रसिद्धः S.K. on P. VIII. 2. 1. cf. also यमानुस्वारनासिक्यानां नासिके V. Pr. I. 74, R. T. 12.

नासिक्य letters or phonetic elements produced in the nose; cf. नासिकायां यमानुस्वारनासिक्या: R. T. 12. See ५ (नासिक्य).

नि (1) personal ending substituted for मि (मिप्) of the 1st pers. sing, in the imperative; (2) a technical term in the Jainendra Vyākaraņa for the term निपात of Pāṇini.

निःसंख्य not possessed of any numbersense; the term is used in connection with indeclinables; cf. अब्यये-म्यस्तु निःसंख्येभ्यः सामान्यविहिताः स्वादयो विद्यन्त एव Kās. on P.I. 4.21.

निःसंधि deprived of Samdhi; without any euphonic combination or euphonic change.

निक् augment नि as seen in the reduplicated syllable किन of the aorist form किनकदत् of the root कन्द्र; cf. कन्देर्छुङि च्लेरङादेशो द्विवचनमभ्यासस्य चुत्वाभावो निगागमश्च निपात्यते । अक्रन्दीदिति भाषायाम्; Kāś. on P.VII.4.65.

ानेगम a statement in the Vedic passage; a Vedic passage; sacred tradition or Vedic Literature in general; cf. the frequent expression इत्यपि निगमा भवति where निगम means word, given instance'; it also means 'Veda'; cf. निगम एव यथा स्यात्। M. Bh. on VII. 2. 64. Durgācārya says that the word it also used in the sense of 'meaning';cf. तत्र खले इत्यंतस्य निगमा भवन्ति Nir. III.9. Durgācārya has also explained the word as गमयन्ति मन्त्रार्थान् ज्ञापयन्ति इति निगमा:, those

that make the hidden meaning of the Mantras very clear.

निमार a kind of sound which apparently is made up of a combination of three phonetic elements ह, म and नासिक्य. It is a peculiar sound through both the mouth and the nose, although no specific place of production is assigned to it; cf. अविशेषस्थानी संस्वीदिनगारी। हकार-मकारनासिक्या वा निगारे R.T.11.

निघण्ड a name given to a collection of words which are mainly Vedic. In ancient times such collections were possibly very general and numerous and the works or treatises on derivation such as the Nirukta of Yāska were based upon them; cf. निघण्डव: कस्मात् । निगमा इम भवन्ति । छन्दोभ्यः समाहृत्य समाहृत्य समाम्नातास्त निगन्तव एव सन्तो निगमनान्निचण्टव उच्यन्त इत्योपमन्यवः। अपि वा आहननादेव समाहता भवन्ति। यद्दा समाहृता (Nir.I.1) where the word is derived from गम् or इन् or हृ. The word निघण्ड is taken as synonymous with निगम by Durgācārya.

निघात toning down; the grave accenting the root निहन् in its various forms is used in the sense of toning down the voice and the word निघात is used in the sense of the grave accent (अनुदात्तस्वर) in the Vyākaraņa and Prātišākhya works; cf. also the words शेषिनघात, सर्वनिघात, etc.; cf. समानवाक्ये निघातयुष्मदस्मदोदशा: P. VIII. 1.18 Vārt. 5.

निङ् substitute नि for the last letter of the word जाया at the end of a bahuvrihi compound; cf. युवजानि:, चढजानि: Kāś. on P.V. 4.134.

निचृत less by one syllable; the word is used as an adjective to the name of a Vedic metre which has got one syllable less than the normal; cf. एकद्रयूनाधिक: सैव निचृ-

द्नाधिका भुरिक् R.Pr.XVII.1.

नित् an affix possessed of the mute indicatory letter न, the word characterized by which has the acute accent on the vowel of the first syllable; e. g. गार्थ:, वाल्य:, cf. Kāś. on P.VI.1.197.

नित्य (1) eternal, as applied to word or sabda in contrast with sound or dhyani which is evanescent (कार्य). The sound with meaning or without meaning, made by men and animals is impermanent; but the sense or idea awakened in the mind by the evanescent audible words on reaching the mind is of a permanent or eternal nature; cf. स्काट: शन्दो ध्वनिस्तस्य न्यायामादुपजायते; cf. also न्यातिमत्त्वातु शन्दस्य Nir.I.1; (2) constant; not liable to be set aside by another; cf. उपबन्धस्तु देशाय नित्यम् , न रन्धे नित्यम् । नित्यशब्दः प्राप्त्यन्तरनिषेघार्थः T.Pr.I.59, IV.14; (3) original as constrasted with one introduced anew such as an augment; cf. T. Pr. VI.14; (4) permanently functioning, as opposed to tentatively doing so; cf. नित्यविरते द्विमात्रम् R. T.37; (5) unchangeable, permanent, imperishable; cf. अयं नित्यशब्दी-स्त्येव कुटस्थेष्वविन्त्रालिषु भावेषु वर्तते M.Bh. on P. VIII. 1.4; (6) always or invariably applying, as opposed to optional; the word in this sense is used in connection with rules or operations that do not optionally apply; cf. उपपदसमासो नित्यसमासः, षष्टीसमासः पुनार्विभाषाः; M. Bh. on P.II.2.19; (7) constant, as applied to a rule which applies if another simultaneously applying rule were to have taken effect, as well as when that other rule does not take effect; cf. कचित्कृताकृतप्रसङ्गमा-त्रेणापि नित्यता Par. Sek. Pari 46. The operations which are nitya according to this Paribhasa take

effect in preference to others which are not 'nitya', although they may even be 'para'; cf. पराजित्यं बलवत् Par. Sek. Pari. 42.

नित्यबळीयस्त्व possession of greater force; the word is used in connection with rules that are called नित्य. See नित्य (7).

नित्यसमास an invariably effective compound; the term is explained as अस्वपद्विप्रहों नित्यसमास: i. e. a compound whose dissolution cannot be shown by its component words as such; e. g. the dissolution of कुम्मनार: cannot be shown as कुम्म कारोति स:। The upapadasamāsa, the gatisamāsa and the dative tatpuruṣa with the word अर्थ are examples of नित्यसमास.

नित्यानन्द्पर्वतीय a scholar of Sanskrit Grammar who wrote glosses on the Mahābhāsyapradīpa, on the Laghuśabdenduśekhara and on the Paribhāsenduśekhara. He was a resident of Benares where he coached many pupils in Sanskrit Grammar. He lived in the first half of the nineteenth century.

निद्दीन illustration; cf. पर्याप्ती ह्येक: पुलाक: स्थाल्या निद्दीनाय M.Bh. on I. 4. 23 Vart. 15; cf. also इला साल्हा चात्र निद्दीनानि R. Pr. I. 22.

निपात a particle which possesses no gender and number, and the case termination after which is dropped or elided. Nipāta is given as one of the four categories of words viz नामन्, आख्यात, उपसर्ग and निपात by all the ancient writers of Prātisākhya, Vyākaraṇa and Nirukta works; cf. Nir. I. 4, M.Bh. on I. 1. Āhnika 1, R. Pr. XII. 8 etc. The word is derived from the root पत् with नि by Yāska who has mentioned three subdivisions of Nipātas ज्यमार्थ,

कर्मोपसंग्रहार्थे and पदपूरण; cf. अथ निपाता:। उचावचेष्वर्थेषु निपतन्ति । अप्युपमार्थे । अपि कर्मोपसंग्रहार्थे । अपि पदपुरणाः । Nir. I. 4. The Nipātās are looked upon as possessed of no sense; cf. निपात: पादपुरणः R. Pr. XII. 8, V. Pr. VIII. 50, (com. by Uvvata). Pāņini has not given any definition of the word निपात, but he has enumerated them as forming a class with \(\frac{1}{2} \) at their head in the rule चादयोऽसत्त्वे where the word असरवे conveys an, impression that they possess no sense, the sense being of two kinds सत्त्व and भाव, and the Nipātās not possessing any one of the two. The impression is made rather the statement of the firm by Vārttikakāra-" निपातस्यानर्थकस्य प्राति-पदिकल्वम् " P. I. 2. 45 Vārt. 12. Thus, the question whether the Nipātas possess any sense by themselves or not, becomes a difficult one to be answered. Although the Rkprātiśākhya in XII.8 lays down that the Nipatas are expletive, still in the next verse it says that some of them do possess sense; ef. निपाता-नामर्थवेशानिपातनादनर्थकानामितरे च सार्थका:on which Uvvata remarks केचन निपाता: सार्थका:, केंचन निरर्थका: | The remark of Uvvata appears to be a sound one as based on actual observation, and the conflicting views have to be reconciled. This is done by Bhartrhari who lays down that Nipatas never directly convey the sense but they indicate the sense. Regarding the sense indicated by the Nipatas, it is said that the sense is never Sattva or Dravya or substance as remarked by Pānini; it is a certain kind of relation and that. too, is not directly expressed by them but it is indicated. Bhoja in his Srngaraprakasa gives a very comprehensive definition of Nipata

as:-जात्यादिप्रवृत्तिनिमत्तानुपप्राहित्वेनासत्त्वभूतार्थाभिधायिनः अलिङ्गसंख्याशक्तय उच्चावचेष्वर्थेपु
निपतन्तीत्क्व्ययविशेषा एव चादयो निपाताः।
He gives six varieties of them, viz.
विध्यर्थे, अर्थवादार्थे, अनुवादार्थे, निषधार्थे,
विधिनिषेधार्थे and अविधिनिषेधार्थे, and
mentions more than a thousand of
them. For details see Bhartrhari's
Vākyapadīya II. 189-206.

निपातद्योतकत्व the view that the nipātas and the upasargas too, as contrasted with nouns, pronouns and other indeclinables, only indicate the sense and do not denote it; this view, as grammarians say, was implied in the Mahābhāsya and was prominently given in the Vākyapadīya by Bhartihari which was followed by almost all later grammarians. See निपात.

निपातन a word given, as it appears, without trying for its derivation in . authoritative works of ancient grammarians especially Pāṇini;cf.दाण्ड-नायनहास्तिनायन॰ P. VI.4.174, as also . अचतुरिबचतुर॰ V.4.77 etc. etc. phrase निगतनात्सिद्धम् is very frequently used by Patanjali to show that · some technical difficulties in the formation of a word are not sometimes to be taken into consideration, the word given by Panini being the correct one; cf. M.Bh.on I.1.4, III.1.22 etc. etc.; cf. also the usual expression बाधकान्येव निपात-नानि. The derivation of the word · from पत् with नि causal, is suggested in the Rk Prātisākhya where it is stated that Nipatas are laid down or presented as such in manifold senses; cf. R. Pr.XII.9; cf. also घातुसाधनका छानां प्राप्त्यथे नियमस्य अनुबन्घविकाराणां रूळार्थं च निपातनम् Bh. Pradipa on P. V.1.114; cf.also M. Bh. on II.1.27.

निपातनस्वर the accent, with which the

Nipātana word is expressed in the Sūtra, which is said to prevail over the accent which ordinarily should be possessed by the word; cf. स निपातनस्वर: प्रकृतिस्वरस्य बाधको भविष्यति M.Bh. on P.I.1.56 Vārt. 23; cf. also M.Bh. on I.3.3, VI.1.123 etc.

निपातानथैकत्व the view prominently expressed by the Varttikakara that nipatas do not possess any sense, which was modified by Bhartthari who stated that they do possess sense which, of course, is indicated and not expressed. See निपात.

निपाताव्ययोपसर्गवृत्ति a short treatise explaining and illustrating the use of indeclinables, written by a grammarian named तिलक who probably lived in Kaśmīra.

निमद् a mode of utterance of words at the performance of a sacrifice. Seven such modes are given in the Taittiriya Prātiśākhya; cf. उपाग्रध्वान-निमदोपन्दिमन्मन्द्रमध्यमताराणि T. Pr. XXIII. 5.

निमित्त (1) the formal cause of a grammatical operation; cf. निमित्तामाने नैमित्तिकस्याप्यमानः given as a Paribhāṣā by many grammarians like Vyāḍi, Sīradeva and others; cf. also प्रकृत्युपपदोपाधयो निमित्तं प्रत्ययो निमित्तं M.Bh. on III.1.1 Vārt. 2; (2) distinguishing sign यः प्रेक्षापूर्वकारी मनित सः अञ्ज्ञेण निमित्तेन ध्रुवं निमित्तमुपादत्ते वेदिकां पुण्डरीकं ना, M.Bh. on I.1.26 Vārt.5.

निमित्तसप्तमें locative case, used in the sense of a cause as prescribed by निम्तालक्रमसंयोगे, P. II.3 36 Vārt. 6 and illustrated by the usually quoted verse चर्मणि द्वीपिनं हन्ति दन्तयोहीन्ति, कुज्जरम्। केशेषु चमरीं इन्ति सीम्नि पुष्कलको हतः M.Bh.on II.3.36 Vārt. 6, also cf. Kāś. on P. I.1.57.

निमित्तापायपरिभाषा a popular name given by grammarians to the maxim निमित्तापाये नैभित्तिकस्याप्यपायः, a thing, which is brought into existence by a cause, disappears on the disappearance of the cause. The maxim is not, of course, universally applicable. For details see Par. Sek. Parī. 56, Sira. Pari. 99.

निमित्तिन् an affix or an augment or a substitute taking place on account of certain formal causes or nimitas; cf. निर्ज्ञातार्थों निमित्तमनिर्ज्ञातार्थों निमित्तमनिर्ज्ञातार्थों निमित्तम, इह चं प्रत्ययोऽनिर्ज्ञातः प्रकृत्युपपदो-पाघयो निर्ज्ञाताः M. Bh. on III. 1.1 Vart. 2.

विशासिश fixed; the word नियत is used in grammar in connection with the nimitta or nimittin in a grammatical operation prescribed by a rule, which, or a part of which, is shown to be superfluous unless there is laid down a regulation; cf. शेषप्रहणं कर्तन्थम्। शेषनियमार्थम्। प्रकृत्यथां नियती प्रत्यमा अनियतास्ते शेषिप प्राप्तुवन्ति M.Bh. on I.3.12 Vart. 6; (2) The grave accent; cf. उदात्तर्य नियतं... स्वयंते R.Pr.III.9.

नियतस्वर (1) an affix whose accent is definitely given by an indicatory mute letter applied to it, cf. M.Bh. on I.1.3; (2) the grave accent; a syllable with a grave accent; grave vowel; cf. नियतस्वरोदये R.Pr.XI.25; (3) name of a Samdhi when a visarga is changed into रेफ and then omitted and the preceding vowel is lengthened; cf. हस्तस्याकाम-नियता उमाविमौ R.Pr. IV.9; cf. also P. VIII.3.14 and VI.3.111.

नियम (1) restriction; regulation; binding; the term is very frequently used by grammarians in connection with a restriction laid down with reference to the application of a grammatical rule generally on the strength of that rule,

or a part of it, liable to become superfluous if the restriction has not been laid down; cf. M.Bh. on I. 1. 3, Kāś. on I. 3.63, VI. 4.11: cf. also the frequently quoted dictum अनियमे नियमकारिणी परिभाषा; (2) limitation as contrasted with विकल्प or कामचार: cf. अनेकप्राप्तावेकस्य नियमो भवति रोषेष्वनियमः पटुमृदुशुक्काः पटुशुक्रमृदव इति: M. Bh. on II. 2. 34 Vart. 2: (3) a regulating rule; a restrictive rule, corresponding to the Parisamkhyā statement of the Mīmāmsakas, e.g. the rule अनुदात्ति आत्मनेपदम् P. I.3.12; the grammarians generally take a rule as a positive injunction avoiding a restrictive sense as far as possible; cf, the dictum विधिनियमसंभवे विधिरेव ज्यायान्. Par. Sek. Pari. 100; the commentators have given various kinds of restrictions, such as प्रयोगनियम,अभिधयनियम,अथनियम, प्रत्ययनियम, प्रकृतिनियम, संज्ञानियम etc.etc.; (4) grave accent or anudātta; cf. उदात्तपूर्वे नियतम् R. Pr. III. 9; see नियत (2).

नियामक limiting; limitative; cf. तुः क्रियते । स नियामको भविष्यति । अमेवापञ्चम्याः इति M. Bh. on II. 4.83; cf. also लोके निमित्तं द्विविधं दृश्म् । कार्यास्थितौ नियामकं तदनियामकं च Par. Sek. Pari. 56.

नियोग an obligatory order or command, such as that of a preceptor, as contrasted with स्वमाव; cf धातो: परः अकारोऽकशब्दो वा नियोगतःकर्तारं ब्रुवन्कृत्संज्ञश्च भवति स्वभावतः कर्तारं ब्रुवन्कृत्संज्ञश्च भवति etc. M. Bh. on P. III. 4.67 Vart. 8 where Kaiyaṭa explains नियोग as आन्वार्यनियोग.

निरनुनासिक pure, unnasalized, as opposed to सानुनासिक nasalized. cf. सन्ति हि यणः सानुनासिका निरनुनासिकाश्चं। M.Bh. on I. 1. Ahnika 1.

निरनुबन्धक possessed of no mute indicatory letter; not possessed of any mute indicatory letter; ६६. क

पुनस्यं (आकारः) सानुबन्धकः क निरनुबन्धकः। M.Bh. on I. 1.14.

निरनुबन्धकपरिभाषा a short term used for the maxim निरनुबन्धकग्रहण न सानुबन्धकस्य ग्रहणम् Par. Sek. Pari. 81.

निरवकारा possessed of no scope of, or occasion for, application; the word अनवकारा is also used in this sense. The niravakāśa rules always set aside the general rules which are always present wherever they i. e. the niravakāsa rules are possible to be applied. Niravakāśatva is looked upon as one of the two criteria for ৰাঘ or sublation, the other one being सामान्यविशेषमान as illustrated by the usual maxim, known as तककोण्डिन्यन्याय. See तककोण्डिन्यन्याय; cf. also अनवकारा हि विधयो बाधका मनन्ति Par. Sek. on Pari. 64.

निरस्त a fault of pronunciation when a vowel is harshly pronounced and hence is not properly audible; cf. निरस्तं निष्ठुरम् Pradīpa on M.Bh. I. I. Ahn. I. The fault occurs when the place and the means of utterance are pressed and drawn in;cf. निरस्तं स्थानकरणायक R. Pr. XIV. 2.

निराकृत (1) set aside; answered; the word is frequently used in connection with faults which are stated to occur or present themselves if a particular explanation is given; (2) prevailed over by another; cf. तदा न रूपं लगते निराकृतम् R. Pr. XI. 30, where Uvvața paraphrases निराकृत as विस्मृत.

were composed to explain the collections of Vedic words by means of proposing derivations of those words from roots as would suit the sense. The Nirukta works are looked upon as supplementary to grammar works and there must have been a good many works of

this kind in ancient times shown by references to the writers of these viz. Upamanyu, Sakatāyana, Sākapūņi, Sākapūrti and others, but, out of them only one work composed by Yāska has survived; the word, hence has been applied by scholars to the Nirukta of Yāska which is believed to have been written in the seventh or the eighth century B. C. i.e. a century or two before Panini. The Nirukta works were looked upon as subsidiary to the study of the Vedas along with works on phonetics (হিাধ্বা), rituals (কল্प), grammar (ब्याकरण) prosody (छन्देस्) and astronomy(ज्योतिष)and a mention of them is found made in the Chandogyopanisad. As many of the derivations in the Nirukta appear to be forced and fanciful, it is doubtful whether the Nirukta works could be called scientific treatises. The work of Yāska, however, has got own importance and place among works subsidiary to the Veda, being a very old work of that kind and quoted by later commentators. There were some glosses and commentary written upon Yaska's Nirukta out of which the one by Durgācārya is a scholarly one. It is doubtful whether Durgācārya is the same as Durgasimha, who wrote a Vrtti or gloss on the Katantra Vvakarana. The word farm is found in the Pratisakhya works in the sense of 'explained'and not in the sense of derived; cf. R. Pr. XV6; V.Pr. IV. 19, 195.

निरुक्तभाष्य a gloss on Yaska's Nirukta written by a modern scholar of grammar named Ugrācārya in the eighteenth century A. D.

निरुद्कादि a class of compound words

headed by the word निरुदक which have their last vowel accented acute; e. g निरुदकम्, निरुपलम्, निर्मक्षिकम् etc.; cf. Kāś. on P. VI. 2. 184.

निरूट প্রয়া potentiality of implication which gives the meaning of a word which is based upon implication; e. g. रथो गच्छति.

निरूदोपंघ a word, the penultimate vowel in which is picked up and taken back, as for instance the penultimate अ of हन् in the word अहस् cf. अहितश्च अहश्च अहुश्च हन्तेर्निरूदोपंघा- द्विपरीतात् Nir. IV. 25.

निर्दिश्यमानपरिभाषा a short form for the maxim निर्दिश्यमानस्यादेशा भवन्ति which means 'substitutes take the place of that or its part which has been actually stated or enunciated in the rule (of grammar)' Par. Sek. Pari. 12. For details see Par. Sek. Pari. 12.

निर्दिष्ठ exhibited, enunciated; cf. तस्मिन्निति निर्दिष्ट पूर्वस्य P.I.1.66; V.Pr.I.

निर्दिष्टपरिभाषा a popular name of the Paribhāṣā तास्मिनिति निर्दिष्ट पूर्वस्य । टि. किं चेह निर्दिष्टपरिभाषाप्रद्यतिर्दुर्वचा । Pari. Bhāskara Pari. 97.

निर्देश mention, actual statement; the word is often used in the Mahābhāṣya in sentences like स तथा निर्देश: कर्तन्थ:, निर्देश कुरुते etc.; cf. also V.Pr. I. 36; cf. also the maxim तास्मिनिति निर्देश पूर्वस्य P. I.1. 66 and V. Pr. I. 134; cf. also अवस्यं क्याचिद्रिभक्त्या केन-चिद्रचनेन निर्देश: कर्तन्थ: M.Bh. on P. I. 2. 39 Vārt. I. Sometimes the mention or exhibition made by a word shows the particular type of word; cf. Durghata Vitti on P. I. 2. 6 and VII. 4. 73 as also Kāś. on P. IV. 3. 11 and V. 2. 20.

निर्धारण (1) selection of one or some out of many; cf. जातिगुणिक्रयाभिः समुदायादे- कदेशस्य पृथक्करणं निर्धारणम् । मनुष्याणां मनुष्येषु

वा श्रीत्रयः श्रूरतमः Kaś. on P. II.2.10 as also on II.3.41; (2) determined or definite sense to the exclusion of another, generally on the strength of the indeclinable एव which is expressed or understood. The word निर्धारण is used for अवघारण in this sense; cf. यत एवकारस्ततोन्यत्राव-घारणम् a maxim used as a Paribhāṣā by some grammarians; cf. also घातोस्तिविमित्तस्यैव । घात्ववधारणं यथा स्याचित्र-मित्तावधारणं मा भूदिति Kāś. on P. VI. 1.81.

निर्बद्ध separated, dissociated, disconnected; cf. न निर्वडा उपसर्गा अर्थात्रिराहुरिति शाकटायन: Nir. I.3.

निर्भुज a name for the Samhitapatha; cf. निर्भुजं संहिताध्ययनमुच्यते R. Pr.I. 3.

निर्मेलद्पेण name of a commentary on the Prakriyā–Kaumudī.

निर्हर name of a grammarian who is believed to have written a gloss (बृत्ति) on the Sūtras of Pāṇini on the strength of a reference to him in the Nyāsa of Jinendrabuddhi; cf. वृत्तिः पाणिनीयसूत्राणां विवरणं चुिक्तभिट्टिनिर्द-रादिप्रणीतम् Nyāsa on I.1.1.

নিব্যান interpretation by means of etymology as found in the Nirukta works; the act of fully uttering the meaning hidden in words that are partially or wholly unintelligible in respect of their derivation, by separating a word into its component letters; cf. নিজ্ফ্য বিশ্ব নিব্যান Durgavitti on Nir. II. 1. For details see Nirukta II.1.

निर्वर्तक (1) productive, as opposed to expressive; cf. िकं पुनरिदं निर्वर्तकम् । अन्तरतमा अनेन निर्वर्त्यन्ते । आहोस्वित्यति पादकम् । अन्यन निर्वर्त्यन्ते । आहोस्वित्यति पादकम् । अन्यन निर्वर्त्तानामनेन प्रतिपत्तिः । M.Bh. on P.I.1.50 Vart. 1; (2) productive of activity; cf. साधकं निर्वर्तक कारकसंत्रं भवतीति वक्तव्यम्; M. Bh. on I.4.23.

कदेशस्य पृथकरणं निर्धारणम् । मनुष्याणां मनुष्येषु | निर्वत्यं one of the many kinds of kar-

man or object governed by a transitive verb or root, which has got the nature of being produced or brought into existence or into a new shape; cf. त्रिविधं कर्म निर्वर्त्य विकाय प्राप्य चेति । निर्वर्त्य तावत् कुम्मकारः नगरकारः। The word निर्वर्त्य तावत् कुम्मकारः नगरकारः। The word निर्वर्त्य is explained as यदसज्जन्यते यद्दा प्रकाद्यते तिर्वर्त्तर्यम् । कर्तव्यः कटः। उच्चार्यः शब्दः Sr. Prakasa; cf. also Vākyapadīya III.7.78; cf. also इह हि तण्डुळानोदनं पचतीति द्वर्ययः पचिः। तण्डुळानपचन्नोदनं निर्वर्त्यति । M. Bh. on I.4.49. For details see the word कर्मन्; also see M.Bh. on I.4.49.

निर्नेति production of the effect; production of the activity by the agents or instruments of activity called Kārakas; cf. साधने हि कियां निर्वर्तयित तामुपसर्गो विश्विनीष्ट M.Bh. on II. 2.19 Vārt. 2.

निहेत a fault of pronunciation by which a letter is uttered harsh or rude; cf. निहेतो छक्ष: Kaiyata on M. Bh.I.1. Ahnika 1

निर्ह्यास (1) abridgment, diminution; cf.सर्वयचनं प्रकृतिनिह्णासार्थम् । निर्ह्धासः अपचयः अल्पत्वमित्यर्थः । Kaiyaṭa on M.Bh.on IV.3.100; (2) being turned into a short (vowel); cf. स्पर्शान्तस्थाप्रत्ययौ निर्हसेते R.Pr.IV.39.

निवर्तक lit. expeller, excluding other forms which are otherwise, that is, incorrect; cf. समाने चार्थे शास्त्रान्यितः अशास्त्रान्वितस्य निवर्तको भवति । M.Bh. on I.1. Siva Sūtra 2.

निवर्ष्य that which should not proceed to the next rule; cf. तच्चावस्यं निवर्षम् M.Bh. on III.2.68, V.1.16, etc. See the word निवृत्ति.

निवात sometimes used for निवात or the grave accent.

निवृत्ति (1) cessation of recurrence of a word or words from a rule to a subsequent rule or rules; non-application of a rule consequent upon the cessation of recurrence or anuvṛtti cf; न ज्ञायते केनाभिप्रायेण प्रसजित केन निवृत्ति करोति M. Bh. on P. 1.1.44 Vart. 8. cf. also एकयोगनिर्दिष्टानां सह वा प्रवृत्तिः सह वा निवृत्तिः Kāt. Par. Vṛ. Pari. 9; (2) cessation or removal; cf. न च संज्ञाया निवृत्तिरूच्यते । स्वभावतः संज्ञा संज्ञिनः प्रत्याच्य निवर्तन्ते । तेन अनु-बन्धानामि निवृत्तिर्भविष्यति M. Bh. on I. 1.1. Vārt. 7; cf. also M. Bh. on I. 1.3 etc.; cf. also the usual word उदात्तिवृत्तिस्वरः

निश्चित्तस्थान places where the substitutes गुण and वृद्धि do not apply; weak terminations; kit or nit affixes in Pāṇini's grammar; cf. अथाप्यस्तेर्निश्चत्तस्थानेष्वादिलेपो भवति । स्तः सन्तीति । Nir. II. 1. The word संक्रम is also used in this sense by ancient grammarians.

निष्कादि a class of words headed by the word निष्क to which the affix इक (ठक्) is added, provided these words are not members of a compound; e. g. निष्ककम, पादिकम, माधिकम् etc.; cf. Kāś. on P. V.1.20.

निष्क्रष्ट separated; taken out from a thing; existing only in conception or idea; cf. इह केचित्रुणाः शब्देन द्रज्यानिष्कृश एव प्रत्याय्यन्ते न तु द्रज्यस्यो-परञ्जकत्वेन । यथा चन्दनस्य गन्धः इति । Kaiy. on P. II. 2. 8.

निष्ठा the affixes क्त and क्तवत् in Pāṇini's Grammar; cf. क्तकवत् निष्ठा .P. I. 1.26.

निष्टित also नि:ष्टित completed, accomplished; used in connection with a grammatically formed word by applying affixes to the bases; cf. अङ्गवृत्ते पुनर्वृत्तावविधिर्निष्ठितस्य Siradeva Pari. 94, where Siradeva has explained the word निष्ठित as प्रयोगाई-अङ्ग.

निहत struck down in tone, grave, possessed of a grave accent; cf. V. Pr. IV. 138.

निहित separated with the intervention of a consonant. The word is used in connection with the detached first part of a compound word not followed immediately by a vowel; cf. अनिहितं अन्यवहितम् Uvvata on V. Pr. V. 30.

नीक् augment नी affixed to the reduplicative syllables of the roots भण, वञ्च, स्त्र, ध्वंम, भ्रंस् कस्, पत, पद and स्कन्द in the intensive; e. g. आपनी-फगत्, वनीवच्यते etc. cf. P. VII. 4.65 and 84.

नीच a term used for the grave accent or for the vowel, accented grave; cf. खरितयोर्मध्ये यत्र नीचं स्प्रात् T. Pr. XIX. 1. उन्नीचे में नीचमुचात् R. T. 54, 55 cf. also V. Pr. I. 111.

नीचे:कर constituting the grave accent, features of the grave accent; cf. अन्ववसर्गो मार्दवमुस्ता खस्येति नीचे:कराणि शब्दस्य M.Bh. on I. 2.30.

नीलकण्ठ author of वैयाकरणसिद्धान्तरहस्य a commentary on the Siddhanta Kaumudi of Bhattoji Dikșita.

नीलकण्डदीक्षित a famous grammarian of the seventeenth century who wrote an independent work on the Paribhāṣās in Vyākaraṇa named Paribhāṣāvṛtti. This Vṛtti is referred to in the Paribhāṣenduśekhara by Nāgeśabhaṭṭa and the views expressed in it are severely criticised in the com. गदा.

नीलकण्डमांखन nephew of Appaya Dīkṣita who has written a commentary on Kaiyaṭa's Mahābhāṣyapradīpa. चुक् augment न् (1) affixed to the words अन्तर्वत् and पतिवत् before the feminine affix छीप् e. g. अन्तर्वत्नी, पतिवत्नी, cf. P. IV. 1.32; (2) affixed to the root ली before the causal affix णिच्, e. g. विलीनयित, cf. P. VII. 3.39; (3) affixed to the reduplicative syllable of roots ending in a nasal consonant and having the penultimate अ as also of the roots जप्, जभू, दह्, दश्, भञ्ज, पश्, चर्, and पल्ल in the intensive; e. g. जङ्गम्यते, तन्तन्यते, यंयमीति, जङ्गमीति, जङ्गम्यते, दन्दद्यते, दन्दद्यीति. चञ्च्यते, पम्पुल्लीत cf. P. VII 4.85, 86, 87.

नुद् augment न prefixed (1) to the gen. pl. ending in आम् after a crude base ending in a short vowel, or in ई or ऊ of feminine bases termed nadī, or in आ of the feminine affix (टाप्, डाप् or चाप्); e.g. अझीनाम्, कत्णाम्, कुमारीणाम्, मालानाम् etc.; cf. P. VII.1.54; (2) to the affix आम् after numerals ed षर and the numeral चतुर as also after the words श्री, ग्रामणी and गी in . Vedic Literature, e.g. जणाम , पञ्चानाम्, चतुर्णाम्, श्रीणाम्, ग्रामणीनाम, गोनाम्; cf. P. VII.1.55, 56, 57; (3) to the part of a root possessed of two consonants, as also of the root अश् of the fifth conjugation after the reduplicative ending in आ, which is substituted for अ; e.g. आनञ्ज, ज्यानदो; cf. P.VII.4. 71,72; (4) to the affix मतुष after a base ending in अन् as also to the affixes तरप् and तमप् after a base ending in \(\) in Vedic Literature, e.g. मूर्घन्वती, अक्षण्वन्तः, सुपथिन्तरः etc.;cf. P. VIII. 2.16, 17; (5) to the initial vowel of the second member of a compound having अ of नज् as the first member; e. g. अन्य:, cf. P.VI. 3.74; (6) to any vowel after न् which is preceded by a short vowel

and which is at the end of a word e.g. कुर्वनास्त, cf. P. VIII. 3.32.

नुम् augment न inserted after the last vowel (1) of a root given in the Dhatupatha as ending with mute इ; e.g. निन्दति, क्रन्दति, चिन्तयति, जिन्यति etc.; cf. P VII.1.58; (2).of roots सुच् and others before the conjugational sign अ (श); e. g. मुञ्जात, ल्रम्पति; cf. P, VII.1.59; (3) of the roots मस्ज, नश्, रध्, जभू and लभ् under certain specified conditions, e.g.मङ्क्त्वा, नेष्टा, रन्धयति, जम्भयति, लम्भयति, आलम्भ्यः etc. cf. P.VII. 1.60-69; (4) of declinable bases marked with the mute indicatory letter ত, ক or ন as also declinable wording অহনু from the root अञ्च and युज्, e.g.भवान, श्रयान्, प्राङ्, युङ्, cf. Kās. on P. VII.1. 70, 71; (5) of the declinable base in the neuter gender, ending with a vowel or with any consonant excepting a semivowel or a nasal, before a case-ending termed Sarvanāmasthāna; e.g. यशांसि, वनानि, जत्नि etc., cf. Kāś. on VII.1.72; (6) of the declinable base in the neuter gender, ending with इ, उ, ऋ or ल before a case-ending beginning with a vowel; e.g. मध्ने, श्चिने etc., cf. Kāś. on P. VII.1.73; (7) of the affix হানু (अন্ of the pres. part.) under certain conditions याती यान्ती; पचन्ती, सीब्यन्ती, cf. 1.VII.78-8; (8) of the word अনুভু before the nom. and voc. sing. affix सु;e.g. अनड्वान्, हे अनड्वन, cf. P. VII. 1. 82; (9) of the words ह्रकू, स्ववस and स्वत्वस before the nom. and voc.sing.affix सु in Vedic Literature, e.g. याहङ्, स्ववान्, स्वतवान्, cf. P.VII.1.83.

नुमागम augment न् inserted after the last vowel of a root or a noun-base in specified cases. See नुम्.

नुचक्ष name of the second Yama letter,

नेमस्पृष्ट partly touched, half touched; semi-contacted; a term used for sibilants and hissing sounds.

नैका च multisyllabic, possessed of many syllables, as contrasted with एकाच्. नैगम(1) belonging to the Veda, Vedic as opposed to लाकिक or भाषिक; cf. नैघण्डुकानि नैगमानीहेह Nir.I. 20; (2) name given to Kāṇḍas 4, 5 and 6 of the Nirukta of Yāska; cf. अनवगत-संस्कारा जहादयो यस्मिनिगम्यन्ते तन्नेगमं Durga Vṛ. on Nir IV.1.

नैघण्डुक mentioned as secondary; lit. निभण्डुकाण्डे वर्तमानानि पदानि; the term is applied to the first three Kāṇḍas or sections of the Nirukta.

नेपातिक accessory; accidental; निपातात् आगतानि.

नौमित्तिक effect; one that is caused; cf. निमित्ताभावे नैमित्तिकस्याप्यभावः a Paribhāṣā given by Vyāḍi, Sīradeva and others.

नैरुक्त (1) obtained by derivation, etymological; (2) etymologist, writer of a Nirukta work.

नैर्देशिक matter of communication; statement made for communication. Uddyota explains the word as निर्देश: बोधः प्रयोजनमस्य नैर्देशिकः । cf. एते खड्यपि नैर्देशिकानां वार्ततरका भवन्ति ये सर्वनाम्ना निर्देशाः क्रियन्ते M. Bh. on P. I.1.67.

नैवासिक tad. affixes अण and others added in the sense of 'तस्य निवास: '(P. IV. 2. 69), as in words like शैव meaning the place of residence of the Sibis.

न्यक् a technical term in the Jainendra Vyākaraṇa for the term उपसर्जन defined by Pāṇini in the rules प्रथमानिर्दिष्टं समास उपसर्जनम् and एक-विभक्ति चा पूर्वानिपाते P.I.2.43, 44.

न्यङ्कुसारिणी a kind of बृहती metre in which the second foot has twelve syllables, while the rest have

eight syllables each; cf. द्वितीय न्यड्कुसारिणी R.Pr.XVI.32.

न्यङ्कादि a class of words headed by the word न्यङ्कु, which are formed by means of the substitution of a guttural consonant in the place of a consonant of any other class belonging to the root from which these words are formed; e. g. न्यङ्कु: भन्गु:, भृगु: etc.; cf. Kās. on P. VII.3. 53.

न्यच् going lower, subordinate, the word is used in the sense of upasarjana as a technical term in the Jainendra Vyākaraṇa, cf. बोक्तं न्यक् Jain. Vy.I.1.93.

स्यवग्रह also नीचावग्रह, the vowel at the अवग्रह or end of the first member of a compound word which has got a grave accent; e.g. the vowel ऊ of नू in तनूनम्बे; cf. उदायन्तो न्यवग्रह-स्ताथाभाव्यः V. Pr. I. 120. See ताथाभाव्य.

न्यस्त name given to अनुदात्त or the grave tone; cf मात्रा न्यस्ततरैकेषामुभे व्यालि: समस्त्रेर R. Pr. III. 17 where Uvvata explains न्यस्ततरा as अनुदात्त्तरा.

न्याय maxim, a familiar or patent instance quoted to explain similar cases; cf. the words अमाकरवाणि-न्याय M. Bh. on P. II 2,24, अपवाद-न्याय M. Bh. on P. I. 3. 9, आवर्ष-कन्याय M. Bh. on P. IV. 1. 88, 89, IV. 2.60, IV.3.131, V. 1.7, 28, VI 2. 11; क्रम्भीधान्यन्याय M.Bh. on P. I. 3.7, कृपखानकन्याय M.Bh. I. 1. Ahnīka 1, दण्डिन्याय M.Bh. on P. VIII.2.83, नष्टाश्वदग्धरथन्याय M. Bh. on P. I.1.50, प्रधानाप्रधानन्याय M.Bh.on P.II.1.69, VI. 3.82, प्रासादवासिन्याय M. Bh. on P. I. 1.8, मांसकण्टकन्यायM. Bh. on P.I.2.39, ल्ट्वानुकर्षणन्याय M.Bh. on Siva Sūtra 2 Vart. 5, शालिपलालन्याय M.Bh. on P. 1.2.39, सूत्रशाटकन्याय M.Bh. on P. I.3. 12. The word came to be used in the general sense of Paribhāṣās

or rules of interpretation many of which were based upon popular maxims as stated in the word लोकन्यायसिद्ध by Nāgesa. Hemacandra has used the word न्याय for Paribhāṣā-vacana. The word is also used in the sense of a general rule which has got some exceptions, cf. न्यायैमिश्रानपवादान् प्रतीयात् R. Pr. which lays down the direction that one should interpret the rule laying down an exception along with the general rule'.

Vyākaraņa Paribhāṣās or maxims as found in Hemacandra's system of grammar, written by Hemahamsagaņin, a pupil of Ratnasekhara, in 1451. The author has written a commentary also on the work, named Nyāsa.

न्यायसंग्रह a work enumerating the Paribhāṣās in Hemacandra's grammar, numbering 140 nyāyas out of which 57 nyāyas are said to have been given by Hemacandra himself at the end of his comment बृहद्वृत्ति on his Sabdānuśāṣana. The work is written by हेमहंसगणि who has added a commentary to it called Nyāyārthamañjūṣa by him, which is also known by the name न्यायरत्नमञ्जूषा which see above.

न्यायसंहित combined euphonically according to rules of grammar; cf. तद्वति तद्वितं न्यायसंहितं चेत् explained as ब्याकरणशास्त्रोक्तसंधिमत् V. Pr. V. 8 com.

न्यायिद्ध established by a maxim; with full justification; cf. न्यायसिद्धमेवैतत् M. Bh.on V.1.19. The word is used as opposed to ज्ञापकासिद्ध by Nagesa; cf. Par. Sek. Pari. 1.

न्यायार्थमञ्जूषा a name given to न्यायं-रत्नमञ्जूषा, See न्यायस्तमञ्जूषा.

न्याय्य proper; fully justified न्यायादन-पेतम् cf. P.IV.4.92; correct; regular; cf. यत्रज्ञभ्यामुक्तत्वादर्थस्य न्याय्योत्पत्तिनं भविष्यति M. Bh. on II.3.1 where Kaiyata however, explains the word differently. Kaiyata states that न्यास्य means a general rule; cf.उत्सर्गः पूर्वीचार्यप्रसिद्ध्या न्यास्य उच्यते Kaiyata on P. II. 3.1. By Pūrvācārya he possibly refers to the writers of the Prātišākhyas and other similar works by ancient grammarians, where the word nyāya is used in the sense of 'a general rule'. See the word न्याय above.

न्यास (1) lit. position, placing; a word used in the sense of actual expression or wording especially in the sūtras; cf. the usual expression कियते एतन्न्यास एव in the Mahabhasya, cf. M. Bh. on I. 1.11, 1.1.47 etc.; (2) a name given by the writers or readers to works of the type of learned and scholarly commentaries on vritti-type-works on standard sūtras in a Sāstra; e. g. the name Nyasa is given to the learned commentaries on Vrtti on Hemacandra's Sabdānusasana as also on the Paribhāṣāvṛtti by Hemaharnsagani. Similarly the commentary Devanandin on Jainendra grammar and that by Prabhacandra on the Amoghāvrtti on Sākatāyana grammar are named Nyāsa. the same way, the learned commentary on the Kasikavrtti by Iinendrabuddhi, named kāvivaranapanjikā by the author, is very widely known by the name Nyāsa. This commentary Nyāsa was written in the eighth century by the Buddhist grammarian Jinendrabuddhi, who belonged to the eastern school of Pānini's Grammar. This Nyasa has a learned commentary written on Maitreya Raksita in the twelfth century named Tantrapradīpa which is very largely quoted by subsequent grammarians, but which unfortunately is available only in a fragmentary state at present. Haradatta, a well-known southern scholar of grammar has drawn considerably from Nyāsa in his Padamañjarī, which also is well-known as a scholarly work.

न्यासोइचोत a learned commentary on Jinendrabuddhi's Nyāsa written by Mallinātha, the standard commentator of prominent Sanskrit classics.

न्यून incomplete in sense or wording as opposed to Pūrņa; cf. अयनावे न्यूने (पाद न संनिकृष्येते) R. T. 76.

प

प् (1) first consonant of the labial class of consonants possessed of the properties श्वासानुप्रदान, अवेष, and कण्डिविन्नतत्व; (2) प् applied as a mute letter to a suffix, making the suffix accented grave (अनुदात्त).

प, पकार the consonant प, the vowel अ and the affix कार being added for facility of understanding and pronunciation; cf. T.Pr. I. 17, 21; प is also used as a short term for consonants of the fifth class (पन्गे); cf. T. Pr. 1.27; V. Pr. I. 64 and R. T. 13.

पक्ष alternative view or explanation presented by, or on behalf of, a party; one of the two or more ways of presenting a matter. The usual terms for the two views are पूर्वपक्ष and उत्तरपक्ष, when the views are in conflict. The views, if not in conflict, and if stated as alternative views, can be many in number, e.g. there are seven alternative views or Paksas re:

the interpretation of the rule इको गुणवृद्धी; cf. M. Bh. on P. I. 1.3; cf. also सर्वेषु पक्षेत्र उपसंख्यानं कर्तेब्यम् M. Bh. on P. I. 2.64.

पक्षादि a class of words headed by the word पक्ष to which the taddhita affix आयन (पक्) causing viddhi is added in the four senses given in P. IV. 2.67-70; e. g. पाक्षायण:, आक्ष्मायन: etc.; cf. Kāś. on P. IV. 2.80.

प्रचादि a class of roots headed by the root पन् to which the krt. affix अ (अन्) is added in the sense of 'an agent'; e. g. श्वपन्यः, चोरः, देवः etc. The class पन्यादि is described as आकृतिगण and it is usual with commentators to make a remark पन्यायन् when a krt affix अ is seen after a root without causing the viddhi substitute to the preceding vowel or to the penultimate vowel अ. cf. अज्याधनार्थमें स्वात् सच्यन्ति भ्यान्तर्यः । अज्याधनार्थमें स्यात् सिच्यन्ति श्वपन्यादयः Kās. on P.III. 1.134.

पञ्चपदी a term used in the Atharva-Prātiśākhya for the strong case affixes viz. the nominative case affixes and the accusative sing, and dual affixes; cf. चत्नारि क्षेप्रञ्च पञ्चपद्मामन्तोदात्तादीनि यात् A. Pr. I. 3.14. The term corresponds to the Sarvanāmasthāna of Pāṇini, which is also termed सुट्; cf. सुडन-पुंसकस्य P. I. 1.43.

पञ्चम the fifth consonant of the five classes of consonants; the nasal consonant, called also वर्गपञ्चम; cf. यथा तृतीयास्तथा पञ्चमा आनुनासिक्यवर्जम् M. Bh. on P. I. 1.9 Vart. 2.

पञ्चमी (1) the fifth case; ending of the fifth or ablative case as prescribed by rules of Pāṇini cf. अपादाने पञ्चमी, P. II. 3-7, 10, etc. (2) the imperative mood; cf. Kāt.III.1.18. पञ्चमीनिद्रा statement by the abla-

tive case, cf. ङ: सि धुट् P. VIII. 3.29; cf. उभयनिर्देशे पञ्चमीनिर्देशे बलीयान् e. g. ङमो हस्वादचि ङमुण्नित्यम् P. VIII. 3.32, Par. Sek. Pari. 70; cf. also उभयनिर्देशे विप्रतिषेधात्पञ्चमीनिर्देशः M. Bh. on P. I. 1.67 Vart. 3.

प्रज्वालपदवृत्ति the usage or the method of the Pancalas; the eastern method of euphonic combinations, viz. the retention of the vowel अ after the preceding vowel ओ which is substituted for Visarga; e. g. यो असी; cf. R. Pr. II. 12; T. Pr. XI. 19. vowel a which is retained, is pronounced like a short ओ or अर्ध-ओकार by the followers of the Sātyamugri and Rāṇāyanīya branches of the Samavedins; cf. commentary on T. Pr. XI. 19 as also M. Bh. Ahnika 1.

पश्चिमा a popular name given to critical commentaries by scholars; cf. काशिकाविवरणपश्चिमा by Jinendrabuddhi which is popularly known by the name न्यास.

पटच् tad. affix पट in the sense of extent (विस्तार) added to the word अवि; e. g. अविपटम् cf. विस्तारे पटज्यक्तब्यः. P. V. 2.29 Vart. 2.

पठन oral recital, the word is used in connection with the use of words by the author himself in his text which he is supposed to have handed over orally to his disciples, as was the case with the ancient Vedic and Sutra works; cf. the words पठित, पठिष्यते, पठ्यते and the like, frequently used in the Mahābhāṣya in connection with the mention of words in the Sūtras of Pāṇini.

पण्डित writer of Cītprabhā, a commentary on the Paribhāṣenduśekhara. A commentary on the Laghuśabdenduśekhara is also aṣcribed to him. He was a Gauda Brāhmaṇa whose native place was Kurukṣetra. He lived in the beginning of the nineteenth century.

पतञ्जाले the reputed author of the Mahābhāsya, known as the Pātañjala Mahābhāsva after him. His date is determined definitely as the second century B.C. on the strength of the internal evidence supplied by the text of the Mahabhasya itself. The words Gonardiya and Gonikāputra which are found in the Mahābhāsya are believed to be referring to the author himself and, on their strength he is said to have been the son of Gonika and a resident of the country called Gonarda in his On the strength of the internal evidence supplied by the Mahait can be said that bhasya, Pataniali received his education at Taksasilā and that he was, just like Pāṇini, very familiar with villages and towns in and near Vahika and Gāndhāra countries. Nothing can definitely be said about his birthplace, and although it might be believed that his native place was Gonarda, its exact situation has not been defined so far. About his parentage too, no definite information is available. Tradition says that he was the foster-son of a childless woman named Gonika to whom he was handed over by a sage of Gonarda, in whose hands he fell down from the sky in the evening at the time of the offering of water-handfuls to the Sun in the west; cf. पतत् + अञ्जलि, the derivation of the word given by the commentators. Apart from anecdotes and legendary information, it can be said with certain-

ty that Patanjali was a thorough scholar of Sanskrit Grammar who had studied the available texts of the Vedic Literature and Grammar and availed himself of information gathered personally by visiting the various schools of Sanskrit Grammar and observing the methods of explanations given by teachers there. His Mahabhasya supplies an invaluable fund of information on the ways in which the Grammar rules of Pānini were explained in those days in the various grammar schools. This information is supplied by him in the Vārttikas which exhaustively given and explained. He had a remarkable mastery over Sanskrit Language which was a spoken one at his time and it can be safely said that in respect of style, the Mahabhasya excels all the other Bhasyas in the different branches of learning out of which two, those of Sabaraswamin and Sankarācārya, are selected for comparison. It is believed by scholars that he was equally conversant with other sastras, especially Yoga and Vaidyaka, on which he has written learned treatises. He is said to be the author of the Yogasūtras which, hence are called Pātanjala Yogasūtras, and the redactor of the Carakasamhita. There are scholars who believe that he wrote the Mahabhasya only, and not the other two. They base their argument mainly on the supposition that it is impossible for a scholar to have an equally unmatching mastery over three different sastras at a time. argument has no strength, especially in India, where there are many instances of scholars possessing

scholarship in different branches of learning. Apart from legends and statements of Cakradhara, Nagesa and others, about his being the author of three works on three different sastras, there is a direct reference to Patañjali's proficiency in Grammar, Yoga and Medicine in the work of King Bhoja of the eleventh century and an indirect one in the Vakyaof Bhartrhari of padīva seventh century A. D. There is a work on the life of Patanjali, written by a scholar of grammar of the South, named Ramabhadra, which gives many stories and incidents of his life out of which it is difficult to find out the grains of true incidents from the legendary husk with which they are covered. For details, see Pātan jala Mahābhāsya D.E.Society's edition Vol. VII pages 349 to 374. See also, the word महाभाष्य.

पद a word; a unit forming a part of a sentence; a unit made up of a letter or of letters, possessed of sense; cf. अक्षरसमुदायः पदम् । अक्षरं वा । V.Pr. VIII. 46, 47. The word originally was applied to the individual words which constituted the Vedic Samhita; cf. पदप्रकृतिः संहिता Nir.I.17. Accordingly, it is defined in the Vājasaneyi Prātiśākhya as 'अर्थ: पदम्' (V. Pr. III. 2) as contrasted with ^४ वर्णानामेकप्राणयोगः संहिता ' (V.Pr.I.158). The definition 'अर्थः पदम्' is attributed to the ancient grammarian 'Indra', who is believed to have been the first Grammarian of India. Pāņini has defined the term पद as 'स्तिङन्तं पदम ' P.I.4.14. His definition is applicable to complete noun-forms and verb-forms and also to prefixes and indeclinables where a case-

affix is placed and elided according to him; cf. अब्ययादाप्सुप: P. II. 4. 82. The noun-bases before case affixes and tad. affixes, mentioned in rules upto the end of the fifth adhyaya, which begin with a consonant excepting य are also termed पद by Pāṇini to include parts words before the case affixes भ्याम. भिस, स etc. as also before the tad. affixes मत्, वत etc. which are given as separate padas many times in the pada-pātha of the Vedas; cf. स्वादि-ष्वसर्वनामस्थाने P. I. 4. 17. See for details the word पदपाट. There are given four kinds of padas or words viz. नाम, आख्यात, उपसर्ग and निपात in the Nirukta and Prātiśākhya works: cf. also पदमर्थे प्रयुज्यते, विभक्त्यन्तं च पदम् M. Bh. on P. I. 2. 64 Vart. 19, वर्णसमदाय: पदम् M.Bh. on I.1.21 Vart. 5, पूर्वपरगोरथोंपलब्धौ पदम् Kāt. I. 1. 20. पदशब्देनार्थ उच्यते Kaiyata on P.I.2. 42 Vārt. 2; cf. also पद्यते गम्यते अर्थ: अनेनेति पदामित्यन्वर्थसंज्ञा Nyāsa on P.III. 1.92. The verb endings or affixs a, त्तस and others are also called The word 95 in this sense is never used alone, but with the word परस्मे or आत्मने preceding The term परसीपद stands for the nine affixes तिप्, तस्, ... मस्, while the term आत्मनेपद stands for the nine affixes त, आताम् ... महिङ्. cf. ल: परमैपदम्, तङानावात्मनेपदम्. It is possible to say that in the terms परस्मैपद and आत्मनेपद also, the term पद taken to could be mean word, and it is very likely that the words परस्मैपद and आत्मनेपद were originally used in the sense of 'words referring to something meant for another' and 'referring to something meant self' respectively. Such words, of course, referred to verbal forms, roughly corresponding to the

verbs in the active voice verbs in the passive voice. There are some modern scholars of grammar, especially linguists, who like to translate परस्मेपद as 'active voice' and आत्मनेपद as 'passive voice'. Pāṇini appears, however, to have adapted the sense of the terms परसीपढ and आत्मनेपढ and taken ... them to mean mere affixes just as he has done in the case of the terms इत् and तद्धित. Presumably in ancient times, words current in use were grouped into four classes by the authors of the Nirukta works, viz. (a) দুর (words derived from roots)such as कर्ता, कारक:, भवनम etc., (b) तद्वित (words derived from nouns) such as गार्ग्य:, काषायम्, etc., (c) Parasmaipada words viz. verbs such as भवति, पचति, and (d) Atmanepada words i.e. verbs like एवते. वर्धते. etc. Verbs करोति and कुरुते or हरति and हरते were looked upon as both परमैपद words and आत्मनेपद words. The question of simple words, as they are called by the followers of Pāṇini, such as नर, तद, गा, अध, and a number of similar underived words, did not occur to the authors of the Nirukta as they believed that every noun was derivable, and hence could be included in the krt words.

पद्काण्ड (1) a term used in connection with the first section of the Vakyapadiya named গ্ৰহাকাণ্ড also, which deals with padas, as contrasted with the second section which deals with Vākyas; a section of the Astādhyāyī of Pāṇini, which gives rules about changes and modifications applicable to the pada, or the formed word, as contrasted with the base (अङ्ग) and the suffixes. The section is called पदाधिकार which begins with the rule पदस्य P.VIII.1.16. and ends with the rule इडाया वा VIII. 3. 54.

पदकार lit. one who has divided the Samhitā text of the Vedas into the Pada-text. The term is applied to ancient Vedic scholars शाकल्य, आत्रेय, कात्यायन and others who wrote the Padapātha of the Vedic Samhitās. term is applied possibly through misunderstanding by some scholars to the Mahābhāsyakāra who has not divided any Vedic Samhitā, but has, in fact, pointed out a few errors of the Padakāras and stated categorically that grammarians need not follow the Padapatha, but, rather, the writers of the Padapātha should have followed the rules of grammar. Patañjali, in fact, refers by the term पदकार to Kātyāyana, who wrote the Padapātha and the Prātiśākhya of the Vajasaneyi-Samhita in the following statement—न लक्षणेन पदकारा अनुवर्त्याः।पदकारैनीम लक्षणमनुवर्त्यम्। यथालक्षणः पदं कर्तब्यम् M. Bh. on P. III.1. 109; VI. 1. 207; VIII. 2.16; cf. also अदीधयुरिति पदकारस्य प्रत्याख्यानपक्षे उदाह-रणमुपपन्नं भवति (परिभाषासःचन of व्याडि Pari. 42) where Vyadi clearly refers to the Vartika of Katya-' दीधीवेब्याश्चन्दोविषयत्वात् ॰ ' yana P. I. 1.6 Vart. 1. The misunderstanding is due to passages in the commentary of स्कन्दस्वामिन् the Nirukta passage I. 3, on अवधातिशाख्य XIII. and others where the statements referred to as those of Patanjali are, in fact, quotations from the Pratiśākhya works and it is the writers of the Prātiśākhya works who are referred to as padakaras by Patanjali in the Mahābhāsya.

पद्चिन्द्रिका a grammar work on the nature of words written by কুল্যুহার of the sixteenth century. पद्पक्ष the same as पदसंस्कारपञ्च. See पदसंस्कारपञ्च.

पद्पाठ the recital of the Veda text showing each pronouncing or word separately as detached from the adjoining word. It is believed that the Veda texts were recited originally as running texts by the inspired sages, and as such, they were preserved by people by oral tradition. Later on after several centuries, their individually distinct words were shown by grammarians who were called Padakāras. The पदपाठ later on had many modifications or artificial recitations such as कम. जटा, घन etc. in which each word was repeated twice or more times, being uttered connectedly with the preceding or the following word, or with both. These artificial recitations were of eight kinds, which came to be known by the term अर्विकृतयः.

प्रमुक्ति a term used in connection with the Samhitā text or संहितापाठ which is believed to have been based upon words (पदानि प्रकृति: यहमा: सा) or which forms the basis of words or word-text or the padapātha (पदानां प्रकृति:); cf पदप्रकृति: संहिता Nir.I.17.

प्रभिद् lit. divisions of words: parts of speech. There are four parts of speech viz.नामन्, आख्यात, उपसर्ग and निपात given by ancient grammarians and the authors of the Prātiśākhya works, while there are given only two, सुबन्त and तिङ्क्त by Pāṇini. For details see pp. 145, 146 Vol. VII. Mahābhāṣya D. E. Society's edition.

पद्मञ्जरी the learned commentary by Haradatta on the काशिकान्ची. Haradatta was a very learned grammarian of the Southern School. and the Benares School of Grammarians follow पदमञ्जरी more than the equally learned another commentary काशिकाविवरणपञ्जिका or न्यास. In the Padamanjarī Haradatta is said to have given everything of importance from the Mahābhāṣya; cf. अधीते हि महाभाष्ये व्यर्था सा पदमञ्जरी. For details see Mahābhāṣya D. E. S. Ed. Vol. VII P. 390-391.

पद्वाक्यरनाकर a disquisition on grammar dealing with the different ways in which the sense of words is conveyed. The work consists of a running commentary on his own verses by the author Gokulanātha Miśra who, from internal evidence, appears to have flourished before Kondabhatta and after Kaiyaṭa.

पद्वाद् or पद्वादिपक्ष view that words are real and have an existence and individuality of their own. The view is advocated by the followers of both the Mīmāmsā schools and the logicians who believe that words have a real existence. Grammarians admit the view for practical purposes, while they advocate that the अल्जाडवाक्य-स्कोट alone is the real sense. cf. Vākyapadīya II.90 and the foll.

पद्विधि an operation prescribed in connection with words ending with case or verbal affixes and not in connection with noun-bases or root-bases or with single letters or syllables. पद्विधि is in this way contrasted with अङ्गविधि (including प्रातिपदिकविधि and धातुविधि), वर्णविधि and अक्षर्विधि, Such Padavidhis are given in Pāṇini's grammar in Adhyāya2, Pādas 1 and 2 as also in VI.1.158, and in VIII.1.16 to VIII.3.54 and include rules in connection with compounds, accents and euphonic

combinations. When, however, an operation is prescribed for two or more padas, it is necessary that the two padas or words must be syntactically connectible; cf. समर्थ: पद्विधि: P. II.1.1.

पदिविराम pause between two words measuring two mātrās, or equal to the time required for the utterance of a long vowel; e.g. in इषे त्वोजें त्वा, the pause between इषे and त्वा is measured by two mātrās; cf. पदिवरामो दिमात्र: T. Pr. XXII.13. Some Prātiśākhya texts declare that the pause between two words is of one mātrā as at avagraha cf. R Pr. II.1 and R. T. 35-38.

पद्व्यवस्थासूत्रकारिका a metrical work on the determination of the pada or padas of the roots attributed to Vimalakīrti.

पद्व्यवस्थासूत्रकारिकाटीका a short gloss on the पद्व्यवस्थासूत्रकारिका written by Udayakirti, a Jain grammarian

पदसंस्कारपक्ष an alternative view with वाक्यसंस्कारपञ्च regarding the formation of words by the application of affixes to crude bases. cording to the Padasamskara alternative, every word is formed independently, and after formation the words are syntactically connected and used in a sentence. The sense of the sentence too, is understood after the sense of every word has been understood; cf. सुविचार्य पदस्यार्थे वाक्यं ग्रह्णन्ति सूरयः Sira. on Pari. 22. According to the other alternative viz. वाक्यसंस्कारपक्ष, a whole sentence is brought before the mind and then the constituent individual words are formed e.g. राम + सु, गम् + अ + ति | Both the views have got some advantages and some defects; cf. Par. Sek. Pari. 56.

पदस्ताट expression of the sense by the whole word without any consideration shown to its division into a base and an affix. For instance, the word रामेण means by Rama' irrespective of any consideration whether न is the affix or इन is the affix which could be any of the two, or even one, different from the two; cf. उपाया: शिक्षमाणानां वालानामपलापना: Vākyapadīya II.240.

पदादि (1) beginning of a word, the first letter of a word; cf. सात्पदाद्योः P. VIII.3.111: cf. also स्वरितो वानुदात्ते पदादौ P. VIII.2.6. Patañjali, for the sake of argument has only once explained पदादि as पदादादि: cf. M.Bh.on I. 1. 63 Vārt. 6; (2) a class of words headed by the word पद् which is substituted for que in all cases except the nom. and the acc. singular and dual; this class, called पदादि, contains the substitutes पद्, दत्, नस् etc. respectively for पाद, दन्त, नासिका etc. cf. Kāś. on P. VI. 1.63; (3) the words in the class, called पदादि, constiting of words पद्, दत्, नस्, मस् हृत् and निश् only, which have the case affix after them accented acute; cf. P. VI. 1.171.

पदादिनिधि a grammatical operation specifically prescribed for the initial letter of a word.

i.e. words which are regularly formed, as contrasted with words in formation. Several grammatical operations, such as accents or euphonic combinations, are specifically prescribed together by Pāṇini at places which are said to be in the Padādhikāra formed by sūtras VIII.1.16 to VIII.3.54.

पदान्त final letter of a word; cf. P. VI.1.76, 109; VII.3.3, 9; VIII.

4.35,37, 42,59. At one place, Patanjali for purposes of argument has explained the word as final in a word; cf.नैवं विज्ञायते पदस्यान्तः पदान्तादिति । कथं तिर्हे । पदे अन्तः पदान्तः पदान्तादिति M. Bh. on VIII. 4.35.

पदार्थ meaning of a word, signification of a word; that corresponds to the meaning of a word: sense of a word. Grammarians look upon both—the generic notion and the individual object as Padartha or meaning of a word, and support their view by quoting the sutras of Panini जात्याख्यायामेकास्मन् बहुवचनमन्यतरस्याम् ${f I}$. 2.58 and सङ्पाणामेकरोष एकविभक्तौ I. 2.64; cf. किं पुनराकृतिः पदार्थ आहोस्विद् द्रन्यम् । उभयमित्याह । कथं ज्ञायते । उभयथा ह्माचार्येण सूत्राणि प्रणीतानि । आकृतिं पदार्थे मत्वा जात्याख्यायामित्यच्यते । द्रव्यं पदार्थे मत्वा सरूपाणामित्येकशेष आरभ्यते. M. Bh. in I. 1. first Ahnika. In rules of grammar the meaning of a word is generally the vocal element or the wording, as the science of grammar deals with words and their formation; cf. स्वं रूपं शब्दस्याशब्द-संज्ञा, P. I. 1. 68. The possession of vocal element as the sense is technically termed शब्दपदार्थकता as opposed to अर्थपदार्थंकता; cf. सोसौ गोशब्दः खस्मात्पदार्थात् प्रन्युतो यासौ अर्थपदा-र्थकता तस्या: शब्दपदार्थकः संपद्यते M. Bh. I. 1.44 V. 3. The word 9318 means also the categories or the predicaments in connection with the different Sastris or lores as for instance, the 25 categories in the Sāmkhyasastra or 7 in the Vaisesika system or 16 in the Nyāyasāstra. The Vyākaraņasāstra, in this way to state, has only one category the Akhandavākyasphota or the radical meaning given by the sentence in one stroke.

पद्मनाम a grammarian who wrote a treatise on grammar known as the Supadma Vyākaraṇa. He is believed to have been an inhabitant of Bengal who lived in the fourteenth century A.D. Some say that he was a resident of Mīthilā.

पद्य forming a part of a word or pada; cf. उपोत्तमं नानुदात्तं न पद्यम् R. Pr. I. 29; cf. also पूर्वपद्यः R. Pr. I. 30. The word is used in this sense (पदावयव) mostly in the Prātiśākhya works. The word is used in the sense of पादसंपन्न, made up of the feet (of verses), in the Rk Prātiśākhya in contrast with अक्षयं, made up of syllables. In this sense the word is derived from the word पाद; cf. पद्माक्षयं स उत्थितः R. Pr. XVIII. 3.

पर (1) subsequent, as opposed to पूर्व or prior; the word is frequently used in grammar in connection with a rule or an operation prescribed later on in a grammar treatise; cf. विप्रतिषेषे परं कार्यम् P. I. 4. 2; (2) occurring after (something); cf. प्रत्ययः परश्च P. III. 1.1 and 2; cf. also तत् परस्वरम् T.Pr. XXI.2. (3)The word पर is sometimes explained in the sense of इष्ट or desired, possibly on the analogy of the meaning শ্বস্ত possessed by the word. This sense is given to the word पर in the rule विप्रतिषेधे परं कार्य with a view to apply it to earlier rules in cases of emergency; cf. विप्रतिषेषे परं यदिष्टं तद्भवति M.Bh. on I.1.3.Vart, 6; परशब्द; इष्टवान्त्री M.Bh. on I. 2.5, 1. 4.2. Vārt. 7; II. 1.69 etc.

परंकार्यत्व or परंकार्यत्वपक्ष the view that the subsequent संज्ञा or technical term should be preferred to the prior one, when both happen to apply simultaneously to a word. The word is frequently used in the Mahābhāṣya as referring to the reading आ काडारात् परं कार्यम् which is believed to have been an alternative reading to the reading आ कडारादेका संज्ञा; cf. ननु च यस्यापि परंकार्यत्वं तेनापि परमहणं कर्तव्यम्; M. Bh. on I. 4. 1; also भवेदेकसंज्ञाधिकारे सिद्धम्। परंकार्यत्वे द न सिद्धचित; M.Bh. on II. 1.20, II. 2.24.

परक्रम a term used in the Prātisākhya works for 'doubling' of a consonant; cf. सान्तःस्थादौ धारयन्तः परक्रमम्। R. Pr. XIV. 23.

परम्रहण the use of the word पर;insertion of the word पर in a rulc; cf. तेनापि परम्रहणं कर्तन्यम्; M.Bh. on I.4.1; cf. also परम्रहणसनधैकम् M.Bh. on III. 1.2.

परन्व posteriority; mention afterwards; the word is frequently used in works on grammar in connection with a rule which is mentioned in the treatise after another rule; the posterior rule is looked upon as stronger than the prior one, and is given priority in application when the two rules come in conflict although technically they are equally strong; cf. परत्वादछोप:; M. Bh. on I. 1.4 Vart 7; परत्वादछोप: I. 1.11 etc.

परत्वन्याय application of the later rule before the former one, according to the dictum laid down by Pāṇini in the rule विप्रतिवेधे परं कार्यम् P. I. 4.2; cf. परत्वन्यायो 'न लिच्चितो भवति Sīra. Pari. 84.

परनिपात lit. placing after; the placing of a word in a compound after another as contrasted with पूर्वानिपात. A subordinate word is generally placed first in a compound, cf. उपसर्जन पूर्वम; in some exceptional cases however, this general rule is

not observed as in the cases of राजदन्त and the like, where the subordinate word is placed after the principal word, and which cases, hence, are taken as cases of प्रनिपात. The words पूर्व and पर are relative, and hence, the cases of प्रनिपात with respect to the subordinate word (उपसर्जन) such as राजदन्त, प्रामजीविक etc. can be called cases of पूर्वनिपात with respect to the principal word (प्रधान) cf. परस्थाताः राजदन्तादित्यात्परनिपातः Kāś. on P. II. 1.39.

परनिमित्तक caused by something which follows; the term is used in grammar in connection with something caused by what follows; cf. परनिमित्तको जादेश: पूर्वविधि प्रति न स्थानिवत् S. K., on अन्न: परसिन्पूर्विश्वी P.I.1.57.

परमञ्ज्ञित the most original base; the original of the original base; the word is used in connection with a base which is not a direct base to which an affix is added, but which is a remote base; cf. आपत्यो वा गोत्रम्। परमञ्ज्ञतेश्च आपत्यः। M. Bh. on P.IV.1. 89; cf. also M. Bh. on IV.1.93,98, 163.

परमाणु a time-unit equal to one-half of the unit called अणु, which forms one-half of the unit called मात्रा which is required for the purpose of the utterance of a consonant; cf. परमाणु अर्घाणुमात्रा V. Pr.I.61. परमाणु, in short, is the duration of very infinitesimal time equal to the pause between two individual continuous sounds. The interval between the utterances of two consecutive consonants is given to be equivalent to one Paramānu; cf. वर्णोन्तरं परमाणु R.T.34.

परह्नप the form of the subsequent letter (परस्य रूपम्). The word is used in grammar when the resultant of the two coalescing vowels (एकादेश)

as for is the latter vowel itself, instance ए in प्रेजते (प्र+ एजते); एडि. पररूपम P.VI.1.94.

परविञ्चन possession of the gender of the final member of a compound word, which, in tatpurusa compounds, is the second of the two or the last out of many; cf. परवाछिक्ने द्दन्द्रतत्प्रुषयो: (P. II.4 26) इति परवालिङ्गता यथा स्यात् M. Bh. on P. V. 4.68.

परविप्रतिषेध the conflict between two rules (by occurrence together) when the latter prevails over the former and takes place by virtue of the dictnm विप्रतिषेधे पंर कार्यम् P. I. 4.2; cf. कथं ये परविप्रतिषेधाः M.Bh. on I.4.2.

परसप्तमी a locative case in the sense of 'what follows', as contrasted with विषयसतमी, अधिकरणसतमी and the like: cf. छुकीति नेषा परसतमी शक्या विज्ञातुं न हि लुका पौर्वापर्यमस्ति । का तर्हि । सत्सप्तमी M.Bh. on P.I.2. 49.

परसवणे cognate of the latter vowel or consonant. The word is frequently used in grammar in connection with a substitute or आदेश which is specified to be cognate (सत्रणें) of the succeeding vowel or consonant; cf. अनुस्वारस्य यथि परसन्तर्णः P.VIII. 4. 58.

परस्परव्यपेक्षा mutual expectancy possessed by two words, which is called सामध्ये in grammar. Such an expectancy is necessary between the two or more words which form a compound; cf. परस्परब्यपेक्षां सामर्थ्यमेके P.II.1.1, V.4; cf. also इह राज्ञ: पुरुष इत्युक्ते राजा पुरुष्रमपेक्षते ममायमिति पुरुषोपि राजानमपेक्षते अहमस्य इति । M.Bh. on II. 1.1.

परस्मेपद a term used in grammar with reference to the personal affixs ति, तः etc. applied to roots. The term परस्मेपद is given to the first nine affixes ति, तः, अन्ति, सि, थः, थ, मि, व: and म:, while the term आत्मनेपद is used in connection with the next nine त, आताम etc.; cf. परसौ परोद्देशार्थफलकं पदम् Vāc. Kosa. term प्रसीपद is explained by some as representing the Active Voice as contrasted with the Passive Voice which necessarily is characterized by the Atmanepada affixes. The term परस्मेभाष in the sense of परस्मैपद was used by ancient grammarians and is also found in the Vārttika आत्मनेभाषपरस्मेभाषयोरुपसंख्यानम P. VI. 3.8 Vart. 1. The term परसमेभाष as applied to roots, could be explained as परस्मै कियां (orिकयाफलं) भाषन्ते इति परस्मैभाषाः and originally such roots as had their activity meant for another, used to take the परस्मेपद affixes, while the rest which had the activity meant for self, took the आत्मनेपद affixes. Roots having activity for both, took both the terminations and were termed उभयपदिनः.

परा

परस्मेभाष lit. speaking the activity or किया for another; a term of ancient grammarians for roots taking the first nine personal affixes only viz. ति, तः... मसु. The term परस्मैपदिन् was substituted for पर्स्मैभाष later on, more commonly. See परस्मेपद above. The term परस्मैभाव along with आत्मनेभाव is found almost invariably used in the Dhātupātha attributed to Pāņini; cf. भु सत्तायाम् । उदात्तः, परस्मैभाषः । एधादय उदात्ता अनुदात्तेत आत्मनेभाषाः Dhātupātha.

परा the highest eternal voice word, the highest and the most lofty of the tour divisions language (वाक), viz. परा,पश्यन्ती, मध्यमा and वेखरी, which, (परा), philosophically is identified with नाद (ब्रह्म) or शब्दब्रह्म. It is described as वर्णादि-विशेषरहिता चेतनिमश्रा सृष्ट्यपयोगिना जगदुपादा-नभूता कुण्डलिनीरूपेण प्राणिनां मूलाधारे वर्तते । कुण्डलिन्याः प्राणवायुसयोगे परा ब्यज्यते । इयं निःष्पन्दा पश्यन्त्यादयः सस्पन्दा अस्या विवर्तेः । इयमेव सूक्ष्मस्कोट इत्युच्यते ।

पराङ्गबद्धाव behaviour as having become a part and parcel of another; treatment of a word as a part of another. The term is used Panini in connection with a word followed by and connected with a word in the vocative case of which it is looked upon as a part for purposes of accent, e. g. कुण्डेनाटन्, मद्राणां राजन etc. Here the words अटन् and राजन, being in the vocative case, are आग्रदात्त, i.e. अ (at the beginning of अटन्) and आ (in राजन्) are acute and as a result all the other vowels in कुण्डेनाटन् and मद्राणां राजन् become अनुदात्त or grave; cf. सुबामन्त्रित पराङ्गवस्थरे P.II.1.2.

परादि initial or first of the next or succeeding word; cf. किं पुनरवं पूर्वान्त आहोस्वित्परादिः आहोस्त्रिदभक्तः M.Bh. on P. I. 1.47 Vart. 3; cf. also M. Bh. on IV.1.87, IV.2, 91.

परादिसस्वर a consonant belonging to the succeeding vowel in syllabication; cf. R.Pr.I.15.

परार्थ (1) the sense of another word; cf. परार्थाभिषानं वृत्तिः इत्याहुः। M.Bh. on II.1.1, Vārt.2; (2) for the sake of, or being of use in, the next (सूत्र); cf. परार्थं मम भविष्यति सन्यत इद्भवतीति, M. Bh. on I.1.59 Vārt. 8.

परिकृष्ट dragged to the latter; cf. Puspasutra III. 114; the word परि stands for पर here.

परिक्रम the same as परक्रम; doubling (द्वित्व) of a subsequent consonant as for example the doubling of स् in रार्मन् स्त्याम; cf. सान्तःस्थादौ धारयन्तः परक्रमं (v. l. परिक्रमं) R.Pr. XIV. 23.

परिगणन lit. enumeration. The word is used in grammar treatises in the sense of 'a definite or complete

enumeration' with a view to exclude those that are not included in the enumeration; cf परिगणनं कर्तन्यम्। यङ्यक्यवलोपे प्रतिषेध: M.Bh. on I.1.4 Vart. 1.

परिग्रह also परिग्रहण. (1) acceptance, inclusion; cf. िक प्रयोजनम्। प्रत्ययार्थं परिग्रहार्थम् M.Bh. on P.III.26.1; (2) repetition of a Samhitā word in the Pada recital, technically named नेष्टक also; repetition of a word with इति interposed; e. g. सुप्राच्या इति सुप्रऽअन्याः Rg. Veda II.13.9, अल्ला भवन्ती-रित्यल्लाऽभवन्तीः Rg. IV.18.6; cf. परिग्रहे स्वनार्धान्तात् तंन वैकाक्षरीकृतात्। परेषां न्यासमाचारं ज्यालिस्ती चेत्स्वरी परी; R. Pr. III. 14. cf. also, R.Pr.XI.32,36,42.

परिनिष्ठित completely formed; with the formation completely achieved; स्वार्थे परिपूर्णम्; cf. परिनिष्ठतस्य पदान्तरसंबन्धे हि गौर्वाहीक इत्यादौ गौण्स्वप्रतीतिन तु प्रातिपदिक्तसंकार्येकायाम् Par. Sek. on Pari. 15.

परिपन्न a kind of Samdhi or coalescence characterized by the change of the consonant म into an anusvāra, as by मोनुस्वार: P. VIII. 3.23, before a sibilant or before रेफ; cf, रेफोष्मणोरुदययोमेकार: अनुस्वारं तत् परिपन्नमाहुः R.Pr.IV.5; cf. also सम्राद्शब्दः परिसं-पन्नापवादः R.Pr.IV.7.

परिभाषा an authoritative statement or dictum, helping (1) the correct interpretation of the rules (sūtras) of grammar, or (2) the removal of conflict between two rules which occur simultaneously in the process of the formation of words, (पदसिद्धि), or (3) the formation of correct words. Various definitions of the word परिभाषा are given by commentators, the prominent ones being— परितो ब्यापृतां भाषां परिभाषां प्रचक्षते(न्यास);or. परितो भाष्यते या सा परिभाषा प्रकीर्तिता. The word is also defined as विधी नियामक-रिणी परिभाषा (दुर्गसिंहवाति). परिभाषा can also be briefly defined

convention of a standard author. Purusottamadeva applies the word परिभाषा to the maxims of standard writers, cf. परिभाषा हि न पाणिनीयानि वचनानि: Puru. Pari. 119; while Haribhāskara at the end of his treatise परिभाषाभास्कर, states Vyādi was the first writer on Paribhāsās. The rules तरिमन्त्रिति निर्दिशे पूर्वस्य, तस्मादित्यत्तरस्य and others are in fact Paribhāsā rules laid down by Pānini. For the difference between परिभाषा and आधिकार, see Mahābhāsya on II.1.1. Many times the writers of Sūtras lav down certain conventions for the proper interpretation of their rules, to which additions are made in course of time according to necessities that arise, by In the different commentators. systems of grammar there are different collections of Paribhasas. In Pāṇini's system, apart from commentaries thereon, there are independent collections of Paribhāsās by Vyādi, Bhojadeva, Purusottamadeva, Sīradeva, Nīlakantha, Haribhāskara, Nāgesa and a few others. There are independent collections of bhāsās in the Kātantra, Cāndra, Sākatāyana, Jainendra and Hemacandra systems of grammar. It is a noticeable fact that many Paribhāsās are common, with their wordings quite similar or sometimes identical in the different systems. Generally the collections of Paribhāsās have got scholiums or commentaries by recognised grammarians, which in their turn have sometimes other glosses or commentaries upon them. Paribhāsendusekhara of Nāgesa is an authoritative work of an outstanding merit in the system of Pāṇini's Grammar, which is commented upon by more than twentyfive scholars during the last two or three centurics. The total number of Paribhāṣās in the different systems of grammar may wellnigh exceed 500. See परिभाषासंग्रह.

परिभाषात्रकाश an independent treatise explaining the various Paribhāṣās in the system of Pāṇini's grammar, written by Viṣṇuśeṣa of the famous Sesa family.

परिभाषाप्रदीपार्चिस् a scholarly independent treatise on Vyākaraņa Paribhāṣās written by Udayamkara Pāṭhaka, called also Nānā Pāṭhaka, a Nāgara Brāhmaṇa, who lived at Benares in the middle of the 18th century A. D. He has also written commentaries on the two Sekharas of Nāgeśa.

परिभाषाभास्कर (1) a treatise on the Paribhāṣās in Pāṇini's grammar written by Haribhāskara Agnihotrī, son of Appājībhaṭṭa Agnihotrī, who lived in the seventeenth century: (2) a treatise on Pāṇiniparibhāṣās, as arranged by Sīradeva, written by Śeṣādriśuddhi.

परिभाषार्थसंग्रह a treatise on the Paribhāṣās in the system of Pāṇini's grammar written by Vaidyanātha Sāstrin.

परिभाषाञ्चित a general name given to an explanatory independent work on Paribhāṣās of the type of a gloss on a collection of Paribhāṣās, irrespective of the system of grammar, whether it be that of Pāṇini, or of Kātantra, or of Jainendra or of Hemacandra. The treatises of Vyāḍi (Pāṇini system), Durgasimha and Bhāvamiśra (Kātantra system), Puruṣottamadeva and Sīradeva (Pāṇini system), Abhyankar (Jainendra system) and others are all known by the name Paribhāsāvritti.

परिभाषावृत्तिदिपणी a very brief commentary on the Paribhāṣāvṛtti of Sīradeva written by Śrīmānaśarman of Campāhattī.

परिभाषावृत्तिदीका a commentary on the Paribhāṣāvṛtti of Śīradeva written by Rāmabhadra Dīkṣita who lived in the seventeenth century A. D.

परिभाषासंग्रह a work containing a collection of independent works on Paribhāṣās in the several systems of Sanskrit Grammar, compiled by M. M. K. V. Abhyankar. The collection consists of the following works (i) परिभाषासूचन containing 93 Paribhāsās commentary by Vyādi, an ancient grammarian who lived Patañjali; (ii) ब्याडीयपरिभाषापाठ, a bare text of 140 Paribhāsās belonging to the school of Vyādi! (iii) शाकटायनपरिभाषासत्र a text of 98 Paribhāṣā aphorisms, attributed to the ancient grammarian Sakatayana, or belonging to that school; [iv) चान्द्रपरिभाषामुत्र a text of 86 Paribhasa aphorisms given at the end of his grammar work by Candragomin; (v) कातन्त्रपरिभाषासूत्रवृत्ति a gloss on 65 Paribhāṣā aphorisms of the Katantra school by Durgasimha; (vi) कातन्त्रपरिभाषासूत्रवृत्ति a short gloss on 62 Paribhāṣā aphorisms of the Kātantra school by Bhāvamīśra; (vii) कातन्त्रपरिभाषासुत्र a text of 96 Paribhāṣā rules belonging to the Kātantra school without author's name associated with it; (viii) काळापपरिभाषासूत्र a text Paribhāṣā rules belonging to the Kālāpa school without any author's name associated with it; (ix) जेनेन्द्रपरिभाषात्रात्ते a gloss written by M. M. K. V. Abhyankar (the compiler of the collection), on 108 Paribhāsās or maxims noticeable in the Mahavrtti of Abhayanandin on the Jainendra Vyakarana of Pujyapāda Devanandin: (x) भोजदेवकृतपरि-মাদানুস a text of 118 Paribhāsā rules given by Bhoja in the second pada of the first adhyāya of his grammar work named Sarasvatīkanthābharana; (xi) न्यायसंग्रह a bare text of 140 paribhāsās (which are called by the name nyāya) given by Hemahamsaganī in his paribhāsā work named न्यायसंप्रह; (xii) लघुपरिभाषात्रृत्ति a gloss on 120 Paribhāsās of the Pānini school written by Purusottamadeva; (xiii) बृहत्परिभाषावृत्ति containing 130 Paribhāsās commentary by Siradeva and a very short gloss on the commentary by Śrimānaśarman; (xiv) परिभाषावात्त a short gloss on 140 Paribhāsas of the Pānini school written by Nilakantha; (xv) परिभाषाभास्कर a collection of 132 Paribhāsās with a commentary by Haribhāskara Agnihotrī; (xvi) bare text of Paribhāṣās given and explained by Nāgešabhatta in his Paribhāsendu-The total number of Paribhāsās mentioned and treated in the whole collection exceeds five hundred.

परिमाषासूचन an old work on the Paribhāṣās in the system of Pāṇini's Grammar, believed to have been written by Vyāḍi, who lived after Kātyāyana and before Patañjali. The work is written in the old style of the Mahābhāṣya and consists of a short commentary on 93 Paribhāṣās.

परिभाषेन्द्वशेखर the reputed authoritative work on the Paribhāṣās in the system of Pāṇini's grammar written by Nāgeśabhaṭṭa in the

beginning of the 18th century The work is A. D. at Benares. studied very widely and has got 25 than commentaries written by pupils in the spiritual line of Nagesa. Well-known among these commentaries are written by Vaidyanātha Pāyagunde (called गदा), by Bhairavamisra (called मिश्री), by Ragha-Gajendragadakara vendrācārva (called त्रिपथगा), by Govindacārya Astaputre of Poona in the beginning of the nineteenth century (called भावार्थदीपिका), by Bhaskarasastri Abhyankar of Satara (called भास्करी), and by M. M. Vāsudevašastri Abhvankar Poona (called तत्त्वादर्श). Besides these, there are commentaries written by Tātyā śāstrī wardhana, Ganapati śāstri Mokāte, Misra. Visnu-Jayadeva sāstrī Bhat, Vishwanātha Daņ-Harinātha Dwiwedi dibhatta, Gopālācārya Karhādkar, shastri Bhagawata, Govinda Shastri Nārāyaņa Shastri Bhāradwaja, Galagali, Venīmādhava Shukla, Brahmananda Saraswatī, Manīsiśe-Manyudeva, Samkarasaśarmā, bhatta, Indirāpati, Bhimācārya Galagalī, Mādhavācārya Wāīkar, Cidrūpāśraya, Bhīmabhatta, Laksmīnīsimha and a few others. Some of these works are named by their authors as Tīkās, others Vyākhyās and still others Tippanis or Vivitis.

परिमल a work on Grammar attributed to Amaracandra.

परिमाण a word used by Pāṇini in तदस्य परिमाणम् V. J.19 and explained by Patañjali as सर्वतो मानम् Samkhyā (number) is also said to be a parīmāṇa. Parimāṇa is of two kinds— नियत or definite as in the case of Khārī, droṇa etc; and आनियत, as in the case of Gaṇa, Saṁgha, Pūga, Sārtha, Senā etc. The term परिमाण, in connection with the utterance of letters, is used in the sense of मात्राकाल or one mora.

परिछोप elision of a phonetic member; the same as lopa in the Grammar of Pāṇini. The term परिछोप and the verbal forms of the root परिछुप् are found in the Prātiśākhya works; cf. उष्मा परिछुप्येत त्रयाणाम् R. Pr. II. 4.

परिवर्तन reversion in the order of words as found in the recital of the Veda at the time of the recital of जहा, घन and other artificial types of recitations.

परिसंख्यान lit. enumeration; enunciation; mention; the word is found generally used by Kātyāyana and other Vārttikakāras at the end of their Vārttikas. The words वक्तव्यम्, वाच्यम्, and the like, are similarly used.

परिसमास application of the complete sense; the word is found used in the three alternative views about the application of the full sense of a sentence,— collectively, individually or in both the ways, to the individuals concerned; cf. प्रत्येक वाक्यपरिसमाति:, समुदाय वाक्यपरिसमाति:, उभयथा वाक्यपरिसमाति:; cf. M. Bh. I. 1.1 Vārt. 12; (2) completion; cf. कृत्करणं स्वादीनां प्वादीनां च परिसमाप्त्यथीमिति Kāś. on VII. 3.80.

परिहार (1) removal of a difficulty, cf. अन्यथा कृत्वा चोदितमन्यथा कृत्वा परिहार: M. Bh. on P. IV. 1.7. Vārt. 3; (2) repetition in the Padapāṭha, Kramapāṭha etc. e. g अकारित्यक:. In this sense the word is found in the neuter gender; cf. रेफवरिहाराणि A. Pr. III. 1.1.

पराक्ष used as an adjective of the word भूत meaning 'past tense'; lit.

behind the eyes, unnoticed by the eyes. The word is generally used in the sense of remote or long (past) or 'perfect'. For the alternative explanation of the word परोक्ष, cf. कथंजातीयकं पुनः परोक्षं नाम । केचित्तावदाहुः वर्षशतवृत्तं परोक्षमिति । अपर आहुः कटान्तरितं परोक्षमिति । अपर आहुः कटान्तरितं परोक्षमिति । अपर आहुः कटान्तरितं परोक्षमिति । अपर आहुः हिट P. III.2.115.

परोक्षा lit. behind the eyes; remote; the term is found used by ancient grammarians and also referred to in the Mahābhāṣya as referring to the perfect tense called लिट् in Pāṇini's grammar; cf. ज्ञापकालरोक्षायां (लिट) न भविष्यति। M.Bh. on P. I. 2.28; cf. also न न्यथते: परोक्षायाम् Kāt. III.4.21.

पर्जन्यवह्रक्षणप्रवृत्ति the application of a grammatical rule or operation like the rains which occur on dry land as also on the sea surface; cf. कृतकारि खल्बिप शास्त्रं पर्जन्यवत् । तद्यथा । पर्जन्यो यावदूनं पूर्णं च सर्वमिभवर्षति । M.Bh. on P.I. 1.29; VI. 1.127; cf. also यथा पर्जन्यः यावदूनं पूर्णं वाभिवर्षति एवं लक्षणमि दिर्घस्य दीर्घस्वम् । चिचीष्रति, बुम्धिति। Vyadi. Pari. 58, cf. कृतकारि शास्त्रं मेघवत् न चाकृतकारि दहनवत् Puruso. Pari. 86.

पपाँदि a class of words headed by the word पर्व to which the tad. affix इक (छन्) is added in the sense of 'moving by' or 'eating along with' (तेन चरति); e.g. पर्पिक:, पर्पिकी; अश्विक:, अश्विकी etc.; cf. Kāś. on P. IV.4.10.

पर्याय (1) serial order or succession as opposed to simultaniety; the word is used in grammar in connection with a rule which, as the objector for the sake of argument, would like to hold and would apply by succession with respect to the rule in conflict, either before it or after it i.e. alternatively; cf. पर्याय:

प्रसच्येत often found used in the Mahābhāṣya as for example on I.4.1 etc.; ci. also तृजादयः पर्यायेण भवन्ति M.Bh. on P. I. 4.2. Vārt. 3; (2) alternative word, synonym; cf. अभिज्ञावचने लृट्ट्। वचनप्रहणं पर्यायार्थम् । अभिजानासि स्मरासे बुध्यसे चेतयसे इति। Kāś. on P. III.2.112.

पर्यायवचन synonym, synonymous word; cf. जित् पर्यायवचनस्यैव राजाद्यर्थम्। इनसभम्। ईश्वरसभम् M.Bh. on I.1.68; cf. also यदयं कस्यचित्पर्यायवचनस्य ग्रहणं करोति । अधिपतिदायोदित M. Bh. on II. 3.9.

पर्यदास (1) exclusion; negation with a view to exclude; one of the two senses (प्रसज्यप्रतिषेध and पर्युदास) of the negative particle নহা, generally found in cases when the particle নস is compounded with a noun, and not used independently with a verbal form or a verbal activity; e. g. अन्नाह्मण:: अनचि च; cf. अन-पुंसकात् । नायं प्रसज्यप्रतिषेधो नपुंसकस्य निति । किं ताहैं। पर्युदासीयं यदन्यन्नपुंसकादिति। M. Bh. on I. 1.43; cf. also प्रसन्यप्रतिषेध: स्यात् । ऋयया सह यत्र नञ् । पर्युदासः स विज्ञेयो यत्रोत्तरपदेन नञ् ॥ (2) removal in general, not by the use of a negative particle; cf. पाठात्पर्युदास: कर्तव्यः । गुद्धानां पटितानां संज्ञाः कर्तव्या । M. Bh. on I. 1.27 Vart. 3.

पर्वन word, pada; lit. member of a sentence; the word is found used in the sense of पद in the old Prātišākhya Literature; cf. अन्तरेण पर्वणी। पर्वशब्देन पदमुच्यते । पदयोर्मध्ये आगमो भवति। यथा प्राङ्मोमः, प्राड्क्सोमः। Uvvaṭa on V. Pr. I. 138.

परवादि a class of words headed by the word पर्श्च to which the tad. affix अ (अण्) is added without any change of sense provided the words पर्श्च and others, to which the affix अ is to be added mean fighting clans; e. g. पार्शव, आसुर; राक्षस:, दाशाई: etc. cf. Kāś. on V. 3.117.

पलचादि a class of words headed by the word पलदी to which the tad. affix अण is applied in the miscellaneous (शैषिक) senses; e. g. पालद:, पारिषद:, रीमक:; पाटचर: etc. cf. Kāś. on P. IV. 2.110.

पलाशादि a class of words headed by the word पलाश to which the affix ল (অল্) is added in the sense of 'a product of' or 'a part of;' e. g. पालाश:, আহিং:, ইকছ্কন: etc. cf. Kāś. on P. IV. 3.141.

पश्यन्ती name of the second out of the four successive stages in the origination or utterance of a word from the mouth. According to the ancient writers on Phoneties, sound or word (ৰাকু) which is constituted of air (वाय) originates at the Mūlādhāracakra where it is called परा. It then springs up and it is called पश्यन्ती in the second stage. Thence it comes up and is called मध्यमा in the third stage; rising up from the third stage when the air strikes against the vocal chords in the glottis and comes in contact with the different parts of the mouth, it becomes articulate and is heard in the form of different sounds. when it is called वैखरी; cf. वैखर्या मध्यमायाश्च पस्यन्त्याश्चेतदद्भुतम् । अनेकतीर्थ-भदायास्त्रय्या वाचः परं पदम Vakyapadiya I. 144, and also cf. पत्र्यन्ती त सा चलाचलाप्रतिबद्धसमाधाना संनिविष्टशेयाकारा प्रतिलीनाकारा निराकारा च परिच्छिनार्थप्रत्यव-भासा संसष्टार्थप्रत्यवभासा च प्रशान्तसर्वार्थ-प्रत्यवभासा चेत्यपरिमितभेदा । पश्यन्त्या रूप-मनपभ्रंशमसंकीर्णे लोकन्यवहारातीतम् । com. on Vākyapadīya I. 144. cf. also तत्र श्रोत्रविषया वैखरी । मध्यमा हृदयदशेस्था पदप्रत्यक्षानुपपत्त्या व्यवहारकारणम् । पद्यन्ती तु लोकन्यवहारातीता । योगिनां तु तत्रांपि प्रकृतिप्रस्ययविभागावगितरस्ति । परायां तु न इति त्रय्या इत्युक्तम् । Uddyota on चत्वारि वाक्परिमिता पदानि • M. Bh. Āhnika 1.

परपञा called also परपञाहिक; name given to the first or introductory chapter (आह्विक) of the Mahabhāsya of Patanjali. The word occurs first in the Sisupalavadha of Māgha. The word is derived from परपदा, the frequentative base of स्पन to touch or to see (ancient use). Possibly it may be explained as derived from स्पज्ञ with अप; cf. शुद्ध-विद्येव नो भाति राजनीतिखस्पद्या Sis.II.112. Mallinatha has understood the word परपदा m. and explained it as introduction to a Sastra treatise: cf. परपदाः शास्त्रारम्भसमर्थक उपोद्धातसंदर्भग्रन्थः। Mallinātha on Šiś, II.112.

पाकवती a word used in the Śikṣā works for a kind of pause or hiatus.

पाक्षिक alternative; occurring optionally or alternatively; cl. पाक्षिक एष दोष: M. Bh. on II.3.46 Vārt. 8; VI. 1.61 Vārt. 4; cf. also पाक्षिक ऐकश्रुत्य-विधिमीवित Kās. on P. I.2.36.

पाञ्चिमिक lit. pertaining to the fifth; name given to the affixes prescribed in the fifth Adhyāya of Pāṇini's Aṣṭādhyāyī, especially in Sūtras V.2.1 to V.2.93.

पाठ (1) recital of a sacred Vedic or Sāstra work; the original recital of an authoritative text;(2) the various artificial ways or methods of such a recital; e.g. पदपाठ, कमपाठ etc. in the case of Vedic Literature; (3) an original recital such as the एत्रपाठ, बातुपाठ, गणपाठ, बार्तिकपाठ and परिभाषापाठ in the case of the several systems of Sanskrit Grammar; the five Pāṭhas are called पञ्चपाठी; (4) recitation; cf. नान्तरेण पाठ स्वरा अनुबन्धा वा शक्या विज्ञातुम् M. Bh. on P.I.3.1 Vārt. 13; (5) reading, variant; cf.

चूर्णोदीनि अप्राण्युपग्रहादिति सूत्रस्य पाठान्तरम् Kāś. on P.V.2.134.

पाठक or उद्यंकरपाठक name of a scholar of Sanskrit Grammar who wrote an independent work on Paribhāsās and commentaries on the Paribhāsenduśekhara and Laghu-sabdenduśekhara. See उद्यंकर and परिभाषाप्रदीपार्चिस.

पाठकी name popularly given to the commentaries written by उदयंकरपाठक. See पाठक.

पाणिनि the illustrious ancient mmarian of India who is wellknown by his magnum opus, the Aştaka or Astādhyāyī which has maintained its position as a unique work on Sanskrit grammar unparalleled upto the present day by any other work on grammar, not only of the Sanskrit language, but of any other language, classical as well as spoken. His mighty integrasped, studied and lligence digested not only the niceties of accentuation and formation of Vedic words, scattered in the vast Vedic Literature of his time, but those of classical words in the classical literature and the spoken Sanskrit language of his time in all its different aspects and shades, noticeable in the various provinces and districts of the vast country. The result of his careful study of the Vedic Literature and close observation of the classical Sanskrit, which was a spoken language in his days, was the production of the wonderful and monumental work, the Astadhyayi, which gives an authoritative description of the Sanskrit language, to have a complete exposition of which, several life times have to be spent, in spite of several commentaries upon it, written from time to time by several distinguished scholars. The work is a not a language linguist's and teacher's. Some Western scholars have described it as a wonderful specimen of human intelligence.or a notable manifestation of human intelligence. Very little is known unfortunately about his native place, parentage or personal history. The account given about these in the Kathasaritsagara and other books is only legendary and hence, it has very little historical The internal evidence. supplied by his work shows that he lived in the sixth or the seventh century B. C., if not earlier, in the north western province of India of those days. Jinendrabuddhi. author the of Kāśikavivaraņapanjikā or Nyāsa, has stated that the word হালাবং mentioned by him in his sūtra (IV. 3.94) refers to his native place and the word शालातरीय derived by him from the word शलात्र by that sutra was, in fact his own name, based upon the name of the town which formed his native Pāṇini has shown in his work his close knowledge of, and familiarity with, the names of towns, villages, districts, rivers and mountains in and near Vāhīka, the north-western Punjab of the present day, and it is very likely that he was educated at the ancient University of Taksasilā. Apart from the authors of the Prātiśākhya works, which in a way could be styled as grammar works, there were scholars of grammar as such, who preceded him and out of whom he has mentioned viz. Āpisali, Sākatāyana, Gargya, Śakalya, Kasyapa, Bharadvāja, Gālava, Cākravarmaņa, Senaka and Sphotayana, grammarian Indra has not been Pāṇini, although mentioned by tradition says that he was the first Sanskrit grammarian of the language. It is very likely that Pānini had no grammar work of Indra before him, but at the same time it can be said that the works of some grammarians mentioned by Pāṇini such as Sākatāyana, Āpiśali, Gargya and others had been based on the work of Indra. The mention of several ganas as also the exhaustive enumeration of all the two thousand and two hundred roots in the Dhatupatha can very well testify to the existence of systematic grammatical works before Panini of which he has made a thorough study and a careful use in the composition of his Ganapātha and Dhātupātha. His exhaustive grammar of a rich language like Sanskrit has not only remained superb in spite of several other grammars of the language written subsequently, but its careful study is felt as a supreme necessity by scholars of philology and linguistics of the present day for doing any real work in the vast field of linguistic research. For details see pp.151-154 Vol. VII of Pātanjala Mahābhāsya, D. E. Society's Edition.

पाणिनिस्त्र called also by the name अष्टक or पाणिनीय-अष्टक; name given to the Sūtras of Pāṇini comprising eight adhyāyas or books. The total number of Sūtras as commented upon by the writers of the Kāśikā and the Siddhāntakaumudī is 3983. As nīne sūtras out of these are described as Vārttikas and two as Gaṇasūtras by Patañjali, it is

there were evident that 3972 Sūtras in the Astaka of Pānini according to Patanjali. A verse Vaivākarana among current schools states the number to be 3996; cf. त्रीणि सूत्रसहस्राणि तथा नव शतानि च। षण्णवतिश्च सूत्राणां पाणिनि: स्वयम । The traditional recital by Veda scholars who look upon the Astādhyāyī as a Vedānga, consists of 3983 Sūtras which are accepted and commented upon by all later grammarians and commentators. The Sutras of Panini, which mainly aim at the correct formation of words, discuss declension, conjugation, euphonic changes, verbal derivatives, noun derivatives and For details see Vol. VII. accents. Vvākarana Mahābhāsya, D. E. Society's edition pp. 152–162.

पाणिनिसत्रवार्तिक name given to the collection of explanatory pithy notes of the type of Sūtras written mainly by Kātyāyana. The Varttikas are generally written in the style of the Sūtras, but sometimes they are written in Verse also. The total number of Varttikas is well-nigh above 5000, including Varttikas in Verse. There are three kinds of Varttikas; cf.उक्तानुकदुरकानां चिन्ता यत्र प्रवर्तते । तं ग्रन्थं वार्तिकं प्राहवीर्तिकज्ञा मनीषिणः। Nāgeśa appears to have divided Värttikas into two classes as shown by his definition ' নুন্নী S नुक्तदुरक्ताचिन्ताकरत्वं वार्तिकत्वम् '. If this definition be followed, many of the Vārttikas given in the Mahābhāsya explaining and commenting upon the Sūtras will not strictly be termed as Vārttikas, and their total number which is given as exceeding 5000, will be reduced to about 1400 or so. There are some manuscript copies which give this reduced number, and it

may be said that only these Varttikas were written by Kātvāvana while the others were added by learned grammarians after Kātyāyana. In the Mahābhāsya there are seen more than 5000 statements of the type of Varttikas out of which Dr. Kielhorn has marked about 4200 as Vārttikas. At some places the Mahābhāsyakāra has quoted the names of the authors of some Varttikas or their schools. in words such as कोशीया: भारद्वाजीयाः पठित्त, सौनागाः पठित्तः etc. Many of the Varttikas given in the Mahābhāsya are not seen in the Kāsikāvrtti, while some more are seen in the Kāśikā-vrtti, which. evidently are composed by scholars who flourished after Patanjali, as they have not been noticed by the Mahābhāsyakāra. It is very difficult to show separately statements of the Bhasyakara popularly named 'istis' from the Varttikas of Kātyāyana and others. For details see Vol. VII Mahābhāsya, D.E. Society's edition pp. 193-224.

पाणिनिस्त्रवृत्ति a gloss on the grammar rules of Pānini. Many glosses were written from time to time on the Sūtras of Pāṇini, out of which the most important and the oldest one is the one named Kāśikāvrtti. written by the joint authors Jayaditya and Vāmana in the century A.D. It is believed that the Kāśikāvrtti was based upon some old Vrttis said to have been written by कुणि, निर्देश चाहि, धोमति वरहिच and others. Besides Kāsikā, the famous Vrtti, and those of कृणि,निदेर and others which are only reported, there are other Vittis which are comparatively modern. Some of them have been printed, while others have remained only in

manuscript form. Some of these are: the Bhasavrtti by Purusottamadeva, Vyākaraņasudhānidhi Viśveśvara, Gūdhārthadīpinī by Sadāśivamiśra, Sūtravrtti by Annambhtta, Vaiyākaranasarvasva by Dharanidhara, Sabdabhūsaņa Nārayana Pandita, Pāninisūtravrtti by Rāmacandrabhatta Vyākaraņadīpikā by Tare and Orambhatta. There are extracts available from a Sütravrtti called Bhagavrtti which is ascribed to Bhartrhari, but, which is evident. written by a later writer (विसलमति according to some scholars) as there are found verses from Bharavi and Magha quoted in it as noticed by Sīradeva in his vṛtti on Pari 76. Glosses based upon Pāņini Sūtras, but having a topical arrangement are also available, famous ones among these being the Prakriyākaumudī by Rāmacandra Sesa and the Siddhantakaumudī by Bhattojī Dīksita. The मध्यमकौमुदी and the लघुकौमुदी can also be noted here although they are the abridgments of the Siddhanta Kaumudi. There are Vrttis in other languages also, written in modern times, out of which those written by Bohtlingk, Basu and Renou are well-known.

पाणिनीयशिक्षा a short work on phonetics which is taken as a Vedānga work and believed to have been written by Pāṇini. Some say that the work was written by Pingala.

पाणिनीयशिक्षादीका name of a commentary on the Siksā of Pāṇini by घरणीघर as ordered by king उत्पल्लसिंह.

पातञ्जलमहाभाष्य the same as महाभाष्य. See महाभाष्य.

पात्रेसमितादि a class of irregular compound words headed by the compound word पात्रेसमित, which are taken correct as they are. This class of words consists mostly of words forming a tatpurusa compound which cannot be explained by regular rules. The class is called आकृतिगण and hence similar irregular words are included in it; e. g. पात्रेसमिता; गेहेशूर: कूपमण्डूक: etc. cf. Kās. on P. II.1.48.

पाद lit. foot; the term is applied to a fourth part of a section such as अध्याय, or of a verse which is divisible into four parts or lines; cf. प्रकृत्यान्त:पादमब्यपरे P. VI.1.115, also गो: पादान्ते P. VII. 1.57.

पाद्पूरण completion of the fourth part or Pāda of a stanza or verse; cf. सोन्नि छोपे चेत् पादपूरणम् P. VI.1.134, also प्रसमुपोद: पादपूरणे VIII. 1.6. As many times some particles, not with any specific or required sense, were used for the completion of a Pāda, such particles were called पादपूरण; cf. सन्ताभिषायकं नाम निपात: पादपूरण; R.Pr.XII.7; also निपातस्त्वर्था-संभवे पादपूरणो भवति V. Pr. VIII.50 Uvvața.

पामादि a class of words headed by the word पामन् to which the tad. affix न is added optionally with मतुष् in the sense of 'possession', e. g. पामनः, पामवान् ; वामनः, वामवान् etc.; cf. Kāś. on V.2.100.

पायगुण्ड, पायगुण्डे A learned pupil of Nāgeśabhatṭa who lived in Vārāṇasī in the latter half of the 18th century A.D. He was a renowned teacher of Grammar and is believed to have written commentaries on many works of Nāgeśa, the famous among which are the 'Kāśikā' called also 'Gadā' on the Paribhāṣenduśekhara, the 'Cidasthimālā' on the Laghuśabdenduśekhara and the 'Chāyā' on the Uddyota. Bālambhaṭṭa Pāyaguṇde, who

has written a commentary on the Mitākṣarā (the famous commentary on the Yajñavalkyasmṛti), is believed by some as the same as Vaidyanātha; while others say that Bālambhatṭa was the son of Vaidyanātha.

पारण the same as पारायण, recital of the Veda in any of the various artificial ways prescribed, such as krama, jaṭā, ghana etc.; cf. ऋते न च द्वैपदसंहितास्वरौ प्रसिध्यतः पारणकर्म चोत्तमम् R.Pr.XI.37.

पारस्करादिगण or पारस्करप्रमृति, words headed by the word पारस्कर which have got some irregularity, especially the insertion of स between the constituent words. For details see पारस्करप्रमृतीनि च संज्ञायाम् P. VI. 1.153 and the commentary thereon.

पारायण oral recital of a sacred work. See पारण.

पाराश्ये lit. serving the purpose of another like the Paribhāṣā and the Adhikāra rules in Grammar which have got no utility as far as they themselves are concerned, but which are of use in the interpretation of other rules; cf. आधिकारशब्देन पाराश्यांत् परिभाषाप्युच्यते. Par. Sek. Pari. 2, 3.

पारिभाषिक (1) technical, as opposed to literal; conventional; e. g. the words संबुद्धि, हेतु etc. cf. दाब्देरथांभिधानं स्वाभाविकम् । न पारिभाषिकमदाक्यत्वात् । लोकत एवार्थावगते: । Kāś on P. I. 2.56; cf. किमिदं पारिभाषिक्याः संबुद्धेर्प्रहणमेकवचनं संबुद्धिराहोस्विदन्वर्थप्रहणं संवोधनं संबुद्धिरिति । M. Bh. on P. I. 2.33; (2) derived on the strength of a Paribhāṣā cf. पारिभाषिकं किन्वदनित्यं स्यात् Kāt. Par. vṛ. Pari. 58.

पारिशेष्य residual nature; the law or rule of elimination; the remaining alternative after full consideration of all the other alternatives; cf. विभाषा कुरुयुगन्धराभ्याम् । पारिशेष्याद्युगन्धरार्था विभाषा Kāś. on P. IV. 2.130; cf. also पारिशेष्याद्वजन्तादेव यत् सिद्ध: Sīra. Pari. 37.

पारिषद् lit. belonging to the assembly; the term पारिषद refers to the results of the discussions held at the assemblies of specially prominent scholars or learned persons; cf. सर्वेवेदपारिषदं हीदं शास्त्र (ब्याकरणम्) तत्र नैकः पन्थाः शक्य आस्यातुम्। M.Bh. on II. 1. 58; VI. 3.14.

पारोध्य remoteness; lit. being out of sight; in grammar, पारोध्य is a condition for the use of the perfect tense (छिट्). See परोक्ष.

पार्षद् पर्वदि भवं पार्षदम्, lit. the interpretation or theory discussed and settled at the assembly of the learned. The word is used in the sense of works on Nīrukti or derivation of words as also works of the type of the Prātiśākhyas; cf. पदप्रकृतीनि सर्वचरणानां पार्षदानि Nir. I. 17 and the com. of दुर्गोचार्य; cf. also पार्षदकृतिरेवा तत्रभवतां नैव लोक नान्य-रिमन्येदे अर्थ एकार: अर्थ ओकारो वास्ति M. Bh. on I. 1. 48; see also pp. 104, 105 Vel. VII Mahābhāṣya D. E. Society's edition. See पारिषद.

पार्षद्व्याख्या name given to the commentary written by विष्णुमित्र on the Rk Prātiśākhya.

पार्षद्स्त्रवृति name given to the works of the type of commentaries written by उन्तर on the old Prātiśākhya books.

पाशादि a class of words headed by the word पाश to which the taddhita affix य is added in the sense of collection; e.g. पाश्या, तृण्या, वात्या etc. cf. Kas. on P. IV. 2.49.

पिङ्गलाचार्ये an ancient scholar who is believed to be the first writer on

Prosody, his work being known as ন্তন্ত্ৰ: যান্ধ of পিন্ধত. Some scholars believe that he wrote a work on Phonetics which is now popularly called পাণিনীয়ান্ত্ৰা.

पिच्छादि a class of words headed by the word पिच्छ to which the taddhita affix इल (इलच्) is added optionally with मत् (मतुप्), in the sense of 'possessed of'; e.g. ।पीच्छल; पिच्छवान, उरसिल: उरस्वान् etc.; cf. Kāś. on V. 2. 100.

पिञ्ज a tad. affix applied to the word तिल in the sense of fruitless, useless; cf. तिलालिप्पलात् पिञ्जपेजी IV. 2.36 Vart. 6; cf. also নিম্কাইনেল নৈল- দিহল: तिल्लेचेज: 1 Kāś. on P. IV. 2.36.

पिट ज् a tad. affix applied to the word नि in the sense of the depression of the nose, the word नि being substituted for नि; e.g. निपिट:; cf. इनच् पिटच् चिक चि च P. V: 2.33

पित marked with the mute letter प which is indicative of a grave accent in the case of affixes marked with it, as for example, the affixes तिन्, सिन् and ामप्; cf. अनुदात्ती मुप्पितौ P. III. 1.4. A Sirvadhatuka affix, marked with the mute consonant q, in Panini's Grammar has been described as instrumental in causing many operations such as (a) the substitution of guna; (cf. P. VII. 3 84,91). (b) the prevention of guna in the case of a reduplicative syllable as also in the case of the roots भू and \(\forall \) (cf. P. VII. 3.87, 88); (c) the substitution of Vrddhi, (cf. P. VII. 3.89, 90), (d) the augments इ and ई in the case of the roots तृह and g respectively (cf. P. VII. 3.92, 93, 94), and (e) acute accent for the vowel preceding the affix in the case of the roots भी, ही, मु and others (cf. P. VI. 1.192). A short vowel (of a root) gets त् added to it when followed by a kṛt affix marked with प्; e.g. विजित्य, प्रकृत्य, etc.; (cf. P. VI. 1.71).

पित्करण marking an affix with the mute consonant प् for several grammatical purposes; see पित्; cf. पित्करणानर्थक्यं चानक्कत्वात् P. III. 1. 33 Vart.5. See पित्.

पिरुक्त a grammatical operation caused by an affix marked with the mute consonant प्; cf. युत्त खडु पिति ङिस्कृतं प्राप्नोति ङिति च पिरुकृतं केन तन्न स्यात्, M. Bh. on III. 1.-3 Vart. 7. For details see पित्.

पित्व the same as पित्करण. See पित्करण and पित.

पिपीलिकमध्या, पिपीलिकमध्यमा name given to a stanza of त्रिष्ट्रप् or जगती or बृहती type consisting of three feet, the middle foot consisting of six or seven or eight syllables only; e. g. Rgveda X. 105, 2 and 7; IX. 110.1, VIII. 46.14; cf. डाध्यक् पिपीलिकामध्या हरीयस्थिति हस्यते R. Pr. XVI. 25, 28, 36.

বিষ্টান্ত [PISCHELL, RICHARD]
a famous European Grammarian
of the nineteenth century who
wrote many articles on grammatical subjects and wrote a work entitled 'Prakrit Grammar.'

पीडन compression; a fault in the pronunciation of vowels and consonants caused by the compression or contraction of the place of utterance; cf. विहारसंहारयोज्यांसपीडने। स्थानकरणयोर्विस्तारे ज्यासी नाम दोषः, संहारे संकोचने पीडनं नाम। R. Pr. XIV. 2; cf. also ज्यञ्जनानामतिप्रयस्तेनोज्ञारणं पीडनं R. Pr. XIV. 5.

पील्वादि a class of words headed by the word पील to which the taddhita affix द्युण (दुण्प) is added in the sense of 'decoction' (पाक). e. g. पीलुकुण: cf. Kāś. on P. V.2.24.

पु short term for the labial consonants प्, फ्, ब्, भ् and म् as prescribed by P. I.1.61 e. g. ओ: पुयण्डयपरे (P. VII. 4.80).

प्वद्भाव restoration of the masculine form in the place of the feminine one as noticed in compound words. formed generally by the Karmadhāraya and the Bahuvrihi compounds, where the first member is declinable in all the three genders: e. g. दीर्घजङ्गः. This restoration to the masculine form is also noticed before the tad. affixes तस्, तर, तम, रूप्य, पाश, त्व as also before क्यङ् and the word मानिन्. For details, see P. VI, 3.34 to 42 and commentaries thereon. See also page 334, Vol. VII of the Pātanjala Mahābhāsya D. E. Society's edition.

पुंस् masculine; a word used in grammar in the पुंलिङ्ग or the masculine gender; cf. स्त्रीपुंनपुंसकेषु Br. Dev. I. 40. cf. also असल्पाणां युवस्थविरस्त्रीपुंसानां विशेषश्चाविवक्षितः सामान्यं च विवक्षितम् । M. Bh. on P. I. 2.68 Vārt. 1; cf. पुंस्प्रवाद, and पोंस्नानि नामानि.

पुंस्क masculine nature, hence masculine gender. The word is generally found as a part of the word भाषित-पुंस्क which means a word which is declined in the masculine and the feminine gender or in the neuter and the masculine gender in the same sense. For details see M. Bh. on P. VI.3.34.

पुक् the augment प् added to the roots कर, ही, कर्य etc. as also to all roots ending in आ before the causal sign णिच् (इ); e. g. अर्पयति, ह्रेपयति, क्नेपयति, दापयति, etc.; cf. अर्तिह्री कर्याक्षमान्यातां पुङ् णो P. VII.3.36.

पुरुत्रराज a famous grammarian of the 12th century who wrote a learned commentaty on a part of the Vākyapadīya of Bhartrhari in which he has quoted passages from famous writers and grammarians such as भामह, दुन्तक, वामन, हेमचन्द्र and others. The name is found written as पुण्यराज also.

पुण्डरीकाक्ष a grammarian of the fourteenth century who wrote a commentary named कात-त्रपरिशिष्टटीका on the कात-त्रव्याकरण.

पुण्यनन्द्न a famous grammarian, who wrote a grammar work, named रूपमाला.

पुण्यराज see पुञ्जराज.

पुण्यसुन्द्रगाणि a Jain grammarian who has written a commentary work on the घातुपाठ of हेमचन्द्र.

पुत्रद् (1) the word पुत्र as given in the ancient list of masculine words marked with the mute letter ट् to signify the addition of the fem. affix हं (डीप्); cf. P. IV.1.15; (2) the substitute पुत्रट् (i. e. पुत्री) for the word दुहितृ optionally prescribed after the words मूत, उम्र, राज, भोज, कुल and मेर in the simple sense of 'girl' and not 'daughter' e. g. राजपुत्री, सूतपुत्री; cf. P.VI.3.70 Vart. 9.

पुनःप्रसङ्गविज्ञान occurrence or possibility of the application of a preceding grammatical rule or operation a second time again, after once it has been set aside by a subsequent opposing rule or rules in conflict; cf. पुनःप्रसङ्गविज्ञानात् सिद्धम् Par. Sek. Pari. 39; cf. M. Bh. on P. I. 4.2 Vart. 7; cf. also Puru. Pari. 40.

पुनः प्रस्व the same as प्रतिप्रस्व counterexception; cf. Candra Vyak. VI.4. 49.

पुनरक a passage which is repeated in the क्रमपाठ and the other Pāthas or recitals; the word is also used in the sense of the conventional repetition of a word at the end of a chapter. The word पुनर्वचन is used also in the same sense; cf. यथोक्तं पुनरुक्तं त्रिपदप्रभृति त्रिपदप्रभृति । T.Pr.I.61; cf. also R. Pr. X.8 and 10.

पुनग्रहण recital of a word again in the Krama and other Pāṭhas for a special purpose, although such a recital after three times is generally discouraged; cf. एवमधीवरोषात पुनरक्तस्य प्रहणं भवति ... Uv. Bhāṣya on V. Pr. IV. 177.

पुनर्वचन use of the same word or expression, which, if noticed in the writing of the Sūtrakāra, is indicative of something in the mind of the Sūtrakāra; cf. अण: पुनर्वचनमपवाद-विषये अनिवृत्त्यर्थम् M. Bh. on P. III. 3. 12 Vārt.1; cf also पुनर्वचनमनित्यत्वज्ञा-पनार्थम् । Kāś. on P. I. 41.

पुनर्विधान prescribing the same affix or operation again, which geneally is attended with some purpose; cf. ज्जुल: क्रियाथापपदस्य पुनर्विधानं तृजादिप्रतिक्षेधार्थम्, P.III. 3.10 Vārt. 1; cf. also पुनर्विधानसामर्थ्यादस्यभपूर्विद्विगोर्छङ् न, Kāś. on P. V.1.57.

पुनर्जृति occurrence of the same operation again after it has once occurred and has been superseded; cf. অঙ্কুতুর पুনর্ত্তিরার্থিই:, M.Bh. on VI. 4.160; VII. 1.30 etc.

पुम् or पुंस् masculine. It appears that both पुम्, and पुंस were current terms meaning 'masculine' in ancient days. cf. पुम: खर्यम्परे P.VIII. 3.12. and पुंसोसुङ् P. VII. 1.89. Although पुम् is changed to पुंस् before a word beginning with a hard consonant, still पुंस is given as an independent word derived from the root पा cf. पातेई मसुन् Uṇādi S· IV. 177; cf. also the expressions पुंवचन, पुंलिङ्ग and पुंयोग.

पुरस्तात occurring beforehand, preceding; cf. पुरस्तादपवादा अनन्तरान् विधीन् वाधन्ते नोत्तरान् Par. Sek. Pari. 59, also M. Bh. on VII. 2.100; cf. also the expression पुरस्ताद्वकर्ष which means the same as अवकर्ष which is opposed to अनुवृत्ति.

पुराण old; the word is used in the sense of old or ancient; cf. पुराणप्रोक्तेषु ब्राह्मणक्रस्पेषु. P. IV. 3.105. It is also used in the sense of old mythological works; cf. इतिहास: पुराण वैद्यक्षं M.Bh. on Āhnika 1 Vārt. 5.

पुरुष a grammatical term in the sense of 'person;' cf. करोति: पचादीनां सर्वान् कालान सर्वान् पुरुषान्सर्वाणि वचनान्यनु-वर्तते, भवति: पुनर्वतंसानकालं चैकत्वं च. These persons or Purusas are described to be three प्रथम, मध्यम and उत्तम corresponding to the third second and first persons respectively in English Grammar; cf. also Nir. VII. 1 and 2.

ব্ৰহণকাৰ name of a commentary on the Sarasvatīkaņṭhābharaņa of Bhoja by Kṛṣṇalilāśukamuni.

पुरुषसंज्ञा the term पुरुष or person viz. the first, the second and the third; the rule prescribing the term पुरुष is तिङ्खीणि त्रीणि प्रथमसध्यमे तमा: P. I. 4. 101; cf. परस्मैपदसंज्ञां पुरुषसंज्ञा बाधेत M. Bh. on P. I. 4. 1 Vart. 8.

पुरुषोत्तमदेव a famous grammarian believed to have been a Buddhist, who flourished in the reign of Laksmanasena in the latter half of the twelfth century in Bengal, Many works on grammar are ascribed to him, the prominent ones among which are the Bhasavrtti and the Paribhasavrtti. the Ganavitti and the Jnapakasamuccaya and a commentary on the Mahabhasya called Pranapaṇā of which only a fragment is available. Besides these works on grammar, he has written some lexicographical works of which Haravalī, Trikandasesa, Dvirūpakoṣa, and Ekākṣarakoṣa are the prominent ones. The Bhāṣāvṛtti has got a lucid commentary on it written by Sṛṣṭidhara.

पुरुषोत्तमविद्यावागीश a famous grammarian of Bengal, who wrote the grammar work Prayogaratnamālā in the fifteenth century. The work betrays a deep study and scholarship of the writer in the Mantrasāstra.

पुरोहितादि a class of words headed by the word पुरोहित to which the taddhita affix यक् is added in the sense of 'duly' or 'nature'; e.g. पारोहित्यम्, राज्यम्, बाल्यम्, मान्द्रम् etc.; cf. Kāś. on P. V. 1.128.

पुषादि a class of roots headed by the root पुत्र of the fourth conjugation whose peculiarity is the substitution of the aorist sign अ (अङ्) for जिल; e. g. अपृषत्, अगुषत्, अनुषत् etc. cf. पुषादिद्युतादश्लादितः परस्मपदेषु P. III. 1.55.

पुष्करण a popular term used for the treatise on grammar by an ancient grammarian Āpīśali. cf. আণিয়ন্ত पुष्करणम् Kāś. on P. IV. 3. 15. It was called Puṣkaraṇa probably because it was very extensive and widely read before Pāṇini. For the reading বুঙ্কর্থা for বুঙ্কর্থা, and other details see Mahābhāṣya Vol. VII. pp. 132-133, D. E. Society's edition.

पुष्करादि a class of words headed by the word पुष्कर, to which the taddhita affix इन् (इनि) is added provided the word ending with the affix forms the name of a district. e. g. पुष्करिणी, पश्चिनी etc. cf. Kāś. on P. V. 2.135.

पुजार्थ lit. for the sake of paying respect. The word is used by commentators in connection with references to ancient grammarians by Pāṇini in his sūtras, where the commentators usually say that the sūtras citing the views of ancient grammarians imply merely an option, the name being quoted merely to show respect to the grammarian; cf. आपिशाल्प्रहणं पूजार्थम् S.K. on P.VI.1.92.

पूज्यपाद originally a title, but mostly used in connection with the famous Jain grammarian देवनन्दिन् whose work on grammar called जैनेन्द्र- च्याकरण is well-known; see देवनन्दिन्.

प्रण an ordinal numeral: lit. the word means completion of a particular number (संख्या); cf. येन संख्या संख्यानं पूर्वते संपद्यते स तस्याः पूरणः । एकादशानां पुरण: एकादश: । Kās. on P.V. 2.48. The word is used also in the sense of an affix by the applicawhich the particular number (संख्या) referring to an object, is shown as complete; cf. यरिमनुपसंजात अन्या संख्या प्रत्ययार्थ: Kāś. on P. V.2.48. These Pūraņa pratyayas are given in P. V. 2. 48-58; cf. पूरणं नामार्थः। तमाह (तीयराब्द: | अत: पुरणम् M. Bh. on P.II.2.3. The word also means 'an ordinal number'; cf. प्रग्रागसुहितार्थ-सद्व्ययत्व्यसमानाधिकरणेन P.II.2.11.

पूरणप्रत्यय a tad. affix showing the completion of the particular number (संख्या) shown by the word to which the affix is applied; cf. अर्धपूर्वपदश्च पूरणप्रत्ययान्तः संख्याशब्दो भवतीति बक्तब्यम् । अर्धपञ्चमः । M. Bh.on P.I.1.23 Vart. 7. These affixes are mentioned by Papini in V.2. 48 to 58.

पूरणान्त ending with an ordinal affix; the same as पूरणप्रत्ययान्त; cf. योसी पूरणान्तात् स्वार्थे अन् सोपि पूरणसेव M. Bh.on P. II. 2.3.

पूर्व (1) ancient, old; (2) belonging to the Eastern districts. The word

is frequently used as qualifying the word সান্থাৰ্য where it means ancient.

प्वेत्रासिद्धवचन the dictum of Panini about rules in his second, third and fourth quarters (Padas) of the eighth Adhyaya being invalid to (viz. not seen by) all the previous rules in the first seven chapters and the first quarter of the eighth as laid down by him in the rule पूर्वत्रासिद्धम् VIII.2.1. The rule पूर्व-त्रासिद्धम is taken also as a governing rule i.e. अधिकार laying down that in the last three quarters also of his grammar, a subsequent rule is invalid to the preceding rule. The purpose of this dictum is to prohibit the application of the rules in the last three quarters as also that of a subsequent rule in the last three quarters, before all such preceding rules, as are applicable in the formation of a word, have been given effect to; cf. एवमिहापि पर्वत्रासिद्धवचन आदेशलक्षणप्रतिषेषार्थमत्सर्ग-লক্ষ্যামাৰাৰ্থ च M.Bh. on P. VIII.2.1 Vārt. 8.

पूर्वत्रासिद्धीय an operation prescribed in the province of the rule पूर्वत्रा- सिद्धम् i.e. in the last three quarters of the eighth book of Păṇini's grammar.

पूर्विनिघात the grave accent for the preceding acute vowel as a result of the following vowel made acute, and the preceding, as a result, turned into grave by virtue of the rule अनुदात्तं पदमेकवर्जम् VI.1.198; cf. मतुब्विभत्तयुदात्तवं पूर्विनिधातस्यानिमित्तं स्यात् । अग्निमान्। वायुमान् । M. Bh. on P.I.1.39 Vart. 16.

पूर्वनिपात placing first (in a compound); priority of a word in a compound, as in the case of an adjectival word. For special instructions in grammar about priority see P. II.2.30 to 38.

प्रविपक्ष lit. the view placed first for consideration which generally is the view of the objector and is generally refuted by the author's view called उत्तरपक्ष or सिद्धान्त.

पूर्वपद anterior member, the first out of the two members of a compound, as contrasted with the next member which is उत्तरपद; cf. पूर्व-पदोत्तरपद्योश्कोददाः पूर्वपदस्यान्तवन्द्रवति, M. Bh. on P.VI.1.85 Vart. 4.

पूर्वपद्प्रकृतिस्वर retention of the original acute accent of the first member in a compound as is generally noticed in the bahuvrihi compound and in special cases in other compounds; cf. बहुनीही प्रकृत्या पूर्वपद्म and the following rules P. VI. 2.1 to 63.

पूर्वपदार्थप्राधान्य importance in sense possessed by the first member of a compound as noticed generally in the case of the avyayībhāva compound, which hence is defined as पूर्वपदार्थप्रधानान्ययोभावः M.Bh. on P.II. 1.6, II.1.20, II. 1.49.

पूर्व रूप substitution of the former letter in the place of the two viz. the former and the latter, as a result of the coalescence of the two; cf. अमि पूर्व: and the following rules P. VI. 1.107-110.

पूर्वविधि (1) an operation or kārya for the anterior; cf. P. I. 1.57; cf. also Mahābhāsya on P. I. 1.57; cf also एकादेश: पूर्वविधो स्थानिवत् M.Bh. on I.2.4 Vārt. 2 and II. 4.62 Vārt. 4; (2) an operation or a rule cited earlier in the order of sūtras; cf. पूर्वविधिमुत्तरो विधिवधित M. Bh. on P. I. 1.44 Vārt. 13.

पूर्वविप्रतिषेघ conflict of two rules where the preceding rule supersedes the latter rule, as the arrival at the correct form requires it. Generally the dictum is that a subsequent rule should supersede the preceding one; cf. विप्रतिषेधे परं कार्यम् P. I. 4. 2; but sometimes the previous rule has to supersede the subsequent one in spite of the dictum विप्रतिषेधे परम्. The author of the Mahābhāṣya has brought these cases of the पूर्वविप्रातिषेध, which are. in fact, numerous, under the rule विप्रतिषेधे परं कार्यम् by taking the word पर in the sense of इष्ट ' what is desired '; cf. इष्टवाची परशब्दः । विप्रातिषेषे परं यदिष्टं तद्भवतीति । M. Bh. on I. 1.3; I.2, 5; I. 4.2; II. 1.69, IV.1.85etc.; cf. also पूर्वविप्रतिषेधो नाम अयं विप्रतिषेधे परमित्यत्र परशब्दस्य इष्टवाचित्वालुब्यः सूत्रार्थः परिभाषास्थेण पञ्चते Puru. Pari 108; for details see page 217 Vol. VII Mahābhāṣya D. E. Society's edition.

पूर्वसवर्णद्धि substitution of the long form of the previous vowel in the place of two vowels as a result of their coalescence, prescribed by Pāṇini in VI. 1.102.

पूर्वसूत्र lit. previous rule; a rule cited earlier in a treatise. The word is, however, frequently used in the Mahābhāṣya in the sense of 'a rule laid down by an earlier grammarian'; cf. वर्ण वाहुः पूर्वसूत्रे M. Bh. Āhnika l, पूर्वसूत्रे गोत्रस्य दृद्धमिति संज्ञा क्रियते M. Bh. on I. 2. 68; cf. also M.Bh. on P.IV.1.14 Vārt. 3, VI.1.163 Vārt. 1, VII.1.18, VIII.

पूर्वस्थानिक a variety of antarangatva mentioned by Nāgeśa in the Paribhāṣenduśekhara, where an operation, affecting a part of a word which precedes that portion of the word which is affected by the other operation, is looked upon as antaranga; e. g. the হিন্টাথ in ন্ধানিষ্ঠ (ন্ধানিন্+ হয়) is looked upon as अन्तरङ्ग with respect to the elision of নিন্ which is বহিন্দে. This kind of antarangatva is, of course, not admitted by Nāgesa although mentioned by him; cf. Par. Śek. Pari. 50,

पूर्वन्ति end of the previous. The word is used in connection with a vowel which is substituted for two vowels (एकादेश.). Such a substitute is looked upon as the ending vowel of the preceding word or the initial vowel of the succeeding word; it cannot be looked upon as both at one and the same time; cf. अन्तादिवच P. VI. 1.85 and उमयत आश्रयेण नान्तादिवत् Sira. Pari. 60; cf. also किं पुनरयं पूर्वान्तः अहोस्वित् परादिः आहोस्विदमक्तः M. Bh. on I. 1.47 Vārt. 3.

पूर्वान्तसस्वर belonging to the previous vowel in syllabication; e. g. a consonant at the end of a word or the first in a consonant group (संयोग).

पूर्वोपरपाद name given to the second pada of the second adhyaya of Paṇini's Aṣṭādhyayī which begins with the Sūtra पूर्वापराघरोत्तरमेकदेशिनेकािकरणे P. II. 2.1.

पुक्त lit. mixed. The term is used in the Prātiśākhya works in connection with the vowel ऋ or ल which is looked upon as a पुक्तस्वर being mixed with the consonant र or ल; cf. पुक्तस्वरो नाम ऋकार: लकारश्च रेपलकारसंपृक्तस्वात् com. on T.Pr.XIII.16.

पृथक् separately as far as hearing is concerned; distinctly separate from another; cf. सत स्वरा ये यमास्ते पृथग्वा R. Pr. XIII. 17.

पृथग्योगकरण framing a separate rule for a thing instead of mentioning it along with other things in the

same context, which implies some purpose in the mind of the author such as anuvitti in subsequent rules, option, and so on; cf. पृथ्ययोग्यक्रणमस्य विधेरनित्यत्वज्ञापनार्थम् Kāś. on P. I.3.7; cf. also Kāś. on I.3.33, I. 3. 84, I.4.58, III.1.56, IV.1.16, VII. 4.33, VIII.1.52, VIII.1.74.

पृथ्वादि a class of words headed by the word पृथु to which the taddhita affix इमन् (इमानेच्) is added optionally with the other usual affixes अण्, त्व and तल् in the sense of 'nature'; e. g. प्रथिमा, पार्थवम्, पृथुत्वम्, पृथुता; similarly म्रदिमा, मादवम् मृदुत्वम्, मृदुता पिटमा पाटवम्, पद्धता पद्धत्वम्; cf. Kāś. on P.V.1.122.

पृथ्वीधराचार्य a grammarian of the Eastern school who wrote the treatise कातन्त्रविवरण on Katantra Grammar.

पृषोद्रादि a group of words, with irregularity in the coalescence of the two constituent members, collected together by Pāṇini and mentioned together with the word पृषोदर at the head; cf. पृषोदरादीनि यथापदिष्टम् P. VI. 3. 109; cf. also थेषु लेपागमवर्णाविकाराः शास्त्रण न विहिताः, हश्यन्त च तानि, यथोपदिष्टानि साधूनि भवन्ति। पृषोदरम्, बलाहकः, जीमूतः, पिशाचः, वृसी, मयूरः, पयोपवसनानाम्, दूव्यः etc. Kās. on P.VI. 3.109.

पेज tad. affix added to the word तिल optionally with the affix पिञ्ज; e. g. तिलपेज:. See पिञ्ज.

पेदुभद्द a grammarian, who has written a treatise named औणादिकपदार्णव on the Uṇādi sūtras.

पैलाई a class of words headed by the word पैल, the tad. affix in the sense of युवन applied to which (words) is elided; e.g. पैल: पिता, पेल: पुत्र:; for details see Kāś. on P.II.4. 59.

पौनःपुन्य frequency; repetition; a sense in which the frequentative affix यङ् and in some cases the imperative mood are prescribed; cf. पौनःपुन्यं भृशार्थश्च कियासमभिहारः S. K. on P. III. 1.22; cf. also S. K. on P.III.4.2.

पौरस्त्यवयाकरण a grammarian of the eastern school which is believed to have been started by जिनन्दबुद्धि the writer of the gloss called न्यास on the Kāśikāvṛtti. The school practically terminated with पुरुषोत्तमदेव and सीरदेव at the end of the twelfth century A.D. Such a school existed also at the time of Panini and Patānjali, a reference to which is found made in प्राचां ष्प ताद्धितः P. IV. 1.17 and प्राचासवृद्धात्मन् बहुलम् IV.1. 160 and प्राचामुपादेरडज्वुचौ च V.3.80 where the word is explained as प्राचामाचार्याणां by the writer of the Kāśikā.

पौर्वापर्य (1) a relation between two operations or rules based upon their anterior and ulterior positions, which is many times taken into consideration for deciding their relative strength; (2) the order of words; cf. शब्देनार्थान्वाच्यान ह्ह्वा हुद्धो सुर्यात् पौर्वापर्यम् M. Bh. on P. 1.4.109 Vart. 10; cf. also पौर्वापर्यमकाल्ड्यपेतं संहिता, P. I. 4.109 Vart. 8.

पौकरसादि an ancient grammarian who belonged to the dynasty of पुष्करसद्, whose views are quoted by the Varttikakāra and the writers of the Prātiśākhya works; cf चयो द्वितीया: शरि पोष्करसादे: P. VIII. 4.48 Vārt. 3; cf. also व्यञ्जनपर: पौष्करसादेनं पूर्वश्च जकारम् T. Pr. V; cf. also T. Pr. XIII. 16; XIV. 2, XVII. 6.

ম a conventional term for ৱন্দ (short) generally applied to vowels in the Jainendra Vyākarana.

प्रकम्प depression of the voice after raising it as noticed in connection with the utterance of the svarita vowels in certain cases and in certain Vedic schools with a view to show the svarita nature of the vowel distinctly, in spite of the fact that such a depression is generally looked upon as a fault; cf. असन्दिग्धान् स्वरान् ब्र्यादिवकृष्टानकाम्पितान् R. Pr. III.18 as also जात्योभिनिहितक्षेत्र क्षेप्रः प्राक्षित्र एव च । एतं स्वराः प्रकम्पन्ते यत्रोचस्वारितोदयाः R. Pr. III.19.

प्रकरण topic; context; a section wherein a particular subject is treated; cf. अर्थात् प्रकरणाजा लोके कृत्रि- माक्वात्रिमयोः कृत्रिमे संप्रत्ययो भवति M.Bh. on I. 1. 23; cf. also सामान्यशब्दाश्च नान्तरेण विशेषं प्रकरणं वा विशेषं प्रवति M. Bh. on I. 2.45 Vart 9.

प्रकरणप्रस्थ literary works in which the treatment is given in the form of topics by arranging the original sūtras or rules differently so that all such rules as relate to a particular topic are found together; the Prakriyākaumudī, the Siddhāntakumudī and others are called प्रकरणप्रस्थ. Such works are generally known by the name प्रक्रियाप्रस्थ as opposed to ब्रात्स्य.

प्रकर्ष eminence; excellence of a particular quality; cf. कथं पुनरन्यस्य प्रकर्षेण अन्यस्य प्रकर्षः स्यात्; cf. also यद्यपि द्रव्यस्य स्वतः प्रकर्षे नास्ति तथापि गुणिकयास्यः प्रकर्षे द्रव्ये उपचर्यते, Kāś on P. V. 4.11.

प्रकर्षगति preferential treatment, special consideration; cf. तत्र प्रकर्षगतिर्वि शास्यते साधीयः यः अस्त्रिधः इति, M.Bh.on P.I. 1.56; cf. also M. Bh. on III. 1.94 Vārt. 6.

प्रकर्षण keeping wide the two parts of the chin which causes a fault in pronunciation called निक्कि?; cf. प्रकर्षण तदु निक्किश्मादुः। इन्नोः प्रकर्षण सर्वे-

तश्रलने विक्रिश्मसंयुक्तं नाम दोषों भवति ; Uvvata on R. Pr. XIV.-3.

प्रकल्पक (fem. प्रकल्पिका) a word or expression causing a change in the nature of another word or expression which has to be taken as changed accordingly; cf. प्रकल्पक-मिति चेन्नियमाभाव: P.I. 1.68 Vārt. 15; प्रल्पयविधिरयं न च प्रत्ययविधी पञ्चम्य: प्रकल्पिका भवन्ति M.Bh. on P.I.1.27 Vārt.1,I.1. 62 Vārt.7; II.2.3 Vārt.1, IV. 1.60; cf. also रुघादिभ्य: इत्येषा पञ्चमी शप् इति प्रथमाया: षष्टीं प्रकल्पयिष्यति, M. Bh. on II 2.3. Vārt. 1, III.1.33.

प्रकल्पिक्य a word in which a verbal activity has to be conjectured, as for example, the words गो:, अश्वः etc. Words which are not actually derived by rules of grammar are called प्रकल्पिक्रय as contrasted with प्रत्यक्षिक्रय.

प्रकार (1) attribute, attribute which differentiates, manner, difference: differentiating description; cf. काचि-त्प्रकारं प्राप्तः इत्थंभूतः Kās. on P.II.3.21; (2) resemblance, similarity of one thing with another with slight deficiency; cf. प्रकारे गुणवचनस्य । प्रकारो भेदः सादृश्यं च । तदिह सादृश्यं प्रकारी गृह्यते । प्रकारे वर्तमानस्य गुणवचनशब्दस्य द्वे भवतः। पटुपटुः मृदुमृदुः । अपरिपूर्णगुण इत्यर्थः । परि-पूर्णगुणेन न्यूनगुणस्य उपमाने सत्यवं प्रयुज्यते Kāś. on P. VIII.1.12; (3) differentiating attribute; cf. प्रकारवन्त्रने थाल V. 3.23, प्रकारवचने जातीयर् V. 3.69, स्थूलादिभ्यः प्रकारवचने कन् V. 4.3 where Kāśīkā defines the word प्रकार as सामान्यस्य भेदको विशेषः प्रकारः Kāś. on V. 3.23 and 69; (4) type, cf. इतिराब्द: प्रकारार्थ: Kāś. on V. 2.93; cf. also आदिशब्द; प्रकारे Kāś. on देवपथादिभ्यश्च P. V.3.100; cf. also आदिशब्द: प्रकारे वर्तते । देवदत्तादय आढ्याः । देवदत्तप्रकारा इत्यर्थ: M.Bh. on I.3.1 Vart. 11.

মনার name of commentary on Bhartrhari's Vākyapadīya by Puñjarāja.

সকীৰ্ণকাত name given to the third Kāṇḍa or book of Bhartrhar i's Vākyapadīya where miscellaneous topics are treated. The third Kāṇḍa consists of 14 sections called by the name Samuddeśa. For details see pp. 381-382 Mahābhāṣya Vol. VII. D. E. Society's edition.

प्रकृत (1) in context, in question; the word is frequently used in connection with words in the preceding rules which are drawn on to the following rules by anuvitti or continuation; cf. प्रकृत गुणवृद्धिग्रहणमनुवर्तते, M.Bh. on I.1.3 Vārt. 2: (2) found or available in a large quantity; cf. तत्प्रकृतवचने मथ्ट । प्राचुर्येण प्रस्तुतं प्रकृतम् । Kās. on P. V. 4.21.

प्रकृति (1) material cause; cf.. तद्ध प्रकृतो । प्रकृतिरुपादानकारणं तस्यैव उत्तरमवस्थान्तरं विकृतिः Kās.on P.V.1.12; (2) original, as opposed to 'modified' (विकृति): the original base of a word which is used in language by the addition of affixes. There are mentioned three kinds of such original words in grammar, roots (धातु), noun bases (प्रातिपादिक) and affixes (प्रत्यय). प्रकृति is defined as ' शास्त्रप्रक्रियाव्यवहारे प्रकृतिप्रत्ययविभागकल्पनय शब्दार्थभावनायां प्रत्ययात् प्रथमम्पादानकारणामेव या उपादीयते तां प्रकृतिरिति ब्यपदिशन्ति ' in the Sringāraprakāsa; cf. अपदाब्दो ह्यस्य प्रकृतिः। न चापशब्दः प्रकृतिः। ह्यपशन्दा उपदिक्यन्ते न चानुपदिष्टा प्रकृतिरस्ति । M.Bh. on Siva Sūtra 2; cf. also कुरप्रकृतिर्धातु: M.Bh. on P. VI. 2. 139 Vart. 2: पदप्रकृतिः संहिता । पदप्रकृतीनि सर्व-चरणानां पार्षदानि Nir. I.17.

प्रकृतिनियम restriction regarding the base, as contrasted with प्रत्ययनियम, cf. किमयं प्रत्ययनियम: प्रकृतिपर एव प्रत्ययः प्रयोक्तब्यः अप्रकृतिपरो नेति । आहोस्वित् प्रकृतिनियम: । प्रत्ययपरैव प्रकृतिः प्रयोक्तब्या अप्रस्थय-परा नेति । M.Bh. on P.III. 1.2.

प्रकृतिप्रत्ययविभाग division of a word

(in use in a language) into the base and the affix, which is looked upon as the main function of grammar.

प्रकृतिप्रत्यापति restoration to the original word from the substituted word; e.g. the restoration of the root इन् in कंसनधमाच्छे कंसं घातयति; cf. आख्यातात्कृदन्ताण्णित्रक्तन्यस्तदाच्छे इत्येत-रिमन्धे। कृष्डुक् प्रकृतिप्रत्यापति; प्रकृतिनच कारकं भन्नतीति नक्तन्यम्, M.Bh. on III. 1. 20 Vart. 6.

प्रकातिभाव phonetical maintenance of a wording without allowing any euphonic modifications as found in the case of a dual form ending in ई, ऊ or ए, as also in other specified cases; cf. ईद्देद्दिवचनं प्रसम् and the following rules P. I. 1.11 to 19, as also जुतप्रसा अचि नित्यम् VI.1.125.

प्रकृतिस्वर the accent i.e. the acute accent (उदात्त) possessed by the original word as contrasted with the accent of the affix (प्रत्ययस्वर) which (latter) is looked upon as more powerful; cf. (बहुब्रीही) पूर्वपदं प्रकृतिस्वर भवति M.Bh. on II.1.24, II. 2.29 Vart. 17. See Pāṇini Sūtras VI.2.1 to 63.

प्रकृत्यन्तर difference in the radical base; a different radical base; cf. कथमुपबहणम् l बृहिः प्रकृत्यन्तरम् M. Bh. on I. 1. 4; cf. also प्रत्ययार्थस्याज्यति-रेकात्प्रकृत्यन्तरेषु मन्यामहे धाद्येश कियामाहेति M.Bh. on P.I. 3.1.

पक्त्यर्थानियम restriction regarding the sense of the radical base; cf. प्रकृत्यर्थनियम अन्येषां प्रत्ययानाममान:। अनुदात्त- ङितस्तृजादयो न प्राप्तुवन्ति M.Bh. on P.I. 3.12 Vart. 5.

प्रकृत्या intact, without any change by rules of euphony, accent etc.; cf.P. VI. 2.1 etc. VI.2.137, VI.3.74 and VI.4.163.

प्रकृष्ट superior, excellent; cf.मध्यमश्च गुक्र-शब्दः पूर्वमपेक्ष्य प्रकृथः परमपेक्ष्य न्यूनः न च न्यूनः

प्रवर्तते; M.Bh. on P. V.3.55 Vārt. 3. प्रक्रम (1) the place of articulation, the place of the production of sound, such as throat, chest, palate and the like; cf. प्रकम्यन्ते अस्मिन्वर्णा इति प्रकमः स्थानमुच्यते M. Bh. Pradipa on सिद्धं तु समानप्रकमवन्त्रनात् P. I.2.30 Vārt. 2; (2) recital of Veda, described as कमपाट cf. उमयथा च प्रक्रमे दोषो भवति M.Bh. on P. VIII. 4.28; cf. also "अष्टुसु प्रक्रमेषु दोषो भवति "quoted in the Mahābhāsya on P.VI. 1.172; (3) regularity in the position of words, regular order of words.

प्रक्रियाकीमदी a well-known work on Sanskrit Grammar by रामचन्द्रशेष of the 15th century, in which the subject matter of the eight chapters of Pānini's grammar is arranged into several different sections forming the different topics of grammar. It is similar to, and possibly the predecessor of, the Siddhanta Kaumudi which has a similar arrangement. The work was very popular before the Siddhänta Kaumudi was written. It has got commentaries numbering dozen viz. प्रक्रियाप्रसाद. प्रक्रियाप्रकाश. प्रक्रियाप्रदीप, अमृतस्तुति. प्रक्रियाव्याकृति,निर्मलदर्पग,तत्त्वचन्द्र, प्रक्रियारज्जन, प्रक्रियाचिवरण and others of which the Prasada of Vitthalesa and the Prakāśa of Śrikrana are the well-

प्रक्रियाकोमुद्दिन्ति called also प्रक्रियाको-मुद्दिन्याख्या or even कृष्णपण्डिता (वृत्ति) written by a learned grammarian named Kṛṣṇapaṇḍita belonging to the famous Sesa family of grammarians.

प्रक्रियाकोमुद्धिसार a commentary on Rāmacandra's Prakriyākaumudī by a grammarian named Kāśīnātha.

प्रक्रियाप्रकाश name of the learned commentary on the प्रक्रियाकौसुदी,

called also प्रक्रियाकोमुदीप्रकाश, by Kṛṣṇaśeṣa, the son of Nṛṣiṇhaścṣa, which is, in a way an improvement upon the commentary Prasada of Vitthaleśa.

प्रक्रियाप्रदीप name of a commentary on the प्रक्रियाकौमुदी, written by चक्रपाणिदत्त.

मिन्नियाप्रसाइ name of the scholarly commentary on Rāmacandra's Prakriyākaumudī, written by Vitthalesa, the grandson of Rāmacandra.

मोकेयासंग्रह a work on grammar by Abhayacandra in which the Sūtras of Śākaṭāyana's Śabdānuśasana are arranged in the form of different sections dealing with the different topics of grammar.

प्रगद्धादि a class of words headed by the word प्रगदिन to which the tad. affix य (ज्य) is added in the four senses prescribed in P. IV.2.67-70; e.g. प्रागद्मम्, शारद्मम् कौविदार्यम् etc.; cf. Kāś. on P. IV.2.80.

प्रगाथ a couple of Vedic hymns divided into three hymns for purposes of singing as Sāman; cf. यत्र द्वे ऋचौ प्रप्रथनेन तिल्लः क्रियन्ते स प्रगाथनात् प्रकर्षगानाद्वा प्रगाथ इत्युच्यते Kās. on P.IV 2.55.

प्रगीत a fault of utterance or recital where a simple word in conversation or recital is uttered in a tone proper for singing or in a manner suitable for singing; cf प्रगीत: सामबद्धारित: Kaiy. on M.Bh. Ahni.1

अगृहीत lit. held as it is, uncombinable by euphonic rules; the same as प्राह्म.

अगृहीतपदा a description of the Samhitā text of the Veda in which a pragrhya vowel preceding another vowel is held up (प्रग्रह्म) i.e. kept as it is, without any euphonic combination; cf. सहोदयास्ता: प्रगृहीतपदा: सर्वत्रेव व्यक्षरान्तास्तु नैव R. Pr. II. 27. সমূন্ত a term used in the Prātisākhya works and by Pāṇini, in the sense of a vowel which is not combined with the following vowel by rules of euphony; e. g. মুজার স্বশ্বনুর, স্বন্ধী সঙ্গ etc; cf. R. Pr. I. 28 and 29; P. I. 1.11-19 and VI.1.125.

সমন্ত absence of euphonic change; the term is frequently used in the Taittirīya Prātišākhya; cf. T. Pr. I.60, IV.1.1-54.

স্বাহ্ন name given to the subdivisions of chapters or sections in certain books.

प्रचय (1) a specific feature or quality (धर्म) of the grave (अनुदात्त) accent when a vowel, accented grave, is preceded by a स्वरित (circumflex vowel) and is followed upon by another grave-accented These grave vowels in succession, i.e. the grave vowels which are not followed by an acute or a circumflex vowel are uttered neither distinctly circumflex nor distinctly grave; cf. also R. Pr. III.11-14. They are uttered like the acute. but slightly so; e. g. the vowels after मे and before ति in इमं मे गङ्क यम्ने सरस्वति; cf. स्वरितात्महितायामनुदात्तानां प्रचय उदात्तश्रतिः T. Pr. XXI.10, 11 also cf. P.I.2.39, where the term एकश्रुति is used for the word प्रचय; (2) the connection of one word with many words; e.g. राज्ञा गोश्चाश्चश्च प्रवश्च where राज्ञ: is connected with गो. अश्व and पुरुष; cf. प्रचये समासप्रतिविधी वक्तव्यः M. Bh. on II.1.1 Vart. 6.

प्रज्ञादि a class of words headed by the word प्रज्ञ to which the tad. affix अ (अण्) is added without any change of sense; e.g. प्राज्ञः, वाणिजः etc.; cf. प्रज्ञ एय प्राज्ञः। प्राज्ञी स्त्री। यस्यास्तु प्रज्ञा विद्यते सा प्राज्ञा भवति। Kas. on P.V. 4.38.

प्रणयन composition (of the original

Sūtra work); cf. द्वयमि चैतत् प्रमाणम् । उभयथा सूत्रप्रणयनात् Kās. on P.IV.2. 117; cf. also Kāś. on P.V.1.94 and V.4.21.

प्रण्यस्त silent; cf. अनादेशे प्रण्यस्ता जिह्ना T. Pr. II.20 explained by Uvvaṭa as अनादेशे अनुपदेशे जिह्ना प्रण्यस्ता तूर्ध्णीभूता भवति।

प्रातिकण्डम् (1) vocally, pronouncedly, expressly without any attention to the derivation or the formation of the word; (2) irregular formation; c.. सर्वशास्त्रार्थं प्रतिकण्डमुक्तम् where प्रतिकण्ड is explained as निपातन by Uvvaṭa; cf. प्रतिकण्ड निपातनम् : उत्सर्गविधिमः साधायेतुमशस्या अपि प्रयोगविशेषा निपात्यन्ते शास्त्रसंपूर्तये. Uvvaṭa on R. Pr. I.23.

সবিক্ষম recital in the reverse order as in some of the artificial recitations of the Samhitā text such as জহা, ঘন etc.

प्रतिजनादि a class of words headed by the word प्रतिजन to which the tad. affix ईन (खज्) is added in the sense of 'good at' (तत्र साधु:); cf. प्रतिजने साधु: प्रातिजनीनः, जने जने साधुरित्यर्थ: Kās. on P. IV.4.99.

प्रतिज्ञा प्रतिज्ञान also; hypothesis, express tenet in a Sastra or convention; cf. आड: स्थ: प्रातिज्ञान इति वक्तव्यम्। अस्ति सकारमातिष्ठते। आगमी गुणवृद्धी आतिष्ठते। विकारी गुणवृद्धी आतिष्ठते M.Bh. on P.I.3. 22; cf. also प्रतिज्ञानुनासिक्याः पाणिनीयाः Kas. on P.I.3.2, VII.1.1. प्रतिज्ञास्विरताः पाणिनीयाः Kas. on P.I.3.11.

मातिद्दन्द्रभाविन् opponent, opposing; अन्तरङ्गं बहिरङ्गमिति प्रतिद्दन्द्वाभाविनौ एतौ पुक्षौ। M.Bh. on P. VIII.3.15.

प्रतिनिर्दिश्यमान predicate, as opposed to the subject; cf. उद्देश्यप्रतिनिर्दिश्यमानशैरेक्यमापादयत्सर्वनाम पर्यायेण तत्ताङ्किङ्गभाक् M. Bh. Pradīpa.

भाविपात्ते knowledge, understanding; cf. तस्मादनभ्युपायः शब्दानां प्रतिपत्तौ प्रतिपद-पाठः । M.Bh. on Ahn. 1; also cf. M.Bh. on P. I. 1. 20. Vart.5, I. 1. 44,46 etc.

प्रतिपत्तिगरीयस्त्व difficulty in understanding; requiring an effort to understand the sense; cf. योगविभागे तु प्रतियोगं भिन्नबुद्धयुद्याद् ब्यक्तं प्रतिपत्तिगरीय-स्त्वम् Puru. Pari. 98.

प्रतिपत्तिगौरव difficulty in understanding; requiring a longer time in understanding the sense; cf. एवं हि प्रतिपत्तिगौरवं स्यात् Sīra. Pari. 50. See प्रतिपत्तिगरीयस्त्व.

प्रतिपत्तिलाघव facility of understanding; cf. प्रतिपत्तिलाघवार्थ ज्ञाजनोर्जा इति दोर्घान्तादेशविधानम् Sīra. Pari. 91.

प्रतिपद्पाठ (1) recital of each and every word; (2) enumeration of every word; cf. किं राज्दानां प्रतिपत्तो प्रतिपद्पाठ: कर्तज्यः, M. Bh. on Ahn. 1.

प्रतिपद्विधान express statement by a definite wording; cf. एवं ताई उभयमनेन कियते अपवादविषये चानिवृत्तिः उत्सर्गविषये च प्रतिपदविधानम् । M. Bh. on III 3. 12. Vārt.1; cf. also प्रतिपदविधाना च षष्टी न समस्येत । का पुनः षष्टी प्रतिपदविधाना का कृत्योगा । सर्वा षष्टी प्रतिपदविधाना शेषलक्षणां वर्जयित्वा । कर्तृकर्मणोः कृति इति या षष्टी सा कृत्योगा; M. Bh. on P. II, 2.8 and II.2.10.

प्रतिपद्विधि an injunction or operation stating expressly the word or words for which it is meant; cf. यं विधि प्रति उपदेशोनर्थंकः स विधिवध्यते । दत्वं प्रति नुमः प्रतिपद्विधिरनर्थंकः, रोः पुनर्नि-मित्तमंवः। M.Bh. on P. VIII. 2.72.

प्रतिपदोक्त expressly stated as opposed to implied or suggested; cf. लक्षण- प्रतिपदोक्तयोः प्रतिपदोक्तयेव प्रहणम्, Par. Sek.Pari.105; cf. also विशेषण प्रतिपादितं प्रतिपदोक्तं Puru. Pari. 3.

प्रतिप्रस्व lit. bringing into life again; the term is used in the sense of a counter-exception; cf. याजकादिभिश्चेति पुनः कारकषष्ठीसमासप्रतिप्रसवाद् न्नाह्मणयाजकादि- षु उत्तरपदमकृतिस्वर एव । Bhāṣāvṛtti on II.2.16.

प्रतियोगिन negative counterpart; cf. न चारतरेण प्रतियोगिन स्पर्धा भवति M. Bh. on II. 1.69. Vārt. 6; also M.Bh. on VIII. 8.4 Vārt. 8; corresponding term; ct. प्रथमप्रहणं च तियोग्यपेक्षत्वाको-प्रयुज्यते Kās. on V. 3.1.

प्रतिरूपक similar in appearance; cf. उपसर्गविभक्तिस्वरणतिरूपकाश्च निपाता भवन्ति M. Bh. on P. II. 2.24 Vart. 22, as also on P. III. 4.2; cf. उपसर्गप्रतिरूपका निपाता:, तिङ्न्तप्रतिरूपका निपाता:; cf. also अस्ति च समासप्रतिरूपको रूढिशब्द: स्वतन्त्र इति Nyasa on P. I. 4.54.

प्रतिलोम lit. regressive; a kind of Samdhi or euphonic combination, in which the consonant precedes and the vowel comes after it; e. g. हन्यवाडम्भिः; cf. प्रतिलोमसंधिषु न्यञ्जनानि पूर्वाणि स्वरा उत्तरे; Uvvata on R. Pr. I. 4.

प्रतिवर्ण for every letter; corresponding to every letter; cf. अनर्थकारत वर्णाः प्रतिवर्णमर्थानुपळ्छेः M. Bh. on Ahnika 2, Siva sūtra 5.

प्रतिविधान counteraction; solving a difficulty by taking the necessary action; cf. अयिभदानों स प्रतिविधानकाल; M. Bh. on P. VII. 4.60 Vārt. 4; cf. also तत्र प्रतिविधान द्विवेचनिमित्ते अचीत्युच्यते, Kās. on P. VI. 1.2; cf. also the usual expression प्रतिविधां देविषु M. Bh. on I. 1.39, I. 3.10, 4.1.1 etc.

प्रतिषिद्ध a rule or operation which is prohibited or prevented from application by a specific negation of it by another rule or operation laid down to prohibit it. Generally the prohibited rule does not apply again; cf. सक्कद्रतौ विप्रतिषेधे यद्वाधितं तद्वाधितम्ब Par, Sek.Pari. 40; cf. नोत्सहत प्रतिषिद्धा सती बाधितुम् | M.Bh. on P. I. 1.43. The word प्रतिषिद्ध which is generally used in ancient works appears to be an earlier word as compared with निषद्ध which is used by later grammarians.

प्रतिषेध prohibition, negation, prohibition of a rule or operation; generally प्रतिषेध or प्रसन्यप्रतिषेध is laid down by the use of the negative particle (नज्) connected with a verbal activity, and not with a noun in a compound in which case the negation is named पर्युदास; cf. प्रसन्ध्यप्रतिषेधा यः क्रियया सह यत्र नज्। पर्युदासः स विशेषः यत्रोत्तरपदेन नज्।

মনিষ্মক a word expressing a prohibition, e. g. the negative particle ন (নহা); cf. নিনি মনিষ্যক: T. Pr.XXII.8.

प्रतिषेधवलीयस्त्व the priority of consideration given to rules laying down a prohibition, for instance, the prohibition of guṇa or vṛddhi by the rule ङ्कित च P. I. 1.5 after giving due consideration to which, the injunctions i.e. the guṇa and vidhi rules are to be applied; cf. निषधाश्च बलीयांस: Par. Sek. Pari. 112; cf. also. एवमप्युभयो: सावकाशयो: प्रतिषधवलीयस्त्वात्प्रतिषध: प्राप्नोति, M.Bh. P. on III. 1.30.

प्रतिषेध्य what is prohibited, as opposed to विधेय : cf. औत्त्वं च प्रतिषेध्यम् ; M.Bh. on P. I. 1.47, I.I.51.

प्रतिसंस्करण editing with improvement, with an attempt to restore the correct version or the original text in the place of the corrupt one; sometimes suitable additions and improvements are also made; e.g. चरकप्रतिसंकरण attributed to Patanjali.

प्रतिहार excessive contact with the sound-producing organ which is looked upon as a fault; cf. वगेंबु जिह्नापथनं चतुर्बु प्रासो मुख्ये प्रतिहारश्चतुर्थे । चतुर्थे वगें (तवगें) प्रतिहार: अतिप्रयत्नो नाम देखो मवति । Uvvata on R. Pr.XIV.7.

प्रतीताथे whose sense is clear and which hence does not require any further explanation; cf. यथा चापि प्रतीतार्थीन स्युस्तथैनान्याचक्षीरन्। Nir. I.13.

प्रतृण्ण lit. broken or split up; the separated words of the Samhitā of the Vedas i. e. the Padapāṭha; the recitation of the Padapāṭha.; cf. शौद्धाक्षरोचारणं च प्रतृष्णम् R. Pr. I. 3.

प्रत्यक्षिक्रय a word in which the verbal activity is actually noticed, as for instance, verbs and ket formations; the term is used as an antonym of प्रकल्पाक्रिय.

प्रत्यय affix, suffix, a termination, as contrasted with प्रकृति the base; cf. प्रत्याय्यते अर्थ: अनेन इति प्रत्यय:; cf. also अर्थ संप्रत्याययति स प्रत्ययः M.Bh. on III. 1.1 Vart. 8; The word प्रत्य is used in the Prātiśākhya works in the sense of 'following' or 'that which follows', e. g. स्पर्शे चोष: प्रत्यये पूर्वपद्य: R. Pr. I. 30 which is explained by Uvvata as उत्र: इत्ययं (शब्द:) पूर्वपदावयव: सन् स्पर्शे प्रत्येय पर्भते इति यावतः रेफ्सिंज्ञो भवति: Uvvata on R. Pr. I.30: cf. प्रत्येति पश्चादागच्छाते इति प्रत्ययः परः T. Pr. V. 7; cf. also V. Pr. III. 8. Pratyaya or the suffix is generally placed after the base; cf. प्रत्यय:, पश्च P. III. 1. 1,2; but sometimes it is placed before the base; e.g. बहुण्डः; cf. विभाषा सुपो बहुच् पुरस्तात्त P. V. 3.68. The conjugational signs (হাণু, হ্মন্ etc.), the signs of tenses and moods (चिछ, सिन्त् , स्य, तास् etc.) and the compound endings (समासान्त) are all called pratyayas according to Pāṇini's grammar, as they are all given in the jurisdiction(अधिकार) of the rule प्रत्यय: III.1.1, which extends upto the end of the fifth chapter (अध्याय). There are six main kinds of affixes given grammar सुप्प्रत्यय, तिङ्प्रत्यय, कृत्प्रत्यय, तद्वितप्रत्यय, घातुप्रत्यय (e.g. in the roots चिकीष, कण्ड्य etc.) and स्त्रीप्रत्यय. word प्रत्यय is used in the sense of realization, in which case the root इ in the word त्यय means knowing' according to the maxim सर्वे गत्यर्था ज्ञानार्थाः; cf. मन्त्रार्थप्रत्ययाय Nir. I.15.

प्रत्ययग्रहणपरिभाषा the guiding rule that when an affix (प्रत्ययं) given in a rule as a निमित्त (causing something), the affix denotes a word-form which begins with that to which that affix has been added and ends with the affix itself: cf. प्रत्ययग्रहणे यस्मात स विहितस्तदादेस्तदन्तस्य च प्रहण्म Par. Sek. Pari. 23. The rule यञियोश्च, which prescribes the affix पक् (आयन), has the word यञ् and इञ् which respectively mean यञन्त and इञन्त: in the word परमगार्ग्यायण from परमगार्ग्य the word गार्ग्य is looked upon as यञन्त to which एक (आयन) is affixed and hence the word परमगार्ग्या-यण is arrived at and not पारमगाग्यं.

प्रत्ययंत्रातु a term applied to secondary roots which are formed by adding affixes like णिच्, सन्, यङ् etc. to primary roots or by the addition of affixes like किप्, क्यच्, कायच् etc. to nouns; e. g. कामय, हारय, चिकीष, जिहीष, जेश्रीय, चेकीय, गङ्गीय, राजाय, पुत्रकाग्य etc.; cf. सनाद्यन्ता धातवः P.1II..1.32; cf. also प्रत्ययधातु । गोपायति, धूपायति, क्रतीयते M. Bh. on VI. 1.162 Vart.3.

प्रत्ययपाद् a conventional name given to the first pada of the third adhyaya of Panini's Astadhyayi which begins with the rule प्रत्यय: III.1.1.

प्रत्ययस्थण an operation caused by an affix which takes place even though the affix is elided; e.g. the term षद is applied to अग्निचित, सोमसुत् etc. on account of the words ending with a case affix although the affix of the nom. sing. has been elided; cf. प्रत्ययस्थि प्रत्ययस्थणम्. P.I.1. 62 and Kās. thereon.

प्रत्ययांचिधि a rule prescribing the addition of a suffix; cf. यस्मात्रत्ययविधि-स्तदिद ह ययेङ्गम्, P.I.3.13. प्रत्ययस्वर an accent caused by virtue of the affix which is added; cf. यथैव हि निपातनस्वरः प्रकृतिस्वरं वाधंत एवं प्रत्ययस्वरमपि वाधंत । जितिश्रिःश्वाप्रत्ययस्वरे भिवेच्यति । M. Bh. on P. I.1 56 Vart. 23.

प्रत्ययान्त (प्रकृति) a base ending in an affix, a secondary base as opposed to the original base, which is described to be of six kinds. सुष्प्रत्ययान्ता (प्रकृतिः) as in अहंयुः, सायंतनम् etc.; तिङ्प्रत्ययान्ता as in पचतितराम्, आस्तिकः, पचतभूजता etc.; कृत्प्रत्ययान्ता as in कृत्रिमम् सांग्रविणम् etc.; तद्धितप्रत्ययान्ता as in गाग्यांयणः, तत्रत्यः etc.; धातुसंज्ञाप्रत्ययान्ता as in चिकीषाँ, कण्डूया etc.; स्त्रीप्रत्ययान्ता as in गाङ्ग्यः, गौरेयः, काद्रवेय; etc.

प्रत्ययार्थ the meaning of an affix. Generally meanings are assigned to affixes when they are prescribed. When the meanings are not assigned, the affix is supposed to bear the sense of the base; cf. अनिदिश्रयाः प्रत्ययाः स्वार्थ Par. Sek. on Pari. 113. The sense given by a word in language is the composite sense of the base and the affix together; cf. प्रकृतिप्रत्यया सहार्थ ब्रतः। न केवला प्रकृतिः प्रयोक्तब्या, न केवलः प्रत्ययः। M. Bh. on P.I.2.64 Vart. 5.

प्रत्यवमर्शे reference (made to something) by a word; cf. ताम्यामिति संप्रदानार्थ प्रत्यवमर्श: Kāś. on P. III.4.75; cf.also तन्नामिकाभ्य इति सर्वनाम्ना प्रत्ययप्रकृतेः प्रत्यवमर्शः Kāś. on P.IV.1.113.

प्रत्याख्यान rejection of a rule or a word or words in a rule shown as redundant, their purpose being shown as served otherwise; cf. लुपि युक्तवद् व्यक्तिवचने इति प्वांचार्याणामेवेदं सूत्रम् । तथा चास्य प्रत्याख्यानं भविष्यति । तदशिष्यं संज्ञाप्रमाणत्वादिति । Kāsi. on I.2.51.

प्रत्याख्यानपञ्च an alternative which proposes the rejection of something such as a rule or its part; cf. यदि प्रत्याख्यान पञ्च: इदमपि प्रत्याख्याने M. Bh.

on Siva Sūtra 4; cf. also अदीवयुरिति पदकारस्य प्रत्याख्यानपक्षे उदाहरणमुपपन्नं भवति Vyãḍi Pari. 42.

प्रत्याख्यानवादिन one who advocates the rejection of something, an opponent, an objector; cf. प्रत्याख्यानवादि। आह-नास्त्यत्र विशेष इति Kaiy. on M. Bh. on P. VI.4.22 Vart. 15.

प्रत्यादान lit. taking again; uttering a word already utttered in the Krama and other recitations of the Vedas; cf. कमो द्वाम्यामतिकम्य प्रत्या-दायोत्तरं तयो: । प्रत्यादाय पुनर्यहीत्वा Uvvaṭa on R. Pr. X-1.

प्रत्यापत्ति restitution, restoration to the previous wording; cf. प्रातिपदिकस्य च प्रत्यापत्तिवेक्तव्या M. Bh. on P. VI.3.34 Vārt.2; restoration to the previous nature; cf. अकारस्य प्रत्यापत्ती दीर्वप्रतिषेध: । खद्वा,माला। M.Bh. on P. VIII.4.68.

मत्यासाय literally, repetition in a contrary way; in the Prātiśākhya literature, the word refers to the repetition of a Vedic passage; repetition by pupils after hearing from the preceptor; cf. प्रत्यासाय: पुनवंचनं Uvvata on R. Pr. XV. 9.

प्रस्थारम्भः (1) statement after prohibition lit. commencing again; inducing a person to do something after he has refused to do it by repeating the order or request for generally by beginning the appeal with the word नह; e.g. नह भोक्ष्यसे? नह अध्येप्यसे; cf. नह प्रत्यारम्भे P. VIII. 1.31 and Kāśikā and Nyāsa thereon. (2) commencement or laying down again in spite of previous mention; cf. रेषवचनात्तु योसौ प्रत्यारम्भात्कृतो बहुन्नीहिः M. Bh. on P. VI-3.46.

प्रत्यासङ्ग close contact or association; तरतमयोश्च अतिराये अदक्षिणप्रत्यासङ्गे । प्रत्यासङ्गः प्रत्यासङ्गता V. Pr. V. 2.

प्रत्यासात्ते immediate proximity; close contact; the same as प्रत्यासङ्ग which

see above; cf. हेतुमाण्णचो विधिः प्रांतवेधोपि प्रत्यासत्तेस्तस्येव न्याय्यः Kāś. on P. I 3.88. cf. also Kāś. on VII.1.95.

प्रत्यासित्तन्याय or प्रत्यासित्तवचन a dictum that a word should, as far as possible, be construed with the nearest word; cf. अनन्तरस्य विधि: प्रतिषेधो वेत्यर्थ: प्रतिपत्तिन्यायळम्य: Sîra. Pari. 48.

पत्याहार lit. bringing together; bringing together of several letters (or words in a few cases, such as roots or nouns) by mentioning the first and the last only for the sake of brevity; the term प्रत्याहार is generally used in connection with brief terms such as अण्, अक् , अच् , हल् and the like, created by Pānini in his grammar by taking any particular letter and associating it with any mute final letter (अनुबन्ध) of the fourteen Sivasūtras, with a view to include all letters beginning with the letter uttered and ending with the letter which precedes the (mute) letter. The practice of using such abbreviations was in existence before Pāṇini, possibly in the grammar attributed to Indra. The term प्रत्याहार is not actually used by Panini; it is found in the Rk. Tantra; cf. प्रत्याहारार्थी वर्णीनवन्धी व्यञ्जनम् R.T.I.3. The term appears to have come into use after Pānini. Pānini has not given any definition of the term प्रत्याहार. He has simply given the method of forming Pratyāhāras and he has profusely used them: cf. आदिरन्त्येन सहेता P. I. 1.71. The word कुञ् in P. III.1.40 and तृन् in P. II. 3.69 are used as Pratyāhāras. For a list of the Pratyaharas which are used by Pānini see Kāśikā on the Māheśvara Sūtras.

प्रत्याहारसूत्र a term for the fourteen Siva Sūtras which are utilized for the formation of Pratyāhāras. प्रत्याहारसूत्रविचार a short treatise explaining the pratyāhāras अण्, अट्, अश् etc. in the grammar of Pāṇini; one such work is written by a southern grammarian named तिमण्णा.

সন্থাহাথান্ত্ৰিক name given to the second Ahnika of the Mahābhāsya which explains the Siva Sūtras অহ্তগ্, কলুক্, etc., and hence naturally discusses the Pratyāhāras.

प्रत्युचार repetition especially of what has been recited by the preceptor; cf. प्रत्युचार्येतद्वचनं परस्य शिष्यस्य स्याद् भी इति चोदना वा, R. Pr. XV. 8.

সন্মুক্তীবন bringing to life again; the term is used in the sense of সনিসম্ব or counter exception.

प्रत्युदाहरण counter instance. order to explain the wording of a grammatical rule clearly, it is customary to give along with the instances of the rule (where the rule has been effectively employed), a few words which would have resulted into other faulty words by the application of the particular rule in case that rule had not been stated or a word or more of it had been omitted: cf. न केवलानि चर्चापदानि ब्याख्यानं शृद्धिः आत् ऐच इति । किं तर्हि । उदाहरणं प्रत्यदाहरणं वाक्याध्याहारः इत्येतत सम्दितं भवति । M. Bh. in Ahnika 1.

प्रथम lit. premier, first; the word is used in connection with the personal affixes तिप्, तस्, हि (अन्ति) of verbal forms. See the word पुरुष above; cf.अस्तिभेवन्तीपर: प्रथमपुरुष: अप्रयुच्यमानेष्यस्तीति । वृक्षः प्लक्षः । M. Bh. on P. II. 3.1 and 4. The word प्रथम is used in the Prātiśākhya works in the sense of the first consonants of the five vargas or groups of consonants; cf. प्रथमिर्द्वती-यास्तृतीयश्चतुर्थाः V. Pr. IV. 110 cf. प्रथमतृतीयादीनामादेशादित्वादेत्वाभावः, M. Bh.

on P. VI. 4.120 Vārt 3, also cf. Kātantra I. 4.1 and Hem. I. 3.35. The word is also used (in the feminine gender) in the sense of the case affixes सु (स्), औ, जन् (अस्) of the nominative case. The word is also used in the sense of the premier accent उदात्त (acute); cf. प्रथमभाविनः उदात्तभाविनः Uvvata on R. Pr. III. 8.

प्रथमा the nominative case; case affixes of the nominative case. cf. प्रातिपदिकार्थालेङ्गपरिमाणवचनमात्रे प्रथमा P.II. 3.46.

प्रदर्शन illustration; cf. विदांकुर्वन्तु इति । इतिकरण: प्रदर्शनार्थः न केवलं प्रथमपुरुषवहुवचनं किं तिर्हे सर्वाण्येव लोड्वचनान्यनुप्रयुज्यन्ते । Kāś. on P. III.1.41; cf. also किमर्थो योग-विभागः । प्रदर्शनार्थः । Kāś. on P.I.2.59.

प्रदान mode of articulation, the same as करण.

प्रदेशि popular name of the famous commentary on the Mahabhasya of Patañjali written by the reputgrammarian Kaiyata in the eleventh century A. D. The commentary is a very scholarly and critical one and really does justice to the well-known compliment given to it, viz. that the Pradipa has kept the Mahābhāsya alive which otherwise would have remained unintelligible and consequently become lost. The commentary पदीप is based on the commentary महाभाष्यदीपिका, or प्रदीपिका written by Bhartthari, which is available at present only in a fragmentary form. The Pradipa is to this day looked upon as the single commentary on the Mahabhasya in spite of the presence of a few other commentaries on it which are all thrown into the back-ground by it.

प्रदीपकार Kaiyatabhatta, the author of the famous commentary प्रदीप

on the Mahābhāṣya, which see above.

प्रदीपित्रवरण called also उद्योत written by the well-known grammarian Nāgesabhatṭa of Vārāṇasī who flourished in the first half of the eighteenth century.

प्रदेश lit. district; sphere of application, place of the application of a rule. The word is frequently used in this sense in the Kāśikā Vṛitti; cf. प्रत्ययप्रदेशाः प्रत्ययलेप प्रत्ययल्खामित्वेवमादयः Kāś. on P. III.1.1; cf. also अनुदात्तप्रदेशाः अनुदात्तो सुप्पितौ इत्यादयः Kāś. on P. I. 2.30. The word प्रदेश is also used in the sense of the place of use or utility; cf. संज्ञाशास्त्रस्य तु कार्यकालपक्षे न पृथ्यवाक्यार्थवोधः किं तु प्रदेशवाक्येन सहैव । ... कार्यज्ञानं च प्रदेशदेश एव Par. Śek. Pari. 3.

प्रदेशशास्त्र a rule, laying down a positive original injunction as opposed to the अपचादशास्त्र; cf. यै: अर्थाः प्रदिश्यन्ते तानि प्रदेशशास्त्राणि com. on R. Pr. XI.35.

प्रधान (1) the principal thing as opposed to the subordinate one; something which has got an independent purpose of its own and is not meant for another; प्रधानमुपसर्जनमिति च संबन्धियान्दावेती M.Bh. on P. I.2.43 V.5; cf. also प्रधानाप्रधानयोः प्रधाने कार्यसप्रयः Par. Sek. Pari. 97; (2) predominant; of main importance; cf. पूर्वपदार्थप्रधानान्ययोभावः etc. M. Bh. on II. 1.6, 20, 49 II.2.6 etc; (3) primary as opposed to secondary; cf. गाणे कर्मणि दुह्यादेः प्रधाने नीहकुष्वहाम्। cf. also प्रधानकर्मण्यास्थेये लादीनाहिकिकर्मणाम्। अप्रधाने दुहादीनाम् M.Bh.on I.4.51

प्रधानिशृष्ट prominently mentioned as opposed to अन्वाचयशिष्टः cf. कर्तुः क्यङ् सलोपश्च । प्रधानिशृष्टः क्यङ् अन्वाचयशिष्टः सलोपः M. Bh. on III.l. 11; cf. also प्रधानान्वाचयशिष्ट्योः प्रधाने संप्रत्ययः Vyādi Pari. 67.

प्रश्वंसिन् disappearing; cf. उच्चरितप्रध्वं-सिनोनुबन्धाः Vyāḍi Pari. 11.

प्रपञ्च amplification, further explanation, clarification. The expression पूर्वरयेवायं प्रपञ्चः or तस्यैवायं प्रपञ्चः is very frequently used in the Kāśikā vṛtti; of. Kāś. on P.II. 1.33,37,41, 58, II.4.28, III.2.61 etc.

মঘান্তক a term used for a division of a work by an ancient writer, as for instance in the case of the Atharvaprātiśākhya.

प्रभा (1), name of a commentary on the Sabdakaustubha by Rāghavendrācārya Gajendragadkar; (2) name of a commentary on Kaiyata's Mahabhāṣyapradīpa.

সমাবন্ধ a Jain grammarian who wrote a learned commentary named Nyāsa on the Amoghāvṛtti of Amoghavarṣa.

प्रभृति a passage or a word at the commencement; cf. इरावंतीप्रभृति आ दाधार T. Pr. IV. 22: ज्ञुतादिप्रभृतीनि च R. Pr. X. 4 तिउद्गुप्रभृतीनि च P.II.1.17.

प्रभेद smaller division, sub-division.

प्रमाण (1) authority; authoritative proof; cf. लोक: अवश्यं राव्देशु प्रमाणम् M. Bh. on I. 2.64 Vārt. 29; (2) measurement, measure; cf. प्रमाणे द्वयसञ्द्रश्वनात्रचः P. V. 2.37; प्रमाणतः अकारो गुण: प्राप्त: Kāś. on P. I. 1.50.

प्रमाद inadvertance, negligence; cf. प्रमादकृतमाचार्थस्य शक्यमकर्तुम् M. Bh. on P. IV. 2.70; cf. also अन्य तु गौरादि- ध्वेतयोः प्रमादपाठमाहुः Kaiy. on P. I. 1.72. Vart. 4.

प्रयतन the same as प्रयत्न; see प्रयत्न.

प्रयत्न (1) effort; the word is used in connection with the effort made for producing sound; cf. तुल्यास्प्रयदनं सवर्णम् P. 1.1.9; these efforts are described to be of two kinds बाह्य and आम्यन्तर of which the latter are considered in determining the

cognate nature of letters (सावण्यं); cf.आम्यन्तरप्रयत्नाः सवर्णसंज्ञायामाश्रीयन्ते; Kāś. on P. I. 1.9; (2) specific measure taken for a particular purpose such as marking a letter with a particular tone or accent or dividing a rule, or laying down a modificatory rule or the like; cf. सैवाननुमृत्तिः शब्देनास्थायते प्रयत्नाधिक्येन पूर्वसूत्रेपि संबन्धार्थम् Kāś. on P. IV. 3.22.

प्रयुक्ताख्यातमञ्जरी a small treatise on verbal forms by सारङ्गकवि.

प्रयोग (1) employment or use of a word in language and literature about which, laying down rules is looked upon as the purpose of grammar; cf. प्रयोगम्लत्ताद् व्याकरणस्मृते: Kaiy. on P. V. 1.16, लोकतार्थप्रयुक्ते शब्दप्रयोगे शास्त्रिण धर्मनियमो यथा लोकिक-धैदिकेषु M. Bh. Ahnika I. Vart. 1; (2) use of speech; utterance; cf. मध्यमेन स वाक्प्रयोग: प्रणवात्मक: कर्तव्य:, T. Pr. XVIII. 4.

प्रयोगांनेयम general rules or principles laid down regarding the use of words in language and literature such as (1) a word recognised as correct should always be u ed, cf. एवमिहापि समानायामर्थगती शब्देन चापशब्देन च धर्मनियमः क्रियते शब्देनैवार्थोभिधेयो नाप-राब्देनेति । एवंक्रियमाणमस्युदयकारि भवति ${f M.}$ Bh. on P. I. 1. Ahnika 1, (2) never a base alone or an affix alone should be used, but always a base with the necessary affix should be used; cf. यावता समय: कृतो न केवला प्रकृतिः प्रयोक्तन्या न केवलः प्रत्ययः M. Bh, on P. I. 2.64 Vārt. 8, also on P. III. 1.94 Vārt. 3; (3) when the sense is already expressed by a word, a word repeating the sense should not be used; cf. उक्तार्थानामप्रयोगः. Besides these, many minor regulations of the type of Paribhāsās are laid down grammarians. For details see Paribhāṣāsamgraha Introduction.

प्रयोगपञ्च a small treatise in verses on the conjugation of roots, written by Bhavanātha Miśra, son of Ramāpati.

पयोगमुखमण्डन known also by the name प्रयोगविवेक, an elementary treatise on syntax, attributed to वरस्व, who must, of course, have been different from the ancient grammarian वरस्वि.

मयोगरत्नमाला name of a recognised treatise on grammar written by पुरुषोत्तमविद्यावागीदा of Bengal in the fourteenth century. The treatise explains many words which, although current in language and literature, cannot be easily formed by rules of grammar. The author has tried to form them by applying rules of grammar given in the grammatical systems of Panini and Katantra. The alphabet given in this treatise is according to the system of the Tantra Sastra which shows a scholarship of the author in that branch The grammar was studied much in Bengal and Assam.

प्रयोगविधि an elementary work on the three constructions which has no name of the author mentioned.

प्रयोगविषय sphere or domain of the use of words; the whole Vedic and classical recognized literature; cf. महान् हि शब्दस्य प्रयोगविषयः । सप्तद्वीपा वसुमती त्रयो छोकाः चत्वारो वेदाः साङ्गाः सरहस्याः बहुधा विभिन्नाः, एकश्वतमध्व-धुशाखाः, सहस्रवत्मा सामवेदः, एकविशतिधा बाह्ह्च्यं, नवधाथवणो वेदो वाकोवाक्यामितिहासः पुराणं वैद्यक्तिमत्येतावाञ्शब्दस्य प्रयोगविषयः M. Bh. Ahnika 1. Vart. 5.

प्रयोजक causing another to do; causal agent; cf. कुर्वाण प्रयुङ्के इति प्रयोजक: Kāś. on P. I. 4.55.

प्रयोजन object, motive or purpose in undertaking a particular thing;

the word is used although rarely, in the sense of a cause also; cf. इमान्यस्य प्रयोजनानि अध्येयं ब्याकरणम् M. Bh. Āhnika 1. For the advantages of the study of Vyākaraṇa, see M. Bh. Āhnika 1. See also Vyākaraṇa Mahābhāṣya Vol. VII pp.226,227, D.E. Society's edition.

प्रयोज्य that which is employed or incited or urged; the word which is the subject in the primitive construction and becomes an object in the causal construction, and as a result, which is put in the accusative case being प्रयोज्यकर्म. As, however, the प्रयोज्यकमें originally occupies the place of the subject in the primitive construction, the term प्रयोज्यकर्ता (प्रयोज्यश्चासो कर्ता च) is often used in connection with it, as contrasted with the term प्रयोजककर्ता which is used with respect to the subject in the causal construction; cf. হু ব भेदिका देवदत्तस्य यज्ञदत्तस्य काष्टानामिति प्रयोज्ये कर्तरि षष्टी न प्राप्नोति । M.Bh. on P. III. 1.26 Vart. 1; cf. also Kaiy. on P. I. 2.65.

प्रवचन (1) recital of Vedic texts; cf. अथेके प्राहुरनुसंहितं तत् प्रारायणे प्रवचनं प्रशस्तम् R. Pr. XV. 16; cf. also इति प्र बाभ्रव्य उवाच च कमं कमप्रवक्ता (बाभ्रव्य:) प्रथमं शशंस च, R. Pr. XI. 33; (2) the reading of the Samhita text प्रावचनो वा यजुषि । प्रवचने भवः स्वरः प्रावचनः । प्रवचनशब्देनार्षपाठ उच्यते । V. Pr. I. 132.

प्रवण circumflex accent; possessed of svarita accent; cf. सर्वः प्रवण इत्येके। प्रकर्षेण वन्येत व्युत्क्षिप्यते इति प्रवणः स्वरितस्वरः T. Pr. I. 47; cf. also प्रवणे यष्टव्यम् M. Bh. on VI. 2.33.

प्रवर्तकोपाध्याय a grammarian who wrote an explanatory gloss named कैयटप्रकाशिका on the महाभाष्यप्रदीप written by Kaiyaṭabhaṭṭa.

प्रवर्तना incitement or inducement which is the sense of the 'lin' affixes in general; cf. प्रवर्तनायां छिड्.

प्रवाद a grammatical explanation; detailed explanation by citing the gender, number, krt affix, tad. affix and the like: cf. लिङ्गसंख्यातद्वितकृतरूप-भेदाः प्रवादाः । पाण्यादिशन्दानां प्रवादेषु प्रथमो (original) नकारा णत्वमाप्नाति स च प्राकृत: I T. Pr. XIII. 9. The word is explained as a change in the form of a word, as for instance, by the substitution of स् for विसर्ग where विसर्ग is, in fact, expected; cf. कबन्धं पृथु इत्येतेषां पदानां प्रवादा रूपभेदा उदय परत्रावस्थिताः दिव इत्येतस्य उपचारं जनयन्ति । यथा दिवस्कबन्धम् , दिवसपृथु: Uvvata on R. Pr. IV. 22; cf. also प्रবादा: ঘারির: परे, R. Pr. IX. 18. In the Nirukta, the word is used in the sense of 'distinct mention'; cf. एवमन्यासामीप देवतानामादित्यप्रवादाः स्ततयो भवन्ति (deities are mentioned under the name of Aditya) Nir II.13; cf. also वैश्वानरोया: प्रवादा: Nir, VII, 23.

प्रवादिनः scholars who explain the changes (प्रवाद) mentioned above; possibly the Padakāras or writers of the पदपाठ; cf. प्रवादिना दूणाशदूखादूलमान ... महाप्रदेशं स्वधितीव चानयेनुदेश R. Pr. XI. 20. Apparently प्रवादिनः (nom. sing.) seems to be the word in the explanation of Uvvata.

प्रविग्रह separate or distinct utrerance of several words of a sentence which are joined together by Samdhi rules in a compound (समास) or otherwise, with a very short pause (अवग्रह) after each word. e. g. उद् उ एति instead of उद्देति; cf. प्रविग्रहेण मृह्यवग्रहेण चर्चयेयुः R. Pr. XV.10, where Uvvata remarks प्रविग्रहेषु प्रक्षित्रं सुर्योत्। कालाधिक्येन सुर्योत्। तथा च उद् उ एति इति पठेन तु उद्देति.

प्रविभक्त made separate with their component parts shown clearly; split up into component parts in such a way that their meaning also is fully stated; cf, तद्वितसमासे-

ष्येकपर्वसु चानेकपर्वमु च पूर्व पूर्व अपरं अपरं प्रविभष्य निर्भूयात् । दण्ड्यः पुरुषः । दण्डमह्तीति वा दण्डेन संपद्यते इति वा । Nir.II.2.

प्रवृत्त (1) complete; cf. अथ ये प्रवृत्ते अथं अमिताक्षरेषु प्रत्येषु वाक्यप्रणा आगच्छान्त पदप्रणास्ते, Nir. I. 9; (2) which has presented itself, which has become applicable; the word is used in connection with a grammatical rule or operation; cf. एवं च कृत्वा धर्मशास्त्रं प्रवृत्तम्; M. Bh. on P. I. 2.64 Vārt.39; समुदाये ब्राह्मणशब्दः प्रवृतोवययेष्वि वर्तते जातिहीने गुणहीने च। M.Bh. on II. 2.6; cf. दिविस्य यण हस्य इति प्रवृत्तं, M. Bh. on P. VI.1.77; also cf. यद्यपि क्लिययमपवादः ... तातिक मन्थरं प्रवृत्तः परेण बाध्यते S. K. on P. VII.1.35.

प्रशृति (1) application or presentation of a rule as opposed to निवृत्ति; cf कचित्रपृति: कचित्रपृति:

प्रवृत्तिनिमित्त cause of the application of a word which is shown by the word when the affix त्व or ता is added to it; cf. तस्य भावस्त्वतला । शब्दस्य प्रवृत्तिनिमित्तं भावशब्देनोच्यते, Kas. on P.V. 1.119. There are given four such causes जाति, गुण, क्रिया and संज्ञा.

प्रवृत्तिभेद difference regarding the cause of application; cf. पूर्विमित वर्तमाने पुनः पूर्वग्रहणं प्रवृत्तिभेदेन नियमप्रति-पत्यर्थम्; Kāś. on P. VI.2;174.

प्रमुद्धादि a class of compound words headed by the word प्रमुद्ध in which the second word, which is a past pass. part., has its last vowel accented acute; cf. प्रमुद्धं यानम्, प्रमुक्ताः सक्तवः, खट्बाह्दः । आकृतिगणश्च प्रमृद्धादिर्द्र- एज्यः । तन पुनरुत्युतं वासा देयमित्यादि सिद्धं भवति Kas. on P. VI.2. 147.

সন্ধিত (1) an additional letter (vowel or consonant) read on splitting up a euphonic combination; cf. সাস্ভায়,

वर्णावेतों M.Bh. on P.I.1.9 Vārt. 2; (2) contracted combination; name of a Samdhi where two vowels coalesce into one single vowel, cf. R.Pr. II. 15-19.

मारिस्यनिर्देश mention of a thing in a coalescence, which when split up, shows a phonetic element or a letter which could not be known before the components were separated; अनुपसर्जनात्। प्रक्षिप्रीनेदेशीयम्। अनुपसर्जन अ अ अत् इति। M.Bh. on I. 1.27 Vārt. 6; cf. also M. Bh. on P.II.3.69.

মস্টাৰ (1) coalescence of two yowels into one, as given in R. Pr. II.6. and 7, corresponding to the गुण, वृद्धि und दीर्घ substitutes prescribed by the rules আর্ण: P.IV. 1.87; अक: सवर्णे दीर्थ: VI.1.101; and वृद्धिरेचि VI. 1.88 which are stated under the jurisdiction of the rule एक: पुर्वपरयो: VI.1.84; (2) finding out the presence of a letter in addition to the letters already present as coalesced, after splitting the combination into its different constituent letters. This practice of finding out an additional letter is resorted to by the commentators only to remove certain difficulties in arriving at some correct forms which otherwise could not be obtained; e.g. see ऋति च where क is believed to be a combination `of गु, कृ and ङ् See प्रक्षिष्ट and प्रक्षिप्रिनिर्देश.

प्रसंधान lit. linking up; joining; repeating a word in the Kramapātha and joining it with the following word; e. g. the second words ईळ पुरोहितम् etc. in अग्नि ईळे । ईळ पुरोहितम् । पुरोहितं यज्ञस्य ।

असक applicable, but not actually applied; the word is used in connection with a grammatical rule or operation that has become

applicable, but has not been applied; cf. इत्सर्गस्य प्रसक्तस्यापवादो वाधको भवति, M. Bh. on P. II.3 32, also प्रसक्तस्यादर्शनं लोपसंशं भवति M. Bh. and S.K. on P.I.1. 60. The term प्रसक्त is opposed to the term अभिनिवृत्त.

प्रसङ्ग applicability; possibility of being applied; the word is used with respect to a grammatical rule or operation which is on the point of being applied or taking place; the word प्राप्ति is also used in the same sense; cf. को हि शब्दस्य प्रसङ्गः यत्र गम्यते चार्थो न च प्रयुख्यते M.Bh. on P.I.1.60: cf. also हो प्रसङ्गो अन्यार्थो एकस्मिन् स विप्रतिषेधः, M. Bh. on P.I.4. 2; also cf. प्रसङ्गे सित सहशतम आदेशः स्यात् S.K. on स्थानेन्तरतमः P. I.1.50.

प्रसुज्यप्रतिषेध prohibition of the possible application of a rule, generally laid down by the use of the negative particle न, together with, or connected with, a verbal activity; e.g न लुमताङ्गस्य P.I.1.63, नामि P.VI 4.3, न माङ्योगे VI.4.74 etc. etc; cf. प्रसज्यप्रतिषेधोऽयं क्रियया सह यत्र नज्; cf. also प्रसज्यायं कियागुणौ ततः पश्चानिवात्तं करोति M.Bh. on P.II.2.6. In some cases the negative particle in a compound has also to be taken as stating a negation by प्रसच्यप्रतिषेध:;cf. M.Bh. on सङ्-वृंसकस्य P.J.1.43, सार्वधातुकमपित I.4.2, चादयोऽसत्त्वे I. 4. 57.

प्रसाद् see प्राक्रियाप्रसाद by Vitthalesa.

प्रसारण a term used by ancient grammarians for संप्रसारण, i.e. the substitution of a corresponding vowel for a semivowel; e.g. इ for य, उ for च, ऋ for र and ल for छ; cf. रिक ज्यः प्रसारणम् P.I.1.4. Vart. 6.

प्रसार्णिन that which gets, or is liable to get the Prasarana or Samprasarana substitute; cf. कविधी सर्वत्र प्रसार्णिभ्यो ड: P.III.2.3 Vart. 1.

प्रसिद्ध (1) established; in existence; cf. क्रमेण नार्थ: पदसंहिताबिद: पुराऽप्रसिद्धा-

अयपूर्वसिद्धिभि:, R. Pr. XI. 34 where the Kramapātha is said to be one which was not established before the Samhitāpātha; (2) known; cf. अनिटि प्रसिद्धे क्से। भविष्यति M. Bh. on P. III. 1.45 Vārt. 4, लोकत एते शब्दा: प्रसिद्धा: स्त्री पुमान नपुंसकीमिति M. Bh. on P. IV. 1.3; (3) brought about, accomplished, realized; तथास्य छः प्रसिद्धो भवति M. Bh. on P. IV. 1.89 Vārt. 2. सर्वत्रैव जक्त्वेन सिद्धं स्यात्, M. Bh. on P.VIII 2.25.

प्रस्ताच context, topic, the same as प्रकरण which see above; cf. प्रस्ताव: प्रकरणम् । यथा मोजनप्रकरणे सैन्धनमानयेति लवणे प्रतीतिर्गमनप्रकरणे त्वश्वे, Kaiy. on M. Bh. I. 1.23 Vart. 4.

प्रस्वार a word or utterance in three mātrās or moras; cf. स ओमिति प्रस्वरित त्रिमात्रः प्रस्वारः स्थाने स भवत्युदात्तः R. Pr. XV.3 whereon Uvvata remarks त्रिमात्रः प्रस्वारः । See the word ओंकार.

भाक् before a particular thing in place, or in recital, or in mention. The word is used generally to show the limit upto which a particular topic extends; cf. तिस्लाद्यः प्राक् पारापः; cf. also प्राक् कडारान्समासः P. I. 4.1; cf. also अथ आख्याः समाम्राथाधिकाः प्राग्निपतात् V. Pr. I. 33.

प्राकृत (1) original, primary, belonging to the Prakṛti as contrasted with a वैकृत modification or a modified thing; cf. प्रकृतिः स्वभावः, तत्संबन्धां प्राकृतः com. on T. Pr. XIV. 28; cf. एतद्विकारा एवान्ये, सर्वे तु प्राकृताः समाः R. Pr. XVII. 23; cf. also तहान् ... पश्ंस्तकात्परः (नकारः) सकारं प्राकृतो नित्ये T. Pr. VI. 14; (2) natural, which can be so ordinarily, without any specific effort; cf. तसात् प्राकृतन्वेतत् कमे यथा कटं करोति, M. Bh. on P. II. 3.5, cf. also M. Bh. on P. III 1.5 Vārt. 8, 9.

प्राकृतसर्वस्व a treatise on the gra-

mmar of Prākṛta Languages attributed to Mārkaṇḍeya.

पाक्कीतीय name given to a group of tad. affixes छ, यत् and others prescribed in the different senses (हित and others) given in rules upto तेन कीतम् P.V. 1.37 from तस्मै हितम् P. V. 1.5.

प्रागिवीय name given to tad. affixes mentioned in rules from P. V. 3.27 upto P. V. 3.95.

प्राग्चितीय name given to tad. affixes prescribed by rules beginning with प्राग्दिताद्यत् P. IV. 4.75 and ending with सोदराद्य; P. IV. 4.109.

प्रान्दिशीय name given to tad. affixes prescribed in rules from P. V. 3.1 to 25.

प्राग्दीव्यतीय name given to tad. affixes prescribed by rules beginning with तस्य विकार: P. IV. 3.134 and ending with the rule कंसीयपरशन्य-योर्यजनी छक् च P. IV. 3.168.

সাক্ত্য districts of the east especially districts to the east of Ayodhya and Pataliputra, such as Magadha, Vanga and others; nothing can definitely be said as to which districts were called Eastern by Pānini and his followers Kātyā-A Vārttika yana and Patanjali. given in the Kāśikā but the Mahābhāsya traceable in defines Pragdesa as districts situated to the east of श्रायवती (probably the modern river Rāvī or a river near that river); cf. प्रागुदखी विभजते हंसः क्षीरोदके यथा । विदुषां शब्द-सिद्धचर्थे सा नः पातु शरावती ॥ Kās. on There is a एङ प्राचां देशे P. I. 1.75. reading सरस्वता in some manuscript copies and सरस्वती is a wellknown river in the Punjab near Kuruksetra, which disappears in the sandy desert to the south; a reading इरावती is also found and হ্যাননী may stand for the river Rāvī. হায়াননী in Burma is simply out of consideration. For details see Vyākaraṇa Mahābhāṣya Vol. VII. pp. 202-204 and 141-142 D. E. Society's Edition.

प्राग्वतीय name given to tad. affixes prescribed in rules from P. V. 1.18 to 115.

प्राग्वहतीय name given to tad. affixes prescribed in rules from P. IV. 4.1 to 76.

प्राचीनमत the view or doctrine of the former or rather older grammarians. The word is used in many commentary books and the meaning of the word is to be decided according to the context. For example in the works of Rāmacandra, the author of the Prakriväkaumudī and his followers, the word refers to the view given by the writers of the Kāśikavrtti and the commentaries thereon: in the works of Bhattoii and his pupils, it refers to the writer of the Prakriyākaumudī in addition to the writers of the Kāśikā, while in the works of Nagesa it refers to the writings of Bhattoji and his pupils. details see Vyākaraņa Mahābhāsya Vol. VII pp. 23-24 D. E. Society's Edition.

प्राच्यपदवृत्ति succession of two vowels where the former vowel, which is either ए or ओ remains without coalescence with the following vowel अ. even though by rules it is liable to be changed; e.g. सुजाते अश्वसृतृते । अध्वर्यो अद्रिभिः सुतम् । In such cases the vowel ar is pronounced like v. This view is held by the senior Sakalya (स्थाविरशाकल्य); प्राच्यपञ्चाल-उपधानिभोदयाः शाकल्यस्य स्थिवरस्थेतरा स्थिति:, R.Pr. II.44;

also स पूर्वस्यार्धसहरामेकेषाम्, T. Pr. XI.19 and the commentaries thereon; cf. also छन्दोगानां सात्यमुग्निराणायनीया अर्धमेकारमर्धमोकारं चाधीयते । सुजाते ए अश्वसूनृते । अध्ययों ओ अद्रिभिः सुतम् । M. Bh. on Siva Sūtra 3, 4 as also on P.I.1.48.

प्राच्यवेयाकरण an eastern grammarian; the term प्राच्य (eastern) being a relative term, the east is to be taken with respect to the place in the context. The word प्राचां occurs many times in Pāņini's Sūtras and the term प्राक्त may refer to countries east of the river शरावती or सरस्वती in the Puniab. See प्राग्देश above. प्रान्वां is understood by some commentators as referring to time, in which case, the word may refer to ancient grammarians अ। पिशलि, शाक्टायन, इन्द्र others who lived Pānini; cf. प्राचीनवैयाकरणतन्त्रे वाचानिकानि ... Par. Sek. Pari. 1. The word प्राचीन is, of course, mostly used in the sense of ancient, rather than the word प्राच. For specific peculiarities of the eastern grammarians see pp. 148-149 Vyākaraņa Mahābhāsya Vol. VII. D. E. Society's Edition.

प्राण air, which is instrumental in producing sound; cf. वायुः प्राणः कण्ट्यमनुष-दानम् R.Pr.XIII.1.

वाजपणा a gloss on the Mahābhāsya of Patañjali, written by the famous eastern grammarian Purusottamadeva of the 12th century A. D., of which only a fragment of a few pages is available. As the legend goes, the name प्राण्या was given to the gloss as it was accompanied by an oath on the part of the author that his life was at stake if he did even the slightest injustice to the author of the Mahābhāsya.

प्राण्यञ् the tad. affix अञ् prescribed by the rule प्राणिरजतादिम्बोऽञ् P. IV.3.

154; cf. मयट: प्राप्यम् विप्रतिषेधेन P.IV.3. 156 Vart. 4.

प्रातिपादेक lit.available in every word. The term प्रातिपादिक can be explained as प्रतिपदं गृह्णाति तत् प्रातिपदिकम् cf. P.IV. 4. 39. The term प्रातिपदिक, although mentioned in the Brahmana works, is not found in the Prātišākhya works probably because those works were concerned with formed words which had been actually in use. The regular division of a word into the base (प्रकृति) and the affix (प्रत्यय) is available, first in the grammar of Pāṇini, who has given two kinds of bases, the noun-base and the The noun-base verb-base. named Prātipadika by him while the verb-base is named Dhatu. The definition of Pratipadika is given by him as a word which is possessed of sense, but which is neither a root nor a suffix; cf. अर्थवद्धातरप्रत्ययः प्रातिपदिकम . P.I. 2.45. Although his definition includes, the krdanta words, the taddhitanta words and the compound words, still. Pānini has mentioned them separately in the rule क्रत्रदितसमासाश्च P.I. 2.45 to distinguish them as secondary noun-bases as compared with the primary noun-bases which are mentioned in the rule अर्थवद्धात्र-प्रत्ययः प्रातिपदिकम्. Thus, Pāṇini implies four kinds of Pratipadikas मूलभूत, कुदन्त, तिद्धतान्त and समास. The Varttikakāra appears to have given nine kinds-गुणवचन, सर्वनाम, अन्यय, तद्धितान्त, कृदन्त, समास, जाति, संख्या and संज्ञा. See Varttikas 39 to 44 on P. I. 4. 1. Later on, Bhojarāja in his Srngāra-Prakasa has quoted the definition अर्थवद्धातु o given by Pānini, and has given six subdivisions.; cf. नामा-न्ययानुकरणकृत्तद्धितसमासाः प्रातिपदिकानि Sr. Prak. I. page 6. For the sense conveyed by a Prātipadika or nounbase, see प्रातिपदिकार्थ.

प्रातिपदिककार्य corresponding to अङ्गकार्य in the case of the declinables, which the Sūtrakāra mentions specifically with respect to the noun-base.

भातिपदिकश्रहण express mention by wording of a noun-base as in दित्यदित्यदित्य, सुघातुरकङ् च etc., and not by description as अदन्त in अत इज् (P.IV.1.95) or in a group of words (गण); cf. प्रातिपदिकश्रहणे लिङ्ग-विशिष्टस्यापि श्रहणम् Par. Sek. Pari. 71, which recommends the feminine form of the base for an operation, provided the base is specifically expressed and not merely described. e. g. युवति: खळति: युवखळित:, चटकस्यापत्यं चाटकरः, बह्नीनां पूरणी बहुतिथी etc.

प्रातिपदिकस्वर the general accent of the Prātipadika viz. the acute (उदात) for the last vowel as given by the Phit sūtra फिन्न: (प्रातिपदिकस्य) अन्त उदात्तः; cf. also प्रातिपदिकस्यस्यावकाशः। आम्रः। M. Bh. on P. VI. 1.91 Vārt. 7.

प्रातिपदिकार्थ denoted sense of a Prātipadika or a noun-base. Standard grammarians state that the denotation of a prātipadika is five-10ld viz. स्वार्थ, द्रव्य, लिङ्ग, संख्या and कारक. The word स्वार्थ refers to the causal factor of denotation or प्रवितानिमित्त which is of four kinds जाति, गुण, क्रिया and संज्ञा as noticed respectively in the words गी:, ग्रुक्ट: चल: and डित्थ:. The word द्वय refers to the individual object which sometimes is directly denoted as in अश्वमान्य, while on some occasions it is indirectly denoted through the genus or the general notion as in নালণ: पूज्य:. लिङ्ग the gender, संख्या the number and कास्क the case-relation are the denotations of the case-terminations, but sometimes as they are conveyed in the absence of a case-affix as in the words पञ्च, दश, and others, they are stated as the denoted senses of the Prātipadika, while the case-affixes are said to indicate them; cf. बाचिका द्योतिका वा स्यु: शब्दादीनां विभक्तयः Vākyapadīya.

प्रातिलोक्य in inverse order, antithesis.
reverse sense; e. g. प्र and प्रा mean the reverse of आ, or प्रति means the reverse of आभ; cf. आ इत्यवींगयें। प्र परेत्येतस्य प्रातिलोक्यम् etc. Nir. 1. 4.

प्रातिशाख्य a work on Vedic grammar of a specific nature, which is concerned mainly with the changes. euphonic and others, in the Pada text of the Samhita as compared with the running text, the Samhita The Prātiśākhya works are neither concerned with the sense of words, nor with their division into bases and affixes, nor with their etymology. They contain, more or less, Vedic passages arranged from the point of view of Samdhi. In the Rk Prātišākhva, available to-day, topics of metre. recital, phonetics and the like are introduced, but it appears that originally the Rk Prātiśākhya, just like the Atharva Prātiśākhya, was concerned with euphonic changes. the other subjects being introduced later on. The word प्रातिशाख्य shows that there were such treatises for everyone of the several Sakhas or branches of each Veda many of which later on disappeared as the number of the followers of those branches dwindled. Out of the remaining ones also, many were combined with others of the same Veda. At present, only five or six Pratisakhyas are available which are the surviving representatives of

the ancient ones-the Rk Prātiśākhya by Śaunaka, the Taittirīya Prātišākhya, the Vājasaneyi Prātiśākhya by Kātyāyana, the Atharva Prātiśākhya and the Rk Tantra by Sākatāyana, which is practically a Prātiśākhva of the Sāma Veda. The word पार्षद or पारिषद was also used for the Prātiśākhvas as they were the outcome of the discussions of learned scholars in Vedic assemblies: cf. परिषदि भवं पार्वदम्. Although the Prātiśākhya works in pature, are preliminary to works on grammar, it appears that the existing Pratiśākhyas, which are the revised and enlarged editions of the old ones, are written after Panini's grammar, each one of the present Prātiśākhyas representing, of course, several ancient Prātisākhyas, which were written before Pānini. Uvvata, a learned scholar of the twelfth century has written a brief commentary on the Rk Prātiśākhya and another one on the Vajasanevi Pratiśākhya. The Taittirīya Prātiśākhya has got two commentaries —one by Somayarya, called Tribhasyaratna and the other called Vaidikābharana written by Gopālayajvan. There is a commentary by Ananta bhatta on the Vajasaneyi Pratisakhya. These commentaries are called Bhāsyas also.

प्रातिश्वन्त places of echo or reverberation viz.chest and others, of sound which gets its origin at the navel but becomes reverberated at chest, throat, top of the mouth, mouth and nose; cf. तस्य (उत्पन्याश्रयस्य शब्दस्य) प्रातिश्वन्त्वानि भवन्ति उरः कण्ठः शिरो मुखं नासिके इति, T. Pr. II. 3.

प्रातिहत name given to the circumflex vowel, standing at the beginning of a word and following the final vowel of the previous word which

is acute (उदात्त); cf. अपि चेन्नानापदस्थ-मुदात्तमथ चेत्सांहितेन स्वयंते स प्रातिहत: T. Pr. XX. 3.

प्राथमकिएक of the first type or kind; primary, as opposed to secondary; cf. अयं खल्विप बहुवीहिरस्त्येव प्राथमकिएको यस्मिनैकपद्यमेकस्वयंमकिवभक्तिकलं च, M.Bh. on P. I. 1. 29, I. 1. 30; I. 2. 42; cf. also अथवेह कौचित् प्राथमकिएको प्रक्षत्य-प्रोधो कौचित् कियया वा गुणेन वा M. Bh.on P. II. 2. 29 Vart. 15.

प्राथम्य first preference; first place; priority; cf. कुत; पुन: प्राथम्यं कि शब्दत: आहोस्विद्यत: । M. Bh. on I. 3. 1. Vart. 11.

भादि a group of words beginning with प्र, which are all prefixes or upasargas e. g. प्र, प्रा, अप etc. cf. कुगतिप्रादय: P. II. 2. 18.

प्रादिसमास a compound with प्र and others prescribed by the rule कुगतिप्रादयः P. II.2.18 and explained in detail by the Vārttikas headed by the Vārttika प्रादयो गताद्यर्थे प्रथमया P. II. 2. 18 Vārt. 4, which comes under the general head तत्पुरुष; the compound is also called प्रादित-तपुरुष; cf. कथं प्रभावो राज्ञः । प्रकृष्टी भाव इति प्रादिसमासो भविष्यति । Kāś. on P. III. 3. 24 cf. also प्रान्तः पर्यन्तः । बहुनीहिरयं प्रादिसमासो वा Kāś. on P. VI. 2. 180.

आदेशिक belonging to the root; the word प्रदेश has here the peculiar sense of a root which has the meaning of the noun (under discussion). cf. तदात्र स्वरसंस्कारी समर्थी प्रादेशिकन गुणेन अन्विती स्थातां संविज्ञातानि तानि Nir I. 12.

प्राधान्य preponderance, principal nature as opposed to the subordinate one (निरोषणत्व); cf. यत्र प्राधान्येन अल् आश्रीयते तत्रैव प्रतिषेधः स्यात् M. Bh. on P. I. 1. 56. cf. also प्राधान्येन व्यपदेशा भवन्ति ।

प्रापक applying in the usual way; lit. leading to the injunction or विधिशास्त्र; cf. किं पुनरिदं नियमार्थं आहोस्वित् प्रापकम् M. Bh. on P. I. 1.70; cf. also M. Bh. on P. III. 4. 110.

प्रापण reaching, arrival; cf. प्रत्यक्षमाख्या-नमुपदेशो, गुण: प्रापणमृदेश: M. Bh. on P. I. 3.2.

प्राप्तविभाषा or प्राप्तविकल्पस्व, optional prescription of some operation or rule which otherwise is obligatory; cf. लोपे विभाषा । प्राप्तविभाषेयम् । किमथैन योगात् । Kāś. on P. VIII. 1.45; cf. also हुकोरन्यतरस्याम् । प्राप्तविकल्पत्वाद् द्वितीयेष । Kāś. on P. I. 4.53.

माप्त application of a rule, arrival at a particular form; incidence, occurrence of a particular rule; cf. अनन्तरा या प्राप्ति: सा प्रतिषिध्यते M.Bh. on P. I. 1.43.

प्राप्तिज्ञ a person who knows only the application of a rule and the realization from it of the form that can be arrived at, as opposed to one who knows the form that is desired or current; cf. प्राप्तिशे देवानां- प्रियः न त्विश्चिशः इच्यते एतद्भूपमिति । M. Bh. on II. 4. 56 Vart. 1; cf. also किरतिं चर्करीतान्तं पचतीत्यत्र यो नयेत् । प्राप्तिशं तमहं मन्ये प्रारक्ष्यस्तेन तंग्रहः । M. Bh. on VII. 4.92.

प्राप्य lit. which is arrived at; an object which is to be reached; cf. प्राप्यं कर्म; the word प्राप्य is used as a word qualifying the word कर्म, in which case it is called प्राप्यकर्म, as for example ग्रामं in प्रामं गच्छित देवदत्तः or वदमधीते माणवकः. The term प्राप्य is defined as क्रियाक्च-तिविशेषानवगतौ कर्तुः क्रियय अनारिथतं आस्थितं वा यदवाप्यते तत् प्राप्यं कर्म। cf. कर्तुरीप्सितमं कर्म। तत्तु त्रिविधं निर्वर्त्यं विकार्यं प्राप्यमिति । यस्य क्रियाक्चतानां विशेषाणां सर्वथानुपल्लियः तत् प्राप्यम्. Sṛngāra Prakāśa IV.

प्रामाणिक authoritative; those that talk with authority; cf. प्रामाणिकमत-मतत्, a phrase often used by commentators. प्रामाण्य authority; cf. यथोत्तरं मुनीनां प्रामाण्यम् S. K. on न वहुत्रीहीं P. I. 1.29; cf. also the usual expression वचनप्रामाण्यात् Kas. on P. VII. 2.7.

प्रामादिक faulty, uttered or expressed with a fault; inaccurate.

प्राय general nature, general public; cf. प्राय इति लोको न्यपदिस्यते, M. Bh. on P. V. 1.16; cf. प्रायोधीं वृत्तमित्येते पादज्ञानस्य हेतव: R. Pr. XVII.16; cf. also, लोकिकी विवक्षा यत्र प्रायस्य संग्रत्यय: M. Bh. on P. V. 1.16.

प्राचिक optional, to be done at pleasure, common, usual; cf. प्राचिकं चैतत्।

प्रायोक्त्र belonging to one who speaks or says; cf. अस्त्येव प्रायोक्त्री विवक्षा अस्ति छौकिकी। M. Bh. on P. V. 1.16.

प्रावचन accentuation, as noticed in the original Samhitāpāṭha; cf. प्रावचनो वा यज्ञिष । प्रवचनशब्देन आर्षपाठ उच्यते । तत्र भवः स्वरः प्रावचनः स च यज्ञिष भवति । तान्ते वा यज्ञकर्मणि । V. Pr. I. 132.

प्राह्मिष्ट name of the circumflex accent possessed by a vowel which has resulted from the coalescence of two similar vowels, as for example in भिन्द्धीदम्। see प्रश्चिष्ट.

प्रासाद्वासिन्याय inclusion of a thing even though it possesses an additional factor, or consideration, other than what is referred to; cf. प्रासादवासिन्यायेन ग्रहणं भवति । तद्यथा केचित् प्रासादवासिनः । केचिद् भूमिवासिनः । केचिदुभयवासिनः । ये प्रासादवासिनः । यहान्ते ते प्रासादवासिग्रहणेन । य भूमिवासिनः ग्रह्मन्ते ते प्रासादवासिग्रहणेन । ये उभयवासिनः ग्रह्मन्ते ते प्रासादवासिग्रहणेन भूमिवासिग्रहणेन च । M. Bh. on P. I. 1.8.

भियादि a class of words headed by the word प्रिया which do not allow their previous word in a bahuvrihi compound to take the masculine base by the rule स्त्रिया: पुंचत... P. VI. 3.34; e. g. कस्याणीप्रिय; For details, see Kāś. on P. VI. 3.34.

प्रेक्षा (1) appearance, the being seen or understood; cf. दूता निर्कत्या इदमा- जगाम । पञ्चम्ययंप्रेक्षा वा षष्ट्यथेप्रेक्षा वा । Nir. I. 17; (2) thoughtful consideration, cf. य एव मनुष्य: प्रेक्षापूर्वकारी मवति सोऽध्रुवेण निर्मित्तन ध्रुवं निर्मित्तमुपादत्ते, M. Bh. on P. I. 1.26 Vart. 5,

मेक्सादि a class of words to which the tad. affix इन is added in the four senses given in P. IV. 2.67-70; e. g. प्रश्ती, ध्रुवकी; cf. Kāś. on P. IV. 2.80.

भेपसु desiderative adjective; a word formed by adding the affix उ in the sense of 'an agent' to a desiderative root by the rule सनाशसभिक्ष उ: P.III.2.168. The term नेप्स was used for such nouns by ancient grammarians.

प्रेषणी a term used by ancient grammarians for the imperative mood or लोट of Pāṇini.

प्रैषादि the senses प्रेष 'order to do', अतिसर्ग 'permission to do' and प्राप्तका- कता 'fitness of time', as possessed by the potential passive participles; cf. विधीयन्ते प्रैषादिषु लोडादय: M. Bh. on P. III. 1.26.

प्रोक्तपुंस्क possessed of the masculine gender

ब्रोहमनोरमा popularly called मनोरमा also; the famous commentary on the Siddhāntakaumudī of Bhattojī Dīkṣita written by the author himself to explain fully in a scholarly manner the popular grammar written by him; the word भौदमनारमा is used in contrast with बालमनोरमा another commentary on the Siddhāntakaumudī by Vāsudevadīkṣita. On account of the difficult nature of it, it is ususal to read the भौदमनारमा upto the end of the Kāraka-prakarana

only in the Sanskrit Pāthaśālās before the study of the Śabdenduśekhara and the Paribhāṣenduśekhara is undertaken.

प्रौहमनोरमाखण्डन (1) a grammatical work written by a grammarian Cakrapāņi of the Sesa family of grammarians. The work is meant to refute the arguments of Bhattoji Diksita in his Praudhamanoramā; (2) a grammar work written by the famous poet and rhetorician Jagannātha in refutation of the doctrines and explanations given in the Praudhamanoramā by the stalwart Grammarian Bhattojī Dīksita. The work is not a scholarly one and it has got a tone of banter. It was written by Tagannatha to show that he could also write works on Grammar and the bearded pedant Bhattoji should not be proud of his profound scholarship in Grammar. The work of Jagannatha was named मनोरमाकुचमर्दन possibly by his followers or even by himself.

प्रोहमनोरमाटीका a commentary on Bhattoji Diksita's Praudhamanoramā written by Bhattoji's grandson Hari Diksita. The commentary is called ल्ह्ह्यान्दरत्न or simple चन्दरत्न which is an abridgment of the author's work बृह्न्छन्दरत्न. The Laghusabdaratna is widely studied along with the Praudhamanoramā in the Pāthaśālās.

प्लक्षादि a class of words headed by the word प्लक्ष to which the tad. affix अण् is added in the sense of 'a fruit' e.g. प्लाक्षम् , ऐङ्गुदम्, cf. Kāś. on P.IV.3.164.

भ्राक्षायण an ancient Vedic scholar who presumably wrote a work on Vedic grammar (of the type of the Prātisākhya works). For a difference

of view he is quoted in the Taittiriya Prātiśākhya; cf. ন ভাঞ্জিভাঞ্জায়াখাখা: T.Pr. IX.6.

ষ্ক্রান্ধি an ancient writer of a Prātiśākhya work quoted in the Taittirīya Prātiśākhya. See তোজাযুগ above. The words তোগ্ধি and তোজাযুগ as also তোগ্ধী (feminine) occur in the Mahābhāṣya also, but not in the Gaṇapāṭha of Pāṇini.

प्छत protracted, name given to vowels in the protracted grade. The vowels in this grade which are termed protracted vowels are possessed of three matras and in writing they are marked with the figure 3 placed after them. In pronunciation they take a longer time than the long or दीर्घ vowels; cf. ऊकालोज्झस्वदीर्घण्टुत: P. I.2.27. The word is derived from ত্ত্ত (মু also) I Atmane, to go, and explained as प्लवते इति. The word प्लवत is often found for प्लतो भवति in the Praissakhya works; cf. also मात्रा हस्वस्तावदव-ग्रहान्तरं, द्वे दीर्घस्तिस्रः प्छत उच्यते स्वर: । अध: स्विदासी ३ दुपरि स्विदासी ३ दु अर्थे प्छतिभीरिव विन्दती3 त्रि: ll R. Pr. I.16.

प्छुति prolation or protraction of a vowel when it is possessed of three mātrās; cf. R. Pr. I.31. See जुत above; cf. अविद्वांस: प्रत्यभिवादे नाम्नो ये न प्छुतिं विदु:। काम तेषु तु विप्रोष्य स्त्रीष्विवायमहं वदत् M.Bh. on P.I.1 Ahnika 1.

प्वादि a class of roots headed by the root q which get their vowel shortened in the four conjugational tenses as also before the pres. part. affix; e.g. पुनाति पुनानः, छुनाति, छुनन etc.; cf. Kas. on P.VII.3.80.

फ

फ् hard labial consonant, aspirate of प्, possessed of the properties श्वास घोष, महाप्राणता, and कण्डविद्यतता.

ৰ্ম (1) the letter or sound 4, the vowel ষ being added for facility of pronunciation;(2) the affix 4 for which সামন is always substituted as given by Pāṇini in P. VII.1.2.

फ्रक् (1) tad.affix फ marked with mute क for effecting the बृद्धि substitute for the initial vowel of the word to which it is applied. The initial letter H of all the affixes beginning with E in Pāṇini's grammar is always changed into आयन्. The tad. affix पक् is affixed (1) in the sense of गोत्रापत्य grandchild and his issues. to the words নত and others as also to the words ending with the affixes यञ् and इञ् and words शरद्वत्, दर्भ, द्रोण etc. e.g. नाडायन:, जालङ्कायन: दाक्षायण: प्लाक्षायण:, द्रोणायन:, यैद:, और्व: etc.; cf. P.IV. 1.99-103; (2) as a caturarthika affix in the four senses mentioned in P. IV. 2.67-70 to the words and others e.g. पाक्षायण:, तौषायण:: cf. P.IV. 2.80.

দন্ধ tad. affix দ marked with স্ causing the Vṛddhi substitute for the initial vowel of the word, applied in the sense of grandchildren and their issues to words অস্ব and others, as also to the word মর্ग; e.g.আপ্রাযন, আন্ধাযন:, মার্গাবण: cf. অ্থাহিম্য: দের্ and মর্গাব্ স্বীগর্ন; cf. P.IV.1.110 and 111.

फणादि a class of seven roots headed by the root प्रम्, which belong to the first conjugation and which have optionally their vowel अ changed into ए and the reduplicative syllable (अभ्यास) dropped, in the forms of the perfect tense before the affix इथ and weak affixes; e. g. पेमातु:, पेमु:, पेमिथ प्रमातु:, प्रमा; प्रभीष etc. cf. P.VI.4.125.

फल (1) fruit or benefit of an action which goes to the agent; cf. फलन्या-पारयोघाँतु: Vaiyākaraṇa-bhūṣana. A root which is given as Ubhayapadin in Pāṇini's Grammar takes the Ātmanepada affixes when the fruit of the activity is meant for the agent, while otherwise it takes the Parasmaipada affixes; (2) The word Ra also means the result of a grammatical operation or grammatical injunction.

फि a common term for the affixes फिन् and भित्र्.

फिइस tad. affix आयनि applied to the word मिमत in the sense of offspring e.g. मैमतायनि:; cf. P.IV.1.150; it is also added in the same sense of (offspring) to the words तिक and others as also to the word कौसल्य, two-syllabled words ending with अण् and to words चिक्त and others;e.g. तैकायनि:, कौसल्यायनि:, वािकनकायनि: etc.; cf. P.IV.1.159.

फिट्सूत्र a small work on accents attributed to Santanava, an ancient Vedic scholar who lived before Patanjali if not before Paṇini, as the latter has not referred to him. There is an anonymous commentary upon it.

फिन tad. affix आयनि in the sense of offspring added according to the Eastern grammarians to words not beginning with आ, ऐ or औ, e.g. ग्लुज़्तायनि:,cf. IV.1.160.

ক্রমন [FADDEGON, BAREND] a scholar of Sanskrit Grammar, who has written a book 'Studies in Pāṇini's Grammar'.

₹

third letter of the labial class which is soft and inaspirate.

ब or बकार the letter ब्, the vowel अ as also the word कार being added for facility of utterance; cf. T. Pr. I. 17.21. The letter ब is sometimes used for व especially when it stands at the beginning of a word, for which scholars use the expression ववयोरभेद:.

बर्नेल् [BURNELL., Dr.] a European Sanskrit scholar who has written a learned booklet 'Aindra School of Sanskrit Grammarians' which discusses the problem of the Aindra grammar. See एन्द्र.

चर्चरता a fault in pronunciation of the type of roughness or barbarousness in the utterance of the letter र्; cf. बरंग्ता असोंकुमार्थ रेफे Uvvata on R.Pr.XIV. 8.

बस्ट्ये (written as बत्स्ट्ये or बर्स्य possibly through mistake in the printed Calcutta Edition); connected with the socket of the teeth. As the utterance of I proceeds from the socket of the teeth, र is called बरुवर्य. उपसंहततरे च जिह्वाग्रमुकारकीरलकारेष cf. बर्स्वेषूपसंहरति T.Pr.II.18.बर्स्व is explained here by the commentator as दन्तपङ्केरपरिष्टादुच्चप्रदेशेषु ऋकारस्य ऋकारस्य लुकारस्य च बर्स्वाः स्थानम् | The word उपरिश्रात् in the explanation given above is questionable; the explanation given by Uvvata in his comment on वर्स्यमेके इच्छन्ति रेफम् R. Pr. I. 20.viz. वर्त्सशब्देन दन्तमूलादुपरिष्टादुक्कृन: प्रदेश उच्यते appears better although apparently वर्से is written in the text for बर्ख or वर्स्व

ৰন্ত**োম** writer of a gloss named ধানুদকাহা on the Dhatupātha of Pānini.

बलादि (1) a class of words headed by the word बल, to which the tad. affix य is added in the four senses given by Pāṇini in IV.2.67-70. e. g. बल्य: कुल्यम्, तुल्यम्, वन्यम् etc. cf. Kāś, on P.IV.2.80; (2) a class of words headed by बल which take the possessive tad. affix मत् optionally with the regular affix इन्

e. g. बलवान्, बली; cf. Kāś. on P. V. 2.136.

बर्कीयस्त्व relative superiority in strength possessed by rules of grammar or by operations based on rules of grammar. This superiority is decided generally on any one or more of the four recognised criteria such as परत्व, नित्यत्व, अन्तरङ्गव and अपवादत्व. The phrase अन्तरङ्गवली-यत्त्वात् very frequently occurs in the Vārttikas and in the Mahābhāṣya; cf. M.Bh. on P. III. 1.67, VI.1.17, 85 Vārt.15, VI. 4.62 and VII.1.1.

बश short term or pratyāhāra for the consonants from च to mute श in the Māheśvara sūtra i.e. the consonants बु, गु, डू and दु.

बाहिरङ्ग a rule or operation which is बहिरङ्ग (lit. external); the word बहिरङ्ग is used in grammar in connection with a rule or operation, the cause (निमित्त)of which occurs later in place or time than the cause of the other which is called अन्तरङ्ग. For the various kinds of बहिरङ्गत्व see the word अन्तरङ्ग where the kinds of अन्तरङ्गत्व are given.

बहिरङ्गपरिभाषा the Paribhāṣā or the maxim असिद्धं वहिरङ्गमन्तरङ्गे (Par. Śek. Pari. 50) which cites the comparative weakness of the rule or operation which is Bahiranga.

चहिरङ्गस्रक्षण an operation or rule which is characterized as बहिरङ्ग; cf. असिद्धं बहिरङ्गस्रक्षणमन्तरङ्गस्रक्षेण M. Bh. on P. I. 1.57; cf. also M.Bh. on P. I. 4.2 Vart. 21.

वहिरङ्गासिद्धत्व invalidity i. e. nonoccurrence or non-application of a bahiranga rule or operation before the antaranga operation which is looked upon as stronger occurring earlier to the mind, or in the wording, as it does. बहु plural, many, the word is used in the sense of abundance also; cf. बहुषु बहुबचनम् P. I.4.21 and बहोलांपो भू च बहो: VI. 4.158.

बहुच् tad. suffix वहु which is always prefixed to a noun in the sense of 'almost complete', 'almost full', 'to a considerable extent'; e.g. बहुगुड़ा द्राक्षा; cf. विभाषा सुपो बहुन् पुरस्तातु P. V. 3.68.

वहुपक्रीत (1) consisting of a large number of verbal parts in derivation; बहुयः प्रकृतये यत्र; (2) a compound in which the constituent words are all in the plural number, cf. सर्वो इन्द्रो विभाषक्त्रक्रवि । बहुप्रकृतिरिति वक्तव्यम् M. Bh. on P.II.4.12 Vart.1; (3) a compound word (पद) made up of many constituent words; cf. बहूनि पदानि यत्र तद् बहुप्रकृति पदम् Vaj. Prat. V. 7.

बहुमध्यात a word which has entered between two constituent words of a compound by splitting in a way the compound e. g. the word च in ईयते नरा च शंस दैन्यम् Rg. Veda IX. 86.42; cf. एतानि परिग्रह्णीयात् बहुमध्यगतानि च। R.Pr.X.7. explained by Uvvata as बहूनां पदानां मध्यगतानि च यानि पदानि तानि अतिक्रम्य परिग्रह्णीयात्।

बहुल lit. variously applicable; the word is used in the rules of Panini in connection with a grammatical rule or affix or the like that is seen necessarily applied in some cases, optionally applied in a few other cases and not at all applied in the other cases still. The word बहुलम् is used by Pāṇini in all such cases. See P. II. 1.32, 57; II. 3.62; II.4.39, 73.76, 84; III. 1.34 etc.; cf. the usual explanation of बहुलम् given by grammarians in the lines कचित्प्रवृत्तिः कचिद्प्रवृत्तिः कचिद्रिभाषा कचि-दन्यदेव । विधेर्विधानं बहुधा समीक्ष्य चतुर्विधं बाहुलक वदन्ति Com. V. Pr. III.18.

बहुरुपाद् name given by grammarians to the third pada of the third adhyāya of the Aṣṭādhyāyī.

बहुवचन the plural number; the affixes of the plural number applied to noun-bases as also to roots; cf. बहुषु बहुवचनम् P. I. 4.21.

चहनीहि a compound similar meaning to the word बहबीहि (possessed of much rice) which, in sense shows quite a distinct object than those which are shown by the constituent members of the compound; a relative or adjective compound. There are various kinds of the Bahuvrihi compound such as समानाधिकरणवहत्रीहि, व्यधिकरणबह त्रीहि, संख्याबहुत्रीहि, दिग्बहुत्रीहि, सहबहुत्रीहि, नञ्बहु-नीहि, and अनेकपदबहुनीहि which depend upon the specific peculiarity noticed in the various cases. Panini in his grammar has not given any definition of बहुत्रीहि, but has stated that a compound other than those already given viz. अन्ययीभाव, द्वन्द्व and तत्पुरुष, is बहनीहि and cited under Bahuvrīhi all cases mentioned above; cf. दोषा बहुन्नीहि: II. 3.23-28; also cf. अन्यपदार्थप्रधानो बहुन्रीहिः ${f M.}$ ${f Bh.}$ on ${f P}_{*}$ II. 1.6; II. 1.20; II. 1.49.

बहुवाहिपाद conventional term used for the second pada of the sixth adhyaya of Panini's Astadhyayī.

वहुत्रीहिम कृतिस्वर the accent peculiar to, or specifically mentioned in the case of the Bahuvrihi compound viz. the retention of its own accents by the first member, in spite of the general rule that a compound word has the last vowel accented acute i.e. उदात. cf. बहुत्रीही प्रकृत्या पूर्वपदम. P. VI. 2.1. The expression बहुत्रीहिस्वर in this very sense is used in the Mahābhāsya cf. बहुत्रीहिस्वर शास्ति समासान्तविधेः सुकृत् M. Bh. on P. VI. 2.1.

under multisyllabled, a word which contains three, or more than three vowels; the word occurs many times in the sūtras of Pāṇini. cf. P. II. 4.66, IV. 2.73, IV. 2.109, IV. 3.67; V. 3.78, VI. 2.83, VI. 3.118.

बह्वपेक्ष lit. depending on many; the word is used in the sense of depending on many causal factors (निमत्तानि) and given as the definition of a kind of बहिरङ्ग by some grammarians; cf. अल्पापेक्षमन्तरङ्गं बह्वपेक्षं बहिरङ्गम्. This kind of अन्तरङ्गबहिरङ्गम्, cited by Kaiyata is, however, disapproved by Nāgesiabhatta; cf. बहिरङ्गान्तरङ्गशब्दाभ्यां बह्वपेक्षत्वाल्पापेक्षत्वयोः शब्दमर्थादया अलाभान्व । तथा सति आसिद्धं बह्वपेक्षमल्पापेक्षे इत्येव वदेत् । Par. Sek. on Pari, 50.

बहुर्थ lit. the meaning of the word बहु. There are many senses of the word बहु out of which 'plurality' is the sense usually seen. The word also means 'collection;' cf. ग्रामराब्दोयं बहुर्थ: । अस्थेन शालासमुदायं वर्तते। तदाया। ग्रामो दग्ध इति M. Bh. on P. I. 1.8, 21.

बहादि a class of words headed by बहु to which the fem. affix है (डीप्) is added to form the feminine base; the words ending in अ in this class take the fem. affix आ (टाप्) in case है which is optional, is not added; other words remain as they are, if है, is not added; e. g. बही, बहु:; पद्धति:, पद्धती; गति:, गती; चण्डी, चण्डा; etc. cf. Kāś. on P. IV. 1.45.

बाध sublation, setting aside; सामान्य-शास्त्रस्य विशेषशास्त्रण वाघः Par. Sek. on Pari. 51.

बाधक lit. that which sublates or sets aside: generally a special rule which sets aside a general rule; cf. यन नाप्राप्ते यो विधिरारम्यते स तस्य वाधको भवति,

Pari. Pātha of पुरुषोत्तमदेव Pari. 51; cf. also नैतज्ज्ञापकसाध्यं अपवादेरुत्सगां वाध्यन्त इति । बाधकनानेन भवितज्यं सामान्य-विहितस्य विशेषविहितेन । M.Bh. on P. II. 1.24 Vārt. 5. बाधक is used as a synonym of अपवाद. cf. अपवादशब्दोत्र वाधकपर: Par. Sek. Pari. 58.

ৰাঘকৰে the same as ৰাখ; sublation: setting aside; this sublation is described to be of two types-(1) complete sublation when the rule set aside, is for ever set aside and cannot, by the maxim called तककीण्डिन्यन्याय, be applied again; cf. दिध ब्राह्मणेभ्यो दीयतां तकं कौण्डिन्यायित सत्यिप संभवे दिघदानस्य तकदानं निवर्तकं भवति। cf. M. Bh. on P. I. 1.47; VI. 1.2. VI, 2.1. etc.; (2) temporary sublation when the rule set aside. can be applied, if possible after the special rule has been applied; cf. सर्वथा अनवकाशस्त्रादेव बाधकस्त्रे स्वस्य (अनवकाशशास्त्रस्य) पूर्वप्रवृत्तिरित्येव बाधः। तत्र बाधके प्रवृत्ते यद्युत्सरीप्रातिभीवति तदा भवत्येव यथा तत्रैव याडादय: Par. Sek.on Pari.57. The sublation or बाबकत्व is not only in the case of सामान्यविशेषभाव and अनवकाशत्व as given above, but a rule or operation which is पर (cited later), or नित्य, or अन्तरङ्ग sets aside the rule or operation which is पूर्व,or अनित्य,or बहिरङ्ग respectively. This वाध्यवावकमाव occupies a very important position in respect of the application of grammar rules for arriving at the correct forms (इष्टल्पसिद्धि) and grammarians have laid down a number of Paribhāsas in the field of बाध्यबाधकभाव.

बारुंभह (बारुंभह) surnamed Pāyaguṇḍa or Pāyaguṇḍe, who has written a commentary on the commentary Mitākṣarā on the याज्ञव स्वयस्मृति. Some scholars say that he was also a great grammarian and identical with वैद्यनाथ पायगुंडे who has written the commentary काशिका or गढा on the Paribhāsenduśekhara, the Cidasthimālā on the Laghuśabdenduśekhara and commentaries on the Vaiyakaranabhūşana, Sabdakaūstubha and Bhāsvapradīpoddvota. Other scholars believe that Bālambhatta was the Vaidvanātha and that he wrote only the commentary on Mitaksarā called Bālambhattī after him. (2) There was also a comparatively modern grammarian of Tanjore who has written small grammar works बालवोधिनी and बालरज्जनी.

बालबोधिनी name of a grammatical work ascribed to Bālambhaṭṭa of Tanjore.

वालमनोरमा name of a commentary on the Siddhānta-kaumudī of Bhaṭṭojī Dīkṣita by Vāsudeva Dīkṣita, a grammarian of Tanjore. There is also another commentary called Bālamanoramā written by Anantadeva on the Siddhānta-kaumudī.

बालरञ्जनी name of a grammar work written by Bālambhaṭṭa of Tanjore. See बालंभइ (2).

ৰাহুন্তক the application of a grammatical rule as a necessity to arrive at some forms in literature especially in the Vedic Literature as also in the works of standard writers, which cannot be explained easily by the regular application of the stated rules; cf. सुतिङ्पप्रहिल्जनराणां कालहलच्-स्वरकर्तृयङां च । न्यत्ययामिन्छति सोपि च सिध्यति बाहलकेन M.Bh. on P. III. 1.85; also cf. बाहलकं प्रकृतेस्तनुदृष्टेः प्रायसम्ब्ययनादपि तेषाम् । कार्यसद्देषिविधेश्च तदुक्तं नैगमरूढिभवं हि सुसाधु M.Bh. on P. III.3.1. In many sūtras, Pāṇini has put the word बहलम् to arrive at such forms; e. g see. P.II.1.32,57; II.3.62, II.4. 39, 73, 76, 84 etc.

बाह्य (प्रयत्न) external effort; the

term is used many times in connection with the external effort in the production of articulate sound, as different from the internal effort आभ्यन्तरप्रयत. The external effort is described to be consisting of 11 kinds; cf. बाह्यप्रयत्नस्त्वेकादशघा। विवार: संवार: श्वासो नादो घोषोऽघोषोऽद्यप्राणो महाप्राण उदात्तोनुदात्त: स्वरितश्चेति S.K.on P. I.1.9.

बाह्वादि a class of words headed by the word बाहु to which the tad. affix इ (इञ्) is added in the sense of a descendant; e.g. बाह्विः, पौष्करसादिः, पाञ्चिः etc. The class called बाह्वादि is looked upon as आकृतिगण on the strength of the word च in the rule, so that similar words, not included in the class, could be explained; cf. Kāś. on P.IV.1.96.

ৰিবাৰি a class of words headed by the word ৰিব to which the affix অ (অস্) is added in the sense of a grand-child and further descendants; e.g. ৰীবঃ, জীবঃ, জাহ্মদঃ, জীহিকঃ etc. The words in this class are mostly names of sages. In the case of such words as are not names of sages, the affix will is added in the sense of the offspring and not any descendant. e.g. पौत्रः, दौहित्रः etc.; cf. Kāś. on P.IV.1.104.

विन्दु anusvāra, letter pronounced only through the nose; a dot to indicate the nasal phonetic element shown in writing above or sometimes after that letter or vowel, after which it is uttered; cf. अं इत्यनुस्वारः । अकार इह उच्चारणार्थः इति विन्दुमात्रो वर्णोनुस्वारसंज्ञो भवति ॥ Kat. I.1.19.

बिल्बकादि a class of words headed by the word বিভাক the affix ईय (छ) placed after which is elided when another tad. affix such as স্বৰ্ণ or the like is placed after them; cf. थिल्या यस्यां सन्ति विरुग्की तस्यां भवाः बैरुवकाः Kāś. on P.VI.4.153.

बिल्वादि a class of words headed by the word बिल्ब, to which the tad. affix अ (अण्) is added in the sense of 'a product' or 'a part'; e.g. बैल्ब: मौद्र:, वैणव: etc.; cf. Kāś. on P. IV. 3.136.

ৰুহ্ৰহন্ত [BUISKOOL H. E.) A European grammarian who has written an essay on the last three Pādas of Pāṇini's Aṣṭādhyāyī (त्रिपादी) under the title 'The Trīpādi'.

बुद्धि notion, mental understanding; mental inclination; cf. बुद्धिः संप्रत्यय इत्यनर्थान्तरम्। or अस्तर्भूभंवतीत्यस्तिबुद्धया भवतिबुद्धिं प्रतिपद्यते M. Bh. on P. I. 1.56 Vārt. 14; (2) mental inclusion; cf. यां यां विभक्तिं आश्रयितुं बुद्धिरपजायते सा साश्रयितन्या M.Bh. on P. I. 1.57; cf. अथ बुद्धिः अविशेषात्स्मपुरा हेत्, M. Bh. on III.2.118 Vārt. 4.

चुद्धिकर्भन् activity of the mind of the type of understanding as contrasted with the activity of the sense organs; cf. इन्द्रियकर्म समापादनं बुद्धिकर्म ज्यवस्य: M. Bh. on P.III. 3. 133 Vart. 8.

बुद्धिसागर writer of a grammar work who lived in the 11th century.

चृंहण keeping; preservation; cf. ऋमादतो-प्यृग्यज्ञुषां च बृंहणम् । बृंहणं संधारणम् ;Uvvata on R. Pr. XI. 37.

वृहच्छब्द्रस्त a learned commentary on the commentary मनोरमा महोजीदीक्षित; the commentary was written by हरिदोक्षित the grandson of The work is called Bhattojī. in contrast with the बहरूछब्दरत्न लघुशब्दरत्न of the same author (हरिदाक्षित) which is generally studied at the Pāthaśālās all over country. The work बृहच्छब्दरत्न is only in a Manuscript form at present. Some scholars believe that it was written by Nagesabhatta, who ascribed it to his preceptor Hari Dīkṣita, but the belief is not correct as proved by a reference in the Laghuśabdaratna, where the author himself remarks that he himself has written the बृहच्छव्दर्रन, and internal evidences show that ल्डुशब्दर्रन is sometimes a word-forword summary of the बृहच्छव्दर्रन एट. बिस्तरस्त अस्मत्कृते बृहच्छव्दर्रने मदन्तेवासिइतल्धुशब्देन्दुशेखेर च द्रष्टब्य: Laghuśabdaratna. For details see Bhandarkar Ins. Journal Vol. 32 pp. 258-60.

बृहच्छज्दरत्नटीका called बृहच्छज्दरत्नज्याख्या written by भवदेव.

बृहती a Vedic metre consisting of four pādas and 36 syllables. There are three pādas of eight syllables and the fourth has twelve syllables. It has got further subdivisions known as पुरस्ताद्बृहती, उपरिष्टाद्बृहती, न्यङ्भुसारिणी or उराबृहती, उर्ध्वबृहती विद्यारबृहती, पिपीलिकमध्यमा and विषमपदा. For details see R.Pr. XVI. 31-37.

बृहर्संज्ञा the same as महत्संज्ञा or महती संज्ञा; a bigger terminology as contrasted with लघुसंज्ञा brief terminology such as दि, चु, भ etc. for which (latter) Pāṇini is very particular. The bigger terms such as सर्वनाम, आत्मनेपद, परसीपद and others are evidently borrowed by Pāṇini from the ancient grammarians who lived before him.

वृहह्पेणा name of a commentary on Kondabhatta's Vaiyākaranabhū-ṣaṇasāra by Mannudeva, who was called also Mantudeva, who lived in the latter half of the eighteenth century.

वृहद्याकरणसिद्धान्तमञ्जूषा a grammar work written by Ramañatha Chobhe.

बेलवलकर [SHRIPAD KRISHNA

BELVALKAR] a well-known Sanskrit scholar of the present day who has been the General Editor of the Mahābhārata published by the Bhandarkar Oriental Research Institute, Poona. He has written a book on grammar reviewing very briefly the various systems of Sanskrit grammar, which is named "Systems of Sanskrit Grammar".

बोधोंड क [BOHTLINGK, OTTO] a German Sanskrit scholar and Grammarian of St. Petersberg, who has written a short gloss in German on Pāṇini's Aṣṭādhyāyī under the title "Pāṇini's Grammatik" with an introduction and various indexes at the end. He has also critically edited Mugdhabodha of Bopadeva.

बोध्य a technical term for the vocative case in the Jainendra Vyākarana.

बाप [BOPP, FRANZ] a German Sanskrit scholar who has written the famous volumes of "The Comparative Sanskrit Grammar".

बोपदेव a great Sanskrit scholar and grammarian belonging to Devagiri in the greater Maharastra who was supported by Hemāgri of Devagiri. He resided at सार्थप्राम on the river Varada in the first half of the thirteenth century. He wrote a short treatise on Sanskrit Grammar, which has a number of peculiar abbreviations for the usual well-known grammatical terms. His grammar had a wide spread in Bengal and it is today a very common text on Grammar Bengal. On this account some scholars believe that he lived in Bengal. He was the son of Kesava and pupil of Dhanesa. He is also the author of the well-known work कविकल्पट्टम on which he has written a commentary named कामधेनु or कान्यकामधेनु.

সহাকাত name given to the first section or Kāṇḍa of Bhartrhari's Vākyapadīya. It deals with Sphota, and in a way it contains in a nutshell the philosophy of Sanskrit Grammar.

न्नसराशि the sacred Sanskrit alphabet given in the fourteen sūtras of Maheśvara, named Akṣarasamāmnāya which is called न्रह्मराशि as it contains the basic letters of शन्द which is Brahma according to Grammarians; cf. सोयमक्षरसमाम्रायो चाक्यसमाम्रायः पुष्पितः पलितश्चन्द्रतारकवत् प्रतिमण्डितो वादितव्यो न्रह्मराशि: M. Bh. Āhnika 2 end; cf. also एते पञ्चषष्टिवर्णा न्रह्मराशिरात्मवाचः V. Pr.VIII. 25.

नाह्मणादि a class of words headed by the word नाह्मण to which the tad. affix य (ध्यम्) is added in the sense of 'nature' or 'duty'; e. g. नाह्मण्यं (नाह्मणस्य भावः कमे वा); cf नाह्मणादिराकृतिगणः आदिशब्दः प्रकारवन्तनः Kāś. on P. V.1.124.

भ

- भ् fourth letter of the labial class which is possessed of the properties कण्ठसंद्वतता, नादानुप्रदान, घोष, and महाप्राणत्व.
- भ (1) the letter or sound म with the vowel अ added for facility of utterance; (2) a technical term in the Grammar of Pāṇiṇi given to a noun base before such case and taddhita affixes as begin with any vowel or with the consonant य. The utility of this designation of भ to the base is (1) to prevent the substitutes which are enjoined for the final vowel or consonant of a pada (a word end-

ing with a case-affix or a base before case and tad. affixes beginning with any consonant excepting 4) just as the substitution of Visarga, anusvāra, the first or third consonant, and others given in P. VIII. 4.37 and the following. For the various changes and operations for a base termed 4 sec P. VI. 4.129 to 175.

भकार the consonant म with the vowel अ and the affix कार added for facility of utterance; cf. T. Pr. I. 17,21.

भक्त forming a part or portion (of something in connection with which it has been prescribed as an augment) cf. तद्भक्तस्तद्ग्रहणेन ग्रह्मते Vyādi Pari. 17; cf. also आम: सुडयं भक्त: आम्ग्रहणेन ग्राहिष्यते M. Bh. on P. VII. 1.33.

भक्तल tad. affix भक्त applied to the words भौरिकि and others in the sense of 'a place of residence;' cf. P. IV. 2.54.

भार्क (1) name given to two of the five divisions of a Saman which are प्रस्तावभक्ति, उदुगीथ, प्रतिहार, उपद्रव and निधानभक्ति; (2) the vowel portion surrounding, or placed after. the consonant { or 평 which (consonant) is believed to be present in the vowel 事 or ऌ respectively forming its important portion, but never separately noticed in it. The vowels 事 and ऌ are made up of one matra It is contended by the grammarians that the consonants ₹ and @ forming respectively the portion of 零 and ऌ, make up halfa-matra, while the remaining half is made up of the भाक्त of the vowel surrounding the consonant or situated after the consonant. The word which is generally used

for this 'bhakti' is 'ajbhakti' instead of which the word स्वरमिक्त is found in the Prātišākhya works; cf. यत्तेद्रभात्परं मक्तेत्वेत व्यवहितत्वान्न प्राप्तोति । यचात्र रेपात्परं मक्तेन् तत् कचिदपि व्यपन्नक्तं हस्यते । M. Bh. on P. VIII. 4.1 Vārt 2; cf. स्वरमिक्तः पूर्वभागक्षराङ्ग R. Pr. I. 17; also cf. रेपात्स्वरोपहिताद् व्यञ्जनोदयाद् ऋतारवणी स्वरमिक्तरा । R. Pr. VI. 13.

भाक्षित lit. eaten up; a fault in pronunciation when a letter is so hurriedly pronounced that it appears to have been dropped.

भक्ष्यनियम a restriction regarding edibles of a particular kind. word is quoted to illustrate the नियमविधि or restrictive rule in grammar. Although the restriction in the instance पञ्च पञ्चनखा मध्याः is of the kind of परिसंख्या and called परिसंख्या, and not नियम, by the Mimamsakas, the grammarians call it There is no परिa niyamavidhi. संख्याविधि according to grammarians; they cite only two kinds of vidhi viz. simple vidhi or apūrva vidhi and niyamavidhi.

भट्टोजी surnamed Diksita; a stalwart grammarian of the Panini system who flourished in the first half of the seventeenth century and wrote many independent books and commentaries such as the Siddhantakaumudī, the Praudhamanoramā, Vaiyākaraņasiddhāntakārikā, the Sabdakaustubha and others. The most reputed work out of these, however, is the Siddhantakaumudi which is very popular even today and which has almost set aside other works of its kind such as the Prakriyākaumudī and Bhattojī was a Telagu Brāhmana, as generally believed, and although he belonged to the

South, he made Vārānasī his home where he prepared a school of learned Grammarians. Although he carried on his work silently in Vārāņasī, he was envied by the reputed rhetorician of his time Pandita Jagannatha, who criticised his work (Bhattojis work) named Manoramā very severely. प्रौढमनोरमा above. The Siddhantakaumudī has got many commentaries of which the Tattvabodhinī written by Bhattoji's pupil Jnanendrasarasvatī is appreciated much by learned grammarians.

मत्व the nature or quality of being called भ which causes many grammatical operations which are given together by Pāṇini in VI. 4.129 to 175. See the word भ above.

भरतमञ्ज a grammarian of Bengal who lived in the sixteenth century and who wrote उपसर्गद्वात, द्वतबोध and other works on grammar.

भगोदि a class of words headed by भगे which are generally names of countries, the taddhita affixes अण् and others added to which are not elided; e.g. भागीं, केंकेयी, कास्मीरी; cf. Kāś. on IV. 1.178.

भतेहरि a very distinguished mmarian who lived in the seventh century A. D. He was a senior contemporary of the authors of the Kāsīkā, who have mentioned his famous work viz. The Vākyapadīya in the Kāśikā. of. राज्दार्थसंबन्बीयं प्रकरणम्। वाक्यपदीयम् Kās. on P. IV.3.88. His Vyākaraņa work "the Vākyapadiya" has occupied a very prominent position in Grammatical Literature. The work is divided into three sections known by the name 'Kāṇḍa' and it has discussed so thoroughly the problem of the relation of word to its sense that sub-

sequent grammarians have looked upon his view as an authority. The work is well-known for expounding also the Philosophy of Grammar. His another work "the Mahābhāsya-Dīpikā" is a scholarly commentary on Patanjali's Mahābhāsya. The Commentary is not published as yet, and its solitary manuscript is very carelessly written. Nothing is known about the birth-place or nationality of Bhartrhari. It is also doubtful whether he was the same person as king Bhartrhari who wrote the Satakatraya '.

भवत् (भवन्त्) ancient term for the present tense found in the Brhaddevatā and other works. The term 'vartamānā' for the present tense was also equally common. The word is found in the Mahābhāṣya, the Uṇādisūtravṛtti of Ujjvaladatta and in the Grammar of Jainendra cf. P.II.3.1 Vārt 11, Uṇadi III. 50 Jain Vyāk. I.1.471.

भवदेव a scholar of grammar who has written a commentary on the Bṛhacchabdaratna of Hari Dīkṣita.

भवन्ती ancient term for the present tense or लट् according to Pāṇini cf. अस्तिर्भवन्तीपर: प्रथमपुरुष: अप्रयुज्यमानीप्यस्ति M. Bh. on P. II.3.1. Vārt. 4; cf. aiso प्रवृत्तस्याविरामे शासितज्या भवन्ती । इहाधीमहे । इह वसाम: । इह पुष्यिमंत्रं याजयाम: । M. Bh. on P. III. 2.123. See भवत् (भवन्त्).

भविष्यत् ancient term for the future tense in general; cf. भविष्यति गम्यादय: । भविष्यतीद्यनद्यतन्य उपसंख्यानम् P. III.3.3 Vārt.l; cf.also the words भविष्यत्काल, भविष्यत्रातिषेष, भविष्यद्धिकार.

भविष्यन्ती ancient term for the future tense in general; cf. परिदेवने श्वस्तनी भविष्यन्त्यर्थे P. III.3.15. Vart.1; cf. also Kat. III.1.15; Hem. III. 3.15. भष् short term (प्रत्याहार) for the consonants स, ঘু হে ছ; (f. ছেফার্ছা বিছ্যা

भण्माच the substitution of the third consonants respectively for the fourth consonants म्, च्, द् and घ्; cf. P. VI.1.13 Vart. 13.

मह्यादि a class of words headed by the word মদ্ধা to which the tad. affix इक (छन्) is added in the sense of 'carrying by'; e.g. মন্ধিক', মন্ধিকা cf.Kas. on P.IV.4.16.

भसंज्ञा the term भ applied to the noun-base in contrast with the term पद.For details see the word भ.

भागवत हरिशास्त्री a modern scholar of grammar who has written a commentary named Vākyārthacandrikā on the Paribhāṣenduśekhara of Nāgeśa; he lived in the first half of the eighteenth century.

भागवृत्ति one of the oldest commentaries on the Sūtras of Pānini, which, although not available at present, has been profusely quoted by Purusottamadeva and other Eastern Grammarians twelfth and later centuries. The authorship of the work is attributed to Bhartrhari, but the point is doubtful as Sīradeva in his Paribhāsāvītti on Pari. 76 has stated that the author of the Bhagavitti has quoted from Maghakavya; cf. अत एव तत्रेव सूत्रे भागवृत्तिः पुरातनमुनेर्मुनिता-मिति पुरातर्नार्नदीरिति च प्रमादपाठावेतौ गतानु-गतिकतया कवयः प्रयुक्तते न तेषां लक्षणे चक्षरिति। Some scholars attribute its authorship to Vimalamati. Whosoever be the author, the gloss (भागवित) was a work of recognised merit; cf. काशिकाभाग इत्योश्चेत् सिद्धान्तं वेतुमस्ति घी:। तदा विचिन्त्यतां भातभीषावृत्तिरियं मम Bhāsavitti at the end. सृष्टिघर in his commentary on the Bhasayrtti also says " सा हि द्वयोविंवरणकर्त्रीं."

Bhandarkar 1837-1925 A. D.] a well-known scholar of Sanskrit Grammar who has written learned articles on many grammatical topics. He was a distinguished Professor of Sanskrit in the latter half of the nineteenth century. He was one of the pioneers of Sanskrit studies in India.

भारद्वाज (1) an ancient grammarian quoted by Pāṇini in his rules to show differences of opinion; cf.ऋतो भारद्वाजस्य VII. 2.63; (2) name of a country in the days of Pāṇini cf. कुकणपणीद्धारद्वाज P. IV. 2.145.

भारद्वाजीय scholars and grammarians belonging to or following the Bhāradwāja School of Grammar whose views are often quoted in the Mahābhāṣya; भारद्वाजीयाः पठन्ति M. Bh. on P. I.1.20Vārt. I, I.1.56 Vārt.11; I.2.22 Vārt.3; I.3.67 Vārt. 4, III.1.38 Vārt.1, III 1.48 Vārt. 3; III 1.89 Vārt. 1, IV.1.79, VI.4. 47 and VI.4.155.

भाव (1) becoming; existence. word is used many times in the sense of धात्वर्थ- the sense of a root which is 'incomplete activity' or 'process of evolving'; cf. तदाख्यातं येन भावं स धातु: R. Pr. XII. 5; cf. also षड् भावांविकारा भवन्ति Nir. I. 36; पुर्वापरीभृतं भावमाख्यातेन आच्छे त्रजतिपच्ती-त्युपक्रमप्रभृति अपवर्गपर्यन्तम् Nir. I. 1; (2) activity as opposed to instruments (साधन or कारक); cf. भाव-गर्हायाम् । धात्वर्थगर्हायाम् Kās. on P. III. 1.24; cf. also भाव: क्रिया, Kāś.on यस्य च भावेन भावलक्षणम् P. II. 3.37; (3) completed action which is shown, not by a verb, but by a verbal derivative noun; cf. घात्वर्थश्च धातु-नैवोच्यते । यस्तस्य सिद्धता नाम धर्मस्तत्र धञादयः प्रत्यया विधीयन्ते Kāś. on ' मावे ' P. III. 3.18; cf. also कुदमिहितो भावो द्रव्यवद्भवति M. Bh. on P. II. 2, 9, III. 1.67, IV. 1.3, V. 4.19; cf. also भावस्त्वेकः M. Bh. on P. III. 1.67; (4) the radical factor for the use of a word; प्रशृत्तिनिमत्त; cf. भवतो स्मादिभ-धानप्रत्यया इति भावः । शब्दस्य प्रवृत्तिनिाभित्तं भावराव्देनोच्यते । अश्वत्वम् । अश्वता । Kās. on P. 5.1.119; (5) thing, object cf. सिद्धराब्द: कटस्थेषु भावेष्वविचालिष् वर्तते M. Bh. I. 1. Ahnika 1; (6) transformation, substitution; change into the nature of another; cf. तत्र प्रथमास्तृतीयभावम् R. Pr. II. 4. cf. also the words मुर्घन्यभाव, अभिनिधानभाव etc. (7) possession of the qualities, nature; तदर्थस्य भावः तादर्थ्यम्; M. Bh. on P. II. 3.13; (8) relationship; cf. गुणप्रधानभाव, प्रकृतिविकृतिभाव etc.

भावकर्तृक having for its subject a verbal derivative in the sense of the भाव or the root activity. The word भाववचन is explained as भावकर्तृक in the Kāsikāvṛtti. e. g. the word रागः in चौरस्य रुजित रोगः Kās. on P. II. 3. 54: cf. भाववचनानां भावकर्तृकाणां Kās. on P II. 3.54.

भावदीप name of a commentary on the Sabdakaustubha by कृष्णमिश्र.

भावदेव a grammarian who has written a commentary on the Brhacchabdaratna of Hari Dīkṣita; possibly the same as भवदेव.See भवदेव. भावना effort, activity.

मानपकारा name of a co

भावप्रकारा name of a commentary on the शब्दकौस्तुभ by वैद्यनाथ पायगुण्डे.

भावप्रत्यय an affix in the sense of quality such as त्व, ता etc.; cf. न ह्यन्तरेण भावप्रत्ययं गुणप्रधानो भवति निर्देशः.

भावप्रधान description of a verb or verbal form in which activity plays the main part as opposed to a noun in which completed activity (ধন্ব) is predominant.

as igniting a hearth, placing a rice-pot on it, pouring water in

it etc., which form the different parts of the main activity viz. cooking; cf. उक्तो भावभेदो भाष्ये M. Bh. on P. III. 3.19, III. 4.67.

भावनचन (1) expressive of भाव or the completed verbal activity; e.g. the word भाव itself, as also হুৱা, বান, and others; (2) having for their subject a verbal derivative in the form of the verbal activity. See भावकर्त्क.

भावविकार kinds of verbal activity which are described to be six in number viz. production, existence, transformation, growth, decay and destruction. These six modes of existence first mentioned by Varsyāyani and quoted by Yāska are explained philosophically Bhartrhari as a mere appearance of the Sabdabrahman or Sattā when one of its own powers, the time factor (কালহাৰিत) is superimposed upon it, and as a result of that superimposition, it (i.e. the Sabdabrahman) appears as a process; cf. षड् भावविकारा भवन्ति इति वाष्या-यणि: । जायते अस्ति विपरिणमते वर्धते अपर्कायते विनक्ष्यति इति । Nir.I.2; cf. also Vākyapadīya III.30.

भावरामेन the author of the कातन्त्रपरि-भाषावृत्ति, a work on the Paribhāṣās in grammar which are utilized in explaining the rules of the कातन्त्रव्याकरण by Sarvavarman.

भावसाधन (1) a word in the sense of मान or completed verbal activity अस्ति भावसाधनो विधिशन्दः । विधानं विधिरिति M. Bh. on P. I.1.57; (2) an affix applied for the formation of a word in the sense of verbal activity; cf. प्रयतनं प्रयतनः । प्रपूर्वाद्यत्तेभीन्वसाधनो नङ् प्रत्ययः M. Bh. on I.1.9.

भावसेन a grammarian of the Kātantra school who wrote the works Kātantrarūpamālā and Kaumāra Vyākaraņa. भावित designated by a technical term; cf. किं पुनिरदं तद्भावितप्रहणं वृद्धिरित्येवं ये आकारैकाराकारा विहिता भाज्यन्ते तेषां प्रहणं आहोस्विद् आदैज्मात्रस्य, M.Bh.on P.I.11.

भाविन which is to come into being; of future time; cf. भावि कृत्यमासीत M. Bh. on III. 4.1; cf. भाविनः सुट आदेशो विधीयते M.Bh. on P. VII. 1. 33; cf. also एवं तर्हि भाविनीयं संज्ञा विज्ञास्यते M.Bh on P. I. 1.45.

भावेपयोग impersonal form of a sentence when there is no activity mentioned on the part of the agent nor resulting upon the object, but there is a mere mention of verb-activity.

भाव्य that which is to be produced; cf. Jain. Vyāk. I.1.72. See भाव्यमान.

भास्यमान lit. which is to be produced; which is prescribed by a rule, like an affix; hence, an affix or an augment or a substitute prescribed by a rule as contrasted with the conditions or the original wording for which something is substituted, or after which an affix is placed, or to which an addition is made, or which is deleted; cf. भाष्यमानेन सवर्गानां महणं न Par. Sek. Pari. 19; also cf. M.Bh. on P.I. 1.50, I.1. 69, VI.1.85, VI.4.160.

भाषा spoken language as opposed to the archaic Vedic Language; cf. भाषायां सदवसञ्जवः; P.III2.108; प्रत्यये भाषायां नित्यम् . P. VIII. 4. 45 Vārt. 1; cf. also R. T. 96, 212; cf. also निति प्रतिषेधार्थीयो भाषायाम् । उभयमन्वध्यायम् Nir. I.4.

भाषानुशासन a work on language attributed to यशःकवि.

भाषामञ्जरी a small treatise on grammar written by Vyankața Subbā-Shastrī.

भाषाद्वात्त a short gloss on the Astadhyāyī of Pāṇini in the 12th century by Purusottamadeva, a reputed scholar belonging to the Eastern grammarians which school of flourished in Bengal and Behar in the 10th, 11th and 12th centuries. The gloss is very useful for beginners and it has given a clear explanation of the different sutras without going into difficult niceties and discussions. The treatise does not comment upon Vedic portions or rules referring to Vedic Language because, as the legend goes, king Laksmana Sena, for whom the gloss was written, was not qualified to understand Vedic Language; cf. वैदिकभाषान ईत्वात् Com. Bhāsāvṛtti by Systidhara. There is a popular evaluation of the Bhasavitti given by the himself in the stanza " काशिकामागृहत्योश्चेत्सिद्धान्तं बोद्धमस्ति धीः। विचिन्त्यतां भ्रातभीषात्रत्तिरियं मम् " at the end of his treatise; for details see पुरुषोत्तमदेव.

भाषावृत्तिदीका a learned commentary on Purusottamadeva's Bhāṣavṛtti by Sṛṣṭidhara a learned grammarian of the sixteenth century.

भाषिक belonging to, or used in spoken language as contrasted with the Vedic Language or निगम; cf. अथापि भाषिकस्यो धातुस्यो नेगमा: कृतो भाष्यन्ते Nir. II.2.

भाषितपुंस्क a word or a noun-base which has the same sense in the masculine gender as in the neuter gender; generally words of quality or adjectives like शानि, मधु etc. fall in this category; cf. तृतीयादिषु भाषितपुंस्कं पुंवद्रालवस्य P. VII. 1. 74; cf. also भाषित: पुमान् यस्मन्नर्थे प्रवृत्तिनिमित्ते स भाषित-पुंस्कशब्देनोच्यते । तद्योगादिभधेयमि यनपुंसकं तदिष भाषितपुंस्कम्। तस्य प्रातिपादकं यन्छन्दरूपं तदिष भाषितपुंस्कम्। स्टं. on VII.1.74.

भाष्य a learned commentary on an original work, of recognised merit

and scholarship, for which people have got a sense of sanctity in their mind; generally every Sūtra work of a branch of technical learning (or Sastra) in Sanskrit has got a Bhāṣya written on it by a scholar of recognised merit. Out of the various Bhāsya works of the kind given above, the Bhasya on the Vyākaraņa sūtras of Pāṇini is called the Mahābhāsya, on the nature of which possibly following definition is based "सूत्रार्थी - वर्ण्यते यत्र पदैः सत्रानुकारिभिः । स्वपदानि च वर्ण्यन्ते भाष्य भाष्यविदो विद: ।". books on Sanskrit Grammar the word भाष्य is used always for the Mahābhāsya. The word भाष्य is sometimes used in the Mahabhasya of Patañjali (cf. उक्ती भावभेदी भाष्ये III.3.19, IV.4.67) where word may refer to a work like लबुभाष्य which Patanjali may have written, or may have got available to him as written by somebody else, before he wrote the Mahābhāsya.

মান্দ্ৰকাৰে Patanjali, the author of the Patanjala Mahabhasya; the term, in this sense, frequently occurs in works on Grammar. See মাথ

भाष्यसूत्र the brief pithy statements in the Mahābhāṣya of the type of the Sūtras or the Vārttikas. These assertions or statements are named 'iṣṭi' also.

भाष्येष्टि the brief pithy assertions or injunctions of the type of Sūtras given by Pata jali in a way to supplement the Sūtras of Pāṇini and the Vārttikas thereon. See the word इष्टि above and the word भाष्यसूत्र also.

मास्करशास्त्री surnamed Abhyankar (1785-1870) a great grammarian in the line of the pupils of Nagesa who was educated at Poona and lived at Sātārā. He taught many pupils, a large number of whom helped the spread of Vyākaraṇa studies even in distant places of the country, such as Vārāṇasi and others. For details see Vyākaraṇa Mahābhāṣya Vol. VII pp. 27-29, D. E. Society's Edition.

भिक्षादि a class of words headed by the word भिक्षा to which the tad. affix अ (अण्) is added in the sense of collection; e.g. भैक्षम, यौवतम, पादातम्; cf. Kās. on P. IV.2.38.

मिद्दि a class of roots headed by the root भिद् to which the krt affix अ (always in the fem. gender as आ) is added in the sense of verbal activity; e.g. भिदा, गुहा, श्रद्धा, भेघा etc. cf. Kas. on P. III. 3.104.

before which the base is looked upon as a Pada and sometimes split up in the Padapāṭha, especially when the preceding word has got no change for its last letter or syllable.

भीमभद्ध writer of the commentary, named भैमी after him, on the Paribhāṣenduśekhara of Nāgeśa.

भीमसेन called भीमदास also, who flourished in the fourteenth century and wrote a treatise on grammar called भैमन्याकरण.

भीमादि a class of words headed by the word भीम in which the Uṇādi affixes म and others, as prescribed by specific Uṇādi sūtras, are found added in the sense of the 'apādāna' case-relation; e.g. भीम: in the sense ' विभेति अस्मात्'. Similarly भीष्म:, भूभ:, रजः etc. cf. Kāś. on P.III.4.74.

भुक्त lit. swallowed or eaten up; the term is used in connection with letters that are uttered imperfectly on account of the proximity of similar letters.

मुन्न name of a Samdhi or coalescence given by the writers of the Prātisākhya works where the diphthong vowels ओ and औ, followed by any vowel which is not labial, are turned respectively into अब् and आब्; e. g. ऋतेन मित्रावरणाञ्चताञ्चधा- इतस्प्रशा (R. Samh.I..2.8); cf. ओष्ट्ययो- स्योभ्रीममनोष्ठये वकारोत्रान्तरागमः । यथा ऋतेन मित्रावरणाञ्चताञ्चधान्तस्प्रशा । अनोष्ठये इति किम् । वायो उक्थेभिः 2.2. (R.Samh. I.2.2). इत्यतः वाय उक्थेमि cf. R. Pr. II.11.

भूत lit, what has become or happened. The word is used in books on grammar in the sense of past tense in general, which has been subdivided into (a) unseen past (परीक्षमूत or छिट्), (b) past, not of today (अनद्यतनमूत or छङ्) and (c) past in general (सामान्यमूत or छङ्), cf. भूते P.III.2.84, परीक्ष छिट् P.III.2.116 and अनद्यतन छङ् P.III.2.111.

मृतपूर्वगति lit. denotation of something which formerly was existing; a consideration of that form of a word which was formerly present. The word is used frequently by commentators when they try to apply a rule of grammar to a changed wording under the plea that the wording required by the rule was formerly there; cf. भूतपूर्वगत्या (पकारलीप कृतिप) दाप भविष्यति, M. Bh. on P.I.1.20 Värt. 9; cf. also M. Bh. on P.I.1.56, VII.1.9 and VII. 3.103; cf. also सांप्रतिकाभावे भृतपूर्वगति: Par. Sek. Pari. 76.

भूपाद name popularly given by Siradeva and other grammarians to the third pāda of the first adhyāya of Pāṇini's Aṣṭādhyāyī as it begins with the Sūtra भ्वादयो भातव: P.I.3.1.

भूमन plurality of the individuals

referred to; cf. बहोर्नञ्बदुत्तरपद्भाम्न P. VI.2.175.

भूगादि the limited senses भूमन् (plurality) and others in which मतुष् and other possessive taddhita affixes should take place, and not in the general sense of the 'presence at one place' as also 'the possession by some one individual;' cf. भूमिन्दा-प्रशंसासु नित्ययोगितिशायने। संसर्गेरितिविवशायां भवन्ति मतुबादय: M. Bh. on V. 2.94.

भूवादि lit. headed by भू, or headed by भू and वा as some scholars like to explain; the term means roots; in general, which have भू as the first root in Pāṇini's list of roots; cf. भ्वादयो धातवः P. I. 3.1; The word भूवादि denoting roots stands in contrast with the word भ्वादि which stands for the roots of the first conjugation. भूवादीनां वकारोयं मङ्गलार्थः प्रयुज्यते । भुवो वार्थं वदन्तीति भ्वर्थां वा वादयः स्मृताः Kāś. on P. I. 3.1.

भृशादि a class of nouns headed by भृश to which the denominative affix य is added in the sense of being or becoming what they were not before; e. g. अभृशो भृशो भश्वति भृशायते; similarly शोव्रायते, मन्दायते, उन्मनायते, दुर्मनायते etc.cf. Kas. III.1.13.

भें दे difference, differentiation; cf. सति भेदे किं वित्तसमानिमित कृत्वा सवर्णसंज्ञा भविष्यति M. Bh. on P. I.1.9, Vart. 2.

भेदक (1) lit. distinguishing; differentiating; cf. भेदकत्वात्त्वरस्य । भेदका उदात्तादयः । M. Bh. on P. I. 1.1 Vārt. 13; (2) adjective; cf. भेदकं विशेषणं भेद्यं विशेष्यम् Kāś. on P. II. 1.57; (3) variety; kind; cf. सामान्यस्य विशेषां भेदकः प्रकारः Kāś. on P.V. 3.23; (4) indicating, suggesting, as contrasted with वाचक; cf. संबन्धस्य तु भेदकः Vākyapadīya.

भेद्य that which is distinguished; the word which is qualified; cf. भेद्र विशेष्यम् Kāś. on P. II. 1.57. भैमन्याकरण a grammar treatise written by भौमरेन in the fourteenth century A. D.

भैमी name of a commentary on the Paribhāṣenduśekhara of Nāgeśa written by Bhīmabhaṭṭa in the latter half of the eighteenth century.

भैरवामेश्र one of the reputed grammarians of the latter half of the eighteenth century and the first half of the nineteenth century who wrote commentaries on several prominent works on grammar. He was the son of भवदेव and his native place was Pravaga. He has written the commentary called Candrakalā on the Laghusabdenduśekhara, Parīksā on Vaiyākaraņabhūsanasāra, called also Bhairavī or Bhairavīgadā on the Paribhāsenduśekhara commentaries (popularly named Bhairavi) on the Sabdaratna and Lingānuśāsana. He is reported to have visited Poona, the capital of the Pesawas and gifts received magnificent exceptional proficiency in Nyaya and Vyākaraņa. For details see pp. 24 and 25 Vol. VII. Patañjala Mahābhāsya D. E. Society's Edition.

भेरवी name given to a commentary in general written by Bhairava-miśra, which see above. The commentary on the Paribhāṣen-duśekhara is more popularly known as Bhairavī.

भोगीनर् tad. affix भोगीनर् suggested by the Vārttikakāra to form words like राजभोगीन, आचार्यभोगीन which are derived by the rule आत्मन्विश्वजनभोगोत्तरपदात् खः P. V. 1.9.

भोज the well-known king of Dhārā who was very famous for his

charities and love of learning. He flourished in the eleventh century A. D. He is said to have got written or himself written several treatises on various śāstras. The work Sarasvatīkanthābharana which is based on the Aṣṭādhyayī of Pāṇini, but which has included in it the Vārttikas and Paribhāsās also, has become in a way a Vyākarana or a general work in grammar and can be styled as Bhoja-Vyākarana.

भोलानाथ a grammarian who has written a commentary named Samdarbhāmṛta on Bopadeva's Mugdhabodha.

भौतपूर्क्य the consideration that a thing was such and such a one formerly, and hence liable to undergo grammatical operations on that ground; cf. इत एन्वे भौतपूर्कात्। भिस ऐस्। M. Bh. on P. VII. 1. 9.

भौवादिक belonging to the class of roots headed by भू; a root of the first conjugation; cf. अस् न्यातौ भौवादिक: Kēs. on P. III, 1.75.

म्यस् case-affix of the dative and ablative plural; cf. स्वीजसमीट्• P. IV. 1. 2.

भ्याम् case-affix of the instrumental, dative and ablative dual; cf. स्वौजसमोट्० P. IV. 1. 2.

भ्रदस् tad. affix भ्रष्ट applied to the prefix अव in the sense of depression of the nose; e.g. अवभ्रष्ट: पुरुष: अवभ्रष्टा नासिका अवभ्रष्टम् (depression of the nose नासिकाया नतत्वम्);cf. Kāś. on नते नासिकायाः संज्ञायां टिट्म् नाटम् भ्रष्टचः P. V. 2.31.

भ्रष्टावसर lit. a person or a thing of which the proper occasion has passed; the word is used in connection with the application of a rule even though the proper time

of its application is gone, on the analogy of a man who is paid his Dakṣiṇā although the proper time has gone (भ्रष्टावसरन्यायेन दक्षिण दीयते); cf. न च पुनर्छक्त्यास्त्रं प्रवर्तते भ्रष्टावसरत्वात् Kāś. on P. VII.2.101.

মান stray or spurious verses or stanzas whose authorship cannot be traced, but which are commonly quoted by scholars; cf. মাজা নাম স্টাকা: M.Bh. on I.1 Ahnika 1; the word মাজ is explained as 'composed by Kātyāyana' by Nāgesabhatta in his Uddyota.

श्रमध्य lit.centre of the brows, or eyebrows which is described as the place of air (which produces utterance or speech) at the time of the evening soma-pressing or sacrifice; cf. प्रात:सवनमाध्यन्दिनसवनतृती-यसवनक्रमेण उर:कण्डभ्रमध्यानि त्रीणि स्थानानि वायोर्भवन्ति । Vāj. Prāt. I. 30; cf. also भ्रवोर्मध्ये प्राणमावेक्य सम्यक्.

भ्यादिगण the class of roots headed by भू; the first conjugation of roots.

म

- म् (1) fifth letter of the labial class of consonants which is possessed of the properties नादानुप्रदान, घोष, कण्डसंत्रतस्य, अस्पप्राणस्य and आनुनासिक्य; (2) substitute म् (मह्म्) for अम् of the lst. pers. sing. in Vedic literature; e.g. वधी वृत्रम्। टा. अमी मह्म् P. VII. 1.40;
- म (1) the consonant म with the vowel अ added for facility of utterance; cf. T. Pr. I.2.1; (2) The substitute म for मस् of the 1st pers. pl. in the perfect tense cf. P परस्मेपदानां ... णह्वमा: III. 4.82 and in the present tense also in the case of the root बिद; (3) tad. affix म added to the word मध्य in the Saisika senses, and to the words

द्य and g in the sense of possession; cf. P.IV.3.8,V.2. 108.

महरन्द (1)name of a commentary by Raṅganātha on the Padamañjarī of Haradatta: (2) name of a commentary on the Supadma Vyākaraṇa by Visṇumiśra.

मকাৰ the consonant ম with the vowel অ and the affix কাৰ added for facility of use and pronunciation; cf. T.Pr.I.17 and 21.

मङ्गलार्थ for the sake of auspiciousness at the beginning of a treatise or work; cf. भूवादीनां वकारोयं मङ्गलार्थः प्रयुज्यते M.Bh. on P.I.3.1.;cf.मङ्गलादीनि हि शास्त्राणि। M.Bh. on P.I.1.1.

मद् tad. affix म applied to a numeral, not preceded by another numeral in the sense of completion; e. g. पञ्चम:, सप्तमः; cf. नान्तादसंख्यादेर्मट् Pān. V.2.49.

मण् tad. affix म, causing viddhi for the word मध्य, in the sense of 'present therein' (तत्र भवः); e.g. माध्यमः; cf. मण्मीयौ चापि प्रत्ययौ, P.IV. 3.60 Vart. 2.

मण्डूकाति lit.the gait of a frog; jump; the continuation of a word from a preceding Sutra to the following Sutra or Sutras in the manner of a frog by omitting one or more Sutras in the middle; the word मण्डूकण्डित is also used in the same sense especially by later grammarians; cf. अथवा मण्डूकगतयोधिकाराः । यथा मण्डूका उल्लुत्योल्लुत्य गच्छन्ति तद्वदिषकाराः ॥ M. Bh. on P.I.1.3 Vart.2, II.3.32, II. 4.34, VI.1.16, VI.3.49, VII. 2.117.

मण्डूकर्न्छाति the same as मण्डूकगति which see above; cf. अथवा मण्डूकप्छतयोधिकाराः MB.h. on P. V.2.4.

मञ्जूषा a popular name given to the work परमलघुमञ्जूषा of Nāgeśa on अर्थ-प्रक्रिया (science or method of interpretation) in Vyākaraņa, which is generally read by advanced students. Nāgeśa has also written a bigger work on the same subject ত্যুম্হসূমা which sometimes is also referred to by the word মহস্মা.

मतु the same as मतुष् a tad. affix showing possession; the word is frequently used in Pāṇini's rules for मतुष. cf. मतोश्च बहुजङ्गात् । P. IV 2.72; cf. also, P.IV. 4.125, 136; V. 2.59, VI.1.215, VI.3.118,130; VIII. 2.9; for the sense of मतु see मतुष् below. The affix मतु (instead of मतुष् of Pāṇini) is found in the Atharva Prātiśakhya.

मतुप् tad. affix मत् changed in some cases to वत (cf. माद्पधायाश्च मतोवींऽ यवादिभ्यः P. VIII. 2.9), applied to any noun or substantive in the sense of 'who possesses that,' or 'which contains it,' or in the sense of possession as popularly expressed. The affix is called possessive affix also, and is very commonly found in use; e. g. गोमान्, वृक्षवान्, यवमान्, etc. cf. तदस्या-स्त्यस्मिनिति मतुप् P. V. 2.91. very general sense of 'possession' is limited to certain kinds of possession by the Varttikakara in the following stanza; भूगानिन्दाप्रशंसास नित्ययोगेतिशायने । संसर्गेऽस्तिविवक्षायां भवन्ति मतुबादयः cf. Kāś. on P. V. 2.94. There are other tad. affixes prescribed in the same sense as मतुप्, such as the affixes ভৰু (V. 2.96-98), इलचु (99, 100, 105, 117), হা and न (100), ण (101), विनि (102, 121, 122), इनि (102, 115, 116, 128, 129-137), अण् (103, 104), उरच् (106), र (107), म (108), व (109, 110), ईरन् and ईरच् (111), वलच् (112, 113), ठन् (115, 116), ठञ् (118, 119), यप् (120). युस् (123, 138, 140), मिनि (124), आलच् and आटच् (125). अच् (127), and ब, भ, यु, ति, तु, त and यस each one applied to specifically stated words. मतुप् is also specially prescribed after the words headed by स्स (cf. रसादिम्यश्च P. V. 2.95) in supersession of some of the other affixes mentioned above which would take place in such cases, if मतुप् were not prescribed by the rule रसादिम्यश्च. The portion of the Astādhyāyī prescribing the possessive affixes is named मतुबधिकार (P. V. 2.92 to 140).

मतुष्पाद a conventional name given by grammarians to the third pāda of the eighth Adhyāya of Pāṇini's Aṣṭādhyāyī as the pāda begins with the sūtra मतुवसीर संबुद्धी छन्दास P. VIII. 3.1.

मतुबर्थिक affix in the sense of मतुप् i. e. in the sense of possession. For these affixes of which इनि (इन्) is very common see the word मतुप्, cf. शैषिकान्मतुवर्थीयाच्छेषिको मतुब-र्थिक;। सरूपः प्रत्ययो नेष्टः सन्नन्तान सनिष्यते॥ . M. Bh. on III. 1.7; V. 2.94.

मतुबर्थीय affix in the sense of मतुष्; see मतुबर्थिक.

मतुङ्लोप elision of the affix मतुष् specially prescribed after words of quality, or words meaning quality, such as गुक्क, कृष्ण which originally mean the white colour, the black colour etc. e. g. गुक्क: पट: cf. गुणवचनेभ्यो मतुषा लुक् P. V. 2.94 Vart. 3.

मतोन्मज्ञा name of a commentary on Kondabhatta's Vaiyākaranabhūṣaṇa written by a grammarian named वनमालिन.

मत्वर्थ sense in which the affix मतु (मतुष्) is affixed; the sense of 'possession' in general; see the word मतुष् above.

मत्वर्थीय an affix which has got the sense of मतु (मतुष्). See the words मतुबर्थिक and मतुबर्थीय above. मध्य lit. middle; middling variety. The word is used in the sense of the middling effort between the open (विवृत) and the close (संवृत) external efforts which technically is called हकार; cf. मध्य हकार: । मध्ये भवः मध्यः । अ सांप्रतिके । तदयमर्थः । सांप्रतिके प्रकृतिस्थे कण्ठे सित हकारो नाम बाह्यः प्रयत्नः कियते । तेन च ब्यञ्जनेषु घोषो जायते । T. Pr. Bhāsya on II.6.

मध्यकोमुदी called also मध्यमकोमुदी a work on grammar which is an abridgment, to a certain extent, of Bhaṭṭojī's Siddhāntakaumudī. The treatise was written by Varadarāja, a pupil of Bhaṭṭojī for facilitating the study of the Siddhānta-kaumudi.

मध्यपतित lit. fallen in the middle; the word is used generally in the sense of an augment which is inserted in the middle of a word. Sometimes an affix too, like अकच् or a conjugational sign like अम् is placed in the middle of a word. Such a middling augment is technically ignored and a word together with it is taken as the original word for grammatical operations; e.g. उच्चक:, नीचक: etc. cf. तन्मध्यपतितस्तद्गहणेन ग्हाते Par. Sek. Pari. 89.

मध्यम (1) the middle person (मध्य-मपुरुष), cf. युष्मद्भपपदे... मध्यम: P. I. 4.105; cf. also Nir. VII. 7; (2) middling tone or effort. cf. मध्यमेन वाक्ययोग: T. Pr. XVIII. where the commentator explains word as उच्चनीचसमाहारविलक्षण: वाक्प्रयोग: I the word मध्यमा is used qualifying in this sense as mode of utterance. वतिः अभ्यासार्थे द्वतां वृत्तिं प्रयोगार्थे तु मध्यमाम् । R. Pr. XIII. 19; cf. also चतुष्कला मध्यमायाम् R. T. 32; (3) one of the seven modes of speech or tones. cf. सत वाचः स्थानानि भवन्ति । उपांशुःवान-निमदोपव्दिमन् मन्द्रमध्यमताराणि T. Pr. XXIII.4 and 5 and also कण्ठे मध्यमम् XVIII.11 where the commentator explains मध्यम as यत्र कण्ठे स्थाने प्रयोग उपलम्यते तन्मध्यमं नाम षष्ठं वाचरस्थानम् । (4) one of the seven musical notes originating or proceeding from the Svarita accent cf. स्वरित-प्रमवा होते षड्जमध्यमपञ्चमाः Pāṇ Śikṣā.

मध्यमकौमुदी (1) name of a treatise on grammar by Rāmasarman; (2) the same as मध्यकौमुदी.

मध्यमपदलोप lit. the dropping of the middle word or member (of a compound generally) as for instance in ज्ञाकपार्थिक for ज्ञाकप्रियपार्थिव: the word मध्यमपदलोप is also used in the sense of a compound. compounds which The the middle word dropped are enumerated by the Varttikakāra under the Vārttika शाकपार्थवा-दीनां मध्यमपदलापश्च Bh. Vr. II.1.60 Vārt.; cf. also Kāt. II.6,30.

मध्यमा or मध्यमत्रृत्ति See मध्यम (2). मध्यासिद्धान्तकोमुदी See मध्यकोमुदी.

मध्येपवाद a rule forming an exception to other general rules being placed between them, one or many of which are placed before and the others afterwards. Such a rule sets aside the previous rules and not the succeeding ones. The statement laying down this dictum is मध्येपवादाः पूर्वान् विधीन् बाधन्ते नीत्तरान् Par. Śek.Pari. 60, also M. Bh. on P.VI.4.148 Vārt. 5.

मध्येपवादन्याय the maxim of the middle rule of exception; see

मध्योदान the acute or udatta accent to the मध्य vowel which is neither the initial (आदि) nor the final one (अन्त) as laid down by the rule उपात्तमं रिति P. VI.1,217; cf. मध्यो- दात्तमपि यमिन्छित तत्र रेफमनुबन्धं करोति M. Bh. on III.1.3.

मध्वादि a class of words headed by the word मञ्ज to which the taddhita affix मत् (मतुप्) is added as a Cāturarthika affix; e. g. मञ्जमान्, विसमान् etc.; cf. Kāś. on P.IV. 2.86.

मन् (1) the affix मिनन् generally found in Vedic Literature added to roots ending in आ and preceded by a noun; e.g. सुदामा, अश्वत्यामा; cf. आतो मिनन् क्रिनिब्बनिपश्च P.III.2.74,75; (2) Uṇādi affix in ओइ; cf. औइ इित उन्देरीणादिके मन्प्रत्येय नलोपो गुणश्च निपाल्यते Kāś. on P. VI.4.29.

मनिन् See मन्.

मनोज्ञादि a class of words headed by the word मनोज, to which the taddhita affix अक (बुज्) is added in the sense of 'nature' or 'duty'; e.g. मानोज्ञकम्, काल्याणकम्, आढ्यकम् etc. cf. Kāś. on P. V. 1.133.

मनोरमा (1) the popular name given to the commentary प्रौडमनोरमा on the Siddhantākaumudī of महोजीदीक्षित by the author himself; the commentary is a scholarly one and very extensive; and its first portion only upto the end of Kāraka is generally read in the Sanskrit Pāthaśālās; (2) name of a commentary on the Madhyasiddhantakaumudī by Rāmasarman; (3) name given to a treatise discussing roots given in the Kātantra Grammar written by रमानाथशर्मा in the sixteenth century. The work is called कातन्त्रधातुवृत्ति also.

मनोरमाकुचमर्दनname given in a bantering tone to the treatise प्राहमनोरमा-खण्डन written by जननाथपण्डित.

भन्तुदेव known also as मन्तुदेव, a famous grammarian of the eighteenth century who has written a commentary named दर्गणा on the Vaiyākaraṇabhūṣaṇasāra of Koṇḍa-

bhatta and a commentary named दांबोद्धण on Nāgeśa's Paribhāṣenduśekhara.

মন্স name given to the Samhita portion of the Veda works especially of the Rgveda and the Yajurveda as different from the Brahmana, Aranyaka and other portions of the two Vedas as also from the other Vedas: cf. मन्त्रशब्द ऋक्शब्दे च यज्ञ:शब्दे च: M. Bh. on P.I. 1.68 Vart. 4. The word मन्त्र occurs several times in the rules of Pānini (cf. P. II. 4. 80, III.2.71, III.3.96, VI. 1. 151, VI.1.210, VI.3.131, VI.4.53, VI. 4.141) and a few times in the Vārttikas. (cf. I. 1. 68 Vārt. 4, IV.3.66 Vart. 5 and VI. 4. 141 Vart. 1). It is, however, doubtful whether the word was used in the limited sense by Panini and Kātyāyana. Later on, the word came to mean any sacred text or even any mystic formula, which was looked upon as sacred. later on, the word came to mean a secret counsel. For details see Goldsuucker's Pāṇini p. 69, Thieme's 'Pāṇini and the Veda' p. 38.

मन्द्र onc of the three places of the origination of articulate speech which is described as situated in the throat; cf. त्रीण मन्द्र मध्यममुत्तमं च । तेषु मन्द्रमुरसि वर्तते Uvvata on R. Pr. XIII. 17; cf. also मन्द्रमध्यमताराणि स्थानानि मवन्ति । T.Pr.XXII.11.

मन्तुदेव See मन्तुदेव.

मप् tad. affix म always added to the krt. affix त्रि (क्रि) prescribed after roots characterized by the mute syllable डु; e.g. क्रुतिमम्, पित्रमम् etc. क्रिमेम्रित्यम् P.IV. 4.20.

मय् abbreviated term or pratyahara for all the consonants of the five classes or Vargas excepting thes consonant ज़; cf. मय उन्ना वा वा P.VIII.3.33.

मय tad. affix मयट् (1) in the sense of proceeding therefrom (तत आगत: P. IV.3.92) added to words showing cause or meaning human being; e.g. सममयम्, देवदत्तमयम्; (2) in the sense of product(विकार)or part(अवयव) added optionally with अण to any word, e.g. असमयम्, आश्मनम् मूर्वामयम् मॉर्वम्, and necessarily to words beginning with आ, ए and औ, words of the class headed by word शर and the words की, पिष्ट, बीहि, तिल and some others; cf. P. IV. 3. 143-150; (3) in the sense of proportion, added to a numeral; e. g. द्विसयमदिश्वद्यवानाम् ; cf. P. V. 2.47; (4) in the sense of 'made up of 'added to the thing of which there is a large quantity; e.g. अन्नमयम्, अपूपमयम्cf;तलकृतवचने मयट्P.V.4.21,22.

मयद् see मय.

मयूरव्यंसकादि a class of compounds of the type of मयूरव्यंसक which are somewhat irregular formations and hence mentioned as they are found in use. The compounds are called simple tatpurusa compounds; e.g. मयूरव्यंसक: इस्तेयहा, एहिएचम, उच्चावचम, खादतमोदता etc.; cf. मयूरव्यंसकादयक्ष P.II.1.72.

मरीस tad. affix मरीसच् 'added to the word अवि in the sense of milk; e.g. अविमरीसम्; cf. अवेर्दुन्धे सोढदूसमरीसच: P. V. 2.36 Vart. 5.

माञ्चिनाय a reputed commentator on many classical poetic and dramatic works, who flourished in the fourteenth century. He was a scholar of Grammar and is believed to have written a commentary on the Sabdendusekhara and another named न्यासोद्योत on the न्यास of जिनेन्द्रबुद्धि.

म्बा personal ending म substituted

for अम् in Vedic Literature; e.g. वर्षा वृत्रम्; cf. अमो मश् P. VII. 1.40; See म.

मस् personal ending of the first person (उत्तमपुरुष) plural; e. g. भवाम:, कुर्म:; cf. तिप्तरिझसिप्o III. 4.78.

मिस personal ending formed by adding इ to मस् of the 1st person (उत्तमपुरुष) pl. in Vedic Literature दीपयामिस, भजयामिस, cf. Kāś. on इदन्ती मिस P.VII.1.46.

महादेव a grammarian of the Kātantra school who has written a gloss on the कातन्त्रज्ञति of दुर्गसिंह.

महानन्द् a grammarian of the eighteenth century who has written a gloss on Kondabhatta's Vaiyākaraņabhūsanasāra.

महान्यास name of a commentary on the Kāśikāvivaranapanjikā (popularly named Nyāsa), mentioned by Ujjvaladatta in his Unādisūtravṛtti.

महात्राण lit. hard breathing, aspirate characteristic (बाह्मयहन) of consonants possessed by the second and fourth consonants of the five classes, and the sibilants হা, ঘ and स which letters are also called महात्राण on that account.

महाभाष्य lit. the great commentary. The word is uniformly used by commentators and classical Sanskrit writers for the reputed commentary on Pāṇīni's Sūtras and the Varttikas thereon by Patanjali in the 2nd century B. C. commentary is very scholarly yet very simple in style, and exhaustive although omitting a number of Panini's rules. It is the first and oldest existing commentary on the Astādhyāyī of Pānīni, and, in spite of some other commentaries and glosses and other compendia, written later on to explain the

Sūtras of Pānīni, it has remained supremely authoritative and furnishes the last and final word in all places of doubt; cf. the remarks इति भाष्ये स्थितम्, इत्युक्तं भाष्ये, इत्युक्तमाकरे etc. scattered here and there in several Vyākaraņa treatises forming, in fact, the patent words used by commentators when they finish any chain of arguments. commenting on the Sutras of Pāṇīni, Patanjali, the author, has raised many other grammatical issues and after discussing them fully and thoroughly, given his conclusions which have become the final dicta in those matters. The work, in short, has become an encyclopaedic one and hence aptly called खनि or आकर. work is spread over such a wide field of grammatical studies that not a single grammatical issue appears to have been left out. The author appears to have made a close study of the method and explanations of the Sūtras of Pāṇīni given at various academies all over the country and incorporated the gist of those studies given in the form of Varttikas at the various places, in his great work. He has thoroughly scrutinized and commented upon the Vārttikas many of which he has approved, some of which he has rejected, and a few of which he has supplemented. Besides the Vārttikas which are referred to above, he has quoted stanzas which verily sum up the arguments in explanation of the difficult sutras, composed by his predecessors. There is a good reason to believe that there were small glosses or commentaries on the Sūtras of Pānīni, written by learned teachers at the various

academies, and the Varttikas formed in a way, a short pithy summary of those glosses or Vittis. explanation of the word वृत्ती साध वार्तिकम given by Kaiyata may be quoted in support of this point. Kaiyata has at one place even stated that the argument of the Bhāsyakāra is in consonance with that of Kuni, his predecessor. The work is divided into eightyfive sections which are given the name of lesson or আह्निक by the author, probably because they form the subject matter of one day's study each, if the student has already made a thorough study of the subject and is very sharp in intelligence. cf. अह्ना निर्वृत्तम् आह्निकम्, (the explanation given by the commentations). Many commentary works were written on this magnum opus of Patanjali during the long period of twenty centuries upto this time under the names टीका टिप्पणी, दीपिका, प्रकाशिका, रत्नावली, स्क्रातिं, वात्ते, प्रदीप, व्याख्यान and the like, but only one of them the 'Pradipa' of कैयटा-पाध्याय, is found complete. learned commentary by Bhartrhari, written a few centuries before the Pradipa, is available only in a fragment and that too, in a manuscript form copied down from the original one from time to time by the scribes very carelessly. Two other commentaries which comparatively modern, written by Narayanasesa and Nilakantha are available but they are also incomplete and in a manuscript form. Possibly Kaiyatabhatta's Pradipa threw into the background the commentaries of his predecessors and no grammarian after Kaiyata dared write a commentary superior to Kaiyata's Pradipa or, if he

began, he had to abandon his work in the middle. The commentary of Kaiyata is such a scholarly one and so written to the point, that later commentators have almost identified the original Bhāṣya with the commentary Pradīpa and many a time expressed the two words Bhaṣya and Kaiyaṭa in the same breath as भाष्यकैयटयो: (एतदुक्तम् or स्पष्टमेतत्).

महाभाष्यदीपिका a very learned old commentary on the Mahābhāsya of Patanjali written by the reputed grammarian Bhartthari or Hari in the seventh century A. D. The commentary has got only one manuscript preserved in Germany available at present, of which photostat copies or ordinary copies are found here and The first page of the manuscript is missing and it is incomplete also, the commentary not going beyond the first seven Ahnikas. For details see page 383 Vol. VII Vyākaraņa Mahābhāsya D. E. Society's edition.

महाभाष्यप्रदीप a very scholarly commentary on Patanjali's Mahabhasya written by Kaiyatabhatta in the eleventh century. The commentary has so nicely explained every difficult and obscure point in the Mahābhāsya, and has so thoroughly explained each sentence that the remark of later grammarians that the torch of the Mahabhasya has been kept burning by the Pradipa appears quite apt and justified. Kaiyata's commentary has thrown much additional light on the original arguments and statements in the There is a learned Mahābhāsya. commentary on the Pradipa written by Nagesabhatta which is named 'vivaraṇa' by the author but which is well known by the name 'Uddyota' among students and teachers of Vyākaraṇa. For details see pp. 389, 390 Vol VII, Pātañjala Mahābhāṣya, D. E. Society's Edition.

महाभाष्यप्रदीपटीका name given to each of the various commentaries on the Pradīpa of Kaiyaṭa written by grammarians, out of which the commentaries of चिन्तामणि, रामचन्द्रसरस्वती, नारायण, नित्यानन्दपर्वतीय and one or two more are available in a manuscript form and those too quite incomplete.

महाभाष्यप्रदीपप्रकाश called also कैयटप्रकाश, name of the commentary on the Pradipa of Kaiyaṭa by Nīlan-kaṇṭhamakhī a versatile writer of the 17th century.

महाभाष्यप्रदीपविवरण (1) original name of the learned commentary on the 'Pradīpa' of Kaiyata written by Nāgesabhaṭṭa, a stalwart and epoch-making grammarian of the 18th century. The commentary is known popularly by the name 'Uddyota' or Pradīpoddyota; (2) name of the commentary on Kaiyaṭa's Pradīpa by Nityānanda Parvatīya. The commentary is also known by the name दोपत्रमा.

महाभाष्यसञ्ज्ञाति name given to the short gloss on the Mahābhāṣya written by the famous eastern grammar-scholar Maitreya-Rakṣita of the twelfth century.

महाभाष्यव्याख्या name given to each of the explanatory glosses on the Mahābhāṣya written by grammarians prominent of whom were Puruṣottamadeva, Nārāyaṇa Seṣa, Viṣṇu, Nīlakaṇtha and others whese fragmentary works exist in a manuscript form. महामिश्र name of a grammarian who wrote a commentary on Jinen-drabuddhi's Nyāsa. The commentary is known by the name Vyākaraṇaprakāśa.

महाविभाषा a rule laying down an option for several rules in a topic by being present in every rule; cf. महाविभाषया वाक्यमपि. विभाषा (P.II.1.11) and समर्थानां प्रथमादा (P. IV.1.82) are some of the rules of this kind.

महासंज्ञा a long term, as contrasted with the very short terms हि, घु, इत and others introduced by Panini in his grammar the sake of brevity. These long terms such सर्वनाम. as परस्मैपद, आत्मनेपद, and many others were widely in use at the time of Pāṇini and hence he could not but pick them up in his grammar in spite of his strenuous attempts at brevity. The commentators, however, find out a motive for his doing this viz. that appropriate words only could be understood by those terms and not others; cf. महासंज्ञाकरणेन तदनुगुणानामेव अत्र संनिवेशात् । S. K. on सर्वांद्यीन सर्वनामानि P. I.1.27.

माहिङ् personal ending of the Atmanepada first person (उत्तमपुरुष) plural; cf. तितरिज्ञ ... बिह्महिङ् P. III.4.78.

महिष्यादि a class of words headed by the word महिषी to which the tad. affix अ (अण्) is added in the sense of 'proper for' (धम्यम्); e.g. माहिषम् पौरोहितम् , हौत्रम्; cf. Kāś. on P.IV. 4. 48.

महोधर a grammarian of the sixteenth century who, besides many small treatises on other subjects, wrote a commentary on the Sārasvata-Prakriyā Vyākaraņa.

महेशनन्दिन् a Jain Grammarian who has written a work on the kāraka topic of grammar, named षट्कारक.

माञ्चन्य name of an ancient writer of Prātišākhya works mentioned in the Rk Prātišākhya; cf. R. Pr. I.2.

माचाकीय an ancient writer of Prātisākhya work, who is quoted in the Taittirīya Prātiśākhya as one, holding the view that a and व preceded by अ and followed by उ and ओ respectively, are dropped provided they stand at the beginning of a Pada (word). माचाकीय, who belonged to the Yajurveda school, is said to have held this view which is generally held by the followers of the Rgveda; cf. उकारीकारपरी छुप्येते माचा-कीयस्य (T. Pr. X.29) on which the commentator adds बहुवृचानामयं पक्ष:.

माणिक्यदेव a Jain writer who has written a gloss on the Unadisūtras consisting of ten chapters popularly called उणादिसत्रदशपदी.

माण्ड्रकेय name of an ancient writer of a Prātiśāhhya work referred to in the Rk Prātiśākhya, cf. R.Pr.I.2.

मातृकाचर्ण letters of the alphabet. See अक्षरसमाम्राय.

मात्रच् a tad. affix in the sense of measure applied optionally with इयस and दन्न to a noun; e.g. ऊरमात्रम् प्रस्थमात्रम्; cf. प्रमाणे इयसज्दन्नञ्मात्रचः P. V.2.37 and Kāśikā thereon which remarks that इयस and दन्न are applied in the sense of height, while मात्र is applied in the sense of any measure; cf. प्रथमश्च द्वितीयश्च ऊर्ध्वमाने मतौ मम Kāś. on P. V.2.37.

मात्रा (1) measure, quantity; cf. भवति हि तत्र या च यावती च अर्थमात्रा M. Bh. on P.I.2.45 and II.1.1; (2) mora, prosodial unit of one instant i.e. the length of time required to pronounce a short vowel; cf. भूयद्धी मात्रा इवर्णोवर्णयोः, अल्पीयसी अवर्णस्य, M. Bh. on I.1.48 Vart. 4; cf. मात्रा हस्वस्तावद-वप्रहान्तरं, द्वे दीर्घः, तिखः प्छुत उच्यते स्वरः 284

R. Pr.I.16; cf. also R. Pr. I.34, Г. Pr.I.37, V.Pr.I.59, R.T.28; also cf. अर्घमात्राट्यवेन पुत्रोत्सवं मन्यन्ते वैयाकरणाः Par. Sek. Pari. 132. The instant is taken to be equal to the throbbing of the eye, or a flash of lightning, or a note of a wood-cock.

মাঘৰ the well-known epoch-making scholar of the 14th century who has written a number of treatises in various Sastras. His খাৱুলুবি is a well-known work in grammar.

माधवीया-धातुवृत्ति a learned gloss on the धातुपाट of Pāṇini by माधव. See माधव.

माध्रीवृद्धि a gloss not composed by, but simply explained by an inhabitant of Mathurā or Madhurā. Such a gloss is referred to in the Mahābhāṣya on P.IV.3.101 Vārt.3, which possibly might be referring to an existing gloss on the Sūtras of Pāṇini, which was being explained at Mathurā, at the time of Patañjali. The term मध्रा was used for मध्रा in ancient times and the word माध्रा वृत्ति is also used for माध्रा वृत्ति.

मान krt affix आन of the present participle with the augment म् prefixed to it by आने मुक् P.VII.2.82; e. g. यजमान:, एधमान:, याचमान: etc.

मार्कण्डेय an old grammarian, who wrote a grammar of Prākṛta languages which is known by the name प्राकृतसर्वस्य.

माद्व softness of the voice characterizing the pronunciation of a grave vowel; cf. मार्दवं स्वरस्य मृदुता रिनग्वता; also cf. अन्ववसर्गों मार्दवमुख्ता खस्येति - नीचैःकराणि शब्दस्य M.Bh. on P.I.2. 29, 30; cf. also, T. Pr. XXII.10.

मান্তা a variety of the utterance of the Veda-Samhita (ব্ৰুখাত); a kind of Krama-Pātha, one of the eight artificial recitations.

माहेन्द्र name of a very ancient, pre-Pāṇinian grammar ascribed to इन्द्र of which some references only are available. The grammar work is also referred to as ऐन्द्र; cf. यान्युज्जहार महेन्द्राद् व्यासो व्याकरणार्णवात् । पदरत्नानि किं तानि सन्ति पाणिनिगोष्पदे Devabodha's com. on the Mahābhārata. For details see p. 124-27 Vol. VII Mahābhāṣya, D. E. Society's Edition.

माहेशसूत्र the fourteen sūtras अइउण्, क्लुक् etc. which are believed to have been composed by Siva and taught to Pāṇini, by means of the sounds of the drum beaten at the end of the dance; cf. न्तावसाने नट-राजराजा ननाद दक्कां नवपञ्चवारम् । उद्धर्तुकामः सनकादिसिद्धानेतद्दिमशैं शिवसूत्रजालम् Nandikesvara-kārīkā 1. For details see Vol. VII Vyākaraņa Mahābhāsya, D. E. Society's edition.

मাই স্বাধ্য the Sūtras, the authorship of which is attributed to Siva; the sūtras সহত্য etc. giving the alphabet. See মাইহানুয়.

मि (भिप्) personal ending of the first person (उत्तमपुरुष) singular; cf. तिप्तरिझ॰ P.III.4.78.

iभेत (1) characterized by the mute letter म्; augments so characterized such as नुम्, अम् and the like, are inserted after the last vowel of a word to which they are to be added; cf. मिदचोन्त्यात् पर: P. I. 1.47; (2) a technical term applied to the fifty-five roots which are headed by the root बर् and which belong to the first conjugation, to the roots ভৰন্ত etc., as also to the roots जन, जू, कम्, रञ्ज् and roots ending in अम्. These roots are not really characterized by the mute letter 习, but they are given the designation मित्. The use of the designation भित् is (a) the shortening of the penultimate vowel which has been lengthened by Vṛddhi before the causal sign जि, and (b) the optional lengthening of the penultimate vowel before the affix चिण् and णमुल्. For a complete list of 'mit' roots see Dhātupātha.

मितवृत्यर्थसंग्रह name of a grammatical work on the Sutras of Panini by Udayana.

मिताक्षरा name of a commentary on the Sārasvatasāra, written by Harideva.

मिन् tad. affix in the sense of possession added to the word गो; e.g. गोमिन्, cf. ज्योत्झातमिस्रा...गोमिन्मलिन-मलीमसा: P.V.2.114.

मिप् personal ending मि of the first person (उत्तमपुरुष) sing. Parasmai. pada; cf. तिप्तरिज्ञ...महिङ् P. III.4.78.

मिश्र roots taking personal endings of both the Padas; Ubhayapadin roots; this term মিশ্ব is given in Bopadeva's grammar.

मिश्री a popular name given to the commentary written by भैरवामेश्र on the Paribhāṣenduśekhara in popular use by grammarians.

मीय tad. affix मीय along with म (मण्) applied to the word मध्य in the sense of a case-affix (locative case-affix) e.g. मध्यमीय; cf. मण्मीयौ च प्रत्ययौ वक्तज्यों Kāś. on P. IV.3.60.

मुक् augment म् prefixed to the affix आन (i.e. शानच्, चानश्, and शानन्) of the pres. part. Atmanepada; e. g. एधमानः, वर्धमानः पवमानः, यजमानः, etc.; cf. आने मुक् P. VII. 2. 82. See मान.

मुख aperture of the mouth; the main place of the utterance of a letter.

मुखनासिकावचन definition of अनुनासिक, a letter which is pronounced through both—the mouth and the nose—as contrasted with नाशिक्य a letter which is uttered only through the nose; e.g. ङ्, ज्,ण्,न्,म् and the nasalized vowels and nasalized यु, व् and लु; cf. मुखनासि-कावचनोऽनुनासिक: Pān. I. 1.8; cf. also अनुस्वारोत्तमा अनुनासिकाः (T. Pr. II.30), where the fifth letters and the anusvāra are called anunāsika. According to Bhattoii, however, anusvāra cannot be anunāsika as it is pronounced through the nose alone, and not through both—the mouth and the nose. As the anusvāra is pronounced something like a nasalized ग according to the Taittirīyas it is called a consonant in the Taittirīya Prātisākhya; cf. अनुस्वारोप्युत्तमनद्यञ्जनमेव असम्ब्छाखायाम् । अर्धगकाररूपत्वात् । Com. on T. Pr. II. 30.

मुखसुखार्थ a mute letter added to an affix or a substitute or the like, which does not really form a part of the affix etc., but which simply facilitates the utterance of it; cf. अथ मुखसुखार्थस्तकारः दकारोपि । M. Bh. on I.1.1, VI.1.87; cf. also आदिति तकारो मुखसुखार्थः, न त्वयं तपरः Kas. on P. III.2.171.

मुख्य main, principal, primary substantive as contrasted with a qualifying substantive; cf. गौणमुख्ययो-मुख्ये कार्यसंत्रत्ययः Par. Sek. Pari. 15.

मुख्यविशेष्य the principal word in a sentence which comes last in the technical expression of the import or शान्दवीय. It is described as primary and not subordinated to any other thing (अन्याविशेषणीमून). This मुख्यविशेष्य is, in a way, the crucial point in the various theories of import; e.g. according to the grammarians the verbal activity is the principal word while, according to the Mimainsakas the bhavana is the principal word and according

ing to the Naiyayikas it is the subject that is the principal word. मृग्धबोध lit. instructions to the ignorant; a treatise on grammar similar to the Astādhyāyî of Pāṇini but much shorter, written by Bopadeva or Vopadeva an inhabitant of the greater Mahārāstra in the Vardha district, in the thirteenth century. After the fall of the Hindu rulers in Bengal, treatises like माषाग्रांचे and others written by eastern grommarians fell into the back-ground and their place was taken up by easier treatises written by Bopadeva and others. Many commentaries were written upon the Mugdhabodha, of which the Vidyānivāsa is much known to grammarians.

मुख्योधटीका a commentary work on Mugdhabodha; the name is given to commentaries written by Rāmatarkavāgīśa (called मुख्योधपरिशिष्ट), by Rādhāvallabha (called सुवोधिनी), by Gangādhara (called सेतुसंग्रह), by Durgādāsa, by Dayārāma and by Rāmānanda.

मुस्त the substitution of सु for the syllable beginning with द in certain cases; cf. अदसोसेदांदु दो म: P. VIII.2. 80.

मुद् a technical term for the sibilants श्, ष् and स् given in the Vājasaneyi-Prātišākhya; cf. मुच V. Pr. I.52, cf. also V. Pr. III.9, III.13,IV. 122.

मुनिश्रय the popular and honorific term for the three prominent grammarians of the Pāṇinian system of grammar viz. पाणिनि, कात्यायन and पतञ्जलि who were the pioneers of 'hat system; cf. मुनिश्रयं नमस्कृत्य Siddhānta-Kaumudī beginning.

सुम् the augment म inserted immediately after the final vowel of the

word for which it is prescribed; cf. अरुद्धिंबदजन्तस्य मुम् P.VI.3.67; cf. also P.III.2.26, V. 4.7 and VI.3.69-72.

मूर्घन the top of the orifice of the mouth; the place of utterance (स्थान) of the letters ऋ, ऋ, ट्, ट्, इ इ and ण्, र् and ष्; cf. ऋदुरणणं सूर्घा S. K. on P. I. 1.9; cf. also षटी सूर्घनि V.Pr.I.67,R.T.6,R.Pr.I.19, and T.Pr. II.37 where र appears excluded.

मूर्धन्य letters pronounced at the place called मूर्धन्; cerebral or lingual letters, the letters क, ऋ,ट्,ठ्,ड्,ड्,ड्, ण्.

मूळ (1) the root of the teeth given as the place of origin for the letter र in the Rk Tantra; cf. रेफरतु दन्त्या दन्तमूले वा. R. T. 8; (2) the main instrument of the utterance of letters known as मूलकरण or अनुप्रदान.

मুক্তমহানি the original base of the word used in language; the root and the prātipadika; the word থ্যমূহনি is also used in the same sense.

स्त the crude base of a declinable word; the prātipadika; the term is found used in the Jainendra Vyākaraṇa; cf. Jain. Vyāk. I..1.5.

मृद् (1) soft in utterance; the term is used in the Vājasaneyi Prātiśākhya for the क्षेत्र, प्रश्लिष्ट, तैरोब्यञ्जन, and पादवत्त varieties of the circumflex accent (स्वरित) out of which the पादवत is the softest (मृद्तम) and consequently always called मृद्, while the others are called मृद् only with respect to the preceding one in the order given above; viz अभिनिहत, क्षेप्र etc.cf.सर्वेतीक्ष्णोभिनिहतः,प्राश्वष्टस्तदनन्तरम्। ततो मृद्तरौ स्वौरा जात्यक्षेत्रावुमी स्मृतौ॥ ततो मृद्तर: स्वारस्तैरोव्यञ्जन उच्यते । पादवृत्तो मृदुतमस्त्वेतत्स्वारबलाबलम् Uvvata on V. Pr. I.125; (2) soft, as opposed to hard; the term is used in connection with the first, third and fifth consonants of the five classes.

मॅक्डोनेल [MACDONELL,ARTHUR ANTHONY] a deep scholar of Vedic Gram. and Literature who has written an exhaustive Vedic Grammar; in treatment, at places he differs from Pāṇini and follows a different method, but the manner of thinking and argument is on original lines.

मेघविजय a Jain grammarian of the seventeenth century who has written a grammar work, similar to the Siddhānta Kaumudī, on the Sabdānuśāsana of Hemacandra. The grammar work is called हैमकौमदी, or चन्द्रप्रभा also.

मैत्रायणीय प्रातिशाख्य a Prātisākhya or Pārṣada work giving the peculiarities of Sandhi, accent and the like, in changing the Maitrāyanīya-Samhitāpāṭha into the Padapāṭha.

मैत्रेयरक्षित a recognised scholar of Pāniniś grammar who belonged to the Eastern part of India and flourished in the beginning of the twelfth century. As it appears from the name Maitreya Raksita he appears to have been a Buddhist grammarian. Subsequent writers in their works refer to him by the name Raksita alone, as also by the name Maitreya, but very rarely by the name Maitreya Raksita. He wrote many works on grammar of which the 'tantrapradipa' a learned commentary on Jinendrabuddhi's Nyāsa on Kāśikā was a reputed one, which, although available in a fragmentary manuform today, has been script profusely quoted by prominent grammarians after him.

मोक्षेत्रकर a grammarian of the fourteenth century who has written a commentary on the Kātantra Vṛṭṭi of Durgasimha. He has written a commentary on the Akhyātavṛtti of the Kātantra school as also a short treatise dealing with the kṛt affixes called Kṛdvṛtti.

म्लेच्छ (I) a word although correct, yet looked upon as incorrect owing to its faulty utterance; (2) a person like the uncultured people, who is not able to pronounce words correctly; cf. म्लेच्छा मा भूमेत्याचेय च्याकरणम् M. Bh. I. 1, Ahnika 1.

य

य (1) a consonant of the palatal class, called semivowel or अन्तःस्थ (spelt as अन्तस्थ also), possessed of the properties संवृतत्व, नाद, घोष and अनुनासिकत्व in addition: (2) a substitute for म when that म is followed by ह which is followed by यु. e. g. कियुँहाः; cf. यवलपरे यवला वा. P. VIII. 3. 26 Vārt.1; (3) य looked upon as possessed of a very little effort in production i. e. which appears as almost dropped but not completely dropped when its elision is prescribed at the end of a word. e. g. भोयू अच्युत; cf. ब्योर्लघुप्रयत्नतर: शाकटायनस्य P. VIII. 3.18.

य (1) the consonant य with अ added to it merely for the sake of facility in pronunciation; यकार is used in the same sense; e. g. ਲਿਟਿ वयो यः; P.VI.1.38 cf. T.Pr.I; 17.21: (2) kṛt affix (यत्) prescribed as कृत्य or potential passive participle; e.g. चेवम्, गेयम्, राप्यम् , राभ्यम् , गद्यम् , अजर्यम् पण्यम् etc.; cf. अचो यत्...अजर्ये संगतम् P. III. 1.97-105; (3) krt. affix क्यप which is also an affix called kṛtya; e. g. ब्रह्मोद्यम् , भान्यम् , धात्यम् , स्तुत्यम् , कल्प्यम्, खेयम्, भृत्यः, भिद्यः, पुष्यः, कृत्यम् also कार्यम् ; cf. P. III. 1.106-123; (4) krt affix ण्यत (which is also कृत्य), e. g. कार्यम्, हार्यम्, वाक्यम्, लान्यम् , कुण्डपाय्यम् , etc.; cf. P. III.

1.124-132; (5) tad. affix 4 affixed (a) in the sense of collection to पाश, वात etc., as also to खल, गो and रथ, e. g. पास्या, रथ्या etc.; cf. P. IV. 2. 49, 50; (b) in the चातुरार्थिक senses to बल, कुल, तुल etc. e. g. बल्य:, कुल्यम्: cf. P. IV. 2. 80, (c) as a Saīṣīka tad. affix to प्राम along with the affix खञ् e.g. ग्राम्यः, ग्रामीणः; cf. P. [V. 2.94; (d) in the sense of 'good therein ' (तत्र साधुः) and stated senses affixed to समा, सादर, पूर्व, and सोम; e. g. सभ्य:, पूर्व्य:; etc. cf. P. IV. 4.105, 109, 133, 137, 138; (e) in the sense of 'deserving it' to दण्ड and other words, e. g. दण्ड्य, अर्ध्य, मेच्य, मेच्य, etc.; cf. P. V. 1.66; (f) in the sense of quality or action to सखि e.g. संख्यम ; cf. P. V. 1.126; (6) tad. affix यत् applied to (a) राजन् श्वशुर, कुल, मनु in the sense of offspring, (b) शूल, उखा, वायु, ऋतु and others, under certain conditions; cf. P. IV. 2.17, 31, 32, 101. (c) to अर्ध, परार्घ, words in the class headed by दिश, छन्दस् and others in specific senses; cf. P. IV. 3-46, 54 etc. and (d) in specific senses to specific words mentioned here and there in a number of sūtras from IV.4. 75 to V.4.25; (e) to शाखा, मुख, जवन and others in the sense of হ্ব (similar to) e.g. হাাভ্য:, मुख्य:, etc.: cf. P. V. 3. 103; (7) case-ending य substituted for के of the dative sing; e.g. रामाय ef. P. VII. 3.102; (8) verb-affix ব্যু applied to the nouns কডু and others to make them (denominative) roots; e. g. कण्डूय,मन्त्य etc. cf. कण्डवादिभ्यो यक P. III. 1.27; (9) Vikarana य (यक्) applied to any root before the Sārvadhātuka personal endings to form the base for the passive voice as also the base for the 'Karmakartari' voice e. g. क्रियते, भूयते, cf. सार्वधातुके यक् P.

III. 1.67; (10) Uṇādi affix य (यक) applied to the root हन to form the Vedic word अद्भ्य; cf. अद्भ्यादयश्च: (11) augment य (यक्) added to the affix क्वा in Vedic Literature; e. g. दत्त्वाय: cf. क्लो यक P. VII.1.47: (12) verb affix यङ added to a root to form its Intensive base (which sometimes is dropped) and the root is doubled. e. g. चेकीयते, चर्करीति; cf. P. III. 1.22,24; (13) short term (प्रत्याहार) supposed to be beginning with य in the affix यङ in the sūtra धातोरेकाचो ... यङ् III. 1.22, and ending with ভ in the sutra ভিত্তথা-হিছ্যুভ III. 1.86, with a view to include the various verb affixes and conjugational signs.

यक् the affix य; see य (8), (9), (10) and (11) above.

यक्षवमेन author of the commentary called चिन्तामणि on the Śabdānuśāsana of Śakaṭāyana.

यङ् see य (12) and (13) above.

यङ्गल a secondary root formed by adding the affix यङ् in the sense of repetition and intensity, to roots having one syllable and beginning with a consonant; cf. घातोरेकाचा हलांद: कियासमाभिहारे यङ् P. III. 1.22, 23,24. See य (12) above.

যজ্নুনন a secondary root formed by adding the affix বহু to roots specified in P. III. 1.22,23,24, which affix is sometimes dropped; cf. বজাৰি ব; P. II. 4. 74. The yanluganta roots take the parasmaipada personal endings and not the ātmanepada ones which are applied to yananta roots.

यङ्ख्रगन्तशिरोमाणि a grammar work dealing with the frequentative roots written by Pandita Sesakisna.

यजादि roots headed by the root यज् which take the samprasāraņa substitute for their semivowel before terminations marked with the mute letter क्; e.g. इज्यते, इप्टि: cf. विचित्विपियजादीनां किति P.VI.1.15. These roots are nine in number, यज्, वप्, वर्, वस् and others which are of the first conjugation given by Pāṇini in his Dhātupaṭha at the end of the roots of the first conjugation.

यञ् (1) short term (प्रत्याहार) formed by the letter य of ह्यवरट् and the mute letter সূ of স্নাস্ including semi-vowels and the third and the fourth consonants excepting घु, दू and ঘু of the five consonant groups; cf. अतो दीर्घी यात्र P. VII. 3. 101; (2) tad. affix added (a) in the sense of गोत्र (grand-children and their descendants) to words of the गर्ग class and some other words under specific conditions, e.g. गार्थ: वात्स्यः, काप्यः etc., cf. गर्गादिभ्यो यत्र and the following P.IV. 1. 105-108; (b) in the sense of collection to केदार, गाणिका, केश and अध, cf. P.IV.2.40 and the Varttika thereon and IV. 2.48; (c) in the Saisīka senses to the word द्वीप, cf. P.IV.3.10; (d) to the word कंसीय e. g. कांस्यम् cf. P.IV.3,168, and (e) to the words अभिजित्, विदम्त् and others when they have the tad. affix अण् added to them e.g. आभिजित्यः cf. P. V. 3. 118.

यण a brief term for letters य, व्, र् and छ i.e. the semi-vowels; cf. इको यणान्द P. VI. 1.77; cf. also I. 1.45 and VI. 4.81.

यण्वत् containing a semi-vowel inside it; cf. संयोगादेरातो धातोर्यण्वतः P. VIII. 2.43.

यत् see य (6).

यस्त (1) effort in the utterance of a letter; the word which is generally used for such an effort is प्रयत्न. This effort is described to be of two kinds आम्यन्तर internal i.e. below the root of the tongue and बाह्य above the root of the tongue i.e. inside the mouth; cf. यत्नो द्विघा। आम्यन्तरो बाह्यश्च। S. K. on P. I. 1.9; (2) specific effort, by adding a word to a rule for drawing some inference, with a view to removing some technical difficulty; cf. तेन पयो घावती-त्यादो यत्नान्तरमास्थेयम् Kāś. on P. VIII. 2. 25. The phrase कर्तव्योत्र यत्नः often occurs in the Mahābhāṣya.

यहमकरण lit. the topic or the section of यत; the section where the tad. affix यत is prescribed. This tad. affix यत is prescribed in the fifth adhyāya of Pāṇini in a number of rules in different and different senses; cf. यहमकरणे रथाच P.V. 1.6 Vārt.1; यहमकरणे महावर्चसाच्च P.V.1.39 Vārt. 1.

यथागृहीतं as they are actually found in Vedic recital with some irregularties of euphonic changes, lengthening of the vowel and the like. Specimens of such phrases are given in R.Pr.II.33 to 39.

यश्रान्यासं as it is actually put in the rule or a treatise by the author. The phrase is often used in the Mahābhāṣya when after a long discussion, involving further and further difficulties, the author reverts to the original stand and defends the writing of the sūtra as it stands. सिस्यत्येवमपाणिनीयं तु मनति or स्त्रं भिद्यते । तिईं यथान्यासमेवास्तु is the usual expression found in the Mahābhāṣya; cf, M.Bh. I.1. Āhnika 1, I.1.1, 9, 20, 62, 65 etc.

यथालक्षणं as formed according to rules. The phrase यथालक्षगमप्रयुक्ते is very often found in the Mahā-bhāṣya as a general guiding remark that noun-forms or wordforms which are not found in use in the language of the people or in literature should be understood

as they are derived by observing all the rules that are applicable.

यथानत् as it is in the original Samhitāpāṭha without any change of accent, etc. when cited in the Padapāṭha; the word अन्ययनत् (not allowing any change or reduction) is given by Uvvaṭa in explanation of यथानत; cf. हरयते पदं यथानत् R. Pr. XI.31.

यथाश्रुतार्थग्राहिन one who grasps the sense as given by the actual wording without going into details re: the use or application etc.; cf. यथाश्रुतग्राहिप्रतिपत्त्रपेक्षोयं यथोदेशपक्षः इति कैयटः Par. Sek. Pari. 2.

यथासंख्ये in respective order, the first for the first, the second for the second, and so on; when the number of subjects and predicates is the same, they should be connected in the respective order; cf. यथासंख्यमनदेश: समानाम P.I.3.10.

यथोदेश (परिभाषा) a short phrase or term for the Paribhāṣā or guiding statement यथोदेशं संज्ञापरिभाषम्: 'technical terms and Paribhāṣās are to be interpreted at the place where they are stated, and not at the place or places of their application or utility.'

यदागम (परिभाषा) short familiar wording for the dictum or Paribhāṣā 'यदागमास्तद्गुणीभूतास्तद्ग्रहणेन रह्मन्ते।' Par. Sek. Pari. 11.

यहच्छाशब्द lit. a chance-word; Samjñā-śabda or proper noun which is given accidentally without any attention to derivation or authority; cf. अयं तर्हि यहच्छाशब्दोऽपरिहायै:। स्वित्र: स्विप्टेंड: M. Bh.on Siva Sūtra 2.

यद्योग a connection with the word (pronoun) यत् by its use in the same sentence and context, which prevents the anudatta (grave) accent for the verb in the sentence; cf. निपातैर्यदादिहन्तकु विने चेचण्कचिद्यत्रयुक्तम् P. VIII. 1.30; cf. also the usual expression यद्योगादानिघात: found in commentary works.

यह त lit. a word formed from यत्; a word which contains the pronoun यत् in it which prevents sarvānudātta for a verb which follows; cf. यदिसम्बर्तते यद्भत्तम् M. Bh. on P. VIII. 1.66; cf. also यद्भत्तापपदाच V. Pr. VI. 14, where Uvvaṭa explains यद्भ त as यदो वृत्तं यद्भृतं सर्विभित्तयन्तं सर्वप्रत्यान्तं च ग्हान्ते । V. Pr. VI. 14 com.

यम् a short term (प्रत्याहार) for the consonants which begin with य् (in इयवरट्) and end (in जमङ्गनम्) before the mute म् i.e. all semivowels, and fifth consonants of the five classes; cf. हलो यमां यमि लोप: Pān. VIII.4.64.

यम (1) one of a pair, a twin letter available in pronunciation before a nasal letter and similar to it, when the nasal consonant is preceded by any one of the four consonants of the five classes; a transitional sound intervening between a non-nasal and the following nasal as a counterpart of the non-nasal; cf. वर्गेष्वाद्यानां चतर्णी पञ्चमे परे मध्ये यमो नाम पूर्वसहशो वर्णः प्रातिशाख्ये प्रसिद्ध: S.K. on P.VIII. 1.1; given to the seven (2) name notes, found in musical singing of Saman; cf. मन्द्रमध्यमतारा-ख्येषु त्रिषु वाचः स्थानेषु प्रत्येकं सत स्ररमेदा भवन्ति । कृष्प्रथमद्वितीयतृतीयचतुर्थमन्द्रातिस्वायीः यमाः । T. Pr. XXIII. 13.14.

यमन्त्रा an obscure term found used in the Phit-sūtras राजिवशेषस्य यमन्त्रा चेत् (आग्नुदात्ती भवति) Phit-sūtra II. 42, where the word यमन्त्रा is explained as दृद्ध by the commentator. For the meaning of दृद्ध, see दृद्धिर्यस्याचा-मादिस्तद् दृद्धम् P. 1.1.73.

यय् short term (प्रत्याहार) for the consonants beginning with य् (in

ह्यवस्ट्) and ending before the mute letter य (in कपय्) i. e. all consonants except श्, ब्, स्, and ह्; cf. अनुस्वास्य यि परसवर्ण: P.VIII 4. 58 by which an auusvāra is changed into a cognate letter of the following which is a letter included in य्य.

यर् a short term (प्रत्याहार) for any consonant except हू, which, (1) standing at the end of a word is optionally changed to the nasal consonant of its class if followed by a nasal letter; cf. यरोनुनासिकेनुनासिके वा P. VIII.4.45; and (2) is doubled if preceded by र or हू as also if preceded by a vowel but not followed by a vowel; e.g. अर्कः, दद्धयत्र; cf. अत्यो रहास्यां है; अनाच च P. VIII.4.46,47.

यल tad. affix य in the sense of possession found in Vedic Literature added optionally with the affix ख (ईन) to the words वेशोभग and यशोभग; e. g वेशोभग्य; वेशोभगीन: यशोभग्य; यशोभगीन: cf. P.IV.4.131.

यक्रोप dropping of the consonant य which prevents the validity of a changed letter (स्थानिक्द्राव); cf. न पदान्तद्विवंचनवरेयक्रोप.....विधिषु P.I.1.58.

out like the Yava grain; name given to a variety of the Gāyatrī which has 7 letters in the first and third (last) feet and 10 letters in the second i.e. the middle foot; the name is also given to a Mahābṛhatī having the first and the last feet consisting of 8 letters and the middle one consisting of 12 syllables; cf. R.Pr.XVI.18 and 48.

यवर्ग the class of the consonants headed by य i.e. the semi-vowels य, व, र and लृ.

यवादि a class of words headed by the word यव, the taddhita affix मत्

after which does not get the consonant म changed into च although the affix मत् be added to a word ending in म or अ, or having म or अ as the penultimate letter; e.g. यवमान, ऊर्मिमान, भूमिमान etc.; cf. Kāś. on P.VIII.2.9. This यवादिगण is looked upon as आकृतिगण.

यशःकवि a grammarian, the author of a treatise named Bhāṣānuśāsana.

यशःसागर a Jain grammarian, the author of a work named Samāsa-sobhā.

यशोवर्भदेव the same as वक्षवर्मन the author of 'चिन्तामणि 'a commentary on the Sabdānusāsana of Sākatāyana.

यस tad. affix य with mute स to indicate the application of the term पद to the preceding base as a consequence of which the final म of the words कम and राम, after which यस is prescribed, gets changed into anusvāra; e.g. कंग्रु:, रायु:; cf. P.V.2.138.

यस्कादि words headed by the word यस्क, the affixes in the sense of 'a descendant' placed after which are elided and the words are to be used in the plural number in the masculine gender; e. g. यस्का:; cf. Kāś. on P. II.4.63.

या substitute for a case affix in Vedic Literature; e.g. उस्या, धृणुया for उस्था, धृणुया, cf. सुपां सुलुक्o P.VII. 1.39.

याच् substitute for a case affix found in Vedic Literature; e. g. साधुया for साधु; cf. सुपां सुळुक् याजाल: P. VII. 1. 39.

याजकादि a class of words headed by the words याजक, पूजक, परिचारक and others with which a word in the genitive case is compounded, in spite of the prohibition of compounds with such words, laid down by the rule क्तीरे च P. II. 2.16; e.g. ब्राह्मण-याजक: ब्राह्मणपूजक: etc.; cf. Kāś. on P. II.2.9. These words, याजक and others standing as the second members of compounds have their last vowel accented acute; cf. P.VI. 2.151.

याद् augment या prefixed to the caseaffixes marked with the mute letter इ (i.e. the dat. sing. the abl. sing, the gen. sing. and the loc. sing.) after a feminine base ending in आ; e. g. रमाये, रमाया:, रमायाम्; cf. याडापः P.VII.3.113.

याचादि a class of words headed by the word याव to which the taddhita affix क (कन्) is added without any specific sense assigned to it; e.g. यावक: मणिक: etc.; cf. Kāś. on P. V.4.29.

यासुद् augment यास् prefixed to the parasmaipada case-endings of लिङ् (the potential and the benedictive) which is accented acute; e.g. दुर्यात, कियात.

with a reputed ancient Nirukta-kāra or etymologist, of the 6th century B.C. or even a few centuries before that, whose work, the Nirukta, is looked upon as the oldest authoritative treatise regarding derivation of Vedic words. Yāska was preceded by a number of etymologists whom he has mentioned in his work and whose works he has utilised. Yāska's Nirukta threw into the back-ground the older treatises on etymology, all of which disappeared gradually in the course of time.

चिद् augment य् prefixed to the tad. affix इष्ठ when it is applied to the word बहु, in which case बहु is changed into भू; e.g. भूयिष्ठ; cf बहोलोंपो भूच बहो:; इष्ठस्य यिद् च; P. VI. 4.158,159. य general wording including the

affixes युच्, युद्, टयुत्, टयुल् and ण्युट् of which only यु remains as the affix, which is changed into अन by the rule युवोरनाकौ P.VII.1.1.

युक् augment य (1) added to a verbbase or a root ending in आ before the affix चिण and krt affixes marked with mute ज or ण; e.g. अदायि, दायक:: cf. आतो युक् चिण्कृतो:, P.VII.3.33; (2) added to the roots शा, (शो), छा (छो), सा (सा), हा (हे), न्या (न्ये), वा (वै) and पा (पा and पै) before the causal affix णिच ; e. g. निशाययति पाययति etc. cf. शान्छासाह्वान्यावेषां युक् P. VII.3.37; (3) added in Vedic Literature to the frequentative base of the root मृज् of which मर्मृज्य is the form of perf. 1st and 3rd pers. sing. instead of ममार्ज: cf. दाधर्ति...मर्भुज्यागनीगन्तीति च P.VII.4.65. युक्त (1) proper, appropriate, justified; the word is very frequently used in the Mahābhāsya and other grammar works; (2) the sense of the original base which is connected with the sense of the affix; cf. अथवा युक्तः प्रकृत्यर्थः प्रत्ययार्थेन संबद्धः, Kāś. on P. I. 2.51; (3) connected

I. 29; तथायुक्तं चानीप्सितम् P. I. 4.50.

युक्तवत् the sense of the original base, the affix after which is dropped by means of the term छुप् as contrasted with the terms छोप and छुक् which are used in the same sense; cf. छुतविदिति निष्ठाप्रत्ययेन चनजुना प्रकृत्यर्थ उच्यते । स हि प्रत्ययार्थमात्मना युनिक Kāś. on P. I. 3.51.

with; cf. उकारश्चेतिकरंगन युक्त: R. Pr.

युक्तवद्भाव lit. behaviour like the original base. The term is used in the sense of possession of, or getting, the same gender and number as was possessed by the base to which the tad. affix was added and subsequently dropped by a rule of Pāṇini in which the word ञुन् is put in the sense of

dropping; e. g. कुरयः देशः or अङ्गाः देशः in the sense of कुहणां or अङ्गानां निवासो जनपदः cf. जनपदे हुप् P. IV.3.81 and हुपि युक्तवद् ब्यक्तिवचन P.I.2.51; cf. also M.Bh. on P. I. 2.51 and 52.

युक्तारोह्यादि a class of compound words headed by the word युक्तारोही which have their initial vowel accented acute in spite of the general dictum that a compound word except a Bahuvrihi compound word, has its last vowel accented acute; cf. Kas. on P. VI. 2.81.

युक्तार्थ the sense possessed by the original word to which the affix, subsequently dropped by means of the word छुप, was added.

युक्ति (1) argumentation; reasoning; (2) current maxim; cf. युक्तिसिद्धमेतत्.

युगपत्प्रसङ्ग simultaneous possibility of the application of two rules or operations, when in grammar no option re: their application is admissible as it is admissible according to Mīmāmsa rules re: two operations enjoined by Vedic behests. In Grammar, only one of such rules applies, the priority of application being based upon the criteria of परस्त्र, नित्यस्त्र, अन्तरङ्गस्त्र and अपवादस्त्र; cf. शब्दपरिवातिषेधो नाम मवित यत्रोमयोर्युगपरअसङ्गः। M.Bh. on VI. 1.158 Vārt. 12.

युगपद्धिकरणवचनता denotation of two or more things by one single member by virtue of their being put together in a dvandva compound of two or more words; the grammarians advocate this doctrine stating that in a dvandva compound such as घरपरो or घरपरम्, the word घर has the capacity of expressing the sense of both घर and घर, which in a sentence घर: परअ, it does not possess. Similarly पर also

has the capacity of conveying the sense of both पट and घट. Possibly this theory is advocated by grammarians, on the analogy of words like पितरा or मातरा for मातापितरा, द्याचा for द्यावाप्रियो and so on; cf. सिद्धं तु युगपदिधकरणवचने द्वन्द्वयचनात् P. II 2.29 Vart. 2. For details see Vyakaranamahābhasya on चाथं द्वन्द्व: P. II. 2.29.

युगपदिधिकरणिनिवक्षा desire to express two or more senses simultaneously (by one word); cf. सर्वाणि इन्द्रे बहुर्थानि । युगपदिधिकरणिनिवक्षायां द्वन्द्रे। भवति M. Bh. on P. II.4.62. See युगपदिधिकरणवचनताः

युगपद्भवनता expression of the senses of two words together by one word; cf. विश्रहे खत्विष युगपद्भवनता दस्यते । दावा ह क्षामा । द्यावा चिदस्नै पृथियी नेमेते। M. Bh. on P. II. 2.29 Vart 6.

युग्म (1) lit, pair; the word is used for the second and fourth consonants ন্তু, ভূ, হু etc. of the five classes which, in a way are combinations of two consonants; cf. युग्ना; सोध्माण: R. T. 16; cf. also युग्मी सोष्माणी where the word सोध्मन is explained as उद्मा वायुस्तेन सह वर्तन्त इति सोध्माण: । खत्र छङ्ग टढ थघ फम; cf.also युग्मयोर्द्धितीयचतुर्थयो:; (2) even, as opposed to odd, referring to the vowels ओ and औ which are even in the enumeration ए ओ ऐ औ. The consonants called युग्न viz. खु. ঘ and others which are defined as युम्म are also the even consonants in their classes.

युच् krt affix य changed into अन, (1) applied in the sense of 'a habituated agent' to intransitive roots in the sense of movement or utterance, to Atmanepadi roots beginning with a consonant, to the roots ज, चंकम, स, गुच्, कुष्, as also to roots in the sense of decoration; e.g. चळन:, शब्दनः; cf. P.III. 2. 148-151; (2) applied to causal roots, as also

to the roots आस् श्रन्थ and others in the sense of verbal activity when the word so formed has always the feminine gender; e.g. कारणा, हारणा, आसना, घट्टना, वेदना etc.; cf. P.III.3.107 and the Varttikas thereon; (3) applied to roots ending in 31 and preceded by the indeclinables इषद्, दुस् or H in the sense of easy or difficult for obtainment and, wherever seen to any root in the Vedic language, as also to some other roots as found in actual use in the classical literature; e. g. ईषहानी गौर्भवता, दुष्पानः, सुपानः etc. सूपसदनः, दुर्योघनः, दुर्मर्षण: etc., cf. P.III.3.128-130.

युद् augment य prefixed to the tad. affix फिन् (आयिन) after the words दगु, कोसल, कमीर, छाग and वृत्र; e.g. दागन्यायिन:, कौसल्यायिन:, कार्मार्यायिण:, वार्ष्यायिण:; cf. P. IV. 1.155 Vart. 1.

युवन lit. young person; masculine; the word is given as a technical term in grammar in the sense of one, who is the son of the grandson or his descendant, provided his father is alive; the term is also applied to a nephew, brother, or a paternal relative of the grandson or his descendant, provided his elderly relative, if not his his father, is alive; it is also applied to the grandson, in case respect is to be shown to him; cf. P. IV. 1.163-167. The affixes prescribed in the sense of युवन् are always applied to a word ending with a tad. affix applied to it in the sense of an offspring (अपत्य) or grandson (गोत्र), in spite of the ruling that in the sense of grandson or his descendant (गोत्र), one affix only इञ् or अण् or the like is added to the base; e.g. गार्ग्यस्यापत्यं गार्ग्यायण:, दाक्षरपत्यं दाक्षायणः; गाग्यें जीवति तस्य भ्राता सपिण्डो वा गायार्यणः तत्रभवान् गार्यः; गार्यायणो वा.

युवपाद a conventional term used for the first pada of the seventh adhyaya which begins with the sutra युवोरनाको P.VII.1.1.

युवभत्यय tad. affix फक् (आयन), फिल् (आयनि) or any other in the sense of युवन् which is to be applied to a base ending with an affix in the sense of offspring (अपत्यप्रत्ययान्त) or with an affix in the sense of a grandson (गोत्रप्रत्ययान्त). The affix is not applied when a female offspring is meant.

युवसंज्ञा the technical term युवन which is given to persons described or mentioned in P.IV.1.163 to 167.

युवादि a class of words headed by the word युवन् which have the taddhita affix अ (अण्) added to them in the sense of 'duty' or 'nature'; e.g. यौवनम् स्थाविरम्, हौत्रम् etc.; cf. Kāś. on P.V.1.130.

युष्मत्पाद conventional name given to the third pada of the fourth adhyaya of Panini's Astadhyayi which begins with the sutra युक्मदरमदोरन्यतरस्यां सञ्जू च P. IV. 3.1.

युष्में designation of the second person, used in the Jainendra Vyākarana.

युस् tad. affix y in the sense of possession applied to (1) the word ऊर्णा; e.g. ऊर्णायु:; cf. P. V. 2.123; (2) to the words कं, कं, अहं and शुमं; e.g. कंयु:, रांयु:, अहंयु:, शुमयुं:, cf. P.V.2.138-140.

येननापासन्याय a term used by grammarians and commentators very frequently for the maxim "येन नाप्राते यो विधिरारम्येत स तस्य बावको भवति" Par. Sek. on Pari. 57. The term अपवादन्याय is used in the Mahābhāṣya which is the same as येननाप्रातन्याय of later grammarians.

योगः (1) a rule of grammar; the word योग in this sense is very fre-

quently found used in the Mahābhāṣya; cf. the frequent statements अयं योगः शक्योऽकर्तुम् M. Bh. on P.I.1. 6, 62, etc. or कान्यस्य योगस्य ध्योजनानि M. Bh. on P. I. 1.31 Vart. 6, I.1. 57 etc.; (2) grammatical connection; cf. शास्त्रकृतो योगश्च Nir. I.2: cf. also षश्ची स्थानयोगा P.I.1.49.

योगरूड a word that can be derived, but is always used in a specific sense, the derivative sense which is wider being limited; e.g. पङ्कजम्.

योगवाह a technical term used for phonetic elements or letters which are mentioned in the alphabet of Pāṇini, viz., the Māheśvara sūtras in contrast with the term अयोगवाह which is used by grammarians for the phonetic elements अनुस्वार, विसर्ग and others which are not mentioned. See अयोगवाह; cf. also M. Bh. on Siva sūtra 5.

योगविभाग division of a rule which has been traditionally given as one single rule, into two for explaining the formation of certain words, which otherwise are likely to be stamped as ungrammatical formations. The writer of the Varttikas and the author of the Mahābhāsya have very frequently taken recourse to this method of योगिवभाग; cf. P.I.1.3 Vārt. 8, I.1.17 Vārt.1,I.1.61, Vārt. 3; I. 4.59 Vārt. 1, II. 4. 2. Vārt.2, III.1.67 Vart. 5, III.4.2. Vart. 6, VI.1. 1 Vārt. 5, VI.1.33 Vārt.1 etc. Although this Yogavibhaga is not a happy method of removing difficulties and has to be followed as a last recourse, the Varttikakara has suggested it very often, and sometimes a sūtra which is divided by the Vārttikakāra into two, has been recognised as a couple of sūtras in the Sütrapātha which has come down to us at present.

योगाङ्ग a partior portion of the rule of the grammarian; cf. सति च योगाङ्ग योगविभाग: करिष्यते M.Bh. on P.I.1.30, II.1.4 etc.

योगापेक्ष concerning only that particular rule to which it refers. The word is many times used in connection with a deduction (ज्ञापक) which is not to be applied in general, but which is restricted to the functions of that rule from which the deduction is drawn; cf. योगोपंक्ष ज्ञापकम् M.Bh. on P. I.1.23 Vārt.10, P.III.1.95 Vārt.2., P.IV. 1.87 Vārt. 2, cf. also M. Bh. on P.I.3.62 and V.1.1.

योगारम्म laying down or citing a rule as done by the writers of sūtras;cf. नैकं प्रयोजनं योगारम्भं प्रयोजयित M. Bh. on P. III.1.67 Vārt. 5; P. VII. 1.96 Vārt. 2.

थॉग्यता compatibility of sense; cf. असत्यि च गोहनने तस्य योग्यतया गोझ इत्यिमधीयते Kās. on P. III.4.73.

योजक causal instrument or causal agent; the word is used in the sense of प्रयोजक in the Jainendra grammar; cf. Jain. I. 2.125.

योनि place of origin; cf. तप: श्रुतं च योनिश्च एतद् ब्राह्मणकारणम्, M. Bh. on P. V.1.115; cf. also M.Bh. on P.IV.1. 48 Vārt. 9; cf. also ओष्ठयोनिरोष्टचः.

योषा a woman; the word is used in the sense of feminine as applicable to gender.

यौगपद्य simultaneity of occurrence; simultaneous possibility of the application of two rules which evidently cannot apply simultaneously, but scope has to be given to one of the two, the priority being decided on the criteria of परत्व, नित्यत्व, अन्तरङ्गत्व and अपवादत्व; cf. न चास्ति यौगपद्यन संभव: M. Bh. on P.

I.1.57; cf. also M.Bh. on I. 4.1, I. 4.2, II.1.3 etc.

योगिक based on derivation; etymological; one of the kinds of words हट, योगिक, योगहट and योगिकहट; cf. सैन्धवशब्दो लवेंग उभयलिङ्गः। योगिकस्या-भिधयनिङ्कम l Kās. on P.II.4.31.

शौधेयादि a class of nine words headed by the word योधेय, a taddhita affix applied to which is not to be elided even though the word be used in the plural number.

₹

🕶 (1) second letter of the यण class (semi-vowels) which has got the properties नादभागित्व, घोषवत्त्व, संवृतत्व and अल्पप्राणता i. e. it is a sonant, inaspirate consonant. Regarding its स्थान or place of production, there is a difference of opinion: generally the consonant ? is looked upon as a cerebral or lingual letter (मुर्धन्य); cf. ऋदुरवाणां मुर्घा S.K.also Pān. Siksā; but it is called by some as दन्त्य or दन्तम् लीय; cf. रेफस्त, दस्त्ये दन्तम् ले वा RT. 8, by others as दन्तम्लीय and and by still others as वसर्य gingival. In the Vājasaneyi-Prātiśākhya it is described as दन्तमुळीय; cf. री दन्तमूळ I. 68, while in the Taittiriya Pratisākhya it is said to be produced by the touch of the middle part of the tip of the tongue just above the root of the teeth ;cf. रेफे जिह्नाग्रमध्येन प्रत्यग्दन्तमुलेभ्य: T. Pr. II. 41; (2) sub-'stitute { (飞乐) for the final letter of the word अहन, as also for the final of अम्रस्, अधस्, अवस् and भुवस् optionally with $\overline{\epsilon}$, which $(\overline{\epsilon})$ is dropped before vowels, and changed to ओ before अ and soft consonants, while it is changed into visarga before hard consonants and surds. e.g. अम्नरेव, अम्र एवः ऊधरेव, ऊधएवः cf. Kāś. on P. VIII, 2-70; (3) the consonant ₹ (technically called ₹ in

Pāṇini's grammar) which is substituted for the consonant H and for the consonant न of the word अहन when the consonant स or न stands at the end of a word. This substitute &, unlike the substitute & is liable to be changed into visarga, or the consonant य, or the vowel उ by P. VIII.3.15, 17, VI.1.113, 114. ₹ (1) the consonant ₹, generally cited as रेफ: the vowel अ is added to र for facility of utterance; cf. T. Pr. I.21; (2) short term (प्रत्याहार) for र् and ऌ; cf. उरण् खरः, Р. І. 1.51: (3) krt affix ₹ applied to the roots नम्, कम्प् etc. in the sense of agent who is habituated to, or expert in the action expressed by the root; e. g. नम्र:, कम्प्र:; cf. निमकभ्पिरम्यजसकम-हिंसदीपो र: P. III. 2. 167; (4) tad. affix z as a Cāturarthika affix applied to the words headed by अश्मन्; e. g. अश्मर:; cf. बुङ्छण् • P. IV. 2.80; (5) tad affix in the sense of possession affixed to the words ऊष, सुषि, मुष्क, मधु, and तमसु with अ of तमस् changed to इ; e.g. ऊषरम्, सुषिरम्, मधुरः, तामिस्ना; cf. Kas. on. P.V. 2.107 and 114; (6) tad. affix t in the sense of diminution affixed to the words कटी, रामी and ग्रण्डा; e.g. कुटीर:, शमीर:, शुण्डार:: cf. Kās. on P. V. 3. 88; (7) tad. affix रक which

the Jainendra Vyākaraņa.
रक् (1) tad.affix र proposed by the Vārtikakāra instead of आरक् for being affixed to the word गोधा to form the word गोधारः; cf. आरग्वननमनर्थकं रका सिद्धत्वात् P.IV.1.130 Vārt. 1; (2) kṛt affix रक् applied to the root ज्या; cf. रिक ज्यः प्रसारणम् P.I.1.4 Vārt. 6.

see below; (8) krt affix (事 which

see below: (9) a term for द्विग्समास in

रक्त lit. coloured i.e. coloured by nasalization; a term used by ancient grammarians for a nasalized letter (अनुनासिक); cf. रक्तरंज्ञी-

नुनासिक: R.Pr.I.17on which Uvvata comments:— अनुनासिको वणो रक्त इत्युच्यते; also cf. अरक्तसंध्यत्यपत्राद्यते पदं R. Pr. XI. 18, where unnasalized आ is stated as अरक्तसंधि and illustrated by the commentator by quoting the passage मन्द्रमा- वरेण्यम् as contrasted with अभ्र आँ अपः।

रक्तपाद conventional name given to the second pada of the fourth Adhyaya of Panini's Astadhyayi as the Pada begins with the Sutra तेन रक्त रागात् P. IV. 2.1.

रक्षित named मंत्रेयरक्षित or मैत्रेय also; a famous grammarian of the Eastern school of grammarians which flourished in Bihar and Bengal in the ninth, tenth, eleventh and twelfth centuries, claiming मेत्रेयरक्षित, पुरक्षात्तमदेव, सीरदेव and others as prominent grammar scholars among others. See the word मैत्रेयरक्षित.

হয়ুনাথ a grammarian of the seventeenth century, who was a pupil of Bhaṭṭojī Dīkṣita and who wrote a small gloss (তমুদাছ্य) on the topic named ' पञ्चसंधि' of the Siddhāntakaumudī.

रङ्ग nasalisation; colouring of a letter by its nasalisation; cf. रङ्गचर्ण प्रयुङ्गीरन् नो प्रसेत् पूर्वमक्षरम् Pāṇ. Sīkṣā. 27.

रङ्गनाथ a grammarian, son of नारायणयज्ञा, who wrote a commentary named मकरन्द on Haradatta's Padama ब्रोबरा.

रजतादि a class of words headed by the word रजत to which the taddhita affix अ (अज्) is added in the sense of 'a product' or 'a part'; e.g. राजतम्, लौहम्, औदुम्बरम् etc.; cf. Kāś. on P. IV.3.154.

रञ् tad. affix र causing vṛddhi, applied to the word अन्नीच् in the sense of Śaraṇa i.e. a room or a place; e.g. आन्नीज़म् cf. अन्नीच; शर्ण रञ् मं च P. IV.3.120 Vārt. 9.

্য্ same as জ্ being only a variant. See জ্ব.

रत्नपाणि a grammarian of the eighteenth century who wrote a short treatise on the Kāraka relations named षट्कारकविवरण.

रत्नाणींच name of a commentary on the Siddhāntakaumudī written by Kṛṣṇamitra, a famous grammarian and Naiyāyika who lived in the eighteenth century and wrote many commentary works on books in the Vyākaraṇa and Nyāya Śāstras.

रतेश a grammarian who wrote a grammar work named लक्षणसंग्रह.

रथ name of one of the eight kinds of recitals of the Veda Samhitā by dividing it into the component words (पद) and reciting the component words by repeating them, in their regular order and reverse order too.

रदानु ६ krt affix रदानु applied to the root जीव्; e.g. जीरदानु:;cf. जीवे रदानुक् । जीरदानु: M. Bh. on Siva Sūtra 5, Vārt. 5.

रचादि a class of eight roots headed by the root रच् which allow the addition of the augment इ (इट्) optionally to the ārdhadhātuka affix beginning with any consonant except च, placed after them; e.g. राधता रहा, त्रता तर्मा तर्मात etc. cf. P.VII.2.35 and VII.2.45.

रन personal ending रन् substituted for the personal ending झ of the प्रथमपुरुष (third person) Atmanepada of 'lin' (potential and benedictive); cf. झस्य रन् P.III. 4.105.

krit scholar of France of the present time who has written some treatises and many articles on Sanskrit grammar out of which his works on the Terminology of Sanskrit Grammar, Kāśikā and Durghaṭavṛtti require a special mention.

रपर with the letter र inserted after it; the term is used in connection with the guna and viddhi substitutes for क. These substitutes are respectively अ and आ, which, by the addition of र, always become अर and आर; cf उरण् रपर: P.I. 1. 51, cf. ककारस्य गुणवृद्धी रेफशिखा अगरावेवेति cf. also चुद्धिर्भवति गुणो भवतीति रेफशिया गुणवृद्धिर्संत्रकेभिनिवेतंते; M.Bh. on P.VI. 4.121, VIII.2.42.

াng that the short term ব for the consonants and হ need not be advocated as done by the learned old grammarians. The treatise was written by Vaidyanātha Pāya-guṇḍe, the prominent pupil of Nageśabhatta.

रप्रत्याहारमण्डन an anonymous work, comparatively modern, refuting the arguments advanced in the প্ৰেয়াহাংকেণ্ডন by Vaidyanātha Pāyagunde.

रम् augment र inserted after the vowel अ of the root अरज, when the letter र which is already present in अरज् (before अ) and the penultimate स are dropped; the result is that the word भर्ज, in short, becomes substituted in the place of अरज्; cf. अरजो रोपघयो रमन्यतरस्याम् P.VI. 4.47, and अरजो रोपघयोलींप आगमी रम् विधीयते as Bhāradvājīya Vārttika thereon.

মানাথমামী a grammarian of the Kātantra school who lived in the fifteenth century and wrote a commentary named Manoramā on the Kātantradhātuvṛtti and Sabdasādhyaprayoga.

रह a short term (प्रत्याहार) used for all consonants excepting य and च्; cf. रहो च्यपधाद्धहादे; संश्च, P.I.2.26.

ve personal ending of the third pers.

(प्रथमपुरुष) substituted for the affix क्षि in the first future (छुट्); cf. छुट: प्रथमस्य डारोरस: II.4.85.

रसचती name of a commentary on his own work 'Sanksiptasāra Vyā-karaṇa' by Kramadīśvara, a sound scholar of grammar in the thirteenth century A.D.

रसादि a class of words headed by the word रस which have the tad. affix मतुप् added to them in the sense of possession in preference to other affixes like इन; e.g. रसवान, रूपवान etc.; cf. Kāś. on P.V. 2.95.

राघवेन्द्रश्चार्य (गजेन्द्रगडकर) a famous scholar of Grammar in the nineteenth century, who taught many pupils and wrote some commentary works, the well-known being प्रभा on the Sabdakaustubha, विषमपद्व्याख्या on the Laghusabdendusekhara and त्रिपथा। on the Paribhāṣendusekhara. For details see p. 27 Vyākaraṇa Mahābhāṣya Vol. VII D. E. Society's Edition.

राजदन्तादि a class of compound words headed by राजदन्त in which the order of words or the constituent members is fixed. There are about 50 words in the class; some of them are tatpurusa compounds such as राजदन्त or अग्रेवण in which the subordinate word which ought to have been placed first is placed second. There are some karmadhāraya compounds in which one particular word is always placed first and not any one of the two; e.g. छिनवासितम्, सिक्तसंमृष्टम् etc. There are some dvandva compounds such as उद्भवलमुसलम्, चित्रास्वाती, भार्यापती etc. in which a definite order of words is laid down. For details see Kāsīkā on राजदन्तादिषु परम् P. II. 2.31.

राजन्यादि a class of words headed by the word राजन्य to which the taddhita affix अक (बुच्) is added in the sense of 'the place of residence'; e. g. राजन्यक:, ओंदुम्बरक: etc. This class named राजन्यादि is called आक्वातिगण and similar words can be included in this class such as मालव, विराद्, त्रिगतं and others from which the words मालवक: वैराटक: त्रेगतंक: etc. can be arrived at: cf. Kāś. on P. IV. 2.53.

राजारामशास्त्री (कालेंकर) a reputed scholar of Sanskrit grammar who resided at Vārāṇasī and established a school of Sanskrit Grammarians there in the nineteenth century. He wrote a treatise on grammar named शब्दब्युलिकौमुदी.

राधाकुरण (गोस्वामी) a grammarian who wrote two elementary grammar treatises (1) अन्ययार्थ and (2) वैयाकरणसर्वस्वसूची.

राधावस्त्रम titled तर्कपञ्चानन, who wrote a commentary named सुनोधिनी on the Mugdhabodha Vyākaraņa.

राम or रामभद्द who wrote a commentary on the Prakriyākaumudī of Rāmacandra Śesa.

राम inhabitant of Mithila who wrote a commentary by name विद्वत्प्रवोधिनी on the Sarasvata Prakriya.

रामार्केकरसरस्वती a grammarian who wrote a small grammar treatise named आशुबोधन्याकरण which is different from the well-known आशुबोध of तारानाथतर्कवाचस्पति.

रাमाकेशोर (चक्रवर्ती) author of (1) প্রচ্মব্ধতা a commentary on the कातन्त्रवृत्ति of Durgasimha, as also of (2) যাভ্রেৰাঘ্যকায়িকা, a small work on the import of words.

रामकृष्ण a grammarian who wrote a treatise on Kāraka relations known by the name शाब्दबोधप्रक्रिया.

रामकृष्णभट्ट a grammarian of the 17th century who wrote वैयाकरणसिद्धान्त-रत्नाकर, a commentary on the different portions of the Siddhanta Kaumudī.

रामकृष्णानन्द writer of a commentary on the Mahābhāṣya which is available in a fragmentary form.

रामचन्द्र (1) रामचन्द्राचार्य (son of कृष्णाचार्य) the well-known author of the Prakriyākaumudī. He belonged to the Sesa family and the latter half of the fifteenth century is assigned as his date. He is believed to have been a resident of Andhra. work, the Prakrivākaumudī, was a popular grammar treatise for some time before Bhattoji's Siddhanta-Kaumudī got its hold, and it had a number of commentaries written upon it especially by his descendants and members of his family which became well-known as the Sesa family of grammarians. The Prakriyākaumudī is named কুভার্কি-करप्राक्रिया also. (2) There was a grammarian named Rāmacandra who wrote a small treatise on grammar named विदग्धवोध. (3) There was another grammarian of the same name who was a pupil of Nagesabhatta of the eighteenth century and who wrote a small commentary called वृत्तिसंप्रह on Pānini's Astādhyāyī. (4) There was also another Rāmacandra who was a scholar of Vedic grammar and who wrote the commentary named ज्योलना on the Vajasaneyi-Pratisakhya.

रामचन्द्र दक्षित a grammarian who wrote (1) Uṇādikosa, (2) Maṇi-dīpikā, a commentary on the Uṇā-disūtras, and (3) Sabdabhedanirūpana.

रामचन्द्रभद्ध तारे one of the senior pupils of Nāgešabhatta who was a teacher of Vaidyanātha Pāyagunde. He wrote a small gloss on the Aṣṭādh-yāyī which i named থাণিনিম্মৃত্বিং

He lived in the first half of the eighteenth century and taught several pupils at Vārāṇasī.

रामचन्द्रशेष See रामचन्द्र (1).

रामचन्द्रसरस्वती pupil of वासुदेवेन्द्रसरस्वती of the sixteenth century who has written a gloss named विवरण on the Mahābhāṣyapradīpa of Kaiyaṭa.

रामतर्कवागीश a learned grammarian who held the titles महामहोपाध्याय and महाचार्य. He was an advocate of the Mugdhabodha School and wrote commentaries on (1) the Mugdhabodha, (2) the Kavikalpadruma, (3) the Amarakośa and (4) the Uṇādi sūtras. He also wrote a short gloss on case-relations, his treatise on the subject being named कारकिटपणी.

रामदास (चकवर्ती) a follower of the Kātantra school of grammar who wrote (1) चित्रका, a commentary on Kātantraparišiṣṭa and (2) कातन्त्रव्याख्यासार.

रामनाथ (चक्रवर्ती) who wrote short glosses on the Kātantra and the Kālāpa Vyākaraņas.

रामनाथ (चोत्रे) a grammarian of the nineteenth century who wrote (1) शब्दन्दुशेखरटीका, (2) वैयाकरणभूषणटीका and (3) वैयाकरणसिद्धान्तमञ्जूषाटीका.

- रामनाथ (विद्यावाचरपति) a Sanskrit scholar of the 17th century who studied Vyākaraņa, Dharma, Alamkāra and other Śāstras and wrote a grammar work कातन्त्ररहस्य, besides many books on other Ṣāstras.

रामनारायण writer of a commentary on the Sārasvataprakriyā.

रामभद्ध writer of a commentary on the Prakriyākaumudī.

रामभद्र दीक्षित son of यज्ञराम दीक्षित, a grammarian of Tanjore of the seventeenth century who wrote a commentary on the Paribhāṣāvṛtti of Sīradeva named परिभाषाद्वतिन्याख्या. He has also written the 'life of Patañjali' (पतञ्जलिचरित) and many miscellaneous works, such as उणादेमणिदीपिका and others.

रामराम a grammarian who has written a commentary on the Kavikalpadruma of Bopadeva.

रामरामा the same as रामतर्कवागीश. See रामतर्कवागीश.

रामसिहनमी possibly the same king of Sringaberapura who patronised Nagesabhatta. He is said to have written some small comments on the Rāmāyaṇa and a small grammar work named वातुरस्नमञ्जरी.

रामानन्द a grammarian of the seventeenth century who wrote a commentary on Bopadeva's Mugdhabodha. He was possibly the same as Rāmarāma (see above) and Rāmānandatīrtha who wrote the Kātantrasamgraha, although different from the well-known रामानन्द-तार्थ of the sixteenth century who was a samnyāsin and who wrote many philosophical and religious booklets.

(see above) who wrote Dhātudīpikā, a commentary on the Kavikalpadruma of Bopadeva.

रामाश्रम a grammarian of the seventeenth century who wrote a commentary named Siddhāntacandrikā on the Sārasvata Vyākaraņa.

रामेश्वर a grammarian who wrote a small compendium on grammar named गुद्धागुनोप.

राशि usually used in the sense of a collection or a heap or a lunar constellation; the word is often used after the word वर्ण when it means the traditional collection of

letters or the alphabet. The words अक्षरराशि, त्रहाराशि and अक्षरसमाम्राय are also used in the same sense.

रिक an augment added optionally with हक and रीक to the reduplicative syllable of the frequentative root from a primitive root which ends in 来 or has a penultimate 来; e.g. चरिकर्ति, नरिनर्ति भरिभ्रत् etc.; cf. रुपिको च लुकि, P.VII. 4.91 and ऋतश्च VII.4.92.

रिङ substitute रि for a verbal base ending in ऋ before হা (the sign of the 6th conj.) यक् (sign of the pass. voice) and a ਲਿਵ੍ਹ affix beginning with a which is not a Sārvadhātuka रिङ् शयग्लिङ्क्ष P.VII.4.28.

रित (1) characterized by the mute consonant & signifying the acute accent for the penultimate vowel;cf. रिति P. VI. 1, 217; (2) उपोत्तमं the same as रिक्ति or रेकि, a visarga which is changeable into 3 when euphonically combined: विसर्जनीयो रिफित: V.Pr.I.160; cf. also भाव्यपथं च रिद्धिसर्जनीयान्तानि रेफेण: V.Pr. VII.9. The terms रिफ्ति, रेक्टि and रित् are given in the Padapatha to a पद or word which ends in a Visarga which has originated from \(\frac{1}{2}\) in the Samhitapatha; e.g. the Visarga in क:, प्रात: etc.; cf. R.Pr.I.30 to 32.

रिफित (1) a Visarga in the Padapāṭha · which has originated from ₹ in the Samhitā-pātha; (2) a word or pada which has got a रिक्ति at its end; cf. क:, स्व: प्रात: etc. (which in the Samhita patha are कर्, स्वर्, प्रातर् etc.;) cf. R.Pr. I.30 to 36 V.Pr.IV. 18,192.

रिल् tad. affix रि added optionally with रिष्टात् to the word ऊर्ध्व which becomes changed into उप; e.g.उपरि, उपरिष्टात्; cf. ऊर्ध्वस्य उपभावो रिल्रिशतिलौ [¬] P.V.3.31 Vārt. 1.

रिप्रातिल tad. affix रिशत् added to ऊर्ध्व; see रिल.

रोक augment रा added optionally with हक and रिक to the reduplicative syllable (अभ्यास) of the frequentative base of roots having # as their penultimate vowel; e.g. वरीबृश्चयते वरीवृश्चीति, नरीनर्ति, चरीकर्ति; cf रीग्रद्पधस्य ₹ P.VII. 4.90.

भोड़ substitute री for the vowel क at the end of a base (अङ्ग) before the affix चित्र as also before य which does not belong to a kit or Sarvadhātuka affix; e.g. मात्रीमूतः, मात्रीयते; cf. शङ्कत: P.VII.4.27.

affix; e. g. आद्रियत, क्रियत, क्रियात्; cf. र (1) substitute र् for the consonant स् at the end of a word as also for the ब of सज्जुर, न of अहन and optionally with र for the final स of अम्रस, ऊधम् and अवस् in Veda; e.g. अग्निरत्र, वायुरत्र, सजूदेविभि: cf. P.VIII. 2.66; the ₹ of this ₹ (as contrasted with the substitute (which see above) is further changed into 3 before a soft consonant and before the vowel & provided it is preceded by the vowel अ, while ₹, prescribed as substitute \(\forall \) (which see above), remains unchanged; e.g. शिवोच्ये:, शिवो वन्द्य: as contrasted with अहरत्र, अहर्गण:; (2) substitute र for the final ज् of अवयज् (e.g. अवयाः), for ह् of श्वेतवहू (e.g. श्वेतवा:), and for श of पुरोडाश (e.g. प्राडा:) before the case affix स: cf.P.VIII.4.67;(3)substitute र् (or द्) for the final स् or द् of a verb-form ending with the personal ending सिष् of the 2nd pers. sing; cf. P. VIII.2.74,75;(4)substitute 3 for the final \(\) of words ending with the affix मत् or वस् in Veda; e.g. मरुत्व: हरिव:; cf. Kāś. on P.VIII.3.1; (5) substitute र for the final न at the end of a word when it is followed by a छब् letter i.e. the first or a second consonant excepting & and

- प्; e.g. भवांश्चिनोति; cf. P.VIII. 3.7; (6) substitute ए for the final न् of नून् before the letter प् as also for the final न् of स्वतवान् and कान् under certain conditions; cf. P. VIII.3. 10.12.
- रक् augment (added optionally with रिक् to the reduplicative syllable; (see रिक् above); e.g. चर्कार्त, नर्नार्च; cf P. VII. 4. 91, 92 as also VII. 4.65.
- रुमान् the primary Yama letter; a term used in the Śikṣā treatises.
- हत् augment र्, prefixed to the pers. ending झ of the प्रथमपुरुष (3rd pers. plural) after the root शो, विद् and in Vedic literature after a few other roots e.g. शेरते, संविद्रते,अदुह्न;cf. शोङो स्ट्: P.VII. 1.6-8.
- च्हादि a term used for the five roots headed by the root च्ह्, which have the augment इ added to a Sārvadhātuka affix in certain cases; e.g. रेदिति, श्वासित, अरोदीत्, अस्वपीत् etc.; cf. P.VII. 2. 76, VII.3.98.
- ব্যুইৰ a grammarian who has written a commentary on the Vaiyākaraṇa-Siddhānta-Bhūṣaṇa of Koṇḍabhatta.
- হয়াহ a class of roots headed by the root হয় which take প্লম্ (ন্) as the conjugational sign inserted after the final vowel, e.g. ফাব্লি (where হয় becomes ফায়). These roots are popularly called roots of the 8th conjugation.
- हह conventional; traditional; one of the four senses in which words are used. The senses are यौगिक (derivative), हद (conventional), योगहद and यौगिकहद; The term हद is also used in the sense of 'a conventional word' cf. प्रथमाशब्दो विभक्तिविशेष हद: Kās. on P. VI. 1.102.
- Samhitāpātha, as contrasted with the Padapātha.

- रुद्धि convention; usage; custom. The word रुद्धि is given along with योग (derivation) as the basis of the use of words which are described to be of four kinds; see रुद्ध above. cf. नैगमरूदिभवं हि सुसाधु P. III 3.1. Vart. 1.
- रूप (1) word-form which is complete with प्रकृति (the base) and प्रत्यय, i.e. the affix which is attached to it: cf. रूपनिर्प्रहश्च शब्दस्य नान्तरेण लौकिकं प्रयोगम् M. Bh. on P. I. 1.22 Vart. 3; cf. also the usual expression का रूपसिद्धिः in the Mahābhāsya; cf. M. Bh. on I. 1.51, 1.2.58 etc.; the word is also used in the sense of a word-base (धातु or प्रातिपदिक); cf. स्वं रूपं शब्दस्याशब्दसंज्ञा $\mathbf{P.}\ \mathbf{I.}\ 1.68$; (2) the word form as characterized by its derivation and properties: cf. तस्य रूपान्यत्वे वर्णान्यत्वम् explained as तस्य शब्दस्य अनुप्रदानादिभिः कारणे रूपभेदे जन्यमाने वर्णभेदः संपद्यते T. Pr. XXII. 2.
- रूपनारायण a grammarian of Bengal of the fifteenth century who wrote short comments on some sections of the Supadma Vyākaraṇa under the names सुवद्मषट्कारक and सुवद्मसमास-संग्रह.
- रूपप् tad. affix in the sense of 'praise' which is, in fact, possessed by the word to which the affix रूपप् is added, without making any change in the sense of the word, the affix being called 'स्वार्थे' i. e. an affix in the sense of the base or प्रकृति ट.स्वार्थेकाः प्रत्ययाः प्रकृत्यर्थविशेषस्य योतका भवन्ति । प्रश्चत्यर्थस्य वैशिष्ट्ये प्रशंसा भवति । युष्ठरूप्यं यः प्रकृत्यर्थस्य वैशिष्ट्ये प्रशंसा भवति । वृष्ठरूप्यं यः प्रकृत्यर्थस्य वैशिष्ट्ये प्रशंसा भवति । वृष्ठरूप्यं यः प्रकृत्यर्थस्य वैशिष्ट्ये प्रशंसा भवति । स्वरं प्रवित । चोरह्पः । Kāś. on P. V. 3.66.
- Sanskrit grammar composed by Vimalasarasvatī, in which the Sūtras of Pāṇini are arranged in different topics many of which are

called माला, such as अजन्तमाला, हलन्तमाला, छान्दसमाला, अञ्चयमाला and so on.(2) the name रूपमाला is also found given to a work giving collections of formed words written by Punyanandana.

रुपसिद्धि lit. the formation of words; the name रूपसिद्धि is given to a small literary work on the formation of words written by Dayanandasarasvatī.

रूपातिदेश the actual replacement of the original in the place of the substitute by virtue of the rule स्थानिवदादेशोनिल्वधौ P. I. 1. 56; one of kinds स्थानिवद्धाव the ofthe word-form of the original (स्थानी) is put in the place of the substitute (अदिश); the other kind of स्थानियद्धाव being called कार्यातिदेश by means of which grammatical operations caused by the original (स्थानी) take place although the substitute (आदेश) has been actually put in the place of the original. About the interpretation of the rule द्विवंचनीच P. I.1.59, the grammarians accept the view of रूपातिदेश; cf. रूपातिदेशश्चायं नियतकालस्तेन कृते द्विर्वचने पुनः आदेशरूपमे-वावातिष्ठते । पपतुः पपुः । आतो लोप इटि च इत्याकारलोपे कृते तस्य स्थानिवद्भावात एकाचो द्वे॰ इति द्विधेचनं भवति Kās on P.I.1.59; cf. also रूपातिदेशश्चायम् । द्विवंचनेचि इत्य-त्रास्य भाष्ये पाठात । Pari. Bhaskara Pari. 97. For details see Mahābhāsya on P.VII.1.95 96.

हपावतार a well-known work on word formation written by घमेकोति a Jain grammarian of the twelfth century. Scholars believe that this work was the first work of the form of topics which was taken as a model by the authors of the Prakriyākaumudī and the Siddhāntakaumudī.

रूप (1) a tad. affix applied to a word

meaning 'a cause' or expressing 'a human being' in the sense of 'proceeding therefrom' e.g. समादागतं समस्प्यम्; देवदत्तरूप्यम्; cf. हेतुमनुष्येभ्योग्यतस्यां रूप्यः P. IV. 3.81; (2) a tad. affix applied to a word in the genitive case in the sense of मृतपूर्व, 'formerly belonging to'; e.g. देवदत्तस्य मृतपूर्वों गौः देवदत्तस्यः; cf. Kāś. on षष्टया रूप्य च P. V. 3.54.

के word-form of the ajbhakti or svarabhakti (a term used in the ancient Prātiśākhya works), where क्र is looked upon as the consonant र surrounded by, or followed by the nature of a vowel. क्र as a vowel is possessed of one mātrā of which in svarabhakti, the consonant र possesses half and the svarabhakti possesses half; cf रेफात् स्वरेगिहताद्यञ्जनोदयाद् क्रकाखणी स्वर्भाक्तरूचरा R. Pr. VI.13.

रे (रेश्) personal ending in Vedic Literature, substituted for त of the प्रथमपुरुष (3rd pers.) plural in the Perfect tense; cf. लिटस्तझयो रेश् इरेच् P. III. 4.81.

रेखा termed also 'लेखा'; one of the subdivisions of the krama-pātha.

रेफ the consonant र; generally the word रेफ is used for र and not रकार; cf. वर्णात्कार: । रादिक: P.III.3.108 Vārt. 3,4. The consonant र is described as one pronounced like the tearing of a piece of cloth and resembling a snarl or a growl; cf. रिस्यते विपाटयते वस्त्रादिपाटनध्वनिवदुचार्थते इति रेफ: ।

रेफिशिरस् (the guṇa or the vṛddhi substitute for क viz. अर् or आर्) with the letter र represented in script by a sign on the top; e. g. अर्क:, आर्जनम्; cf. वृद्धिमेनति गुणा भनतीति रेफशिरा गुणवृद्धिसंज्ञकोऽभिनिर्नर्तते M.Bh. on P. VI.4,121.

रेफिन a term applied(1)to the Visarjasnīya letter preceded by any vowel excepting अ and आ, (2) to the Visarjaniya preceded by अ in some specified words such as श्रातः, भाः, अविभः, आदः, कः etc. under certain conditions, as also, (3) to the Visarjaniya in हातः, सनितः etc. For details see R. Pr. I.30-36.

रेवत्यादि a class of words headed by the word रेवती to which the affix ठक्क is added in the sense of 'an offspring'; e. g. रैवितक:, आध्यालिक:, द्वारपालिक; etc.cf.Kāś. on P. IV.1.146.

रैसितिकादि a class of words headed by रैसितिक to which the taddhita affix ईय (छ) is added in the sense of 'belonging to'; e. g. रैसितकीय:, औदबाहीय:, बैजनापीय: etc. cf. Kaś. on P. IV. 3.131.

रोमश one of the faults in pronunciation; cf. प्रगीत उपगीत; क्ष्मिणो रोमश इति M. Bh I. 1. Ah. 1.

री personal ending substituted for the प्रथमपुरुविद्वचन (3rd pers. dual affix तस्) in the periphrastic or first future; e. g. कतारी; cf. लुट; प्रथमस्य डारीरस: P. II. 4.85.

रौढीय a term jocularly used with the word घृत preceding it, for students of a famous scholar named घृतरौढि; cf. ओदनपाणिनीयाः घृतरौढीयाः M.Bh. on P. 1.1.73.

रांख्यादि another name given to the कौड्यादि class of words which are headed by कौडि and which take the affix घ्यङ् to form their base in the feminine; e. g. कौड्या लाड्या; cf. सिद्धं तु रौड्यादिष्पसंख्यानात् । के पुना रौड्यादय:। ये कौड्यादय: M. Bh. on P. IV. 1.79.

रोधादिक a root belonging to the class of roots headed by रुष् which take the conjugational sign न् (अम्). See रुधादि above.

हिंस् (1) a tad. affix termed also विभक्ति which is applied to the word इदम् in the sense of the locative case, the word इदम् being changed into एत;

e. g. एतिई: cf. इदमो हिंख P. V. 3.16 and एतती रथा: P. V. 3.4. (2) tad. affix applied in Veda to तत् and other pronouns; e.g.ताईं, कईं, याईं, cf. P. V. 3.20, 21.

7

ਲ (1) a consonant of the dental class which is a semi-vowel (यण) with liquid contact in the mouth, and which is inaspirate (अल्पप्राण), voiced (घोष) and both nasalised and unnasalised; (2) name in general (তকাर) given to the personal endings applied to roots in the ten tenses and moods which take different substitutes ति, तः, अन्ति etc. and have various modifications and augments in the different tenses and moods; (3) substituted as a semi vowel (यण) for the vowel ਲ followed by any other vowel in the euphonic combinations: (4) applied at the beginning of nontaddhita affixes as a mute letter indicating the acute accent for the vowel preceding the affix: लिति; P. VI. 1.193; substituted for त, थ, द, घू or न् before of cf. P.VIII.4. 60; (6) substituted under certain conditions for the consonant र् (a) of the root ऋप्, (b) of prefixes प्र and प्रा before the root अयु, (c) of the root ग in frequentative forms and optionally before affixes beginning with a vowel, and (d) of the word परि before च and अइ; cf. P. VIII. 2. 18 to 22.

छ (1) consonant छ; see छ above'
(2) a general term usually used by ancient grammarians to signifyछोप (elision or disappearance) of a letter or a syllable or a word; cf. सर्वसादेद्विगोश्च छ: । स्वार्तिकः, द्वितन्त्रः M. Bh. on P.IV.2.60; (3) tad. affix

ল added to the word ক্লিল when चিল্ and ণিত্ are substituted for the word ক্লিল; e.g, चিল্ল:, ণিল্ল: cf. P.V. 2.33 Vart 2.

ন্তকাৰ (1) the consonant নৃ:; see নৃ (1) above; (2) the personal endings affixed to roots; see নৃ (2).

स्था (1) a rule or a sūtra composed by the ancient Sūtrakāras; the word is very frequently used in this sense by the Bhāṣya-kāra and later commentators; cf. लक्ष्यलक्षणे ब्याकरणम् ;cf. also लक्षणे हि नाम ध्वनति, भ्रमति मुद्देनमि नावतिष्ठते M.Bh. on P.I.1.3 Vārt 10; (2) characteristic or sign; cf. लक्षणेनाभिप्रती आभिमुख्ये P. II. 1. 14; cf. also P.I.4.90 and III. 2.12; (3) indirect way of expression; cf. लक्षणप्रतिपदोक्तयोः प्रतिपदोक्तस्यैन प्रहणम् Par. Sek. Pari. 105.

छक्षणप्रतिपद्देक्त a short term used for the well-known Paribhāṣā लक्षणप्रति-पदोक्तयो: प्रतिपदोक्तस्यैन प्रहण्म Par. Sek. Pari. 105, laying down that when a question arises as to which of the two words लक्षणोक्त (arrived at by certain changes or modifications) and प्रतिपदोक्त, (directly expressed) be accepted, the latter should be preferred.

रुक्षणसंग्रह a work on grammar written by a grammarian named रलेश.

ভক্তমা implication; potentiality of implication; this potentiality of words viz. তথ্যলা is not recognised by grammarians as a potentiality different from the अभियाशक्ति or the power of denotation. Later grammarians, however, like the Alamkārikas, have used the word in the sense of potentiality of implication as different from that of denotation; cf. अन्त्यशब्दे लक्षणा न च Paribhāṣenduśekhara.

स्वभणस्रि a grammarian who has

written a booklet on the six dialects, which is named षड्भाषाचन्द्रिका.

छक्ष्मीनृश्चिह a grammarian of the eighteenth century who has written (1) Siddhāntakaumudīvilāsa, a commentary on the Siddhāntakaumudī and(2)Triśikhā, a commentary on Nāgeśa's Paribhāṣenduśekhara.

उद्भ्य lit. target; illustration; example of a grammatical rule; cf. लक्ष्ये लक्षण सक्तदेव प्रवर्तते Paribhāṣā; also लक्ष्यानुसारि व्याख्यानमेव शालम् Paribhāṣendu-sekhara; cf. also शन्दो लक्ष्य: सूत्रं लक्षणम् M. Bh. on P.I.1.1 Vārt. 14.

रुक्ष्यार्थ implied sense. See the word लक्षणा.

लघु (1) a term used in the sense of light or short as contrasted with गुरु meaning heavy or long, which is applied to vowels like अ, इ etc. cf. हुन्सं लघु P.I. 4. 10; (2) brevity; brief expression; cf. लघ्य है है संज्ञाकरणम् M.Bh. on P.I.2,27 Vart. 6 also संज्ञा हि नाम यते। न लगीय:; (3) small, as qualifying an effort in writing or explaining something as also in utterance; cf. इयोलघुप्रयत्नतर: ज्ञाकटायनस्य P.VIII.3.18.

लघुकौमुद्री known as लघुसिद्धान्तकौमुदी also, an abridged work based upon the Siddhantakaumudi of Bhattojī Dikşita, written Bhattoji's pupil Varadarāja. The work is very valuable and helpful to beginners in grammar. It has got the same topics as the Siddhäntakaumudī. but arranged differently. The work, named सार-सिद्धान्तकौमदी is the same as लघुसिद्धान्त-कौमुदी.Possibly सारसिद्धान्तकौमुदी was the original name given by the author.

लघुता smallness of effort as contrasted with गुरुता; cf. तत्राप्ययं नावस्यं गुरुलघुतामेवोपलक्षयितुमईति, M.Bh. on P. I.1.3 Vart. 7.

लघुन्यास (1)short writing, brief putting in, brief expression; cf. सोयमेवं लघुना न्यासेन सिद्धे etc.; (2) the word is given as a name to grammatical work, written by देवेन्द्रसुरि on the शब्दानुशासन of Hemacandra, possibly in contrast with the बहन्त्यास written by Hemacandra himself or with Kāsikāvivaranapanjika popularly called written by Jinendrabuddhi on the Kāśikāvrtti of Javaditya Vāmana. See न्यास.

ভযুपरिभाषाद्वात्ते an independent work on Paribhāṣās written by Puruṣo-ttamadeva in the twelfth century A. D. called ভয়ুपरिभाषाद्वित in contrast with the बृहत्परिभाषाद्वित of सीरदेव. The Vṛtti is named 'Lalitā' also, by the author.

लघुमिनेया name of a grammar treatise based on the Sabdānuśāsana of Hemacandra written by Vinayavijaya where the sūtras of Hemacandra are arranged in different topics as in the Siddhāntakaumudī of Bhottojī.

रुप्रयत्नतर requiring still less effort for utterance than that required for the usual utterance; the term is used in connection with the utterance of the consonant य which is substituted for Visarga following upon long आ and followed by any vowel. In such cases य is not pronounced at all according to Sakalya, while it is somewhat audibly pronounced according to Sakatayana; cf. ब्योलंब्रुप्रयत्नतर: शाकटा-यनस्य P. VIII. 3.18.

लघुभूषणकान्ति name of a commentary work by Harivallabha on Kondabhatta's Vaiyākaraṇabhū-saṇasāra.

लघुभूषणदर्पण or लघुद्र्पणा name of a commentary by Mannudeva on

Kondabhatta's Vaiyākaraņabhūṣaṇasāra.

ন্তহ্যুমতনুৰা name of an independent work on the meaning of words and their interpretation written by Nāgeša of which the प्रमल्ड्यमञ्जूषा is a popular short extract by the author himself.

ठाउँ व्याप्त name of a commentary on Bhattoji's Manoramā by his grandson Hari Dīkṣita, which is generally read together with the Manoramā, by students upto the end of the Kāraka Chapter after they have completely read and mastered the Siddhāntakaumudī. The commentary is called लघु- यान्यस्न which differentiates it from the युह्च्छ्य्यस्न written by the same author viz. Hari Dīkṣita.

लघुराब्देन्द्रशेखर name of a commentary on Bhattojī's Siddhāntakaumudī written by Nāgeśa Bhatta, the stalwart Grammarian of the eighteenth century. The work is named लघुशब्देन्द्रशेखर which differentiates it from the author's another work बृहच्छन्देन्द्रशासर of which the former is an abridgment. As the study of the Laghusabdenduśekhara is very common and as the Brhatsabdendusekhara is seldom studied, it is always the Laghusabdendusekhara that is understood by the simple and popular name Sekhara.

लघुराब्देन्दुरोखरच्याख्या a commentary on the Laghusabdendusekhara. There are more than a dozen commentary works on the popular Laghusabdendusekhara called by the usual names टीका or ब्याख्या the prominent among which are गदा, भरवी and विजया. A few of them have special names e. g. चिद्रस्थिमाला, चन्द्रकला, ज्योत्ला, विषमी etc.

उद्यसारस्वत an epitome of the Sāras- : vata Vyākaraṇa, by कल्याणसरस्वती. उद्यसिद्धान्तकोम्दी see उन्नकीम्दी.

लङ् name given to the affixes of the imperfect tense; cf. अनदातने लङ् P. III. 2.111, explained by Bhaṭṭojî as भूतानदातने लङ् स्थात् in his Siddhānta-Kaumudī.

ख्य tad. affix छ applied optionally with the affix मतुष् to words ending in आ and meaning a detachable or undetachable part of an animal, as also to words mentioned in the group headed by the word सिम, as also to words बत्स and अस showing affection and strength respectively; e. g. चूडाल:, सिमल:, बत्तल:, etc.; cf. P. V. 2. 96-98.

छद general personal ending applied to roots (1) to show the present time for which the personal endings ति तः...महि are substituted for the formation of verbs and अत् (रातृ) and आन or मान (राानच) for the formation of the present participle; (2) to show past time when the indeclinable स is used in the sentence along with the verbal form or when the indeclinables नन, न, न, पुरा,यावत्, कदा,कहिं etc.are used along with the verbal form under specific conditions; e. g. कटं करोति देवदत्तः, यजति स्म युधिष्ठिरः, अहं नु करोमि, वसन्तीह पुरा छात्राः, यावद भुङ्के etc.: cf. P. III. 2.118-123, III. 3.4-9.

छत्व change of र into छ. See छ above. छितावृत्ति name given to the Paribhāṣāvṛtti written by Puruṣottamadeva, a famous grammarian of the Eastern branch of Pāṇini's system which prevailed in Bengal from the eighth to the end of the twelfth century A.D. See पुरुषोत्तमदेव.

स्रसावेधातुक a personal ending substituted for ल which in certain cases gets the grave accent in spite of the general rule that affixes (which include personal endings) are acute; cf. तास्यनुदार-न्छिददुपदेशाह्मसार्वधातुकमह्निङोः P. VI. 1. 186.

लाक्षाणिक (1) secondary; taken or understood in the secondary sense; (2) stated by a rule (रुक्षण); cf. एवं तिहं न लाक्षणिकस्य स्वरस्य प्रतिषेषं शिष्मः M.Bh. on P. I. 4,2 Vārt. 9.

लाघन brevity of expression; expressing in as few words as possible; brevity of thought and conception. About brevity of expression, rules or sūtras of the ancient Sūtrakāras are noteworthy especially those of the grammarian Pāṇini, whose brevity of expression is aptly extolled in the familiar expression अर्धमात्रालाघनेन पुत्रोत्सन मन्यन्ते नैयाकरणा: Par. Sek. Pari. 122; cf. also in contrast पर्यायहादानां लाघनगीरनचर्चा नाद्रियते Par. Sek. Pari.115.

ह्याचन्याय law of minimisation, parsimony in the use of words or parsimony in expression, followed generally by the Sutra writers.

लादेश substitutes तिप्, तस् झि (अन्ति) सिप्
.....महिङ् for ल्, signifying the ten
ल् affixes or lakāras लट्, लिट्, लुट् etc.,
applied to roots in the senses of
the different tenses and moods; cf.
P.III.4.78.

लालविहारिच a grammarian of the nineteenth century who wrote a gloss on Nāgesa's Paribhāṣenduśekhara.

लावस्था the original condition of ल् or the personal endings before the affixes तिप्, तस् and others are substituted for them in accordance with the time or mood, as also the person and the number in view;cf. लावस्थायामेव स्यादयः, सार्वधातुके स्यनादयः M. Bh. on P.III. 1. 33.

छि a common term used (1) for the a orist vikarana affix च्लि for which सिन्, वस, अङ् etc. are substituted as prescribed; (2) for लिट् and लिङ् affixes; e.g. मन्त्रे घसह्र्रणशवृदहाद्-वृच्कुगमिजनिम्यों ले: P.II.4.80.

छिङ् general term for the affixes called ভিছ্ (optative) which includes the potential (विधिलिङ्) and the conditional (আহাার্লিঙ্ছ) affixes; .cf. विधिनमन्त्रणामन्त्रणाधीष्टसंप्रक्षप्रधिनेषु लिङ् and आहिषि लिङ्लोटौ P. III. 3. 161 and 173.

কিছু (1) sign or characteristic mark; generally the mute letter prefixed or suffixed to roots, affixes, or augments and their substitutes with a specific purpose; cf. किंचिलिड्रमासच्य वक्ष्यामि M. Bh.on I.1.1 Vart.7, अवयवे कतं लिङ्गं समुदायस्य विशेषकं भवति M. Bh. on P.I.3.62 Vart. 5; (2) proof, evidence (प्रमाण); the word is often used in the Paribhāsenduśekhara and other works in connection with a rule or part of a rule quoted as an evidence to deduce some general dictum or Paribhāsā; (3) gender; cf. लिङ्गं स्त्रीलिङ्गपुंलिङ्गनपुंसकानि Kāś. on P. II. 3. 46; cf. प्रातिपादिकप्रहणे लिङ्गविशिष्टस्यापि प्रहणम्. Par. Sek.Pari.71.The gender of a word in Sanskrit language does not depend on any specific properties of a thing; it simply depends on the current usage; cf. लोकाश्रयत्वाहिङ्गस्य which is often quoted Mahābhāṣya; cf. M. Bh. on P. II. 1.36, II.2.29, II.4.12, IV. 1.3, V.3.66, V.4.68, VIII.1.15. details see Mahābhāsya on P.IV.1. 3 where after a long enlightening discussion the definition संस्त्यानप्रसवी लिङ्गम् is given.

लिङ्गनिर्णयभूषण a work on genders by a southern grammarian अणीयाचार्य.

लिङ्गवाचकप्रत्यय an affix such as आ (टाप, डाप, चाप) or ई (डीप, डीप, डीन्) which is added to a masculine base; cf. P.IV. 1.3 to IV.1.77. তিক্লবিহ্যিন্দ্রমন্থল inclusion of the feminine form of a word when a word in the masculine gender is used in a rule, for certain operations such as the application of affixes and the like;cf. the usual dictum regarding this practice viz. the Paribhāṣā মানিদবৈক্সন্থ তিক্লবিহান্থনাদি স্বল্ম Par. Sek. Pari. 71. as also M. Bh. on P. IV. 1. 1 Vārt. 5 to Vārt. 15 for places of the application of the dictum and those of its rejection.

लिङ्गविशिष्टपरिभाषा the dictum to include the feminine form of a when in a rule word is used in the masculine gender: प्रातिपदिक्रमहणे **ि छिङ्कविशिप्टस्यापि** प्रहणम् Par. Sek. Pari. 71. See लिङ्ग-विशिष्ट्रग्रहण.

लिङ्गच्यत्यय transposition of genders, as noticed often in Vedic language; e. g. मधोर्यह्माति or मधोरतृप्ताः for मधुनः; cf. M.Bh. on P. I. 4.9.

िङ्गानुशासन lit. science of genders; a short comprehensive old treatise on the gender of words attributed to Pāṇini as its author. Other works with the same designation are attributed to वामन, दुगोंचम and others.

खिङ्गानुशासनटीका name of a commentary on Pāṇini's लिङ्गानुशासन; some commentaries of this kind are the लिङ्गार्थचन्द्रिका by सुजनपण्डित,लिङ्गार्थचन्द्रिकाश्चार by चकार, लिङ्गानुशासनटीका by दुर्गोत्तम and लिङ्गानुशासनटीका by तारानाथ.

लिङ्गार्थचन्द्रिका see लिङ्गानुशासनटिका.

छिङ्प्रत्ययार्थ sense of the optative and the potential moods given or expressed by affixes under the common name छिङ् prescribed by P.III.3.161, 164, 173.

छिद् an affix of the perfect tense; cf. परोक्षे छिट् P.III.2.115 for which the specific affixes पल्, अतुस् उस् etc. are substituted after roots which take Parasmaipada affixes. Before the lit

affixes, a monosyllabic root reduplicated while dissyllabic roots denominative and secondary roots, formed by adding an affix to an original root, take the affix आम after which all 'lit' personal endings are dropped and the forms of the roots कृ,भू and अस with the necessary personal-endings, are placed immediately after the word ending in आम, but often with the intervention of a word or more in the Vedic language and rarely the classical language; cf. ਹੋ पातयां प्रथममास पपात पश्चात: cf. कारप्रत्यया-दाममन्त्रे लिटि P.III.1. 35 to 42.

हित् an affix marked with the mute letter ल्such as ल्युट्, तातिल्, तल्, तासिल्, विषल्, भक्तल् etc. where the mute ल् signifies the acute accent for the vowel of the base which immediately precedes the affix; e.g. चिकिषिकः; in which the vowel ई is acute; cf. लिति VI.1.193.

खित्स्वर the acute accent for the vowel immediately preceding the affix caused by that affix being marked with the mute consonant ल्. See लित् above; cf. अनुदात्तलं क्रियतां लित्स्वर इति किसन कर्तन्यम् M. Bh. on P. II. 4.33.

European grammarian belonging to Breslau who lived in the last quarter of the nineteenth and the first quarter of the twentieth century. He made a critical study of Sanskrit grammar and edited the Cāndra Vyākarana and the Ksīrataranginī.

প্ত elision of an affix or its part in the process of the formation of a word as prescribed by the specific mention of the words ভুক্, মন্ত and ভুপ্ which have the syllable ভু as common. The specific feature of

the elision by the use of these letters is the prohibition of any such operation for the preceding base as is conditioned by the elided affix; cf. प्रत्ययलेष प्रत्ययलक्षणम् । न लुमताङ्गस्य P.I.1.62,63.

ন্তুক্ (1) disappearance (ভুল্থন হনি ভূক্); a term used by Pāṇini for the disappearance of an affix or its part under specified conditions as prescribed by a grammar rule with the mention of the word ভূক্; e.g. সন্থাব্য ভূক্ষভূত্ব: P.I.I.61; (2) augment ভূ added to the root ভা in the sense of melting (an oily thing); cf. ঘূর্ন বিভাভযানি. See Kāś. on P.VII.3. 39.

लुग्विकरण a term used by grammarians especially in the Mahābhāsya; (cf. M.Bh. on P.I. 2.4, I.2.12, II.4. 77 etc.) for such roots as have their Vikaraṇa (conjugational sign) dropped by a rule with the mention of the word ढुक्;e.g. the roots of the second conjugation as contrasted with other roots; cf. लुग्विकरणालु- विकरणसे एक्टिकरणस्य Par. Sek. Pari. 90

ন্তু an affix applied to a root, showing action of immediate past time as contrasted with affixes called ভিত্ৰ or ভত্ত. The affix দুভ্ is found used, however, in the sense of the past time in general, and irrespective of time in Vedic Literature; cf. ভাৰবাৰ প্ৰভুক্তভ্ভিত: P. III. 4.6. The conjugational affixes নি, ন:, etc. are substituted for দুভ্ as for the lakāras of other tenses and moods and the distinguishing sign or নিক্লা is added to a root before the affix called ভুড্; cf. ভিত্ত দুঙ্গি and the following P. III. 1.43 etc.

ञ्जद general name for affixes of the first future which are added to roots when the future time is not the present day, but the next and the succeeding ones; cf. अनदाती ञ्चर

P. III. 3.15. The affixes ति, तः etc. replace the affix ढुट् in accordance with the number and person in view; cf. तिप्तिस्झिसिष् P. III. 4 78.

छुप् disappearance (खुप्यते इति लुप्); a term used by Panini with reference to the disappearance of an affix or its part under specified conditions by the express mention of the word ভুণু. Although after the disappearance of an affix no operation for the base before, can take place as conditioned by the affix, i. e. although there is no प्रत्ययलक्षण, still, when the disappearanee is mentioned as हुप्, the base gets the gender and number of that original form of it which existed before the affix, has disappeared, was applied; cf. कुरवः देशः, चञ्चेव पुरुषः चञ्चाः cf. लुपि युक्तवद् व्यक्तिवचने. P. I. 2,51 and Kāśikā thereon.

द्वस that which has been elided or dropped during the process of the formation of words. As elision or लेप is looked upon as a kind of substitute, in short a zero-substitute, the convention of the substitute being looked upon as the original one, viz.the sthānivadbhāva, applies to it.

स्तिनिर्देष्ट supposed to be mentioned although not seen or heard in a particular rule, for the sake of bringing about some grammatical operation with a view to arriving at some desired forms; cf. ल्रान्तस्येत्यत्र वकारोऽपि निर्दिश्यते । किं वकारो न ध्रयते । छुनानिर्दिशे वकारः । M. Bh. on P. I.1.3. Vart. 10; cf. also M. Bh. on I.3.7, III. 1.44 etc.; also cf. क्किति च P. I. 1.5 where the consonant ग is supposed to be present in the word क्किति.

लुप्तांवेकरण a term applied to roots after which the conjugational sign is dropped; e. g. roots of the second and third conjugations; cf. न लुप्तविकरणेभ्योनुदात्तत्वं भवति, M. Bh. on P. VI.1. 186.

छुमत् lit. possessed of the syllable or wording छ. The word is applied to the terms लुक्, श्लु, and लुप् which contain the letter छ and which all mean the disappearance of a wordelement; cf. न छमताङ्गस्य । छक् श्लु छुप् एते लुमन्त: S.K. on P. I. 1.63.

ন্ত common term for the affixes ভূহ (second Future) and ভূছ (conditional), the remnant being ভূ after the mute consonants ছ্ and হ have been dropped.

हुन्ह general term for the personal affixes of the conditional, which are applied to a root to show the happening of an action only if there was another preceding action, both the actions being expressed by लुङ् or conditional affixes; e.g. देवश्रेदवर्षिण्यत् सुभिक्षमभिविण्यत्: cf. लिङ्निमिन्ते लुङ् कियाति पत्ती P. III.3.139, 140. लुङ् is also used under certain other conditions when some specific particles are used; cf. P.III.3.141-146, 151.

लूट् a general term for the general affix लू of the second future which is applied in the sense of future time in general, without any specific conditions, the affixes ति, त:, अन्ति being substituted for the लू and the sign (vikarana) स्थ being added to the root; cf. P.III.3. 3 and III. 3. 133. The terminations अत and आन are substituted for the affix लूट् to form future participles; e.g. भिव-ध्यत, एधिध्यमाण, cf. लूट: सद्वा P.III.3.14.

होसा one of the varieties or developments of the ऋमपाठ or the artificial recitation of the separate words of the Samhitā, छेद a general term for the affixes of the Vedic subjunctive, the usual personal-endings ति, तस् etc. being substituted for छेट् as in the case of other tenses and moods. The augments अद and आद are sometimes prefixed to the छेट् affix and the sign (विकरण) स् (सिष्) is sometimes added to the roots. The forms of छेट् are to be arrived at as they are found actually used in Vedic language, even by placing personal-endings of a person or number different from what is actually required.

छेश such a slow or indistinct utterpronunciation of the ance or letter यु or वू preceded shows that it is almost dropped. This indistinct or slurred utterance of य or व, which is described as advocated by the Prātisākhyakāra Vātsapra, corresponds to the utterance of yor q with a very low tone as mentioned by Pāṇini in the rule ब्योर्लवप्रयत्नतरः शाकटायनस्य; e.g. आप उन्दन्तु; या जाता ओषधयः etc.; cf. लेशो वात्सप्रस्य एतयोः T.Pr. 10.23; cf.also लेशेन प्रयत्नशैथिल्येन ब्यञ्जनानां वचनम्चारणं कियते Uvvata on R.Pr. XIV.5.

रेड्ड a grammatical operation or a rule of grammar concerning gender; cf. यदि तींह कृत्स्नः पदार्थोभिधीयते लेड्डाः सांख्याश्च विधयो न सिध्यन्ति M.Bh. on P.II.2.24 Vart. 8, 9.

स्रोक a term used in the Mahābhāṣya in contrast with the term वेद, signifying common people speaking the language correctly; the term छोक is also used in contrast with the term शास्त्र or its technique; cf. यथा लोके or लोकत: M. Bh. on P.VII. 1. 9, I.1.44 Vārt. 3; also cf. न यथा लोके तथा ज्याकरणे M. Bh. on P.I.1.1 Vārt. 7. लोकविज्ञान use or understanding of a word current among the people; cf. अन्तरेणैव वचनं लोकविज्ञानात्सिद्धमेतत् M. Bh. on P. I,1.21 Vart. 5.

ন্তাকাপ্তথনৰ dependence upon the people for the use. The phrase ন্তাকাপ্তথনান্তিব্ধন্য, referring to the fixation of gender depending entirely on the people's usage, is very common in the Mahābhāṣya; cf. M.Bh. on P. II.1.36, II.2.29, etc.

होंद् a term for the affixes of the imperative mood or आजार्थ, applied to roots in the same sense in which the 'hin' affixes are applied; cf. विधिनिमन्त्रणामन्त्रणायिष्टसंप्रश्रार्थनेषु लिङ्। लोट् च P. III.3.161, 162. These affixes, specifically the affixes of the second person singular and plural, are also applied in the sense of frequency or collection, to a root when that root is repeated to show that frequency; e.g. लुनीहि लुनीहि इति लुनाति; भ्राष्ट्रमट मठमट खबूरमट इति अटित; cf. Kās. on P. III. 4. 2,3.

लोप disappearance of a word or part of a word enjoined in grammar for arriving at the required forms of a word; cf. अदर्शन लेप: P. I.1.52; cf. अदर्शनमश्रवणमनुष्चारणमनुपलन्धिरभावे। वर्णवि-नाश इत्यनर्थान्तरम् । एतः शब्दैर्योथोभिधीयते तस्य लोप इतीयं संज्ञा भवति Kas. on P.I.l. This disappearance in the case of an affix is tantamount to its notional presence or imaginary presence, as operations caused by it do take place although the word disappeared; cf. has element प्रत्ययलोपे प्रत्ययलक्षणम् । प्रत्यये लुतेपि तद्धेतुकं कार्य भवति Kāś. on P. I.1.62.

स्रोपबस्थि the superior strength or superiority of elision as a grammatical operation in contrast with other operations, by virtue of which the elision, which is prescribed, takes place first and then other operations get a scope for their application; cf. सर्वविधिम्यो लोपविधिवेलीयान् Par. Sek. Pari. 93.

लोमस्य the utterance of an aspirate letter rather harshly, with a stress on it, when that utterance is looked upon as a fault; cf. ऊष्मणां घोषाणां लोमस्यमसौकुमार्य क्षेडनम् अधिको वर्णस्य व्वनिः Uvvata on R. Pr. XIV.6.

लोमादि a class of words headed by the word लोमन् to which the tad. affix, द्या, in the sense 'possessed of' is added optionally along with the usual affix मत् (मतुप्); e.g. लोमदाः, लोमवान्, रोमदाः रोमवान् बश्चदाः, हरिद्याः, कपिदाः etc. cl. Kās. on P. V.2.100.

स्रोहितादि(1)a class of words headed by लोहित to which the affix क्यव् (य) is added in the sense of 'becoming', to form a denominative root-base which gets the verb-endings of both the padas; e. g. लोहितायति, लोहितायते; निद्रायति, निद्रायते; the class लोहितादि is considered as आकृतिगण so that similar denominative verb-bases could be explained; cf. Kas. on P.III.1. 13; (2) a class of words headed by छोहित, to which the fem. afflx ष्फ (आयनी) is added after they have got the taddhita afflx যুসু added to them in the sense of 'a grandchild'; e. g. लौहित्यायनी, कात्या-यनी etc.; cf. Kāś. on P. IV. 1.18.

लोकिक prevalent in common utterance of the people as contrasted with वैदिक; cf. यथा लौकिकवैदिकषु कृतान्तेषु M.Bh.on Ahnika 1.See लोक above.

ह्यप् krt affix य substituted for the gerund termination क्ला when the root, to which ला has been applied, is preceded by a prefix with which it (the root with the affix) is comcompounded; cf. समासेऽनज्यूचे क्लो ल्यप् P. VII. 1. 37.

ल्यु kit affix य changed into अन in the sense of an agent applied to the root नन्द् and others (after which it is seen actually used in language); e.g. नन्दनः, दूषणः, साधनः, रोचनः cf. नन्दिप्राहिपचादिस्यो ल्युणिन्यचः P.III.1.134.

ल्युद् kit affix अन in the sense of verbal activity as also in the sense of an 'abode' or 'an instrument'; cf. P. III.3.113,115, 116, 117.

ल्वांदि a class of roots, headed by the root छ, the past. pass.part. affix त placed after which becomes changed into न; e.g. छन:, छनवान; जीन:, जीनवान:, etc. cf. Kāś.onP.VII. 2.44.

व

व (1) fourth letter of the class of çonsonants headed by यु, which are looked upon as semi-vowels; व is a dental, soft, non-aspirate consonant pronounced as ब in some provinces and written also sometimes like ब्, especially when it stands at the beginning of a word: (2) substitute for उ which is followed by a vowel excepting उ; e. g. मधु+अरि: = मध्यरि:; cf. इको यणचि P. VI, 1. 77; (3) the consonant g, which is sometimes uttered with very little effort when it is at the end of a word and followed by a vowel or a semivowel, or a fifth, fourth or third consonant or the consonant \(\xi_{\cdot} \) In such cases it is called लघुच्चारणः cf. यस्योच्चारणे जिह्वाग्रोपाग्रमध्यमूळानां देशियल्यं जायते स लघुच्चारण: S. K. on P.VIII.3. 18;(4) solitary remnant of the affixes किंपु,किन्, ण्वि and the like, when the other letters which are mute are dropped and the affix the or the like becomes a zero affix. This ৰু also is finally dropped; वेरपृक्तस्य P. VI.1.67.

the sense of an agent applied to the | व (1) the semivowel व; see व; (2)

313

personal-ending substituted for वस in the perfect (लिट्) first person (उत्तमपुरुष), and in the present tense in the case of the root विद; cf. परस्मैपदानां गलतसम o and विदो लटें। वा. P. III. 4.82,83; (3) krt affix किप, किन or वि of which only व remains; cf. आनेगन्तोञ्चतौ वप्रत्यये P. VI. 2.52; cf. also विष्वर्यवयोश्च टेरद्यञ्चतौ वप्रत्यये VI.3.92 the affix is mentioned as वृत्रत्यय by Pānini, but, in fact. it is ब्, अ being added for ease in pronunciation; (4) tad. affix in the sense of possession added along with the other affixes इन, इक, and वत to the word केश and to some other words such as मणि, हिरण्य, राजी, अर्णस etc. as also to गाण्डी and अजग: cf. P. V. 2. 109, 110.

चैशादि a class of words headed by the word वंदा, the word भार placed after which gets the taddhita affixe added to it, as prescribed in the senses 'takes it', 'carries it' or 'produces it'; e.g. बांग्रभारिक:; cf. Kās. on P.V. 1.50. The tad. affixes as prescribed in the senses mentioned above are added to the words वंदा etc. and not to भार according to some commentators; e.g. बांग्रिक:, कोटजिक: etc.; cf. Kāś. on P.V. 1.50.

ৰকাৰ the consonant বু with the vowel স and কাৰে being added for facility of utterance; cf. T. Pr. I. 17, 21, also বৃদ্ধিকাৰ: P. III.3.108, Vart. 3.

or prescribed; the word is frequently found used by the Vārttikakāra when he suggests any addition to, or modification in Pāṇini's rules. Sometimes, the word is added by the author of the Mahābhāṣya in the explanation of a Vārttika after stating what is lacking in the Vārttika.

वक्त्र mouth, or orifice of the mouth which, in general is the place of utterance for all letters, but especially for the vowel अ; cf. सर्व- मुख्तस्थानमवर्णस्य केचिदिच्छन्ति l

वङ्गसेन a grammarian who wrote a grammatical work on verbs named आख्यातप्रकरण.

বৰন (1) lit. statement; an authoritative statement made by the authors of the Sūtras and the Varttikas as also of the Mahabhasya; cf. अस्ति ह्यन्यदेतस्य वचने प्रयोजनम् M. Bh. on Siva Sūtra 1 Vārt. 1. The word is also used predicatively in the sense of वक्तव्यम by the Varttikakara; cf. ल्रति ल वावचनम् , ऋति ऋ वावचनम् ; (2) number, such as एकवचन, द्विवचन, बहुबचन etc.; cf. वचनमेकत्वद्वित्वबहुत्वानि Kas.on P.I.2.51; cf छिप युक्तिवद् ब्यक्ति-वचने । लुकि अभिधयविक्षज्जवचनानि भवन्ति। लवणः सूपः। लवणा यदागूः। M.Bh.on P.I. (3) expressive word; cf. गुणवचनब्राह्मणादिभ्यः कर्मणि च P. V.1.124 where the Kāśikā explains word गुणवन्त्रन as गुणमुक्तवन्ता गुणवन्तनाः; cf. also the terms गुणवचन, जातिवचन, कियावचन etc. as classes of words; cf. also अभिज्ञावचेन लुट् P.III.2.112; (4) that which is uttered; cf. मुखना-मुखसहित। नासिका सिकावचनोननासिकः । मुखनासिका । तथा य उच्चार्यते असौ वर्णः Kās. on P. I.1.8.

चज्राञ्चिति the form of वज्र or thunderbolt, in which (form) the Jihvāmūliya (letter) is shown in writing; cf. वज्राकृतिर्जिह्वामूळीय: Kāt. I.1.17. See जिह्वामूळीय.

वत् substitute for मत् of मतुप्. See मतुप्.

चाति (1) tad. affix वत् in the sense of similar activity or thing; e.g. राजवद्वतेते, मथुरावत् सुन्ने प्राकारः; cf. तेन तुस्यं किया चेद्वतिः । तत्र तस्येव P.V.1.115, 116; (2) tad. affix वत् in the sense of deserving; e.g. राजवत् पालनम्; cf. तदहम् P.V.1.117; (3) tad. affix वत्

applied to prefixes in Vedic Literature without any sense of its own; e.g यदुद्वतो निवतो याति बप्सत्; cf. उपसर्गा-च्छन्दसि धात्वर्थे P.V. 1. 118.

वातिनिर्देश specific statement by putting the word वत् for the sake of extended application (अतिदेश); e.g. ब्राह्मणवदधीते; cf. स तर्हि वितिनिर्देश: कर्तव्यः। न झन्तरेण वितमतिदेशो गम्यते। M.Bh. on P. I.1.23 Vart. 4.

वती the posssssive affix वत् (मतुप्) with fem. ई added; cf. विश्वदेव्यसोमो वत्याम् (दीर्त्रमापद्यते) V.Pr.III.117.

वतु or बतुप् tad. affix बत् applied to the pronouns यत्, तद्, एतद्, किम् and इदम् in the sense of measurement; e.g. यावान्, तावान्, एतावान्, कियान्, इयान्, कीवान् ; टि. यत्तदेतेभ्यः परिमाणे बतुप्, किमिदेभ्यां वो घः P. V. 2.39,40. Words ending with this affix बतु are designated संख्या; cf. बहुगणवतुडति संख्या P.I.1.23.

वनमान्नि a grammarian of the seventeenth century who wrote a commentary named मतोन्मजा on Kondabhatta's Vaiyākaranabhūṣana and a grammar work named सिद्धान्ततत्त्विवेक.

वनस्पत्यादि a class of compound words headed by वनस्पति which retain the original accent of the members of the compound, as for example, in the compound word वनस्पति both the words वन and पति have got their initial vowel अ accented acute; cf. Kāś.on P.VI.2.140.

चनिष् kit affix वन् applied in the sense of agent in Vedic literature to a root ending in आ and in spoken language to any root where forms are seen; e.g. भूरिदाना, विजावा; cf. आतो मनिन्कानिज्वानिष्ध। अन्येभ्योषि दृक्यते P. III. 2. 74, 75.

चर or वस्च krt affix वर applied to the roots स्था, ईश्, भास, पिस् and कस्, as also to the intensive base of या in the sense of a habituated agent; e.g. स्थावर, ईश्वर, यायावर etc. cf. स्थेशभास- पिसकसो वरच् । यश्च यङ: P. III. 2, 175, 176

वरणादि a class of words headed by वरण which have the taddhita affix elided, if it is added to them in the four senses mentioned in P.IV.2.67-70; cf. वरणानामदूरमवं नगरं वरणा; । कहुकबदर्श अदूरमवो प्रामः कहुकबदरी । cf. Kāš. on P.IV.2.82.

वरदराज a scholar of grammar and a pupil of Bhattoji Diksita who flourished in the end of the seventeenth century and wrote abridgments of the Siddhanta-kaumudi for beginners in grammar named लघुसिद्धान्तकोसुदी and मध्यसिद्धान्तकोसुदी as also धातुकारिकावली and गीवीणपदमञ्जरी. The work under the name सार-सिद्धान्तको भदी, which is the shortest abridgment, is, in fact, the লম্ব-सिद्धान्तकौमुदी itself. It is possible that the auother first prepared the सार-सिद्धान्तकौमदी and then, he himself or a pupil of his, put additional necessary matter and prepared the Lagliusiddhānta-kaumudī.

वररांचे (i) a reputed ancient grammarian who is identified with Kātyāyana, the prominent author of the Varttikas on the Sutras of Pānini. Both the names ब्रहिंच and कात्यायन are mentioned in commentary works in connection with the Vārttikas on the Sūtras of Pānini, and it is very likely that Vararuci was the individual name of the scholar, and Kätyāyana his family name. The words कात्य and कात्यायन are found used in Slokavārttikas in the Mahäbhäsya on P.III.2.3 and III.2.118 where references made are actually found in the prose Vārttikas (see कविषो सर्वत्र प्रसाराणभ्यो ङ: P.III. 2. 3 Vart. । and स्मप्रा भतमात्रे न समप्राद्यतने P.III.2.118 Vart. 1) indicating that the Slokavārttikakāra believed that the Vārttikas were composed by Kātyāyana. There is no reference at all in the Mahābhāşya to Vararuci as a writer of the Varttikas; there is only one reference which shows that there was a scholar by name Vararuci known to Patanjali, but he was a poet; cf. वाररूचे काव्य in the sense of · 'composed' (कृत and not प्रोक्त) by वरहाचि M. Bh. on P. IV. 2.4. (2) वरहाचि is also mentioned as the author of the Prakrta Grammar known by the name प्राकृतप्रकाश or प्राकृतमञ्जरी. वरहाचे, who also was कात्यायन by Gotra name, was a grammarian later than Patafijali, who has been associated with Sarvvarman. (the author of the first three Adhyāyas of the Kātantra Sūtras), as the author of the fourth Adhyaya. Patanjali does not associate वरराचि with Kātyāyana at all. His mention of वरहचि as a writer of a Kavya is a sufficient testimony for that. Hence, it appears probable that Kātyāyana, to whom the authorship of the Vājasaneyi Prātiśākhya and many other works allied with Veda has been attributed, was not associated with Vararuci by Patañjali, and it is only the later writers who identified the grammarian Vararuci, who composed the fourth Adhyāya of the Kātantra Grammar and wrote a Präkrit Grammar and some other grammar 'works, with the ancient revered Kātyāyana, the author of Värttikas, the Vajasaneyi Prātisākhya and the Puspasūtra; (3) There was a comparatively modern grammarian named वरस्चि who wrote a small treatise on genders of words consisting of about 125 stanzas with a commentary named Lingavṛtti, possibly written by the author himself. (4) There was also another modern grammarian by name वरसचि who wrote a work on syntax named प्रयोगमुख्यमण्डन discussing the four topics कारक, समास, तदित and कृदन्त.

वरवर्णिनी name of a commentary on the Paribhasendusekhara written by Guruprasada Sastri, a reputed grammarian of the present cenutry.

चराहादि a class of words headed by वराह which have the taddhita affix क (कक्) added to them in the four senses mentioned in P. IV. 2.67-70 e.g. वाराहकम्, पालाशकम् etc.; cf. Kāś. on P. IV. 2.80.

वरी feminine form of the affix वनिप्; e.g. कतावरी, शर्वरी; etc.; cf. वनो र च P. IV. 1.7.

वर्ग name given to the different classes of consonants which are headed by an unaspirate surd; e. g. क्वगं, च्वगं, ट्वगं, त्वगं and प्वगं. The several consonants in each group or class, are, in their serial order, named वर्गप्रथम, वर्गद्वितीय etc. On the analogy of these five classes, the semivowels are called by the name युवगं and sibilants, are called by the name श्वगं.

वस्योदि a class of words headed by the word वस्ये which have their initial vowel accented acute when they stand as second members of a tatpurusa compound other than the karmadhāraya type of it; e. g. वासुदेववस्य:, अर्जुनपस्य:; cf. Kās: on P. VI. 2.131.

and found used generally in the

masculine gender, but occasionally in the neuter gender too; e. g. उपादिश इमे वर्णा: M. Bh. Āhnika 1. also मा कदाचिदवंण मूत् M.Bh. on Śiva Sūtras 3, 4.

वर्णप्रहण mention of a grammatical operation concerning a single letter or caused by a single letter; cf. न वर्णप्रहणेषु (एषा अर्थवत्परिभाषा प्रवति). Sīradeva Pari 10.

चर्णपाठ serial mention or enumeration of letters in the fourteen Siva Sutras. The word is also used in the sense of the alphabet given in the Prātiśākhya and grammar works; cf. एवं तर्हि वर्णपाठ एव उपदेश: करिंध्यते M. Bh. on P. I. 1.69.

বর্ণমন্ধায় a minor work upon letters and their nature by a grammarian named Ghanasyāma.

वर्णराशि the collection of letters as mentioned in works on grammar and Prātiśākhyas; cf. इति वर्णराशिः कमक्ष R. Pr. I. 10.

वर्णविकार change of one letter into another (in the formation of a word) the discussion of which is looked upon as one of the features of grammar; cf. लोपागमवर्णविकारज्ञो हि सम्यावेदान्यरिपालायेष्यरि.M.Bh. Ahnika 1.

वर्णविचाल disappearance of a letter; cf. वर्णाश्रय: प्रत्ययो वर्णविचालस्यानिमित्तम् । दाक्षि:। M. Bh. on. P. I. 1. 39 Vārt. 10.

वर्णाविधि an injunction or operation conditioned by a single letter; लोदेशो वर्णाविधर्मवत्यन्तरङ्गत: M. Bh. on P. 1.4.2.

वर्णविपर्यय changing the place of letters; cf. सिंहा वर्णविपर्ययात् Vart 20.

वर्णविवेकचिन्द्रका a minor grammar work on the nature of letters by a grammarian named काशीनाथ.

वर्णक्यत्यय transposition of letters; cf. वर्णक्यत्यये चार्थान्तरगमनात् (अर्थवन्तो वर्णाः);

M. Bh. on Śiva Sūtra 5; cf. कृतेस्तर्कुः कसे: सिकताः । हिंसे: सिंह: । वर्णव्यत्यया नार्थ-व्यत्ययः । M. Bh. on. Śiva sūtra 5.

वर्णसमाम्राय a collection of letters or alphabet given traditionally. Although the Sanskrit alphabet has got everywhere the same cardinal letters i.e. vowels স, ছ etc., consonants क. ख etc., semivowels यू, र, लू, व, sibilants হা বু মু ই and a few additional phonetic units such as अन्स्वार. विसर्ग and others, still their number and order differ in the different traditional enumerations. has not mentioned them actually but the fourteen Siva Sūtras, on which he has based his work. mention only 9 vowels and 34 consonants, the long vowels being looked upon as varieties of the short ones. The Siksa of Panini mentions 63 or 64 letters, adding the letter ळ (বু:ম্মৃষ্ট); cf. সিष্টি: चतःषिथवीं वर्णाः शम्भुमते मताः Pānini Šiksā. St.3. The Rk Prātišākhya adds four (Visarga, Jihvāmūlīya, Upadhmānīya and Anusvāra) to the forty three given in the Siva Sutras and mentions 47. The Taittirīya Pratisakhya mentions 52 letters viz. 16 vowels, 25 class consonants. 4 semivowels, six sibilants (রু, বু, মু, 夏,×垂,×互,) and anusvāra. The Vajasaneyi Pratisakhya mentions 65 letters 3 varieties of अ, इ, उ, ऋ and ल, two varieties of ए, ऐ, ओ, খা, 25 class-consonants, four semifour vowels. sibilants, जिह्वामुलीय, उपध्मानीय, विसर्जनीय, नासिक्य and four यम letters; cf. एते पञ्चषष्टिवर्णा ब्रह्मराशिरात्मवाच: V. Pr. VIII. 25. The Rk Tantra gives 57 letters viz. 14 vowels, 25 class consonants, 4 semivowels, 4 sibilants, Visarga Jihvāmūlīya, Upadhmānīya, Anunāsika, 4 yamas Anusvāras. The Rk two

Tantra gives two different serial orders, the Uddesa (common) and (traditional). The the Upadesa common order or Uddeśa gives the 14 vowels beginning with 3, then the 25 class consonants, then semivowels, the four the four sibilants and lastly the eight avogavāhas, viz. the visarjanīya and others. The traditional order gives the diphthongs first, then long vowels (आ, ऋ, ऌ, ई and ऊ) then short vowels (ऋ, ऌ, इ, उ, and lastly अ), then semivowels, then the five fifth consonants, the five fourths, the five thirds, the five seconds, the five firsts, then the four sibilants and then the eight ayogavāha letters and two Ausvāras instead of one anusvāra. Panini appears to have followed the traditional order with a few changes that are necessary for the technique of his work.

वर्णानशैवरच the view that letters do not possess the sense, as individually in every letter no separate sense is seen; cf. अन्धेकास्त etc. M. Bh. on Siva Sūtra 5, Vārt. 14 and 15.

वर्णाधेवरव the theory or view that individual letters are severally possessed of different senses. For instance, the difference in the meanings of the words कूप, यूप, and सूप is due to the difference in their initial letter. The theory is not acceptable to the Vaiyākaraṇas nor the theory वर्णानर्थ-वस्त्र given above. They follow the theory of संवातार्थवन्त्र i. e. sense given by a group of words together. See M.Bh. on Siva Sūtra 5, Vārttikas 9 to 15.

वर्णाश्रय a grammatical operation depending upon a single letter i.e. an operation caused by a letter singly; cf. वर्णाश्रये नास्ति प्रत्ययस्वधाम् । Par.Śek.Pari.21; cf.also वर्णाश्रय: प्रत्ययो वर्णविचालस्यानिमित्तम् 1 दाक्षि:1 M.Bh.onP. I.1.39 Vārt.10.

वर्णिकुबेरनाथ or वर्णिकुबेरानन्द an old writer on grammar who has written a work named शब्दविवरण on the meanings of words. The work forms a part of his bigger work दानमागवत. Both the works are incomplete. The शब्दविवरण is based mostly upon ancient grammar works of Patañjali Vararuci, Vārttikakāra, Sarvavarman, Bhartihari and others.

वर्णैकदेश a part or a portion of a combined letter i.e.संयुक्तस्वरor संयुक्तव्यञ्जन. diphthongs or संयुक्तस्वरं are divisible into two Svaras, for instance ऐ into आ and ए, औ into आ and ओ. Similarly double consonants like क्कू, च्चू, क्मू, क्त etc. are also divisible. Regarding the point raised whether the individual parts can be looked upon as separate letters for undergoing or causing a grammatical operation, the decision of the grammarians is that they cannot be looked upon as separate, when they are completely mixed as the dipthongs;cf.नाव्यपत्र्वतस्यावयवस्य तद्विधिर्यथा द्रव्येषु M. Bh. on Siva Sūtra 3, 4 Vārt, 6.

वर्ते a term used by ancient grammarians and later on by commentators for compound words; cf. वर्तनं वर्त; समास: Nyāsa on Kāś. II.4.15.

वर्तमान the present tense; cf. वर्तमान छट् P.III.2.123; cf.also क्तस्य च वर्तमान P. II 3.67; also वर्तमानसामीन्ये वर्तमानवद्वा P. III. 3.131.

वर्तमाना a term used by ancient grammarians for the present tense, along with the term वर्तमान also; cf. यदा हि बुद्धिकर्म तदा वर्तमाना भविष्यति, M.Bh. on P. III.3.133 Vart.8.

वार्तिन from वर्त which means a compound; see वर्त. (1) The term वर्तिन् or

नितंपद is used in the sense of a member of a compound; cf. नितंप्यास्तीति वर्ति समासानयन भूतम् Nyāsa on P. II. 4.15. (2) The term नितं न is also used for a syllable (अक्षरम्); cf. नितं R.T.47, explained by the commentator as अकारादिषु नितं न्यञ्जनं नितं चाप्यकरं भनित। cf. also गुर्वक्षराणां गुरुवृत्ति सर्ने R. Pr. XVIII.32.

वर्स्य lit. gingival, or produced at the gums; the letter र according to some scholars who believe that र is produced at the root of the teeth i.e. at the gums; cf. एके आचार्या रेफं वर्स्यभिच्छन्ति । वर्से भवो वर्स्यः । वर्स्यञ्देन दत्तमूलादुपरिष्टादुच्छूनः प्रदेशः (gums) उच्यते Uvvata on R.Pr.I.20.

वरस्येत future, belonging to future;cf. बर्त्यंत्रवृत्त्या इह कार्याणि क्रियन्ते Paribhāṣā 87 given by Sīradeva.

वधेमान (1) a long vowel;(2)name of a famous Jain grammarian, disciple of Govindasūri, who lived in the beginning of the twelfth century A.D. and wrote a metrical work on ganas or groups of words in grammar, named गणरत्नमहोद्वि, and also a commentary on it. The work consists of 8 chapters and has got some commentaries besides the well-known one by the author himself. He also wrote two other works on grammar कातन्त्रविस्तर and कियागुप्तक as also a few religious books.

वर्ष name of an ancient scholar of grammar and Mīmāmsā, cited by some as the preceptor of कारवायन and Pāṇini. If not of Pāṇini, he may have been a preceptor of Kātyā-yana.

बस्त्यें or वस्त्रें gingival, produced at the gums; the word वस्त्रें is probably the correct word meaning the root of the teeth or gums; the word वसे was also used in the same

sense as वस्वे from which the word वस्वे could be derived. वस्वे and वस्वे are only the variant pronunciations of वस्वे and वस्वे. The word वस्त्वे, with त inserted between र and स्, is given above as explained by Uvvata from वस्ते. It is very likely that वर्त्से is wrongly written for वस्ते or वसे.

चल् short term (प्रत्याहार) for consonants excepting यु; cf. लोपो न्योवील P. VI. 1.66; आर्धधातुकस्येड् वलादे: P. VII.2.35.

चल (1) tad. cāturarthika affix वलच् applied to the word शिखा in the four senses country and others; e.g. शिखावलं नगरं देशो वा Kāś.on P.IV.2.89; (2) tad. affix वल in the sense of possession applied to words रजस्, इशि and others as also to दन्त and शिखा when the word is used as a proper noun (संज्ञा) and to the word ऊर्जस्; e.g. रजस्वला, क्रवीवलः, ऊर्जखलः etc.; ci. रजःकृष्यासुतिपरिषदो वलच्, दन्तिशिखात्संज्ञायाम् and ष्योत्स्ना ... ऊर्जस्वल .. मलीमसाः P. V. 2.112, 113, 114.

ৰন্তম named হাবৈল্পম also, who wrote a commentary on Nāgeśa's Śabdenduśekhara.

चश् short term (प्रत्याहार) for consonants from a in ह्यवरट् to the mute श् in जवगडदश् i.e. all semi-vowels excepting य, and the fifth, the fourth and the third class consonants; cf. नेड् बाश कृति cf.P.VII.2.8.

चर्गम name given in the Prātiśākhya works to letter-combinations where a consonant gets a change suitable to the neighbouring consonants as given in the Rk. Prātiśākhya in IV.1 to IV.5 including जरुव, अनुनासिकादेश, छत्व, परसवण, अनुस्वार and others, as given in P. VIII.2.39, VIII.3.7, VIII. 3.23, VIII.4.40, 46, 58, 59, 62, 63; cf. न हाज अवश्गमसंघाविव अपरिणतानि व्यञ्जनानि संयोगं गच्छन्तिUvvata on R.Pr.IV.5.

वस् (1) pres. participle affix वसु substituted for शतृ applied to the root विद; e.g. विदस, cf. विदे: शतुर्वस: P.VII. 1.36; (2) perf. part. affix कसु substituted for the general affix लिट् mostly in Vedic Literature, but in specific cases in spoken language; e.g. see सेदिवस, शुश्रुवस, उपेयिवस cf. P III.2. 107-9. See कस.

वसन्तादि a class of words headed by the word वसन्त, which are mostly names of seasons, to which the affix इक (ठक्) is added in the sense of 'that which one studies or knows'; cf. वसन्तसहचारतीयं प्रन्था वसन्तस्तमधीते वासन्तिक: l वार्षिक: Kāś. on P. IV. 2.63.

वसु the krt. affix कसु which see above. The word वसु is used for कसु by the Varttikakara; cf. वसुसंप्रसारणमाण्विधी सिद्धं वस्तब्यम् P.VI.4.22 Vart. 9.

विह ātmanepada personal-ending of the first person (उत्तमपुरुष) dual, substituted for the general ल् affix; cf. तितस्क्षि ... महिङ् P.III.4.78.

चा a term often used in the Sūtras of Pāṇini and others, to show the optional application of a rule; cf. न वेति विभाषा P.I.2.44; cf. also वा गम:I. 2.13 etc. See विभाषा.

वाकरनागळ [WACKERNAGELL], a German Professor and scholar of Sanskrit Grammar who collaborated in the work of editing 'Altindisch Grammatik'.

चाकिनादि a class of words headed by the word वाकिन to which the taddhita affix आयान (भिन्न्) is added in the sense of an 'offspring' when along with the tad. affix आयान the augment क् (कुक्) is added to the base (वाकिन or the like); e. g. वाकिनकायान:; cf.Kās. on P.IV.1.158.

वाक्य a sentence giving an idea in a single unit of expression consisting of the verb with its kārakas or instruments and adverbs; cf.आख्यातं साज्ययं सकारकं सकारकिविशेषणं ्वाक्यसंज्ञं भवतीति वक्तज्यम् । साज्ययम् । उच्चैः पठित । सकारकम् । ओदनं पचित । M. Bh. on P. II. 1.1. Vart. 10. Regarding the different theoretical ways of the interpretation of a sentence see the word शाज्दकोष. For details, see वाक्यपदीय II. 2 where the different definitions of वाक्य are given and the अखण्डवाक्यस्ताट is established as the sense of a sentence.

বাৰ্যকাণ্ড name given to the second chapter of Bhartrhari's Vākya-padīya in which problems regarding the interpretation of a sentence are fully discussed.

वाक्यकार a term used for a writer who composes a work in pithy, brief assertions in the manner of Sutras, such as the Vārttikas. The term is found used in Bhartrhari's Mahābhāṣyadīpikā where by contrast with the term Bhāṣyakāra it possibly refers to the Vārttikakāra Kātyāyana; cf. एषा भाष्यकारस्य कल्पना न वाक्यकारस्य Bhartrhari Mahābhāṣyadīpikā. cf. also Nāgeśa's statement वाक्यकारी वार्तिकमारभते; cf. also खुङ्ग्पादयो वाक्यकारीया; Mādhavīyā Dhātuvrtti.

वाक्यपदी name of a work on the denotation of words in verse-form with a comentary of his own written by a grammarian named गङ्गादास. The name वाक्यपदी is confounded with वाक्यपदीय of Bhartinari through mistake.

वाक्यपदीय a celebrated work on meanings of words and sentences written by the famous grammarian Bhartrhari (called also Hari) of the seventh century. The work is looked upon as a final authority regarding the grammatical treatment of words and sentences for their interpretation and often quoted by later grammarians. It consists of three chapters the Padakāṇḍa or Brahmakāṇḍa, the Vākyakāṇḍa and the Samkirṇakāṇḍa, and has got an excellent commentary written by Puṇyarāja and Helārāja.

वाक्यपदीयदीका name of a commentary on Bhartrhari's Vākyapadīya written by Puņyarāja on the first and the second Kāṇḍa. Some scholars hold the view that the commentary on the first kāṇḍa was written by Bhartrhari himself.

वाक्यपदीयप्रकीणेप्रकाश name given to the commentary on the third Kāṇḍa or book of Bhartrhari's Vākyapadīya by Helārāja.

वाक्यपारिसमाप्ति completion of the idea to be expressed in a sentence or in a group of sentences by the wordgiven, ing actually nothing to be understood as contrasted with वाक्यापरिसमाप्ति used in the Mahābhāsya; cf. वाक्यापरिसमातेवाँ P.I.1.10 Vart. 4 and the Mahabhāsya thereon. There are two ways in which such a completion takes place, singly and collectively; cf. प्रत्येकं वाक्यपरिसमाप्तिः illustrated by the usual example देवदत्तयज्ञदत्तविष्णु-मित्रा भोज्यन्ताम् where Patanjali remarks प्रत्येकं (प्रत्यवयवं) भुजि: परिसमाप्यते; cf. also समुदाये वाक्यपरिसमाप्ति: where Pātanjali remarks गर्गी: शतं दण्ड्यन्ताम् । अर्थिनश्च राजानो हिरण्येन भवन्ति न च प्रत्येकं दण्डयन्ति । M. Bh.on P.I.1.1Vart.12; cf. also M.Bh. on P.I.1.7, I.2.39, II.2.1 etc.

ৰাক্যমনায় a work on the interpretation of sentences written with a commentary upon it by ভ্রম্মন্ত্রন্ of North Gujarat who lived in the seventeenth century A.D.

वाक्यप्रदीप a term sometimes seen

(wrongly) applied to the Vākyapadīya of Bhartrhari. It may have been the name of the commentary on the Vākyaprakāśa.

चाक्यभेद् a serious fault of expression when a sentence is required to be divided into two sentences for the sake of its proper interpretation; cf. केचिद्रा सुप्यापिशळेरित्यनुवर्तयन्ति तद्राक्यभेदेन सुन्धातौ विकल्पं करोति Kāś. onP.VI. 1.94; cf. also तद्धि (स्थानप्रहणं) तृतीयया विपरिणमय्य वाक्यभेदेन स्थानिन: प्रसङ्गे जायमान: etc. Par. Sek. on Pari. 13.

वाक्यरोष complement of a sentence; something required to be understood to complete the sense of a sentence generally according to the context; cf.कल्प्यो हि वाक्यरोषां वाक्यं वक्त्यंघांनं हि। M.Bh. on P. I. 1.57 Vart. 6; cf. कामचारश्च वितिनदेशे वाक्यरोषं समध्यितुम्। तद्यथा! उशीनरवन्मदेषु गावः! सन्ति न सन्तीति। मातृवदस्याः कलाः! सन्ति न सन्तीति! M.Bh. on P.I.3.62.

वाक्यसंस्कारपक्ष the grammarian's theory that as the individual words have practically no existence as far as the interpretation or the expression of sense is concerned, the sentence alone being capable of conveying the sense, the formation of individual words in a sentence is explained by putting them in a sentence and knowing their mutual relationship. The word गाम cannot be explained singly by showing the base गो and the case ending अम unless it is seen in the sentence गाम आनय; cf. यथा वाक्यसंस्कारपक्षे संबुद्धयन्त उपभेद ऋषेः क्तिनि कृते कृष्ण ऋष् ति इति स्थिते असिद्धत्वात्पूर्वमाद्गुणे कृते अचो रहाभ्यामिति द्वित्व . . Pari. Bhaskara Pari. 99. The view is put in alternation with the other view, viz. the पदसंस्कारपक्ष which has to be accepted in connection with the गौणमुख्य-न्याय; cf. पदस्यैव गौणार्थकत्वस्य प्रहेण अस्य

(गौणमुख्यन्यायस्य) पदकार्यविषयत्वेमवोच्चितम् । अन्यथा वाक्यसंस्कारपक्षे तेषु तदनापात्तः Par. Sek. on Pari. 15. The grammarians usually follow the वाक्यसंकारपक्ष.

वाक्याथे the meaning of a sentence, which comes as a whole composite idea when all the constituent words of it are heard; cf. पदानां सामान्ये वर्तमानानां यद्विशेषेऽवस्थानं स वाक्यार्थः, M.Bh. on P.I.2.45 Vart. 4. According to later grammarians import or meaning of a sentence (वाक्यार्थ) flashes out suddenly in the mind of the hearer immediately after the sentence is completely uttered. The import is named प्रतिमा by Bhartrhari, cf. Vákyapadīya II.45; cf. also वाक्यार्थश्च प्रतिभामात्रविषय: Laghuma गाँउ ... details and the six kinds of vakyartha, see Vākyapadīya II.154.

वाक्यार्थचान्द्रिका name of a commentary on the Paribhāṣenduśekhara by Hari Śastrī Bhāgawata.

वाक्येकदेश part of a sentence which sometimes, on the strength of the context, conveys the whole meaning; cf. हस्यन्त हि वाक्येषु वाक्येकदेशान् प्रयुज्ञानाः पदेषु च पदेकदेशान् । प्रविश तर्पणम्। पदेषु पदेकदेशान् । प्रविश तर्पणम्। पदेषु पदेकदेशान् देवदत्तो दत्तः। सत्यमामा भामेति M.Bh. on P.I.1.45 Vart. 3.

बाच् (1) expression from the mouth; speech; series of sounds caused by expelling the air from the lungs through differently shaped positions of the mouth and the throat; cf. स संत्रातादीन प्राप्य वाग्मवित Vaj. Pr.I.9; see the word वाणी; (2) the sacred or divine utterance referring to the Veda; cf. त्रय्या वाचः परं पदम्; (3) term used for उपपद in the Jainendra Vyākaraņa; cf. वाग्विमक्तः कारकिनियसित्वेळीयसी Jain. Pari. 104.

वाचक expressive, as contrasted with द्योतक, ब्यञ्जक, तूचक and भेद^क which

mean suggestive; the term is used in connection with words which directly convey their sense by denotation, as opposed to words which convey indirectly the sense or suggest it as the prefixes or Nipatas do.

बाचिनिक expressly cited by a वचन or a statement of the authors of the Sūtra, the Vārttika and the Mahābhāṣya, as contrasted with what naturally occurs or is inferred from their statements; cf. नेदं वाचिनिकमिलङ्गता असंस्थता च (अन्ययानाम्)। स्वामानिकमेनत् M.Bh. on P.I. 1.38 Vārt. 5 and P. II.2.6; cf. also M.Bh. on P.I.2.64 Vārt. 53.

वाचिनिकी See वाचिनिक above; cf. किं स्वामाविकी निवृत्तिराहे। स्विद्धाचिनिकी M.Bh.on P. II.2.6; cf. also the usual expression वाचिनिकी एषा with respect to some Paribhāṣās or maxims.

वाचिका expressing directly, denoting; (fem. of वाचक); cf. तयोरभिसंबन्धस्य षष्टी वाचिका भवति M. Bh. on P.II. 1.1 Vart. 4.

वाच्य (1) directly expressed (sense) as contrasted with ब्यञ्ज्य or प्वनित; cf. इब्देनार्थान् वाच्यान् दृष्ट्वा बुद्धो क्वर्यात्पीर्वाप्यम् I M.Bh. on P. I.4.109 Vart. 10; (2) which should be stated or which deserves to be stated. The word वाच्य is generally put in connection with the additions or corrections to the sūtras by the Vārttikakāra and the Mahābhāṣyakāra in their explanations; cf. तत्रतावद्वाच्यम्, M.Bh. on P. I.4.1; cf. also वाच्य ऊर्णोणुवद्वाव: M.Bh. on P. III.1. 22 Vārt. 3; III. 1. 36 Vārt. 6.

बाजप्यायन an ancient grammarian who holds the view that words denote always the jāti i.e. they always convey the generic sense and that the individual object or the case is understood in connection

with the statement or the word, as a natural course, when the purpose is not served by taking the generic sense; cf. आकृत्यिभधानाद्वा एकं राज्दं विभक्ती वाजप्यायन आचार्यों न्याय्यं मन्यते M. Bh. on P. I.2.64 Vart. 35.

वाजसनेयिप्रातिशाख्य the Prätiśākhya work belonging to the Vajasaneyi branch of the White Yajurveda, which is the only Pratisakhya existing to-day representing the branches of the Sukla Yajur-Its authorship is attributed to Kātyāyana, account of its striking resemblance with Pānini's sūtras at various places, its author Kātyāyana is likely to be the same as the Vārttikakāra Kātyāyana. It is quite reasonable to expect that the subject matter in this Prātiśākhya is based on that in the ancient Prātiśākhya works of the same White school of the Yajurveda. The work has a lucid commentary called Bhāsya written by Uvvata.

बाडच possibly the same as Kuṇaravāḍava; an ancient grammarian quoted in the Mahābhāṣya; cf. तत्र सौर्यभगवतोक्तमनिष्टिशो वाडवः पठति, M. Bh. on P. VIII. 2. 106 Vārt 3.

बाणी speech; utterance; the same as बाच् which is believed to be of four kinds as cited by the grammarians and explained by Bhartrhari; the four kinds are based upon the four places of origin, the three first places belonging to the inarticulate speech and the fourth belonging to the articulate one; cf.चत्वारि वाक्परिमेता पदानि तानि विदुर्जाह्मणा ये मनीषिण: । गुहा त्रीणि निहिता नेज्ञयन्ति तुरीयं वाचो मनुष्या वदन्ति, M. Bh. I Ahnika l and the Pradipa and Uddyota thereon.

वात्सप्र an ancient writer of Prātiśā-

khya works who believed in the very feeble utterance (लघुप्रयत्नतर) of the consonants य and व, when preceded by अ and standing at the end of a word. See लघुप्रयत्न.

वादनक्षत्रमाला a work on grammatical debates etc. by Appaya Diksita, a well-known scholar and a senior contemporary of Jagannātha in the seventeenth century.

चादि roots headed by वा and similar to वा. Really there is no class of roots headed by वा given anywhere but in the interpretation of the rule भ्वादयो धातवः it is suggested that 'the roots which are similar to वा are termed roots (धातु)' could also be the interpretation of the rule; cf. भ्वादय इति च वादय इति M.Bh. on P. I. 3.1. Vart. 11.

वादियटमुद्रर name of a commentary on the Sārasvata Vyākaraņa by a grammarian Jayanta.

वान the suffix वन् mentioned as वान in the Atharvaprātiśākhya and illustrated in the word ऋतावान; cf. A. Pr. III. 24.

वामन name of one of the joint authors of the well-known gloss or चृति upon the Sūtras of Pānini, who lived in the seventh century A. D. It cannot be ascertained which portion of the Kāśikā was written by Vāmana and which by his colleague जयादित्य. There was another famous scholar of Kashmīr by name Vāmana who flourished in the tenth century and who wrote an independent grammar treatise विश्वान्तविद्याधर, together with उणादि- सूत्रशृक्षि and लिङ्गानुशासन.

वायु air or प्राण, which is believed to spring up from the root of the navel and become a cause (even a material cause according to some scholars) of sound of four kinds produced at four different places, the last kind being audible to us; cf. प्राणा वणीनभिन्यच्य वर्णेष्वेवापळीयते Vāk-yapadīya I.116;cf. also R.Pr.XIII. 13. V.Pr. I.7-9; T.Pr.II.2; Sikṣā of Pāṇini st. 6.

वारणावतेश a grammarian of the seventeenth century who wrote a gloss named अमृतस्त्राति on the Prakriyā-kaumudī.

बारहचं a work attributed to बरहाचि; cf. बारहचं काब्यम् M. Bh.on P. IV.3.101; cf. also बारहचां प्रन्थ: S.K.on P.IV.3. 101. This work possibly was not a grammar work and its author also was not the same as the Varttikakara Kātyāyana. See बरहाचे above. The name बारहचच्याकरण was given possibly to Kātyāyana's Prakrit Grammar, the author of which was बरहाचे surnamed Kātyāyana. For details see p.395 Vyākaraņa Mahābhāṣya Vol. VII. D. E. Society's Edition.

बारहचकारिका an ancient grammarwork in verse believed to have been written by an ancient scholar of grammar, who, if not the same as Kātyāyana who wrote the Vārttikas, was his contemporary and to whom the authorship of the Unādi Sūtras is ascribed by some scholars. See बरहाचे.

चार्त of no use; serving no purpose; the word is possibly derived from वार्ता (छोकवार्ता) meaning people's gossip; cf एतच वार्तम् M.Bh.on P.I.2. 64 Vārt. 25; also on P. II.2.24, II. 4.13 etc.

वार्तिक a statement which is as much authoritative as the original statement to which it is given as an addition for purposes of correction, completion or explanation. The word is defined by old writers in an often-quoted

verse उक्तानुक्तदुरुक्तानां चिन्ता यत्र प्रवर्तते । तं प्रन्थं वार्तिकं प्राहर्वार्तिकज्ञा मनीषिण:॥This definition fully applies to the varttikas on the Sūtras of Pāṇini. The word is explained by Kaiyata as वृत्ती साध वार्त्तिकम् which gives strength to the supposition that there were glosses on the Sūtras of Pāņini of which the Varttikas formed a faithful pithy summary of the topics discussed. The word vārttika is used in the Mahābhāsya at two places only इन्ते: पूर्वविप्रविषेधा वार्त्तिकनैव ज्ञापित: M.Bh. on P III. 4.37 and अपर आह यहात्तिक इति M.Bh. on P. II.2.24 Vart. 18. In अपर आह यद्वार्त्तिक इति the word is contrasted with the word वात्तसत्र which means the original Sūtra (of Pānīni) which has been actually quoted, viz. संख्ययाब्ययासनाठ II.2. 25. Nāgeśa gives 'सूत्रे अनुक्तदूरक्तिच-न्ताकरत्वं वार्त्तिकत्वम as the definition of a Vārttika which refers only to two out of the three features of the Vārttikas stated above. If the word उक्त has been omitted with a purpose by Nagesa, the definition may well-nigh lead to support the view that the genuine Värttikapätha of Kātyāyana consisted of a smaller number of Varttikas which along with a large number of Varttikas of other writers are quoted in the Mahābhäsya, without specific names of writers. For details see pages 193-223 Vol. VII Pātanjala Mahābhāsya, D.E. Society's Edition.

चार्त्तिककार believed to be Kātyāyana to whom the whole bulk of the Vārttikas quoted in the Mahābhāsya is attributed by later grammarians. Patañjali gives the word वार्त्तिककार in four places only (in the Mahābhāsya on P.I.1.34, III.1.44; III.2.118 and VII.1.1) out of which his statement स्यादि-

विधि: पुरान्त: यद्यविशेषण भवति किं वार्त्तिककार: प्रातिषेधेन करोति in explanation of the Slokavarttika स्यादिविधि:...इति वृवता कात्यायनेनेह, shows that Patabjali gives कात्यायन as the Varttikakara (of Vārttikas in small prose statements) and the Slokavarttika is not composed by Katyayana. As assertions similar to those made other writers are quoted with the names of their authors (भारद्वाजीया:, सौनागाः, कोष्टीयाः etc.) in the Mahābhāsya, it is evident that the Vārttikas quoted in the Mahāexcluding bhasya- (even Slokavārttikas) did not all belong to Katvavana. For details see pp. 193-200, Vol. VII, Vyākaraņa Mahābhāsya, D. E. Society's Edition.

ৰান্দিন্দাত the text of the Vārttikas as traditionally handed over in the oral recital or in manuscripts. As observed above(see বার্নিক),although a large number of Vārttikas quoted in the Mahābhāṣya are ascribed to Kātyāyana, the genuine Vārttikapāṭha giving such Vārttikas only, as were definitely composed by him,has not been preserved and Nāgesa has actually gone to the length of making a statement like "বার্নিক্যাত: মতু:"; cf. Uddyota on P.I.1.12 Vārttika 6.

वार्त्तिकवचन a small pithy statement or assertion in the manner of the original sūtras which is held as much authoritative as the Sūtra; cf. न ब्रुमो शृतिस्त्रवचनप्रामाण्यादिति । किं तिहैं । वार्तिकवचनप्रामाण्यादिति । M.Bh. on P.II..1.1 Vārttika 23.

वात्तिकसिद्धान्त categorical conclusive statements made by the Varttikakara many of which were cited later on as Paribhaṣas by later writers. For details see pp. 212220 Vol. VII, Vyākaraņa Mahābhāṣya, D. E. Society's edition.

वात्तिकस्त्र the same as वार्तिकवचन which see above. The Varttikas are termed Varttika sutras on account of their close similarity with the original Sutras, which in contrast are termed Vrttisutras.

वार्ष्यांयणि an ancient grammarian quoted in the Mahābhāṣya and the Nirukta in connection with the six-fold diwision of bhāva or verbal activity; cf. षड् भावविकारा भवन्तीति वार्ष्यायणि: l जायते अस्ति विपरिणमते वर्षते अपक्षीयते विनस्यतीति Nir. I. 3.

वावचन citing an option not specifically by the particle वा, but by the terms विभाषा, अन्यतरस्याम् and the like; cf हुकीर्वावचने अभिवादिदशोरात्मनेपद उपसंख्यानम् P. I. 453 Vart. 1; cf. also M.Bh. on P.I.3.79, II.1.18 etc.

वाविधि, वाविधान also, laying down an option regarding a grammatical operation; cf. स्वस्तियोगे चतुर्थां कुशलार्थे- राशिष वाविधानात् P.II.3.16 Vārt.1; cf. also अविशेषेण अयादिनां वाविधिमुक्त्वा सार्वधातुके नित्यसिति वक्ष्यामि M.Bh.on P.III. 1.31 Vārt. 2; cf. also M.Bh. on P. III.1.94.

वासह्यस्याय the dictum 'of applying optionally any two or more kit affixes to a root if they become applicable at one and the same time, only provided that those affixes are not in the topic of स्त्रियाम (P.III.3.94 etc.) and are not the same in appearance such as n, अ, क etc, which are the same viz. अ; cf. वासरूपे।ऽस्त्रियाम् P.III.1.94; cf. also वासक्षान्यायेन ण्वलिप भाविष्यति M.Bh. on P.III.2.146 Vārt.1; cf.also M.Bh. on P.III.2.150 Vart. 1. The word वासरूप and वासरूपविधि are also used in the same sense; cf. ताच्छीलिका वासरूपेण न भवन्तीति M.Bh. on P.III. 2.150 Vārt. 2, as also तान्छीलिकेषु वास-रूपविधिनोस्ति Par. Šek. Pari. 67.

वासुदेव दीक्षित son of महादेव दीक्षित, the author of the Bālamanoramā, a commentary on the Siddhānta-kaumudī. Vāsudevadīkṣita was a resident of Tanjore who lived in the beginning of the eighteenth century A.D. and wrote a few works on Pūrvamīmāinsā.

वासदेव (शास्त्री) surnamed Abhvankar. who lived from 1863 to 1942 and did vigorous and active work of teaching pupils and writing essays, articles, commentary works and original works on various Shāstras with the same scholarship, zeal and acumen for fifty years in Poona. He wrote गृढार्थप्रकारा a commentary on the Laghusabdendusekhara and तत्त्वादशे a commentary on the Paribhāsendusekhara in 1889. edition of the Patanjala Mahabhasya with full translation and notes in Marāthī can be called his magnum opus. See अभ्यंकर.

ৰি (l) Uṇādi affix বি quoted by Pāṇini in the rule জায়ীs বি বিল্লান্ত জিন্ন VII. 1.85; e.g. জায়বি:; cf. জুহান্ত লাম্ম: কিন্ Uṇādi IV. 54; also ছুহুম্মা বিন্ IV.53; (2) common term for the affixes কিন্, কিন্, ভিন, তিন, তিন্, বিন্ and বিহ্. See বৃ.

विक् augment वि as seen in the word द्विद्युतत् given as a nipātana in the sūtra दाधार्तिदर्धति ...P. VII.4.65; cf. द्विद्युतदिति द्युतर्थङ्ङ्गन्तस्य शतिर अभ्यासस्य संप्रसारणाभावः अत्वं विक् आगमश्च निपात्यते Kāś. on P.VII.4.65.

विकाम्पत a fault in the pronunciation of vowels, the utterance being attended with a kind of tremor; cf. ग्रस्त निरस्त...विकिथ्यतम्। M. Bh. at the end of Ahnika 1.

विकरण an affix placed between a

root and the personal ending, for showing the specific tense or mood or voice to convey which, the personal ending is applied; e. g. the conjugational signs राप, स्थन, भु, रा, अम्, उ, आ and यक, आम्, as also स्य, तास्, सिप्, आम् and िल with its substitutes. Although the term विकरण is used by ancient grammarians and freely used by the Mahabhāsyakāra in connection with the affixes, mentioned in the sutras of Pāṇini, such as शप्, स्यन् and others, the term is not found in the Sūtras of Pānini. The vikaranas are different from the major kinds of the regular affixes तिङ्, कृत्य and other similar ones. The vikaraṇas can be called কুনু; so also, as they are mentioned in the topic (জাঘিকাर) of affixes or Pratyayas, they hold the designation 'pratyaya'. For the use of the word विकरण see M.Bh. on P. I.3. 12, III, 1.31 and VI. 1.5. The term विकरण is found in the Yajñavalkya Siksa in the of change, (cf. उपधारञ्जनं क्योंन्मनोविंकरणे सति) and possibly the ancient grammarians used it in that very sense as they found the root क modified as कर or कुर, or चि as चिनु, or भू as भव before the regular personal endings तिप्, तस् etc.

विकर्ष (1)a fault in the utterance of a vowel with its proper accent (acute, grave or circumflex) which results from the proper accent being mixed with another in the utterance; cf. विकर्षी नामा शिष्ट्रता Uvvata on R. Pr. III. 18; (2) protraction of the accent especially of the circumflex accent.

विकल्प choice or option re: the application of a rule as stated by the word वा, विभाषा, अन्यतस्याम् or the like; cf. नेति प्रतिषेषो वेति विकल्पः तयोः प्रतिषेषविकल्पयोः 'विभाषा' इति संज्ञा मवति

विभाषाप्रकरणे प्रतिपेधविकरूपी उपितिष्टेते ! तन्न प्रतिपेधेन समीकृते विषये पश्चाद्विकरूपः प्रवर्तते Kās. on P, I. 1 44.

चिकल्पित made applicable optionally. चिकार lit. change; modification; modification of a word-base or an affix, caused generally by the addition of suffixes; cf. प्रकृतेखस्थान्तरं विकार: Kāś. on P. IV.3.134; cf. also लेपागमवर्णविकारज्ञो हि सम्यग्वेदान् परिपाल- विष्यति Mahābhāsya Āhnika 1.

विकार्थ lit. changeable; that which gets changed in its nature; a variety or subdivision of कर्म or the object; cf. त्रिविधं कर्म। निर्वर्त्य विकार्य प्राप्य चेति। Kāś. on P. III. 2.1. The विकार्यकर्म is explained as यस्य प्रकृत्युच्छेदो गुणान्तरं वा उत्पद्यते तद्विकार्यम्। यथा भुक्त ओदनः। स्त्र्यमानः केदारः। Sṛngāraprakāśa II; cf. also, Vākyapadīya III. 7.78.

विकीणे a fault in the utterance of a vowel when one vowel appears, or is heard as another; cf. विकीणों वर्णान्तरे प्रसुत: । एकोप्यनेकनिर्भासीत्यपरे Pradipa on the Mahābhāsya Ähn. 1 end.

विकृत mutilated, changed in nature e.g. the word राम into राम in राम which is equivalent to राम न और For technical purposes in grammar a word, although mutilated a little by lopa, agama or var avikara, is looked upon as the original one for undergoing operations; cf. एकदेशाविक्तमनन्यनत् Par. Sek. Pari. 37.

विकृतनिर्देश utterance of a word in its mutilated form with some object in view; e.g. दीव्यत् for दीव्यति in प्राग्दीव्यतोऽण् P. IV. 1. 83; cf. किं पुन: कारणं विकृतनिर्देशः कियते । M. Bh. on P. IV.1.83; cf. also कर्ष इति विकृतनिर्देशः क्रमतोर्निष्टस्यर्थः Kāś on P. VI. 1. 159; cf. also गोह इति विकृतिकरणं विषयार्थम् Kāś. on P. VI. 4. 89.

विकात change, modification as different from the original which is

called प्रकृतिः cf. प्रकृतिस्पादानकारणं दस्यैव उत्तरमवस्थान्तरं विकृतिः Kas. on P. V. 1.12.

विकृतिबद्धी a work on the modified recital of the Veda words, or पदपाठविकृति, ascribed to Vyādi who is believed to have been a pupil of वर्ष.

विक्रतिवह्नीदोका name of a commentary on विक्रतिवह्नी (which see above) written by a Vedic scholar गङ्गाधर.

विक्रम (1) name given to a grave vowel placed between two circumflex vowels, or between a circumflex and an acute, or between an a circumflex; acute and स्वारितयोर्मध्ये यत्र नीचं स्यात्, उदात्तयोर्वा अन्यतरतो वा उदात्तस्वरितयोः स विक्रमः T.Pr. XIX.1; (2) name given to a grave vowel between a pracaya vowel and an acute or a circumflex vowel: cf. प्रचयपुर्वश्च के।एडिन्यस्य T.Pr.XIX.2: (3) repetition of a word or पद as in the Krama recital of the Veda words; (4) name given to a visarjanīya which has remained intact, as for instance in य: प्राणता निमिषतः: cf. R.Pr. I.5; VI.1; the word विक्रम is sometimes used in the sense of visarjanīya in general; cf. also अनिङ्गयन् विक्रममेषु कुर्यात् R.Pr. XIII.11.

विकान्त name given to a samdhi where the visarga remains intact although it can optionally be changed into a sibilant consonant; e.g. यः कक्रुभः, यः पञ्च, यो वः शिवतमो रसः। cf. विकान्तसंधिरतु प्राष्ट्रतापथो वेदितन्थो यत्र विसर्गः श्रृथेत R.Pr.IV.11.

विक्रिप्ट a fault in the utterance of a letter when there does not take place the necessary contact with the proper place of the utterance of a word; cf. इन्वो: प्रकृषणे सर्वतश्चलने विक्रिप्ट नाम दोषो भन्नति । विक्रिप्ट नाम असं- युक्तम् R.Pr.XIV.3.

is विगृहीत shown by separating the com-

bined elements, for instance, the two or more words in a compound or, the base or affix from a word which is a combination of the base (प्रकृति) and the affix (प्रत्ययः); cf. तदेव सूत्रं विगृहीतं ब्याख्यानं भवति M.Bh. on I.1. Ahnika 1, Vart. 11, 14; also cf. अवारपाराद् विगृहीतादिष P. IV.2. 93 Vart.1.

विग्रह lit, separation of the two parts of a thing; the term is generally applied to the separation of the constituent words of a compound word: it is described to be of two kinds: (a) शास्त्रीयविष्रह or technical separation; e. g. राजपुरुष: into राजन ङम् पुरुष सु and (2) लौकिकविग्रह or common or popular separation; e. g. राजपुरूष: into राज्ञ: पुरुष:. also divided into two kinds according to the nature of the constituent words (a) स्वपदाविग्रह separation by means of the constituent words, e.g. राजहितम् into राज्ञ हितम्;(b) अस्वपद्विप्रह, e.g. राजार्थम् into राज्ञे इदम् :or e.g. सुमुलीinto शोभनं मुखं अस्याः cf. M.Bh. on P.V.4.7. The compounds whose separation into constituent words cannot be shown by those words (viz. the constituent words) are popularly termed nityasamāsa. The term नित्यसमास is explained as नित्यः समासो नित्यसमास:। यस्य विग्रहे। नास्ति। M.Bh. on P.II.2.19 Vārt. 4. The upapadasamāsa is described as नित्यसमास. Sometimes especially in some Dvandva compounds each of the two separated words is capable of giving individually the senses of both the words e.g. the words द्यावा and क्षामा of the compound द्यावाक्षामा. The word विग्रह is found used in the Pratisakhya works in the sense of the separate use of a word as contrasted with the use in a compound; cf. अच्छेति विग्रहे प्छतं भवति R.Pr.VII.1. विग्रह is defined as दुस्ययांवबोधकं वाक्यं विग्रह: in the Siddhantakaumudī.

विश्रहण enclosure or closure (वेष्टन) by the use of the word इति as done in the Krama and other Veda-recitals.

विद्यात immolation; sacrifice; destruction, as applicable to a word or part of a word or a relation of words; cf. अनेकाल्लस्य तदाश्रयत्वाद् वर्णाद्दास्य विद्यातो न भाविष्यति M.Bh. on P. I.1.50 Vārt. 15; cf. also the famous Paribhāṣā संनिपातलक्षणो विधिरनिमित्तं तद्दि- धातस्य Par. Sek. Pari. 85; M.Bh. on P.I.1.24 etc.

विञ्चञ्चत impediment to an operation caused by something preceding on account of its coming in the way; a vyavāya or vyavadhāna or intervention which is not admissible just as the interruption of palatals, linguals, dentals and sibilants excepting টু for the change of न into ण; cf. अञ्चवतं विष्रहे विष्ठकृद्धिः R.Pr. V.25.

विस् krt affix वि (which also becomes nil or zero) applied to a root in the sense of an agent, as observed in Vedic and classical use, as also to the root यज् with उप and roots ending in आ generally in Vedic Literature but sometimes in popular language; cf. विज्ञेष छन्दिस । आती मिन्कानिब्बनिपश्च । अन्येभ्योपि दृश्यन्ते । क्रीलालपाः, ग्रुभंयाः etc. Kāś. on P. III. 2.73, 74, 75.

विचार विचारणा, examination, question or topic or subject for examination; cf. कुत: पुनिरियं विचारणा। M.Bh. on P. I. 1.50 Vart. 1.

विचाल immolation, destruction; cf. वर्णाश्रय: प्रत्ययो वर्णविचालस्यानिमित्तम् । दाक्षिः M.Bh.on P.I.1.39 Vārt. 10; cf. also Par. Sek. on Pari. 85.

विचिक्तित्सार्थीय the indeclinable नूनम् called विचिक्तित्सार्थीय in the Nirukta; the word विचिक्तित्सा is explained as confirmation after deliberation by Durgacarya. cf. भाषायाम् । उभयमन्व-ध्यायम् । विचिकित्सार्थीयश्च पदपुरणश्च । नूनमिति विचिकित्सार्थीयः Nir. I.5.

বিভিন্ন of various or wonderful kinds beyond our ken or comprehension cf. বিভিন্নাংবাব্লিবভূবথ: M.Bh. on P.II. 4.32 Vart. 7; VI. 1. 99 Vart. 2.

विच्छेद (1) breach or break (in the Samhitāpāṭha); utterance of words separately by breaking their coalescence; cf. पदिवच्छेद; असंहित: V. Pr.I.156; (2) doubling of a consonant technically called यम; cf. अन्त:पदे अपञ्चमः पञ्चमेषु विच्छेदम् V.Pr. IV.163.

विजयगणिन a Jain grammarian of the seventeenth century who wrote a commentary on the Haimalaghuprakriyā.

विजया name of a commentary on the Laghusabdendusekhara by Sivanārāyaņa.

विजयानन्द called also विद्यानन्द, a grammar scholar of the Kitantra school who wrote (1) Kitantra-dhātuvṛtti (2) Kitantrottara and (3) Kriyākalāpa.

विज्ञान specific knowledge or understanding; cf. सिद्धं तु धर्मोपदेशने अनवयव-विज्ञानाद्यथा लोकिकवैदिकेषु; M. Bh. on P. VI.1. 84 Vart. 5.

विशेष a matter of special understanding; the phrase अवस्यं चैति द्विशेषम् very frequently occurs in the Mahābhāsya; cf. M.Bh. on P.I.1.1. 3, 5, 22, I.2.47, 48, 64, I.4.23 etc.

विद krt affix (बि, ब् or nil) applied to the roots जन्, सन्, खन्, कम् and गम् and to the root अद् in special cases as seen in Vedic Literature; e.g. अब्जा:, गोधाः, कृपखाः, दिवकाः, etc.

विद्वलं or बिहलेश grandson of रामचन्द्रशेल the author of the प्रक्रियाकीमुदी. He was a Telagu Brāhmaņa of Āndhra who lived in the beginning of the sixteenth century and wrote a commentary named प्रसाद on the Prakriyā-Kaumudī and two small works अन्ययार्थानेरूपण and पाणिनिस्त्रवृत्ति.

विडच् or बिडच् tad. affix विड applied to the word नि in the sense of depression of the nose. See under बिडच्; cf. P. V.2.32.

विद्यानन्द See विजयानन्द.

विद्यानिवास name of a commentary on Bopadeva's Mugdhabodha.

विद्याविनीद् grandson of Rāmesvarabhatta of Pratisthāna who wrote a grammar of the Prākṛta dialects.

विद्वस्प्रबोधिनी name of a commentary on the Sārasvata-prakriyā by a grammarian named Rāma.

विधमेक possessed of different phonetic properties.

विधल् tad. affix विध applied to the words भौरिक and others in the sense of 'inhabited country'; e.g. भौरिकि- विध:, वैपेयविध:; cf. Kāś. on P. IV. 2.54.

विधा characteristic feature of an activity; cf. संख्याया विधार्थे था। विधा प्रकार: सर्विक्याविषय एव गृह्यते Kāś. on P. V.3.42.

विधान (1) prescription, statement; cf. लोपे हि (प्रत्यवलक्षण-) विधानम् P.I. 1.62 Vārt. 3; cf. also तत्र बृद्धिविधानम् P. VI. 1.85 Vārt. 16; (2) instrument or cause of an activity; cf. विधिविधानविधिमाजां त्रयाणां सैनिधाने तदन्तविधिम्भिवति Sīradeva Pari. 13.

विधारण mention of a consonant as intact i.e. without any phonetic coalescence or संधि; the same as স্থানীনিঘান. The term is used in this sense in the Prātiśākhya works.

विचि (1) a prescriptive rule; cf. तत्र अपूर्वो विधिरस्तु नियमोस्तु इत्यपूर्व एव विधि-भीविष्यति न नियम: M.Bh. on P.I. 4.3; cf. also समर्थ: पदविधि: । विपूर्वाद्धाञः कर्म-साधन इकारः । विधीयते विधिरित M.Bh.on P.II. 1.1; (2) prescription, statement; injunction; cf. अस्ति भावसाधन: । विधानं विधि: । M.Bh. on P. I. 1. 57.

विधिवलीयस्त्व the superior strength of an injunctive rule; the term is very frequently used by grammarians in speaking about] the relative strength of rules; cf. the term लोपविधिवलीयस्त. M.Bh. on P.VII.2.3.

विधिवास्य an injunctive statement or sentence.

विधेय (1) predicate as constrasted with उद्देश्य; cf.समर्थाधिकारस्य विधेयसामाना- धिकरण्याक्रियमानर्थकः M.Bh. on P.II.1. 1 Vārt. 17; (2) that which should be prescribed as contrasted with प्रतिषेष्य; cf. तिङ् च कश्चिद्विषेयः कश्चित् प्रतिषेष्यः M.Bh. on P.I. 2.64 Vārt. 9.

विध्यादि the senses headed by विधि as given in the rule विधितमन्त्रणामन्त्रणाधी- एसंप्रश्नप्रार्थनेषु लिङ् P. III. 3.161; cf. विध्यादिषु सतमी च Kat. III.1.20; cf. also विध्यादिषु कियाथीछिङ् भवति Candra Vyak. I.3. 121.

विध्यकवाक्यता forming one single statement or idea with the prescriptive statement; union with the prescriptive rule so as to form one rule with it. The term is used in connection with प्रतिषेष or prohibitive assertions which have to be explained in combination with the prescriptive sentences or vidhivakyas; cf. निषयवाक्यानामपि निषयविशेषाकाङ्क्षत्वाद्विध्येकवाक्याव्यवानमपि निषयदेशेषाकाङ्क्षत्वाद्विध्येकवाक्याव्यवानमिष निषयSek. on Pari. 2, 3.

चिन् tad. affix (विनी) in the sense of possession applied to the words तपस्, सहस्न, ऊर्जस्, माया, मेथा, सज् and words ending in अस्, as also wherever it is seen (बहुलं) in Vedic literature; e.g. तपस्विन्, ऊर्जस्विन्, मायाविन्, साविन्, पयस्विन् etc.; cf. P. V. 2.102, 114, 121, 122.

विनत cerebralized, turned into a

cerebral letter ण् or ष्; see the word नित meaning cerebralization or Mūrdhanyabhāya.

विनयविजय a Jain grammarian who has written a gloss on हैमलघुप्राक्रिया.

वि तथादि a class of words headed by विनय to which the taddhita affix इक (ठक्) is applied without any change of sense; cf. विनय एव त्रैनायकः । भामियकः । औपथिकः । Kas. on P.V.4.34

विनाम cerebralization; cf. the word नितः; the word was used in ancient grammar works in the sense of णत्व (change of न into ण्); cf. अप्रहणं चन्नुङ्विधिलादेशविनाभेषु ऋकारप्रहणम्; M. Bh. on P.VIII.4.1 Vart. 2.

विनादा disappearance, elision; the word is frequently used in the sense of lopa; cf. एतच नित्येषु शब्देषु नेपपद्यते यस्सतो नाम बिनाशः स्यादसतो ना प्रादुर्भावः M.Bh. on P. I.1.56 Vart.12.

विनि tad. affix विन. See the word विन. विनिग्रहाथींय meant to cause prohibition or opposition; cf. अह इति च ह इति च विनिग्रहाथींयौ इदं ह करिष्यति । इदं न करिष्यतीति Nir.I.5.

विनिमत्त caused by different conditions; due to different causes; cf. बहुनह्थांहि ब्राह्मणयुःलानि विनिमत्तावतौ M. Bh. on P.VII.1.72 Vart. 3.

विनियोग employment separately of different persons or things for different purposes; cf. अहति विनियोगे च P.VIII. 1.61;cf. also अह विनियोगे । विनियोगे नाम द्वयोः पुरुषयोरेकस्मिन्कर्मणि एकस्य पुरुषस्य संबन्धः अन्यस्मिन्कर्मणि अपरस्य V.Pr. VI.21.

विनिवर्तक lit. sending away; causing prohibition; cf. विशेषण निवर्तयतीति विनिवर्तकः। त्वथैवेति विनिवर्तकाधिकारकावधारकाः T.Pr. XXII.6.

विन्यय the same as विन्यास; placing or employment of the instrument of sound to touch the various places or sthanas where sound is produced;cf. अनुप्रदानात्संसर्गात् स्थानात् करणविन्य-यात् । जायते वर्णवैद्योष्यं परीमाणाच पञ्चमात् ॥ T. Pr. XXIII.2.

चिपरिणाम change; cf. कार्यविपरिणामाद्वा सिद्धम्। कार्यस्य संप्रत्ययस्य विपरिणाम: कार्य- विपरिणाम: M.Bh. on I.1.56 Vart. 14. The word is very frequently used in connection with a change of the case of a word in a grammar rule which becomes necessary for interpretation; cf. विभक्तिविपरिणामाद्वा सिद्धम् as also अर्थाद्विभक्तिविपरिणामो भवति। M.Bh. on P.I.3.9,12;V.3.60, VI.J. 4, VII.3.50.

विपरीत (1) in the opposite or reverse way; cf. विपरीताचेति वस्तव्यम्। पारावारीणः M.Bh. on P. IV. 2.93 Vārt. 2; (2) change of का into इ, seen sometimes in Vedic Literature when that क is preceded or followed by a palatal letter; e.g. शङ्के into शिङ्के (Rk. Samh. V.2.9) विभूयात् into विभियात्(Rk.Samh. X.X.9) विचृत्त into विचित्त Rg. Veda II.27.16; cf. अनन्तरे ताहेपरीतमाहुस्तालब्धे शङ्के विभयाहिचुत्ताः R.Pr.XIV.17.

चिप्रयेच change in the reverse order; reverse transposition; interversion; cf. the usual expression वर्णविपयेच.cf. वर्णागमाद भनेदंस: सिंहो वर्णविपयेचात्। S.K. on P.VI.3.109. The word ब्यत्यच is used in this sense in the Mahābhāṣya; cf. वर्णब्यत्यचे ऋतस्तर्कः। हिंसे: सिंहः! M.Bh. on Siva Sūtra 5 Vārt. 15; cf. also Kāś. on P.VI.3.109 and Cāndra Vyākaraņa II.2.48.

विप्रकर्ष distance; standing at a distance; cf. न च कालनक्षत्रयो: संनिकर्षवि-प्रकर्षों स्त: M.Bh. on P.IV.2.3.

विष्रकृष्ट remote; at a distance, with a word or two intervening; cf. संनिकृष्टविष्रकृष्टयोः संनिकृष्टस्य । given like a Paribhāṣā-Sūtra V.Pr.I.144.

विप्रतिपन्न (1) doubtful; a matter of doubt; cf. विद्याद् विप्रतिपन्नानां पादवृत्ताक्षरै-र्कचाम् R.Pr. XVII.13; (2) perverted; cf. तेम्य एवं विप्रतिपन्नजुद्धिस्यः अध्येतृभ्यः इदं शास्त्रमन्त्राच्छे M.Bh. on I.1 Ahmika 1. विप्रातिषिद्ध standing in conflict; conflicting; contradictory; cf. परस्परिवर्द्ध विप्रतिषिद्धम् Kas. on P. II 4. 13.

विप्रतिषेध conflict, opposition; opposition or conflict between two rules of equal strength, which become applicable simultaneously when Panini's dictum विप्रतिषेधे पर कार्यम applies and the rule mentioned later on, or subsequently, in the Astādhyāyī is allowed to apply; cf. विप्रतिषेषे परं कार्यम् P.I.4.2; cf. also यत्र द्वी प्रसङ्गी अन्यार्थी एकस्मिन्युगपत् प्रानुतः स जुल्यबलविरोधो विप्रतिषेधः Kāś. on P.I. 4.2: cf. also विप्रतिषेध उत्तरं बलबदलेषि V. Pr. I.159. The dictum of the application of the subsequent rule is adopted only if the conflicting rules are of equal strength; hence, rules which are either nitya, antaranga or apavāda, among which each subsequent one is more powerful than the preceding one and which are all more powerful than the qq or the subsequent rule, set aside the पर rule. There is another dictum that when by the dictum about the subsequent rule being more powerful, an earlier rule is set aside by a later rule, earlier rule does not apply again in that instance, barring a few exceptional cases; cf. सक्कद्रती विप्रतिषधे यद बाधितं तद बाधितमेव । पुनःप्रसङ्गविज्ञानात् सिद्धन Par. Sek. Pari. 40, 39.

विप्रयोग use of a word against the warrant of experience, i.e. against what is actually seen; e. g. इश्येत खहनपि निषयोगः। तद्यथा। अक्षीणि मे दर्शनीयानि, पाद। मे सुकुमारतराः M. Bh. on P.I.4.21 Vart. 1.

विमराजेन्द्र a grammarian who has written पाणिनिस्त्रविनरण, a gloss on the Sūtras of Pāṇini.

विमक्ति lit. division, separation; sepa-

of the base ration i.e. factor which shows the base separately. The word विभाक्त is generally used in the sense of case affixes; but in Pānini's grammar the term विभाक्त is applied also to personal endings applied to roots to form verbs; cf.विभाक्त-श्च। सप्तिङो विभक्तिसंज्ञो स्तः S.K. on Pān. I.4.104. The term is also applied to tad affixes which are applied to pronouns, किम and वह, ending in the ablative or in the locative case or in other cases on rare occasions. Such affixes are तम् (तसिल्), স, (স্ত্), ह, अत्, दा, ऋहिल्, दानीम्, था (थाल्) and यम given in P.V.3.1 to V.3.26.The case affixes are further divided into उपपदविभक्ति affixes and कारकविभावित affixes. For details see P.II.3.1 to 73.

विमक्तिपाद conventional name given to the third pāda of the fifth Adhyāya of Pāṇīni's Astādhyāyī, as it begins with the Sūtra प्राग्दिशे विभिन्तः P.V.3.1.

विभक्तिमतिरूपक a term applied to such words ending with kṛt affixes as appear similar to words ending with case-affixes; such words have no further case affixes put after them, and hence, they are called by the term 'avyaya'; e.g. कर्तुम्: cf. विभक्तिप्रतिरूपकमञ्चयम् similar to उपस्पित्वस्वरप्रातिरूपकमञ्चयम् similar to उपस्पित्वस्वरप्रातिरूपकमञ्चयम् निपाताः gaṇasūtra inside the Cādigaṇa P. I.4.57.

विभक्तिबलीयस्त्व the relative superior strength possessed by the कारकविभित्त which takes place in supersession of the उपपदिविभित्त when both become applicable at one and the same time; e.g. मुनित्रयं नमस्कृत्य and not मुनित्रयाय नमस्कृत्य; cf. उपपदिविभवते: कारकविभित्तवेळीयसी Par. Sek. Pari. 94.

विभक्तिस्वरप्रतिरूपक similar in form to a word ending in a case-affix or to a vowel. Such words are looked upon, and are treated as indeclinables; e.g. हाने:, चिरेण, अस्ति, उ, ए etc.; cf. the usual expressions तिङ्न्तप्रतिरूपकमञ्चयम् etc. cf. विभिन्नत्वरप्रतिरूपकमञ्चयम् etc. cf. विभिन्नत्वरप्रतिरूपकमञ्चय निपाता मवन्ति M. Bh. on P. VIII.3.1; cf. also उपसर्गविभावितस्वरप्रतिरूपकाश्च निपाता: a gaṇasūtra inside the चादिगण mentioned in P.I.4.57.

विभक्त्यर्थ lit. the sense of a case-affix, as also of a personal affix; the term is applied to the Kāraka Prakaraņa or Kāraka chapter or topic in grammar where senses of the विभक्ति affixes are fully discussed and illustrated; cf. विभक्त्यर्थी: a chapter in the Siddhānta-kaumudī of Bhattojī Dīkṣita.

चिभक्त्यर्थनिर्णय a general term given to a chapter on case-affixes as also to treatises discussing the sense and relations of case-affixes. There is a treatise of this name written by Giridhara and another written by Jayaktsna Mauni.

विभक्त्यर्थप्रकारा a work on syntax of words written by a grammarian named Kamalākarabhaṭṭa.

विभवन्यश्रेष्ठधान an indeclinable, which is generally described as having the sense of a case affix as predominant in it; e.g. तत्र, अधः, नीचः etc.; some indeclinables have the sense of a root viz. the verb-activity as predominant; cf. किंचिद्व्ययं विभक्त्यर्थ-प्रधानं किचित् कियाप्रधानम् M. Bh. on P. I.1.38.

a word, or of arriving at the complete form of a word by putting all the constituent elements of the word such as the base, the affix, the augment, the modification, the accent, etc. one after another and then arriving at the form instead of completing the formation stage

by stage; e. g. in arriving at the form खोन्नी the wording खोन + अ + ई is to be considered as it stands and not खोन + अ = सोन्न and then खोन्न + ई. The विभन्न्यान्वाख्यानपञ्च in connection with the formation of a word corresponds to the पद-संस्कारपञ्च in connection with the formation of a sentence.

विभाग (1) lit. division, splitting; the splitting of a sentence into its'constituent parts viz. the words; the splitting of a word into its constituent parts viz. the base, the affix, the augments and the like; (2) understanding or taking thing separately from a group of two or more; cf.अवस्यं खब्विप विभज्यो-पपदग्रहणं कर्तव्यं यो हि बहनां विभागस्तदर्थम् । साकास्यकेम्यश्च पाटलिपुत्रकेम्यश्च माथुरा आभि-रूपतरा:, M. Bh. on P.V.3.57; splitting of a Samhitā text the Vedas into the Pada text; cf. अथादावृत्तरे विभागे हस्वं व्यञ्जनपरः T. Pr. III.1, where विभाग is explained as पदिविभाग by the commentator; cf. also R.Pr.XVII.15; (4) the capacity of the Kārakas (to show the sense); cf. कारकशाक्ति: विभाग: Nyāsa on Kāś.I.2.44.

विभाषा optionally, alternatively; the word is explained by Pāṇini as नवा in the rule न वेति विभाषा (P.I.1.44)in consonalce with its derivation from the root भाष् with वि; cf. नेति प्रतिषेधे वेति विकल्पस्तयो; प्रतिषेधविकल्पयो- विभाषात्र तेत्र मनति। विभाषाप्रदेशेषु प्रतिषधविकल्पयो- विभाषात्र तेत्र मनति। विभाषाप्रदेशेषु प्रतिषधविकल्पानुपतिहेते। तत्र प्रतिषधेन समीकृते विषये पश्चाद्विकल्पः प्रवर्तते. The option (विभाषा) is further divided into three kinds प्राप्त विभाषा, अप्राप्त विभाषा and उभयत्र विभाषा. For details see Mahābhāṣya on P. I.1.44.

विभाषित (1) stated or enjoined optionally; cf. मेध्य: पशुर्विभाषित: । आल्ल्बब्यो नाल्ल्बब्य इति M. Bh. on P. I.1. 44 Vart. 15; cf. also मन्ये धातुर्विभाषित: ।

M. Bh. on P.III.1.27 Vārt.4; (2) roots taking personal affixes of both the Padas.

चिमलकोर्ति a Jain grammarian of the sixteenth century who wrote a short metrical work on the padas of roots, known by the name पदन्यवस्थासूत्रकारिका.

विमलमाते an old grammarian who is believed to have written a gloss named भागवृत्ति on Pāṇini's Sñtras which the to grammarians Purusottamadeva, Sîradeva and others of the twelfth century refer. Some scholars say that भागवृत्ति was written by but it is not feasible, as there is a reference Māghakāvya to In books on grammar,. भागश्रति. especially of the Eastern School in the 11th and the 12th century. there are several quotations from the Bhagavitti. See भागवाति.

विमलसरस्वती a grammarian who wrote a small grammar work named ह्पमाला.

चिमुक्तादि a class of words headed by the word विमुक्त to which the taddhita affix अ (अण्) is added in the sense of 'possessed of', provided the word so formed, denotes a chapter or a lesson of a sacred work; cf.विमुक्तशब्दोस्मिनस्ति वैमुक्तकोध्यायः अनुवाको ना। देवासुर:। Kāś. on P. V. 2.61.

विमोक्ष liberation of the last letter (especially a class consonant) of a word from phonetic modifications by coalescence with the initial letter of the following word, or liberation of modification of a consonant or vowel standing at the end of a verse or sometimes even in the middle of a verse; e.g. तत् ने भित्र:, सम् यौमि, संमधुमतीमधुमतीभिः पृच्यन्ताम् गुक्तं दुदुहे अहयः; cf. V. Pr.I.90,91.

विराग omission of a consonant, sometimes when it is preceded and also followed by another consonant, as if it were squeezed between the two; this is no doubt looked upon as a fault; e.g. the omission of the consonant द in उपमा षट्द्रा द्वा uttered as उपमा षट् वा हाः टरिअन्योन्येन ज्यञ्जनानां विरागः R. Pr.XIV where Uvvata explains विराग as लोप.

विराम an ancient term used in the Prātiśākhya works for a stop or pause in general at the end of a word, or at the end of the first member of a compound, which is shown split up in the Padapatha, or inside a word, or at the end of a word, or at the end of a vowel when it is followed by another vowel. The duration of this virama is different in different circumstances; but sometimes under the same circumstances, it is describthe different ed differently in Prātiśākhyas. Generally, there is no pause between two consonants as also between a vowel and a consonant preceding or following it. The Taittirīya Prātiśākhya has four kinds of विराम (a) ऋग्विराम,pause at the end of a foot or a verse of duration equal to three matras or moras, (b) पदविराम pause between two words of duration equal two mātrās; e. g. इषे त्वा ऊर्जे त्वा, (c) pause between two words the preceding one of which ends in vowel and the following with a vowel, the vowels being not euphonically combined; pause has a duration of one matra e,g. स इधानः, त एनम् , (d) pause between two vowels inside a word which is a rare occurrence; this has a duration of half a matra; e.g. प्रउगम्, तितउः; cf. ऋग्विरामः पदविरामो विवृत्तिविरामः समानपद्विवृत्तिविरामस्त्रिमात्रो । द्विमात्र एकमात्रोधमात्र इत्यानुपूर्व्यण T. Pr. XXII. 13. The word विवृत्ति is explained as स्वरयोरसंधि:. The vivittivirāma is further divided वत्सानसति which has the preceding vowel short and the succeeding long, वत्सानुसारिणी which has the preceding vowel a long one and the succeeding vowel a short one, पाकवती which has both the vowels short, and पिपीलिका which has got both the vowels long. This fourfold division is given in the Siksa where their duration is given as one matra, one matra, three-fourths of a matra and one-fourth of a mātrā respectively. The duration between the two words of a compound word when split up in the पदपाठ is also equal to one mātrā; cf. R.Pr.I.16. The word विराम occurs in Panini's rule विसमोऽ वसानम् P.I. 4.110 where commentators have explained it as absence; cf. वर्णानामभावीवसानसंज्ञः स्यात् S.K.on P. 1.4.110; cf. also विरातिविराम: । विरम्येत अनेन इति वा विराम: Kāś. on P.I.4.110. According to Kāśikā even in the Samhita text, there is a duration of half a mātrā between the various phonetic elements, even between two consonants or between a vowel and a consonant, which, however, is quite imperceptible; cf. परी संनिक्षों वर्णानां अर्धमात्राकालन्यवधानं संहितासंज्ञो भवति Kās. on P. I.4.109, cf. also विरामे मात्रा R.T.35; cf. also R.Pr.I.16 and 17. For details see Mahābhāsya on P. I. 4.109 and I.4.110.

विरीसच् tad. affix विरीस or विरीस applied to the word नि in the sense of flatness of nose. See विरीस above; cf. P. V. 2.32..

বৈথিষ opposition or conflict between two rules where, the rule which is subsequently mentioned is regarded as stronger and given preference to, as far as its application is concerned; cf. तुल्यबलयोविंरोघो विप्रतिषेधः । विप्रतिषेधं परं कार्यम् P. I.4.2; (2) contradiction where one thing prevents another; cf. सर्वनामस्थान इति अनुवर्तमानमपि विरोधादिह न संवध्यते Kāś.on P.VII.1.86.

विलम्बत a kind of tone where the interval between the utterance of two letters as also the time required for the utterance of a letter is comparatively longer than in the other two kinds, viz. हुत and मध्य; cf. ये हि हुतायां वृत्ती वर्णाः त्रिभागाधिकास्त मध्यमायाम्, ये मध्यमायां वर्णाक्षिभागाधिकास्त विलम्बितायाम् M. Bh. on P.I.1.70; cf. also हुतविलम्बतयोश्चानुपदेशात् P. I.1.69 Vārt. 11.

विलम्बता द्वित retarding or slow manner of speech in which the letters are uttered quite distinctly; this kind of speech is followed by the preceptor while teaching Veda to his pupils; cf. अभ्यासाथें द्वृतां प्रयोगायें तु मध्यमाम् । शिष्याणामुपदेशायें दुर्याद् वृत्तिं विलम्बताम् R. Pr. XIII. 19. cf. also T. Pr. XXIII. 24. See विलम्बित above.

বিভাষ name of a commentary by Jayakṛṣṇa Maunī on the Madhya-siddhānta Kaumudī of Varadarāja.

विलिङ्ग (1) a substantive which is declined in all the three genders of. Hemacandra III. 1.142; (2) of a different gender (although in the same case); of. विलिङ्ग हि भनान् लोके निर्देश करोति M.Bh. on P. I. 1.44 Vart 5.

विले। प the same as लोप which see above. The term विलोप was possibly in use before Pāṇini's time; cf. उदात्तपूर्वे नियतस्वरोदये परो विलोपोऽनियतो यदावरः R. Pr. XI. 26; cf. also विलोपो विनाशः Uvvata on R. Pr. XI. 28.

विलोम reverse, in the opposite way; the same as प्रतिलोम which see above.

विवक्षा intention or desire, generally of the speaker with regard to the sense to be conveyed by his words; the words वक्तुर्विवक्षा are often used by grammarians in this sense; cf. विवक्षात: कारकाणि (Paribhāṣā) cf. also कथम्। विवक्षात: 1 M. Bh. on P. II. 1.66-67, I. 2.64 Vārt. 53, IV. 1.3; cf. also विवक्षाधीना शब्दब्युत्पत्तिः Durgh. Vr. II. 2.8; cf. also इतिकरणो विवक्षार्थ: Kāś. on P. II. 2.27, IV. 2.21, IV. 2.55, 57, etc.

विवरण critical comment; a name given by a writer of commentary works to a critical commentary work written by him; e.g. काशि-काविवरणपञ्जिका (न्यास) by Jinendra-buddhi, भाष्यप्रदीपविवरण (उद्योत) by Nāgeśa, as also लघुराव्देन्दुरेश्वरविवरण by Bhāskaraśastrī Abhyankar.

विवर्तन transformation; the word is generally used in the sense of transformation of the Padapātha into the Samhitāpātha.

विवार name given to an external effort in the production of a sound when the vocal chords of the glottis or larynx are extended; cf. कण्ठविलस्य विकास: विवार: Uddyota on M. Bh. I. 1.9. cf. also विवरणं कण्ठस्य विस्तरणम् । स एव विवाराख्यः बाह्यः प्रयत्नः । तास्मन्सित श्वासो नाम बाह्यः प्रयत्नः कियते । तद्ध्वनिसंसर्गाद्धेषो नाम बाह्यः प्रयत्नो जायते इति शिक्षायां स्मर्यते Bhāṣya on T. Pr. II. 5.

विविभक्ति possessed of a different caseaffix; cf. एवमपि विविभक्तीनां न प्राप्नोति। समर्थात् समर्थे पदात् पदे इति M. Bh. on P. II. 1.1. Vārt 19; cf. also M. Bh. on P. I. 1.27, VI. 4.1; VII. 2.82.

विवृत name given to an internal effort (as contrasted with the exter-

nal effort named विवार) when the tip, middle, or root of the tongue which is instrumental in producing a sound, is kept apart from the place or sthāna of the production of the sound; cf. तत्रोत्पत्तेः प्राम्यदा जिह्नाग्रोपाग्रमध्यमूलानि तत्तद्वणोत्पात्तिस्थानानां तास्यादीनां दूरतः वर्तन्ते तदा विवृतता. Tattvabodhini on S. K. on P.I.1.9.

वित्रुतकण्ड produced by fully extending the chords of the throat. The first and the second class-consonants are described as वित्रुतकण्ड; cf. तत्र वर्गाणां प्रथमद्वितीया विवृतकण्डाः श्वासानुप्रदाना अभोषा; M. Bh. on P. I. 1.9. Vart. 2.

विवृततर possessed of the internal effort viz. विवृत which is specially strengthened. The diphthongs have got at the time of their production the internal effort विवृत specially strengthened; cf. यदत्रावर्ण, विवृततरं तदन्यस्मादवर्णात् M. Bh. on Siva Sūtra 3,4 Vārt. 10.

विद्युत्त separated, disjoined; the word is used in connection with the separated elements of a euphonic combination; the words विद्धिः, अनेकीभूत and पृथग्भूत are used in the same sense.

विश्वात्ते (1) separation of the two vowels which were euphonically combined into one: the hiatus or position of two vowels near each other; cf. विवृत्तिः स्वरयोरसंधिः; (2) the interval between two placed near each other; cf. स्वरयो-रनन्तरयोरन्तरं विवृत्तिः V. Pr. I. 119; cf. also संहितायां यत्स्वरयोरन्तरं तदिवृत्तिसंज्ञं स्यात Uvvata on R. Pr. II. 1. This interval is one matra according Taittirīya Pratisakhva. it is only half-a-mātrā the Rktantra and according to the Rk-Prātisākhya; cf. T. Pr. XXII. 13; R. T. 35. See विराम.

विशयवत् doubtful; possessed of a doubt about itself; cf. विशयवत्या हि वृत्तयो भवन्ति। यथार्थे विभक्तीः संनमयेत्। प्रत्तम्। अवत्तम्। Nir.II.1.

বিহান্ত (1) lit. specific; qualified by, characterized by: cf. কন নাইবাহাট-নান্ত্; P. II.1.60; cf. also দাবিপাই-ক্সন্ত্ল ভিন্তাবিহাছবোণি সহ্লন্ Par. Sek. Pari.71; (2) different; cf. বিহাছ-ভিন্নানা দিন্নভিন্নানা হাত্ৰানা Kās. on P.II. 4.7.

विशेष specific nature causing a difference; difference; specific feature; cf. सामान्यप्रहणे विशेषानतिदेशः(Paribhāṣā) cf. also यस्तु प्रयुङ्क्ते कुशले विशेषे etc. M. Bh. in Ahmika 1; cf. also कियावाचकमाल्यातमुपसर्गो विशेषकृत् Uvvaṭa on V.Pr.VIII.50.

विशेषक determining; determinant; cf. अस्यत्र विशेष:। राजा विशेषक: प्रयुज्यते तेन विशिष्टस्यानयनं भवति; M. Bh. on P.II. 2.6; cf. अवयवे कृतं लिङ्गं समुदायस्य विशेषकं भवति; M.Bh.on P.I.3.62 Vart.5.

विशेषण attribute; adjective; any word which qualifies another; hence, subordinate; cf. विशेषणानां चाजाते:। जातिर्यद्विशेषणम्, आहोरिवत् जातेर्यानि विशेषणाना । M.Bh. on P.I.2.52.

विशेषणसमास (1) a tatpuruṣa compound of the type of Mayūravyaṁsakādi where both the words which are compounded together are adjectival; (2) a karmadhāraya compound where the second member is an adjective; a determinative compound; cf. गमनं च यशिरंच गमनिंदरमिति विशेषणसमासोयम् Kāś. on P.VI.2.6.

विशेषप्रतिपत्ति a clear understanding, or a determined sense in a place of doubt; cf. ज्याख्यानतो विशेषप्रतिपत्तिनिहि संदेहादलक्षणम् Par. Sek. Pari. 1; also M.Bh. in Āhnika 1.

विशेषविहित specifically prescribed, as contrasted with prescribed in general which is set aside; cf. सामान्य-

विहितस्य विशेर्षार्वाहतेन वायः; M.Bh. on P. II.1.24; cf. also M.Bh. on P.III. 1.94 Vārt.10, III. 2.77 etc.

विशेष्ण substantive, as opposed to विशेषण adjective or qualifying; cf. भेदकं विशेषणम्, भेद्यं विशेष्यम् Kās. on P. II 1.57; cf. also विशेषणिक्षेष्यमावो विवक्षानिबन्धन: Kās. on P. II.1.36.

विश्रम्म relaxation, a characteristic of the grave accent, as contrasted with आयाम which characterizes the acute accent; cf. उदानक्षानुदानक्ष स्वरितक्ष त्रयः स्वराः । आयामिविश्रम्माक्षेपस्त उच्यन्ते ऽ क्षराश्रयाः । विश्रम्भः अश्वागमनं गात्राणाम् Uvvaṭa on R.Pr.III.1.विश्रम्भ is the same as अन्ववसर्गं which is explained in the Mahābhāṣya as अन्ववसर्गो गात्राणां शिथिखता. M. Bh. on. P. I.2.29,30.

विश्रान्तविद्याधर name of a grammar work of a general type which once occupied a prominent position and was studied as a text book of grammar, representing an independent system. The work is referred to by Hemacandra and Haribhadra. It is attributed to Vāmana who may be the same as one of the joint writers of the Kāśikāvrtti. In that case the date of the work is the 7th century A. D.:cf. the popular verse परंत्र पाणिनी-यज्ञाः काचित्कालापकोविदाः । एके विश्रान्तविद्याः स्यरन्ये संक्षितसारकाः quoted in Vol.VII p. 388 Vyākaraņa Mahābhāsya D.E. Society's edition.

विन्द्रेष separation of vowels that are in coalescence; showing separately the two vowels that are combined together in the Samhita Text. The term is contrasted with प्रकार which is the same as एकादेश in the terminology of Pāṇini.

विश्वकर्मशास्त्री name of a grammarian who wrote a commentary सद्मित्रयान्याकृति on the Prakriyā-kaumudī.

विश्वनाथद्णिडमह a well-known grammarian of the nineteenth century who wrote several commentary works of which the commentaries on the two Sekharas of Nāgesa are well-known to scholars.

विश्वक्षप a grammarian of the sixteenth century who has written a small grammar treatise called विश्वक्षनियन्ध.

विश्वेश्वरतीर्थे a grammarian who has written a gloss on the Siddhanta-kaumudī.

विषमपद्द्याख्या or विषमी (1) a critical commentary on Nāgesa's Laghu-sabdendusekhara written by Rāghavendrācārya Gajendragadkar of Satara who lived in the first half of the nineteenth century and who has also written a gloss named त्रिप्यमा on the Paribhāṣendusekhara; (2) name of a commentary on Nagesa's Paribhāṣendusekhara by Cidrūpāśraya; (3) name of a commentary on Sīradeva's Paribhāṣāvītti,

विषमरागता incorrect nasalization, mentioned as a fault of pronunciation; cf. संद्युता निषमरागता च। R. Pr. XIV. 4.

विषय domain; province; cf. प्रकल्प चापवाद्यविषयं तत उत्सर्गोभिनिविश्रते । Par. Sek. Pari. 63.

विषयता being a subject of discussion of; coming under the domain of, applicability; the meaning of विपयसतमी which is similar to विवसा.

विषयाविषायभाव relation between the object and the subject; cf. प्रतिलक्ष लक्षणभदादस्ति विषयविषयिभावः Kaiyata on P. VI. 4. 104 Vart. 2.

विषयसप्तमी locative case denoting the domain or province of a particular suffix or a substitute or the like, which could be actually applied later on; this क्षियसमी is contrast-

ed with परसतमी when the thing mentioned in the locative case is required to be present in front; cf. असित पौर्वापर्ये विषयसतमी विज्ञास्यते M. Bh. on P. II. 4.35; cf. also आर्ध- घातुके इति विषयसतमी Kas. on P. II. 4.35; cf. also M. Bh. on P. III. 1.26 and IV. 1.90.

विषयार्थ meant for showing the province or domain of the application of a particular rule; cf. तत्रप्रहणं (in तत्रोपपदं सतमिस्थम्) विषयार्थम् M. Bh. on P. III. 1.92 Vart.6.

বিজ্যুদাণ্ডল a grammarian belonging to the famous Śeṣa family of grammarians, who has written a small treatise on Paribhāṣās or maxims of interpretation which he has named দ্বিমান্যকাহা.

विष्णुसङ्घ (विष्णुशास्त्री भट) a scholar of grammar of the latter half of the nineteenth century who has written learned commentaries on the works of Nagesa Bhatta, two of which viz. चिचिन्द्रिका and विष्णुभट्टी are well known to scholars.

विष्णुमद्दी name given to the commentary on the Paribhāṣenduśekhara written by Viṣṇubhaṭṭa. See विष्णु-मृद्द above.

विष्णुमित्र a Vedic scholar who wrote a gloss on the Rk-Prātisākhya which is known as पाईदःबाख्या.

विष्णुमिश्र a scholar of the Supadma system of grammar who has written a commentary named मकरन्द on the सुपद्मन्याकरण and also a commentary on the सुपद्मसमाससंग्रह.

विसर्ग aspiration, leaving off the breath generally at the completion of the utterance of a word when there is a pause; the term विसर्जनीय was in use in ancient times. Although not mentioned in his alphabet by Pāṇini, this phonetic element, visarga, is looked

upon as a letter; it is mentioned as one of the letters in the Sikṣā and the Prātiśākhya works and Patañjali has advised its inclusion in the alphabet. As visarga cannot be found in use independently of another letter (which is any vowel after which it occurs) it is called अयोगबाह.

विसर्जनीय same as विसर्ग which see above; cf. विस् ज्यते पुनर्गोंने संबध्यते इति विसर्गः; Durgasimha on Kat. I. 1. 16. The term विस् छ is also used in the same sense. The visar-janīya has the same position (स्थान) in the mouth as the vowel after which it occurs. It is a glottal sound; the Rk-Prātiśākhya says that some scholars describe visar-janīya as a chest sound; cf. कण्डयो-कार: प्रथमपञ्चमी च द्वावूष्माणी के विदेतानुरस्थी। R. Pr. I 18; cf. also उरिस विसर्जनीयो च R. T. 3.

विसृष्ट the same as Visarjanīya or Visarga, which see above.

विस्थान belonging to a position of utterance (स्थान) other than the one assigned, or referred to; cf. विस्थाने स्पर्श उदये मकार; R. Pr. IV. 3.

विस्पष्ट clear and correct; the term is used in connection with the pronunciation of Vedic words; cf. यथो एतत् । अविस्परार्थी भवन्तीति Nir. I. 16.

the word विराष्ट्र which retain their own accents in a compound when they are the first members of a compound, provided that any word of quality is the second member; e. g. विराष्ट्रकटुकम् । ज्यक्तल्यणम् where the words विराष्ट्र and ज्यक्त are used in the sense of clear, referring to the different tastes; cf. Kāś. on P. VI. 2. 24.

विस्वर characterized by a faulty or incorrect accent, which is looked upon as a fault of pronunciation.

विद्वार expansion of the position (ध्यान) and the means of utterance (करण) of a sound beyond the necessary extent, which produces a fault of pronunciation, called ज्यास; cf. विहारसहारयोज्यासपिंडने। स्थानकरणयोविंहारे विस्तारे ज्यासो नाम देखो जायते Uvvata on R. Pr. XIV 2.

बिहित prescribed by a rule; that for which a vidhi or injunction has been laid down. The word is very frequently used by grammarians with respect to an affix prescribed after a base.

विदित्तिवेशेषण an adjectival word generally in a different case from that of the word to which it is applied as an adjective, and hence, translated as 'prescribed after' and not as 'belonging to' cf. विदित्तिशिषणं घातुम्रहणम्। धातोयों विदित्त इति। M. Bh. on P. I. 1.5 Vart 3; cf. also M. Bh. on II.4. 74. Vart 1.

वीष्सा complete application to all the different parts; comprehensive inclusion of every part or unit; desire to occupy completely; cf. ब्याप्तिविदेशविषया प्रयोक्तुरिष्ण विष्सा । नानावाचिनामधिकरणानां कियागुणाभ्यां युगपत्त्रयोक्तुव्यां प्रवच्याप्तिमिष्णा नानाभृतार्थवाचिनां बद्धानां यान्य-धिकरणानि वाच्यानि तेषां कियागुणाभ्यां युगपत्त्रयोक्तुमिष्णा वीष्सा; e.g. ग्रामा ग्रामा रमणीयः । Kaś. on P.VIII.1.4. For details see Mahābhāṣya on P.VIII.1.1 and 4.

ৰ general term for the augment ৰুক্ and the affixes ৰুক্, ৰুক্, ৰুক্ and ৰুক্. After the indicatory letter has disappeared the remnant ৰ of the affixes and not of the augment, is always changed into অক; cf. যুবা-P. VII.1.1 चुक् (1) augment च added (a) to the word भ्र after it, when the tad. affix ढक् (एय) in the sense of अपत्य is affixed to it; cf. भ्रवा चुक् च !'. IV. 1.125; (b) to the root भ्र before an affix beginning with a vowel in the perfect and the aorist tenses; e.g. वभूय, अभूयन् etc.; cf. P. VI. 4.88; (c) to the root भ्र in the Perfect third pers. sing.; e.g. सम्ब, P.VII.4.74; (2) tad. affix अक applied to the word कन्या as seen in use in the Bannu (वर्णु) district; e.g. कान्यकम्, cf. P.IV.2.103.

ব্ৰু tad. affix अक applied optionally with the affixes ঘ and হল to the preposition 39 when the whole word is used as the name of a man e.g. उपक:; cf. Kāś. on P. V. 3.80. बुज् (1) tad. affix अक causing vrddhi to the vowel of the first syllable of that word to which it is added, as prescribed, (a) to the words denoting an offspring as also to the words ভন্ন, ভন্ছ etc. in the sense of 'a group'; e.g. औषगवकम् , औष्ट्रकम् , कैदारकम् etc.; cf. P.IV.2.39, 40; (b) to the words राजन्य and others in the sense of 'inhabited country'; e.g. राजन्यक: देवनायकः etc., cf. P. IV.2.53, (c) to the words headed by अरीहण such as द्वचण, खदिर, भेत्रायण, काशकृत्स्न etc. in the quadruple senses; e. g. आरीइणकम्, द्रीयणकम्, cf. F. IV.2.80, (d) to the word খন্ব meaning a desert, to words with यु or र for their penultimate, to words ending in प्रस्थ, पुर and वह as also to words headed by धूम, नगर, अरण्य, क्षर, अगन्बर etc., under certain conditions in the miscellaneous senses; e.g. सांकाश्यकः, पाटालीपुत्रकः, माकन्दकः, आङ्गकः, वाङ्गकः, धामकः, नागरकः, आरण्यकः etc.; cf. P. IV.2.121-130,134,135, 136; (e) to the words शरद्, आध्युजी, ग्रीन्म, वसन्त, संवत्सर,आग्रहायणी and others

in the specific senses given; cf. P. IV. 3.27, 45, 46, 49, 50; (f) to words denoting descendence or spiritual relation, words meaning families and warrior clans, words কুন্তান্ত and others, words meaning clans, and students learning a specific Vedic branch in specific senses prescribed; e. g. आचार्यक, मातामहक, ग्लै।चुकायनक, कालालक, काटक, etc.; cf. P. IV. 3.77, 99, 118, 126; (g) to the words নাকত, ভভ, उमा and जगा in the specially given senses; e.g. शाकल:, संव:, ओप्ट्क:, ओमम् ऑर्णम्, cf.P.IV.3.188,157,158; (h) to words with य as the penultimate, and a long vowel preceding the last one, to words in the dvandva compound, and to the words मनोज, कल्याण and others in the sense 'nature' or 'profession';e.g.रामणीयकम् गोपालपशुपालिका, गार्गिका, काठिका etc ; cf. P. V.1.132,133, 134; (2) krt affix अक added to the roots निन्द् हिंम् and others, and to the roots বৰ and কুৱা with a prefix before, in the sense of a habituated, professional or skilled agent; e.g. निन्दक:, परिक्षेपक:, अनुयक:, परिदेवक:, आक्रीशक:; etc. cf. P.III.2. 146, 147.

वर (1) krt.affix अक added to the roots प्र, स्, and द्ध in the sense of 'a skilled agent' and to any root in the sense of 'an agent who is blessed'; प्रवकः, सरकः, लवकः, (meaning जीवतात्) नन्दकः, (meaning नन्दतात्); cf. P. III. 1. 149, . 150; (2) tad. affix अक added to(a) the words 新年 and others in the sense of 'a student of '; e.g. 邪甲零:, पदकः शिक्षकः मीमांसकः; cf. P. IV.2.61; (b) the words পুরাল্ল, अपराह्व etc. as also the words पथिन and अमाबास्या in the sense of 'produced in'; e.g. पुर्वे एक ,पन्थक, अमावास्यक ; cf. P. IV.3. 28, 29, 30; (c) the words कलापि, अश्वत्य, यन and बुस in the sense of 'debt paid at the time of', the words वासुदेव and अर्जुन in the sense of 'devoted to' and the dvandva compounds when the words so formed mean either 'enmity' or 'nuptial tics';e.g. कलापकम् (ऋणम्), यवकम् (ऋणम्) वासुदेवकः, अर्जुनकः, काकोऌकिका, कुत्सक्-शिकिका: cf.P.IV.3.48, 98,125; (d) the words गोषद, इषेत्व etc. in the sense of 'containing' or 'possessing', and the word पाधन in the sense of 'expert' e.g. इषेत्वक:, पथक:: cf. P.V.2.62, 63; and (e) the words पाद and शत preceded by a numeral, in the sense of बांप्सा, as also in the senses of दण्ड (fine) and व्यवसर्ग when those words are preceded by a numeral; e.g. द्विपदिकां (ददाति), द्विशातिकां (ददाति), द्विपदिकां दाण्डित:: cf. Kāś. on P. V.4.1 and 2.

वृत्त a word signifying the end of a particular group of words; the word frequently occurs in the Dhātupātha of Pāṇini but not necessarily at the end of each class or group therein; e.g. दुओाध गतिवृद्धयोः। वृत् । अयं वदातिश्च बदाती परसीभाषों । Dhātupātha at the end of the First Conjugation. Similarly वृत् is used at the end of the fourth, fifth, and sixth conjugations.

वृतादि a class of roots headed by the root वृत् which take optionally the Parasmaipada affixes when the vikarana स्य of the future tense and the conditional mood, or the desiderative vikarana सन् is added to them; c.g. वर्त्स्यति, विविध्यते; अवर्त्स्यत, अवर्तिध्यत,; विवृत्सति, विवर्तिधत cf. Kāś. on P.I. 3.92; cf.also P. VII. 2.59.

वृत्त (1) arrived at or accomplished, as a result of वृत्ति which means a further grammatical formation from a noun or a verb; resultant from a verti; cf. यावता कामचारो बृत्तस्य ये विञ्जलंद्ये ते अतिदेद्येते न पुनः प्राम्वृत्तेर्ये M. Bh. on P.I.2.51; cf. also युक्तं

पुनर्थद् वृत्तिनिमत्तको नाम अनुबन्धः स्यात्; (2) employment, the same as प्रयोग, cf. बृत्ताद्वा। वृत्तं प्रयोगः। Pradipa on P. I. 3.9; (3) behaviour, treatment; cf. नकारस्योष्मवद् वृत्तं R. Pr. X.13; (4) manner of Veda writing, metrical form, metre; cf. तद् वृत्तं प्राहुश्छन्दसाम् R. Pr. XVII.22.

ब्रोत (1) treatment, practice of pronunciation; (2) conversion of one phonetic element into another; cf. R.Pr.I.95;(3) position of the padas or words as they stand in the Samhita text, the word is often seen used in this way in the compound word पदवृत्ति; आन्पदा: पदवृत्तय: R.Pr. IV.17: (4) modes of recital of the Vedic text which are described to be three दूत, मध्य and विलाभित based upon the time of the interval and the pronunciation which differs in each one; cf. M. Bh. on P. I.4. 109, Vart. 4; also I.i.69 Vart. 11; (5) nature; cf. गुर्वक्षराणां गुरुवृत्ति सर्वम् R.Pr.XVIII.33; (6) interpretation of a word: (7) verbal or nominal form of a root; cf. अर्थानित्य; परीक्षेत केनचिद् वृत्तिसामान्यन Nir. II.1; (8) mode or treatment followed by a scientific treatise; cf. का पुनवेति: । वृत्तिः शास्त्रप्रवृत्तिः । M.Bh. in Ahnika 1 on वृत्तिसमवायार्थे उपदेश: Vārtttika 10; (9) manner of interpretation with the literal sense of the constituents present or absent, described usually as two-fold जहत्स्वार्थी and अजहत्स्वार्थी. but with a third kind added by grammarians viz. (10) a जहदजहत्स्वार्थाः compound word giving an aggregate different from the exact literal sense of the constituent there are mentioned five vrittis of this kind; cf. परार्थाभिधानं वृत्ति:। कृत्तद्धि-तसमासैकदेशधातुरूपाः पञ्च वृत्तयः । वृत्यर्था-वबोधक वाक्यं विष्रह: S. K. at the end of the Ekasesaprakarana; (11)

of a interpretation collection statements: the word was originally applied to glosses or comments on the ancient works like the Sūtra works, in which the interpretation of the text was given with examples and counterexamples where necessary; cf. बृत्ती भाष्ये तथा नामघातुपारायणादिषु: introductory stanza in the Kāsīkā. Later on. when many commentary works were written, the word बृत्ति was differentiated from भाष्य, वार्तिक, टीका, चर्णि, निर्युक्ति, टिप्पणी, पाञ्जिका and others, and made applicable to commentary works concerned with the explanation of the rules with examples and counter-examples and such statements or arguments as were necessary for the explanation of the rules or the examples and counter examples. In the Vyākarana-Sastra the word occurs almost exclusively used for the learned Vrtti on Pāṇīni-sūtras by Vāmana and Tayaditya which was given the name Kāśikā Vrtti; cf. तथा च वृत्तिकृत् often occurring in works on Pāṇini's grammar.

वृत्तिग्रन्थ commentary works of the type of Vitti, which see above; cf. तथा च वृत्तिग्रन्थेषूपलभ्यते.

वृत्तिचन्द्रिका name of a grammar work written by a grammarian Kāśinātha who also is believed to have written वर्णविवेकचन्द्रिका and वैयाकरणसर्वस्व.

वृत्तित्रयवार्तिक a very short work in verse-form explaining in a very general manner the nature of Sūtras and Vārttikas; the work is anonymous.

वृत्तिदीपिका a treatise on the different ways in which the meaning is conveyed by words according to the conventions of grammarians, written by a grammarian Kṛṣṇa-bhaṭṭa surnamed Maunī.

वृत्तिपक्ष the alternative method of speaking by the use of compound words as contrasted with simple words; both the methods are observed in use among the people: cf. इह द्वी पक्षा बृत्तिपक्षश्चावृत्तिपक्षश्च । स्वभाव-तश्चेतद् भवति वाक्यं च समासश्च । M.Bh.on P.II.1.1,II.1.51, III.1.7,IV.1.82.

वृत्तिपरिगणन a definite enumeration of words used in a specific sense (as contrasted with वार्तिपरिगणन) which means a definite enumeration of the senses in which an operation, such as a compound-formation or so, takes place; cf. अधितस्मिन्सित अनिभाने यदि वृत्तिपरिगणनं कियते, वर्तिपरिगणनमिप कर्तन्थम; cf. M. Bh. on P. II. 2.24 Vārt. 16.

ब्रातिसंग्रह name of a gloss on Pāṇini's Aṣṭādhyāyī written bỳ Rāmacandra.

मृत्तिसमवाय serial arrangement of letters in a specific way (as for instance in the Māhesvara Sūtras) for the sake of grammatical functions; cf. वृत्तिसमनायार्थ उपदेश: । वृत्तिः शास्त्रप्रवृत्तिः । समनायो वर्णानामानुपूर्वेण सानवेश: M. Bh. on Āhnika 1.

द्वतिसमुद्देश name given to the last of the fourteen sections of the third chapter of Bhartrhari's Vākyapadīya (viz. the संक्रीर्णकाण्ड) in which the taddhita affixes and their interpretations are discussed.

चृत्तिसूत्र a rule forming the basis of a vitti, i. e. a rule on which glosses are written, as contrasted with बार्तिकसूत्र or बार्तिक a pithy Sūtralike statement composed as an addition or a modification of the original Sūtra; cf. केचित्ताव-दाहुर्येद् वृत्तिसूत्रे इति । संख्ययाब्ययासन्नादूराधिकसंख्या; संख्येय (P. II. 2.25) इति । M. Bh. on P. II. 2. 24.

बद्ध (1) a term used in Pāninis grammar for such words or nouns (प्रातिपदिक) which have for their first vowel a vrddhi vowel, i. e. either आ or U or औ; e.g. शाला, माला etc.; cf. वृद्धिर्यस्य अचामादिस्तद् वृद्धम्; (2) a term applied to the eight pronouns headed by त्यत् for pur. poses of the addition of tad. affixes prescribed for the Vrddha words, such as छ by बुद्धान्छ: P. IV.2.114; (3) a term applied to words having ए or ओ as the first vowel in them. provided such words denote districts of Eastern India, e. g. गोनदी, भोजकट etc. cf. एङ् प्राचां देशे, P.I.1.73, 74 and 75; (4) a term used in the Prātisākhya works for a protracted vowel (তুর) which has three mātrās; cf. तिस्रो वृद्धम् R. T.44.

मुद्धि (1) a technical term used by Pāṇini to denote the vowels आ, ऐ and औ; a vowel belonging to the third grade out of the three grades of vowels which are known as zero, normal and long grades; cf. वृद्धिराँदेच् P I. 1.1; (2) lengthening completely of a vowel which is called छति in grammar; the term is used in the Rk Tantra Prātiśākhya in this sense.

वृद्धिनिमित्त lit. cause of Vṛddhi (वृद्धेनिभित्तम्) such as the employment of
the indicatory letter ज् or ण् in an
affix or the lettter ज् in tad.affixes;
the term is, however, found used
in the sense of having in it a
cause of Vṛddhi, i.e. an indicatory
letter ज्, ण् or क्.; cf. वृद्धिनिमित्तस्य च
तद्धितस्यारक्तविकारे P. VI. 3.39. cf.
वृद्धेनिमित्तं यास्मिन्स वृद्धिनिमित्तः M. Bh.
on P. I.1.1.

नुद्धिपाद name given to the first pāda of Pāṇini's Aṣṭādhyayī by grammarians, as the beginning of the pāda is made by the Sūtra नृद्धिरादेच्. चुबन (वृषा), a term used in ancient grammar works for a word of the masculine gender as contrasted with योषा.

वृषादि a class of words headed by the word वृष which have their initial vowel accented acute; cf. Kāś. on P. VI.1.203.

वृष्ण्यण् tad. affix अण् prescribed by the sutra ऋष्यन्धकवृष्णिकुरुभ्यक्ष after words denoting members of the Vṛṣṇī race; cf. वृष्ण्यणाऽवकादा; वासुदेव: । बळदेव: ।

बेद a term applied to roots which optionally admit the application of the augment ६ (इट्) to the Ardhadhātuka affixes placed after them, e. g. roots having got the indicatory vowel क added to them as also the roots स्तृ, स्, स् and the roots headed by ख as also some specifically mentioned roots under certain conditions; cf. P. VII. 2.44-51.

चेतनादि a class of words headed by वेतन which have the taddhita affix इक (ठक्) added to them in the sense of 'earning a livelihood' e.g. वतिनक: । धानुष्कः; दाण्डिकः; cf. वतनन जीवित वैतिनकः कमकरः Kas. on P. IV. 4.12.

वेद language of the Vedic Literature as contrasted with the term টাক; ${\it cf.}$ नैव लोके न च वेदे अकारो विवृतोहित ${\it M.}$ Māhesvara Sūtra; cf. Bh. on रक्षार्थे वेदानामध्ययं ब्याकरणम् M. The term Bh. Ahnika 1. referring to words found in Vedic language is also frequently used in the Mahabhasya. Panini, however, has used the term छन्द्स, मन्त्र and निगम, and not वेद, out of which the first term छन्दस् is often used; cf. बहुलं छन्दिस P. II. 4.39, 76; III. 2.88; V. 2.122; or छन्दिस च P. V. 1.67, V. 4.142, VI. 3.126. VI. 1.34, VII. 1.8, etc.

वद्भित्र an ancient writer of a Prātiśākhya work mentioned in the Ŗk Prātiśākhya.

वेबर् [WEBER, ALBRECHT of Berlin, 1825-1901] a sound scholar of Vedic Literature who has written many articles on Sanskrit Grammar in "Indische Studien."

वेष्टक lit. enclosure or envelope; the term is used in the sense of प्रिम्नह with reference to the repetition of one and the same word more than once in the Krama and other artificial recitals; cf. प्रिम्नह स्वनार्धान्तात् तेन वैकाक्षरीकृतात् । परेषां न्यास-माचारं, ब्यालिस्तों नेत् स्वरो परी || on which Uvvata remarks प्रिमृह वेष्टके.

वैकल्पिक lit. optional, voluntary; the term is used in connection with a rule or operation prescribed alternatively with another, where there is an option to apply any one of the two and arrive at two forms in the same sense;.

चैकृत lit. subjected to modifications; which have undergone a change; the term, as contrasted with प्राञ्चत, refers to letters which are noticed in the Samhitāpātha and not in the Padapātha. The change of अस् into ओ, or of the consonant त् into द before soft letters, as also the insertion of त between त and स etc. are given as instances. cf. वेकृता: ये पदपाठे अह्या: । यथा प्रथमास्तृती-यम्ता:, अन्तःपाताः इत्येवमादयः

वैचिज्यार्थ simply for the sake of variety without any specific purpose in view; cf. बषड्ग्रहण वैचिज्यार्थम्। विचित्रा हि स्वस्य दृतिः पाणिनः। Kāś. on P. I. 2.35 cf. also Käs. on P. III. 3.96, IV. 1.148, 153, 160.

वैदिक found in Vedic Literature; the term is used in contrast with छोकिक which means 'found in common use'; cf. यथा छोकिकवैदिकेषु M. Bh. Ahnika 1. Kaiyata explains वैदिक as श्रुत्युपनिवद्ध.

वैदिकीप्रक्रिया name of that section of Bhattoji's Siddhantakaumudi which deals with Vedic peculiarities noticed by Pāṇini in his sūtras. There is a well-known commentary upon this section named सुवेधिको written by Jayakṛṣṇa a famous grammar scholar of the Maunin family.

वैदिकीप्रक्रियाटीका (1) a commentary on the sutras of Pāṇini dealing with the Vedīc words and their peculiarities written by a grammarīan named Murāri; (2) a commentary on the section of Bhattojī's Siddhāntakaumudī named वैदिकीप्रक्रिया written by Jayakṛṣṇa Maunin and named Subodhiṇī.

वैद्यनाथ, Vaidyanātha Pāyaguņde, a famous grammarian of the eighteenth century, who was one of the chief pupils of Nagesa and who prepared a line of pupils at Vārānasī. He has written learned commentaries on standard works on grammar, the principal ones being the Prabha on the Sabdakaustubha, the Bhavaprakasika Brhaccabdendusekhara, on the the Cidasthimālā on the Laghuśabdenduśekhara, the Kāśikā or Gadā on the Paribhāsendusekhara and an independent short treatise named Rapratyaya-khandana.

वैभक्त belonging to a case-affix; cf. काभ्यां सो वैभक्तः (मूर्धन्यमापद्यते) । ऋक्षु । विशिष्ठु । cf. also वैभक्तस्य णत्वे P. VI. 1.85 Vārttika 6.

वैभाषिक optional, alternative; cf. वैति वैभाषिक: T. Pr. XXII. 7; see वैकल्पिक. वैयाधिकरण्य lit. possession of separate residences, as contrasted with सामा-नाधिकरण्य; absence of apposition; use in different cases, non-agreement in case.

वैसर्भ absence of any purpose or utility; the word is used many times in the case of a rule, or a word or two of it, in whose case वैसर्भ or absence of utility is shown, and, with a view to prevent its being looked upon as a serious fault, something is deduced and the purpose is shown; cf. सूत्रवेसर्भ प्रसङ्गात् and व्यथ सन्ज्ञापयित used in grammar treatises.

वैयाकरण lit. a student of grammar; ज्याकरणमधीते वैयाकरण: cf. Kāś. on P. IV. 2.59. The word is used in the sense of 'a scholar of Grammar;' or, 'a person who has obtained proficiency in Grammar.' The word is used several times in this sense in the Mahābhāṣya. cf. M. Bh. on P. I. 1.3; I.4.2, II. 1.53, II.2.29, II.3.18, II.4.56, III.2.115 etc. The word is also used in the sense of 'pertaining to grammar' or 'found in grammar.'

वैयाकरणजीवातु a term used for the grammar treatise written by Cangudāsa which is also called Cāngusūtra or Cānguvyākaraņa.

वैयाकरणभूषण a well-known work on the grammatical interpretation of words written by Kondabhatta as an explanatory work (ज्याख्यान) on the small work in verse consisting of only 72 Kārikās written by his uncle Bhattoji Diksita. The trea-. tise is also named Brhadvaivakaranabhūsana. A smaller work consisting of the same subjectmatter but omitting discussions, is written by the author for facithe understanding students to which he has given Vaiyākaraņabhūşanathe name This latter work has got three commentary works written

on it named Kāśikā, Kānti and Matonmajjā and one more scholarly one Sāṅkarī, recently written by Shankar Shastri Marulkar.

वैयाकरणभूषणसार a slightly abridged form of the Vaiyakaranabhūṣana by the author Kondabhaṭṭa himself, for students and beginners. It consists of the same number of fourteen chapters as the main treatise, which are given the name Nirnaya. See Vaiyakaranabhūṣaṇa.

बेयाकरणभूषणसारटीका a commentary written on the well-known work on the sense of words and syntax written by Kondabhatta. There are many commentaries out of which, the well-known ones are (1) Darpaṇā by Harivallabha, (2) Laghubhuṣaṇakānti by Gopāladeva, a pupil of Balambhatta Pāyagunde, and (3) Kāśikā by Harirāma Keśava Kāle and Śānkarī by Śankaraśastrī Mārulakara.

वैयाकरणभूषणसारवृत्ति a commentary on the Vaiyākaraṇabhūṣaṇa, written by Mahānanda in the beginning of the nineteenth century.

वैयाकरणशब्दमाला, वैयाकरणशब्दरत्नमाला a treatise on the use of words written as a helpful guide to Sanskrit writers, by a grammarian named Somayājin in 1848 A.D.

वैयाकरणशाब्दबोध import of a sentence according to the grammarians, in which verbal activity occupies a predominant place, and the residing place of the subject as also that of the verbal activity is identical in the active voice, while the object and the verbal activity have got the same place of residence in the passive voice. The other auxiliaries of activity such as the

instrument, location and the like, are connected with the verbal activity. The import of the sentence चेत्र: पचित, in short, can be expressed as चैत्रकर्तृका वर्तमानकाछिका पाकिकया.

वैयाकरणसर्वस्व a small treatise on grammar written by a scholar of grammar named Kāśinātha who has also written a few more small works वर्णविवेकचान्द्रिका, वृत्तिचन्द्रिका, धातुम- अर्रो etc.

वैयाकरणसिद्धान्तकारिका a very scholarly work by Bhattoji Diksita on the interpretation of words and sentences, based upon the learned discussions on that subject introduced in the Mahabhasya, Vākyapadīya, Pradīpa etc. and discussed fully in his Sabdakaustubha by the author himself. work although scholarly and valuable, is compressed in only 72 verses (kārikās) and has to be understood with the help of the Vaiyākaraņabhūşaņa or Bhūsansara written by Kondabhatta, the nephew of the author. See वैयाकरणभूषण and वैयाकरणभूषणसार.

वैयाकरणसिद्धान्तकौमुदी an extremely popular work on the subject Sanskrit grammar written for the use of students, which, although difficult at a few places, enables the students by its careful study to get a command over the subject and enable him to read other higher works on grammar. The work is based on the Astadhyayi of Panini without omitting a single Sūtra. The arrangement of the Sutras is, entirely different, as the author, for the sake of facility in understanding, has divided the work into different topics and explained the Sūtras required for the topic by

bringing them together in the topic. The main topics or Prakaranas are twelve in number, viz. (1) संज्ञापरिभाषा, (2) पञ्चसंधि, (3) सबन्त or षडालेङ्ग, (4) स्त्रीप्रत्यय, (5) कारक, (6) समास, (7) ताद्धित, (8) तिङन्त, (9) प्रक्रिया, (10) कुदन्त,(11) वैदिकी and (12) स्वर which are sometimes styled as ब्याकरणद्वादशी. The work is generally known by the term सिद्धान्तकोसदी, or even कीमुदी, and it has got a large number of scholarly and ordinary commentaries as also commentaries on commentaries, all numbering above twelve, and two abridgments the Madhyakaumudī and Laghukaumudi. The work was written by the reputed scholar Bhattojī Dīksita of Vārānasī in the seventeenth century. See Bhattoit Dīksita.

वैयाकरणसिद्धान्तकोमुदीटीका or सिद्धान्त-कोमदीन्याख्या a general name given to the large number of commentaries written by members of the line of pupils, and pupils of pupils of Bhattoji. The well-known among the commentaries are प्रौढमनोरमा by the author himself, तत्त्वबोधिनी by ज्ञानेन्द्रसरस्वती, सुबोधिनी by जयकृष्णमह मौनी बालमनेरमा by वासुदेवदीक्षित, and crowning all, the लघुराब्देन्द्रशेखर by नागेशमह. The श्रीदमनोरमा has got a learned commentary written by हरिदोक्षित called लघुराब्दरत्न or राज्दरत्न, which also has on it commentaries named भावप्रकाश by बाळंभट्ट and शब्दरत्तदीप by कल्याणमल्ड. The Laghusabdendusekhara has got commentaries reaching about ten in number.

वैयाकरणसिद्धान्तभूषण the same as वैयाकरणभूषण, which see above.

वैयाकरणसिद्धान्तमञ्जूषा a well-known work on the syntax and denotation of words written by Nagesabhatta which is popular by the name Laghumañjūṣā. The Paramalaghumañjūṣā is an abridgment of this work by the author himself.

वैयाकरणासिद्धान्तरत्नाकर name of a commentary on the Siddhanta-kaumudī by Ramakṛṣṇa in the latter half of the seventeenth century.

वैयाकरणासिद्धान्तरहस्य name of a commentary on the Siddhantakaumudī by Nīlakantha.

वैयात्रपद्य name of a treatise of grammar written in ten chapters by an ancient grammarian ज्यात्रपाद; cf. दशकं वैयात्रपद्यम् Kāś.on P. IV 2.65. For details, see Vyākaraṇamahābhāṣya Vol. VII. D. E. Society's Ed. pp. 133, 134.

वैवचन a term used for the Pragrhya vowel, possibly the same as दैवचन, which means a specific feature of दिवचन or the dual number. The term is used in some Siksā works.

वैत्रुत्त name given to the svarita or circumflex accent on the vowel following upon a vowel accented acute, when there is a vivitti or pause between the two vowels; e. g. य इन्द्र:; cf. वैत्रत्ततेराज्यज्ञना क्षेप्रामिनिहती च तान्। R. Pr. III. 10.

वैशिष्टच specific feature, peculiarity.

वैशेष्य special differentiating feature; cf. अनुप्रदानात्संसर्गात् स्थानात् करणविन्ययात्। जायते वर्णवैशेष्यं परीमाणाच्च पश्चमात् ॥ T.Pr. XXIII. 2.

वैषम्य diversity in number or properties; cf. एवमपि पञ्चागमास्त्रय आगमिन; वैषम्यात्मंख्यातानुदेशो न भवति M. Bh. Ahnika 1; cf. also M. Bh. on P.I. 2. 27, I. 3. 10 Vart. 4, I. 4.101.

वैषायक (1) pertaining to the word विषय in the sutra विषयो देशे P. IV.2. 52; the term refers to the tad. affixes prescribed in the sense of 'country' or 'district' (विषय) in

P. IV. 2.52-54 as contrasted with नैनासिक affixes prescribed in the sense of 'inhabited district' by P. IV. 2.69-80; (2) one of the three senses of the locative case, viz. the sense 'substratum' of the locative case, which is not physical but which is a topical one, forming an object or aim of an action as specified by the word 'about'; cf. अधिकरण नाम त्रिप्रकार ब्यापकमापकेराविक विषयिकमिति।

व्यक्त distinctly perceived ie. perceived with reference to the individual referred to, which enables the speaker to apply the specific affixes in the sense of gender and number; cf. प्रातिपादिकं सामान्यभूतेर्थे वर्तते । सामान्य चाप्यपदिष्टं व्यक्तस्य सतो वर्तसानस्य व्यक्तिरपजायते । लिङ्कसंख्याभ्यामन्वितस्य बाह्यनार्थेन योगो भवति । M.Bh. on P.I.1.57.

ड्यक्ति (1) lit.distinct manifestation, as for instance that of the generic features in the individual object; cf.सामान्य वर्तमानस्य ज्याक्तरपजायते, M.Bh. on P.I.1,57; (2) gender, which in fact, is the symbol of the manifestation of the generic property in the individual object; cf. हरीतक्यादिषु ज्यक्तिः P.I.2.52 Vārt. 3, as also छपि युक्तवद् ज्यक्तिवचने P.I.2.51; (3) individual object; cf. ज्यक्तिः पदार्थः

च्याकिपदार्थवाद the same as द्रव्यपदार्थवाद; the view that a word denotes the individual object and not the generic nature. The oldest grammarian referred to as holding this view, is व्याडि who preceded Patanjali.

ह्यङ्कटसुङ्बाशास्त्री a grammarian who has written a grammar treatise named भाषामञ्जरीज्याकरण.

ed with the denoted sense; (2) the supreme or ultimate suggested

sense viz. Sphota which is the ultimate sense of every sentence.

व्यञ्जन a consonant; that which manifests itself in the presence of a vowel, being incapable of standing alone; cf.न पुनरन्तरेणाचं व्यञ्जनस्योच्चारणमपि भवति । अन्वर्थे खल्वपि निर्वचनम् । स्वयं राजन्ते स्वराः । अन्वक् भवति व्यञ्जनम् । M.Bh.on I.2.30; cf. also अथवा गतिरपि व्यञ्जेरथः । विविधं गच्छत्यज्ञपरागवद्यादिति व्यञ्जनम् । उपरागश्च पूर्वपराच्छानिधानेपि परेणाचा भवति न पूर्वेण । Kaiyaṭa on P. I. 2. 30; cf. व्यञ्जनं स्वराङ्गम् T.Pr.I.6; cf. also व्यञ्जनसमु-दायस्तु स्वरसंनिद्दित एव अक्षरं भवति । Uvvaṭa Bhāṣya on V. Pr.. III.45.

च्यञ्जनसंधि a junction or coalescence of two consonants as distinguished from स्वरसंधि. In Pāṇini's system of grammar the name इल्संधि is given to च्यजनसंधि and the Siddhāntakaumudī has given a separate section for it.

डयअनसंनिपात or संयोग, conjunction or falling together of two consonants; cf. हलोनन्तरा: संयोग: P.I.1. 7.

ड्यञ्जनाविद्यमानवद्भाव consideration of a consonant being not present as far as the accentuation of a vowel is concerned, the vowel being looked upon as the initial or the final, irrespective of the consonant or consonants respectively preceding it, or following it; cf. स्वरविधो ब्यञ्जन-मविद्यमानवद् भवति Par. Sek. Pari. 79.

च्यत् tad. affix च्य added to the word भ्रात् in the sense of अपत्य, e.g. भातृच्यः; cf. P.IV.1. 144.

व्यतिकर (1) confusion of one numberaffix for another number-affix
(वचन), as noticed in the statements
e. g. अक्षीणि मे दर्शनीयानि; पादा मे सुकुमारंतराः M. Bh. on P.I. 4. 21; (2) any
confusion, say confusion of one
grammatical element for another;
cf. हि: परस्मेपदानां यथा स्यात्, स्व आत्मनेपदानां, न्यतिकरो मा भूत् M. Bh. on P.

III.4.1 Vārt. 2.

च्यतिरिक्त distinct from, separate from, cf. कर्मादिभ्यान्यः प्रातिपदिकार्थंब्यतिरिक्तः स्वस्वामिसंबन्धादिः शेषः । Kāś. on P.II. 3. 50.

व्यतिरेक (1) surplus, excess; (2) separate presence; (3) contrary thing; cf. तत्र पलव्यतिरेकापि स्यात् । M. Bh. on Ahnika 1.

व्यतिषङ्ग reciprocal junction or connection; cf. ह्रस्वानुस्वारुव्यतिषङ्गवत् परे;R.Pr. XIII.16.

च्यतिहार exchange of activity; cf. कर्तिरि कर्मन्यतिहारे P.I.3.14.

व्यत्यय occurrence of one for another; transposition; cf. सु:तिङ्कपग्रह ... व्यत्यय-भिच्छति शास्त्रकृदेषां... M. Bh. on P.III. 1.85. See विपर्यय.

ड्यथन alteration of a phonetic element; change of sound; mispronunciation; cf. तदापायन्यथनानि दोषा: R.Pr.XIV. 1.

व्यधिकरण characterized by different case-relations or case-affixes; possessed of different case-affixes; कः प्रसङ्गा यद् व्यधिकरणानां समासः स्यात् M. Bh. on P. II. 1.67.

ड्यन् tad. affix ब्य causing the acute accent for the first vowel of the word, added to the word आतृ when the sense of the word so formed, is 'enemy'; see ब्यत् above; cf. P.IV 1.145.

व्यपकर्ष exception to a rule; cf. किमिदं व्यपकर्षविज्ञानादिति । अपवादविज्ञानात् M.Bh. on P.VIII.4.61 Vart 4.

च्यपदेश (1) special designation or representation; cf. आङ्गतिन्धपेदेशानां प्राय आदित आदितः R. Pr. XVII. 4; (2) main designation; cf. निभित्तसद्भावाद्वि-शिष्टपेदेशः न्यपदेशः मुख्यो न्यवहारः Par. Sek. Pari. 30; cf. also यो द्वयोः षष्टी-निर्दिष्टयोः प्रसङ्गे भवति, लभतेसै अन्यतरतो न्यपेदशम्। M.Bh.onP.I.1.51 Vart. 7.

dary thing as the principal one, e. g. a person or a thing, without any second or any others, looked upon as the first or the last; cf. ब्यपदेशिवदेकस्मिन् कार्य भवतीति वस्तब्यम् M. Bh. on P. I. 1.21. Vārt. 2. The remark or expression ब्यपदेशिवद्भावन भविष्यति is found often given in the Mahābhāṣya; cf. M. Bh. Āhnika l Vārt 14; I.1.9, I. 1.51 I,1.72; I.2.48 etc. For details see Par. Sek. Pari. 30.

व्यपदेशिवद्वचन statement of Vyapadesivadbhāva; cf. तत्र व्यपदेशिवद्वचनम्— एकाचो द्वे प्रथमार्थे षत्वे चादेशसंप्रत्ययार्थम् । M. Bh. on VIII.3.59 Vārt. 7.

व्यपवगे (1) division of a single thing into its constituent elements; cf. स्थानिवद्भावाद् ब्यपवर्ग: M. Bh. on VII. 2.36, VII.3.44 Vart. 3; (2) distinct comprehension as possessed of a specific quality; cf. न हि गौरित्युक्ते ब्यपवर्गी गम्येत ग्रुङ्गा नीला कपिला कपोतिति। M.Bh. on P. I.2.64 Vart 37; (3) separation into parts, cf. काश्चदिक्तेनेव प्रहारेण न्यपवर्ग करोति, M.Bh.on V.I.119 Vārt 5; (4) distinct notion as a separate unit after the things have been combined; cf. एकादेशे कते व्यवन्त्रीभावः संबुद्धिलोपो न प्राप्तोति M. Bh. on P. VI.1.69 Vart 3; cf. also M. Bh. on VII.1.80.

व्यपचुक्त distinctly separated as two or more consonants joined together in a conjunct consonant, as contrasted with the two vowels in a diphthong which cannot be called व्यपवृक्त; cf. नाज्यपवृक्तस्यावये तादिषियंथा द्रज्येषु. M. Bh. on Siva Sūtra 3.4 Vārt. 9. cf. also वर्णेकंदशा: के वर्णप्रहणेन एहान्ते। ये ज्यपवृक्ता अपि वर्णा भवान्ते, M. Bh. on Siva Sūtra 3,4 Vārt. 11.

as obtaining between two different words (पद) connected with each other in a sentence, as contrasted with compositeness of sense as seen in two words joined into a compound word (समास); ब्यपेक्षा is given as an alternative definition of the word सामध्ये along with एकार्थीमान as the other one, in the Mahābhāṣya; e. g. there is ब्यपेक्षा between सर्पि: and पिन in the sentence सर्पिचिन, but not in तिष्ठतु सर्पिः पिन त्नमुद्दकम्; cf. तथदमपर देतं मनति एकार्थीमानो ना सामध्ये स्याद् ब्यपेक्षा नेति। M. Bh. on P. II,1.1; cf. also Kāś. on P. VIII.3 44.

व्यपेत having an intervention of (a letter, or letters or a pada); the word is used in the same sense as व्यवहित; cf. स्वापिप्रहणं व्यपेतार्यम् । व्यपेतार्यम्मः । सुष्वापियष्रति । M. Bh. on P.VII.4.67.

ब्यमिचार lit. deviation or discrepancy; irregularity re: the application of a rule; cf.संज्ञान्यमिचारार्थश्रकार: Kāś.on P. III.3.19; cf.also. बहुलग्रहणं व्यभिचारार्थम्। प्रवाहिका, विचर्चिका। न च भवति। शिरार्ति:; Kāś. on P. III.3.108.

ज्यभिचारिन deviating, being irregular in application, not applying necessarily: cf. अभ्रशह्रस्यापूर्वनिपातस्य लक्षणस्य ज्यभिचारित्वात.

ह्यय lit. loss; disappearance; the word is used in the sense of inflectional changes. An indeclinable is called अन्यय because it has no inflectional changes. cf. तत्कथमनुदात्तप्रकृति नाम स्यात्। इष्टब्यं त भवति। Nir. I.8; V.23.

ड्ययनत् (1) possessed of ब्यय or inflectional change; a declinable word; cf. यस्य पुनर्विभक्त्यादि।भिर्विकारः कियते स ब्ययवान् । आद्युदात्तः स च अन्तःशब्दो भवति । V. Pr. II.26; (2) characterized by a loss of accent i.e. the loss of the original accent and the presence of another accent; cf. पदान्तस्य पदे दृष्टं स्विरितत्वं न दृश्यते । अदृष्ट्यमनुदात्तत्वं च दृश्यते । Uvvata on R. Pr. XI.31.

(1) useless, serving no purpose,

superfluous; the word is usually used in the sense of useless or futile in connection with a rule or its part, which serves no purpose, its purpose or object being served otherwise; such words or rules have never been condemned as futile by commentators, but an attempt is made invariably by them to deduce something from the futile wording and show its necessity:cf. ज्यर्थे सज्ज्ञापयति a remark which is often found in the commentary literature; cf. अन्यथा अन्तरङ्कत्वाहीर्घे कत एव प्रत्ययप्राप्त्या तद्यर्थता स्पर्वेव । Par. Sek. Pari. 56; (2) possessed of various senses such as the words अक्षा: माषा: etc.; cf. ब्यर्थेषु च मुक्तसंशयम् । M.Bh.on P.I.2.64 Vart. 52. The word ज्यर्थ possibly stands for विविधार्थ in such cases. It appears that the word ब्यर्थ in the sense of futile was rarely used by ancient grammarians; the word अनर्थक appears to have been used in its place. See Mahābhāsya in which the word ब्यथ does not occur in this sense while the word अनर्थक occurs at several places.

ह्यविष्ठिन्न (1) separated; detached from a specific thing by the loss of connection with it; cf. एवमेतासी-न्नुभयतो व्यवच्छिने यदि स्वार्थे जहाति जहातु नाम M. Bh. on P. II. 1.1. Värt. 2; (2) characterized or possessed of an intervention by similar things cf. तहा अनेकेन निपातनेन व्यवच्छिनं न शक्यमनुवर्तियतुमिति। M. Bh. on P. III. 3.83; cf. also P. VI. 4.2.

व्यवधान (1) intervention; the word is used in connection with the intervention or occurrence of letters or phonetic units between the cause (निमित्त) of an operation and the operatee (विधिमाक्); cf लोपे कृते नास्ति व्यवधानम् । स्थानिवद्भावाद् व्यवधानम् । The word is used also in the sense of intervention in gene-

ral, which separates the two connected things; ज्यवधानं च भवित वाक्ये राज्ञ ऋद्धस्य पुरुषः; the word ज्यवाय is used in the same sense; cf. अट्कुप्वाङ्नुम्ज्यवायेषि; (2) an inserted letter or phonetic element; cf. ज्यवधानः अन्त्यविकारे T. Pr. 185, 186.

ह्यवधायक causing an intervention; intervener which is required to be of a different kind; cf अतज्जातीयकं व्यवधायकं भवति M. Bh. on P. I. 1.7. Vart 8.

स्यवस्था lit. definite arrangement; restriction regarding the application of a rule, especially when it seems to overlap, as done by the Varttikakara, and later on by the Paribhāṣās laid down by grammarians regarding the rules of Pāṇini; cf. स्वाभिषेयापेक्षावाधिनियमो व्यवस्था S. K. on P. I. 1.34; cf. also लक्ष्यानु- साराद्यवस्था Par. Sek. Pari. 99, 108.

व्यवस्थितविभाषा an option which does not apply universally in all the instances of a rule which prescribes an operation optionally, but applies necessarily in some cases and does not apply at all in the other cases, the total result being an option regarding the conduct of the rule. The rules अजेर्क्यघनपो: P. II. 4.56, लट: शतृशा-नचावप्रथमासमानाधिकरणे III. 2.124 and वामि I. 4.5 are some of the rules which have got an option described as ज्यवस्थितविभाषा. The standard instances of ब्यवास्थितविभाषा are given in the ancient verse देवत्रातो गला प्राहः इतियोगे च सद्विधिः । मिथस्ते न विभाष्यन्ते गवाक्ष: संशितत्रत: || M. Bh. on P. III. 3.156; VII.4.41.

ज्यवित having an intervention by a dissimilar thing; separated by something coming between; cf. संयोगासंज्ञा ज्यवाहितानां मा भृत् M. Bh. on I. 1.8. Vart. 5.

व्यवाय intervention, separation by insertion; separation by means of the insertion of a phonetic element. See व्यवधान above. cf. अट्कुप्वाङ्नुम्व्यवायेषि P. VIII. 4.2; अडम्यासक्यवायेषि P. VI. 1.26; cf. अङ्गक्यवाये चाङ्गपर: R. T. 190; संयोगानां स्वरमक्त्या क्यवाय: R. Pr. XIV. 25.

elements; separated by a new insertion; a recital of the Vedic text by separating a coalesced vowel, which is looked upon as a fault of recital.

व्याकरण Grammar; the development of the meaning of the term can be seen by the senses given below in a serial order and the examples after those senses; (a) analysis or explanation by analysis; (b) rules of explanation; (c) specific rules explaining the formation of words; (d) explanation of the formation of rules; (e) a treatise in which such an explanation is given; (f) a collection of such treatises and (g) a systematic explanation of the formation of words in a language (ब्याकरणशास्त्र or शहानुशासन); cf.(a) न्याकियते अनेन इति ब्याकरणम् ; M.Bh.on Ahnika 1. Vart. 12; cf. (b) लक्ष्यलक्षणे ब्याकरणम्; M. Bh. Ahnika 1, Vart. 14; cf. (c) न यथा लोके तथा ब्याकरणे M. Bh. on P. I. 1.1. Vārt. 7; (d) सर्वत्रैव हि ब्याकरणे पूर्वोच्चारित: संज्ञी परोच्चारिता संज्ञा M. Bh. on P. I. 1.1. Vart 7; (e) न तथा लोके यथा ब्याकरणे M.Bh. on P. I. 1,23 Vār*. 4: cf.(f)इह च ब्याकरणे शब्दे कार्यस्य संभव:, अर्थे असंभव: 1 M. Bh. on P. I. 1.68. cf. (g) ज्याकरणं नाम इयमुत्तरा विद्या | M. Bh. on P. I. 2.32. The word ब्याकen is mostly used in the sense of 'the Science of Grammar' in the Mahābhāsya. It is explained by modern scholars as 'the law of the correctness of speech and etymological science' and described both as a science and an art.

व्याकरणचिन्द्रिका a short treatise on grammar written by Kṛṣṇācārya.

च्याकरणदर्शन the science of Vyākaraņa with the element of Sphota introduced in it and brought consequently on a par with the other Darsanas by the stalwart grammar-scholar Bhartrhari of the 7th century A. D. For details see Sarvadarsanasamgraha 'Pāṇinidarsanam' and page 385 Vol. VII. of the Vyākaraņa Mahābhāṣya edited by the D. E. Society, Poona.

स्याकरणदीप a small treatise on grammar by Cidrūpāśraya.

स्याकरणदीपिका name of a short gloss or Vṛtti on the Sūtras of Pāṇini written by a modern scholar of grammar Orambhaṭṭa of Vārāṇasi.

ভ্যাক্রবেজমান্য name of the commentary written by Mahāmiśra on Jinendrabuddhi's great work 'Kāśikāvivaraṇapañjikā' or Nyāsa.

व्याकरणमहाभाष्य see महाभाष्य.

च्याकरणमहाभाष्यगुढार्थदीपिनी a brief commentary on the Mahābhāṣya, written by Sadāśiva, son of Nīla-kaṇṭha and pupil of Kamalākara Dīkṣita. The gloss confines itself to the explanations of obscure and difficult passages in the Mahābhāṣya and criticizes Kaiyaṭa's explanations.

ह्याकरणमहाभाष्यप्रदीप the original name of the learned commentary on Patañjali's Mahābhāṣya by Kaiyaṭabhaṭṭa the well-known grammarian of Kashmir of the eleventh century. See प्रदीप and केयट.

व्याकरणमहाभाष्यप्रदीपविवरण () a gloss on the Mahābhāṣyapradīpa of Kaiyata, written by ईश्वरानन्द, a pupil of सत्यानन्द; (2) a gloss on the Mahābhāṣyapradīpa of Kaiyaṭa by नारायण.

व्याकरणमहाभाष्यप्रदीपोद्द्योत the wellknown scholarly commentary by the stalwart grammarian Nāgeśabhaṭṭa on the Mahābhāṣyapradīpa of Kaiyaṭa. See उद्दोत and नागेश.

व्याकरणमहाभाष्यव्याख्या see महाभाष्य above.

च्याकरणरत्नावली a short work on grammar written by विद्यारन गौरमोदन.

च्याकरणसंग्रह a small grammar work written by a grammar scholar Gangadhara which is based upon the Mugdhabodha of Bopadeva.

व्याकरणसुधानिधि a gloss on the Sūtras of Pāṇini written by Viśveśvara.

द्याकरणाध्ययनप्रयोजन the purpose of the study of Grammar which is beautifully summed up and discussed in the first Ahnika by Patanjali in his Mahābhāṣya.

ड्याकरणान्तर a term used by scholars of the Pāṇiniyan system of grammar with respect to grammar works of other systems such as the Kātantra, the Sākaṭāyana, and others; cf. अन्थिमान्धिदामिसवञ्जीनां लिट: किस्वं ज्याकरणान्तरे S.K. on अश्रातेश्च P. VII.4.72.

व्याख्यान (1) explanation of a rule, or a line, or a verse by analysing the rule and giving examples and counter-examples; cf. न केवलानि चर्चापदानि व्याख्यानं दृद्धिः आत् ऐजिति। किंति । किंति । उदाहरणं प्रत्युदाहरणं वाक्याध्याहारः इत्येत्तसमुदितं व्याख्यानं भवति। M.Bh. Āhnika 1 Vārt.11;(2) authoritative decision given in places of doubt by ancient scholars; cf. व्याख्यानतो विशेषप्रातिपत्तिः न हि संदेहादलक्षणम् M.Bh. Āhnika 1; Par Sek.Pari.1.

ब्याझपाद् name of an ancient grammarian who is quoted in the Prātiśākhya works and the Mahābhāşya, His grammar work was called 'daśaka' possibly on account of its consisting of 10 chapters; cf. माध्य-न्दिनिर्वष्टि गुणं व्यागन्त नपुंसक ब्याग्रपदां वरिष्ट: Kāś. on P.VII.194; cf. also दशका वैयाग्रपदीया: Kāś. on P.IV.2.65.

ह्याद्रभूति name of an old grammarian later than Patañjali who is quoted by later grammarians; cf. इयाद्रभूत्याद्यस्त्वेनं नेह पेटुरिति स्थितम् Siddhāntakaumudi on आत्मने रदेष्यनतः P. VII. 1. 5.

च्याञ्चादि a class of words headed by ज्याञ्च which, as standards of comparison, are compounded with words showing objects of comparison provided the common property is not mentioned; e.g. पुरुषञ्याञ्च:, नृसिंह: etc., cf. Kāś. on P.II. 1.56.

म्याडि name of an ancient grammarian with a sound scholarship in Vedic phonetics, accentuation, derivation of words and their interpretation. He is believed to have been a relative and contemporary Pānini and to have written a very scholarly vast volume on Sanskrit grammar named 'Samgraha' which is believed to have consisted of a lac of verses; cf. संग्रहो व्याडि-कृतो लक्षसंख्या प्रन्थ: Nāgeśa's Uddyota; cf. also इह पुरा पाणिनीये अस्मिन्व्याकरेण व्याङ्यपराचितं लक्षग्रन्थपरिमाणं निवन्धनमासीत् Vak. Pad. Tika. The work is not available at present. References to Vyādi or to his work are found in the Prātiśākhya works, the Mahābhāsya, the Vārttikas, the Vakyapadiya and many subsequent treatises. A work on the Vyakarana Paribhāsās, believed to have been written by Vyādi, is available by the name परिभाषासूच्यन which from its style and other peculiarities seems to have been written after the Vārttikas, but before the Mahābhāṣya. Vyādī is well-known to have been the oldest exponent of the doctrine that words denote an individual object and not the genus. For details see pp. 136-8, Vol. 7 Vyākaraṇa - Mahābhāṣya D. E. Society's Edition.

व्याडीय name given to the pupils and students belonging to the school of Vyādi; cf. M.Bh. on P.VI.2.36.

व्यापक covering or applying to the whole in entirety, and not in parts; cf. आधिकरणं नाम त्रिप्रकारं व्यापकमी-पक्षापिकं वैषियकमिति M. Bh. on P.VI.1. 72;cf. इतरो व्यापकत्वाच्छास्त्रासिद्धत्वं प्रदेशान्तर एव स्थापितं मन्यमान आह । Kaiyaṭa on P. VI.4. 22.

व्यापित्त lit. loss or disappearance; the word is used in the sense of conversion of one thing into another in the Prātiśākhya works; cf. अथा-प्यन्तन्यापित्तभैवति Nir. II. 1; cf. also अन्येरेकाराकातिरत्र पूर्वी ततो न्यापित्तभवतीति विद्यात् R. Pr.V.1.

ज्यास occupied fully; cf. तदाधिकरणं यत्र कृत्स्न आधारात्मा ज्याता भवति M. Bh. on P.I.3.11 Vārt. 7; cf. also M.Bh. on P.I.4.42; यावता सर्वमद्यापवादेज्यातम् P.IV. 3.134 Vārt. 2.

च्याप्ति occupation; presence; comprehensive nature; cf. ज्यातिमत्ताजु राज्दस्य Nir.I.2, where ज्याप्ति refers to the permanent presence of the word in the minds of the speaker and the hearer, the word राज्द referring to the नित्यराज्द or स्पोट.

न्याप्तिन्याय the general method of taking a comprehensive sense instead of a restricted one in places of doubt; cf. न्याप्तिन्यायाद्वा Kāś. on P. III. 2. 168.

ज्याच्य lit. that which is occupied; the word refers to a kind of an object where the object is occupied by the verbal activity of the transitive root; the word आप्य is also used in this sense; cf. कमं निर्वत्यं विकायं प्राप्यं च यस्य प्रकृत्युच्छेदो गुणान्तरं वोत्पद्यते तद्विकार्यम् Śringāra- Prakāša 2. The term is used as a technical term instead of the term कमं in the Hemacandra, Cāndra and other systems of grammar; cf. Hem. II.2.3; Cāndra I.1.23.

ज्यायत separated; one out of the two conjoined consonants separated by inserting a vowel in between; cf. ज्यस्यन्त्यन्तर्महताऽ ज्यायतं तं दीर्वायुः स्यौं स्वादीतं ऊजम् R. Pr. XIV. 19, where Uvvaṭa gives the explanation-दीर्वात्यरं अज्यायतं अपृथग्भूतं रेपेण सक्तमित्यथः एवं- भूतं ज्यस्यान्त पृथनकुर्वन्ति । यथा । दीरिवायुः । स्त्रियः । स्वादीरिते । अरजम्. ऐk Samhitā I. 85. 39, X. 158. 1, IX. 91.3 and IX. 63. 2.

and going back from a subsequent word to the previous one, as in the Krama, Jatā and other artificial recitals of Veda.

व्यानाति pushing aside; removal; the word is frequently used in connection with the setting aside or removal of the application of such rules, as also of the contingency of such rules as are not desired in the formation of a correct word. by means of applying another rule necessary for the correct formation; cf. तदि इदं तिष्यपुनर्वेसु इत्यत्र तद्वयातृत्यर्थम् Par. Sek. on Pari. 34; as also तांद्धे असवर्णग्रहणं ईषत्रित्यादौ इयङादिन्यावृत्त्यर्थम् Par Sek. on Pari 55: cf. also the usual statement ब्यावित: कियते ।

व्याश्रय resting on, or applying to, different words or elements of words or parts of words; the word is used in connection with a grammatical operation which affects one part of the word, as distinguished from another

operation which affects another part; cf. आभीयं कार्यं समानाश्रयमसिद्धम्। ब्याश्रयं सिद्धं मनति। M.Bh. on P.III.1. 44, VI. 4.22 Vārt.12, VI.4.42 etc.

च्यास (1) showing separately; separate expression as contrasted with समास; (2) fault of pronunciation of the type of unnecessarily extending the place of origin as also the instrument of the production of sound; cf. स्थानकरणयोविंस्तारे ज्यासो नाम दोषो जायते Uvvatā on R. Pr. XIV. 2.

व्याहृति or व्याहृती lit. the utterance of a word; the word is generally used in the sense of the specific utterance of the words मू:, भुवः etc: cf. एताभिव्याहृतीभिः प्रजापतिः Tait. Sam I. 6. 10; cf. also भुवश्च महाव्याहृतेः P. VIII. 2.71.

व्युत्क्रमण the same as ब्यावर्तन or परिवर्तन, which see above.

च्युत्पत्ति derivation of a word from a root which formed a special feature of the Nairukta school of Vedic scholars in ancient times; the word निर्वचन is used in the same sense; cf. सित समये ब्युत्पत्तिरन्यथा कर्तब्या रूटेरनियमात् Kāś. on P. V. 2.93.

ब्युत्पत्तिपक्ष the view that every word is derived from a suitable root as contrasted with the other view viz. the अब्युत्पत्तिपक्ष. The grammarians hold that Pāṇini held the अब्युत्पत्तिपक्ष, i.e. the view that not all words in a language can be derived but only some of them can be so done, and contrast him (i.e. Pāṇini) with an equally great grammarian Sākaṭāyana who stated that every word has to be derived; cf. न्यग्रोध्यतीति न्यग्रोध इति ब्युत्पत्तिपक्षे नियमार्थम्। अब्युत्पत्तिपक्षे विध्यर्थम् Kāś.on P.VII.3.6.

च्युत्पत्तिवाद (1) name given to a topic in grammar which deals with the derivation of words as suitable to the sense; (2) name given to treatises discussing the derivation and interpretation of words.

ह्युत्पन्नत्व derivation, correct understanding of the sense by derivation.

ह्युत्पन्नपञ्च the view that every word in the language has been derived from a root which explains its sense; see ब्यूराचिवक्ष.

च्युदास setting aside of a rule or operation by means of another more powerful rule, or by means of a conventional dictum.

च्युष्टादि a class of words headed by the word च्युड to which the taddhita affix अ (अण्) is added in the sense of the place where something is given or prepared; cf. च्युड दियते कार्य वा वैयुष्टम् । नैत्यम्; Kāś. on P.V.1.97.

च्यूह (1) resolution or determination; cf. अकृतन्यृहाः पाणिनीयाः । न कृतो विशिष्ट ऊही निश्चयः शास्त्रप्रवृत्तिविषये यैः इत्यर्थः Par. Sek. Pari. 56; (2) separation of the phonetic elements in a word, done especially for the recital of the Vedic texts according to metre; cf. न्यूहः संपत्समीक्ष्योने क्षेप्रवर्णेकभाविनाम् । न्यूहः पृथक्रणेन Uvvaṭa on R. Pr. VIII.22.

बीड़न lowering of the chin, resulting in a fault of utterance; cf. इन्वोन्नीडन निचैमांवे संदर्ध नाम दोषो भवति । Uvvața on R.Pr. XIV.3.

नोह्यादि a class of words headed by नीहि to which the taddhita affixes इन् and ठन् are applied in the sense of possession along with the usual affix मत् (मतुष्); e. g. नीही, नीहिकः नीहिमान्। मायी, मायिकः मायावान्; cf. Kās. on P.V. 2. 116.

DWIGHT, 1827-1894] a sound scholar of Vedic grammar who has, besides some books on Linguistic studies, written a work on Vedic Grammar and edited the Atharvaveda Prātišākhya.

श

ম্ (1) a sibilant letter of the palatal class, possessed of the properties, শ্বাধানুমবান, স্থান and কডবিহুমান; (2) the initial indicatory (হুন্) letter হ্য of a non-taddhita affix in Pāṇini's grammar, which is dropped; (3) substitute for ল্ফ when followed by an affix beginning with a nasal consonant; e.g মুদ্ধ;, cf. P.VI.4.19;(4) substitute for स when followed by হ্য or any palatal letter; e.g. হুপ্লম্ভাবেষনি নুম্বন্ধীন Kāś.on P. VIII. 4.40.

श् (1) conjugational sign(विकरण) applied to the roots of the sixth conjugation (तदादिगण) in all conjugational tenses and moods (i. e. the present, the imperfect, the imperative and the potential) before the personal-endings; cf. तुदादिभ्य: शः, P. III.1.77; this sign হা (া) has got the initial consonant য় as an indicatory one, and hence this अ is a Sārvadhātuka affix, but, it is weak and does not cause गुण for the preceding vowel; (2) tad. affix য় in the sense of possession applied to the words लोमन् and others; e. g. लोमशः, रोमश:cf. P.V.2. 100; (3) krt affix (अ) applied to the roots पा, ब्रा, ध्मा, धे and हशु when preceded by a prefix, to the roots लिम्पू, विन्द् etc.not preceded by a prefix, and optionally to दा and घा of the third conjugation in the sense of 'an agent'; e.g. डात्पेबः, उत्पश्यः, लिम्पः, विन्दः ददः, दाय: ; cf. P.III.1.137-139.

হাক্ষেই name of a grammarian of the eighteenth century who wrote a commentary, called আক্রী after him, on Nāgeśa's Paribhāṣenduśekhara.

शंकरशास्त्री (मास्लकर) a modern scholar of grammar who lived in Poona and did the work of teaching and writing commentaries. He has written a commentary named शांकरी on the Vaiyākaraṇabhūṣaṇasāra of Koṇdabhatta.

इंखिंग name given to a Yama letter in the Sikṣā treatises.

शकन्युक name of a class of words in whose case the last vowel of the first word does not coalesce with the first vowel of the next word; e. g. शक अन्युक ईश । अक्षपा असि । वपा इव त्मना । सुपथा अङ्गण्यन् । cf. शकन्युकादीनाम् R.T.87 which is explained by the commentator as शकन्युकादीनां च न संनिङ्ग्ध्यते.

इाकन्स्वादि name of a class of words in which an irregular coalescence of the vowels of the kind of the latter vowel in the place of the former and latter both is observed; e.g. शकन्यु:, कुल्टा, सीमन्तः,मनीषा etc. cf. कन्य्वादियु च (परक्षं वाच्यम्) P.VI.1. 94 Vart. 4.

হাৰন endowed with হাৰিন i.e. the potentiality to express the sense; potent to show the particular sense.

शांक्त potentiality of expressing the sense which is possessed by words permanently with them; denotative potentiality or denotation; this potentiality shows the senses, which are permanently possessed by the words, to the hearer and is described to be of one kind by ancient grammarian as contrasted with the two (अभिषा and लक्षणा) mentioned by the modern ones. It is described to be of two kinds—(a) स्मारिका शाक्त or recalling capacity which combines चेत्रत्व with पाक, and अनुमावि-का शक्ति which is responsible for the actual meaning of a sentence. For details see Vakyapadīya III.

श्चय the substratum of potentiality

which forms the object pointed out by means of the potentiality to the hearer by the word (i.e. शब्द) which directly communicates the sense, in which case it is termed वाचक as contrasted with भदक or द्योतक when the sense, which is of the type of संबन्ध is conveyed rather indirectly. This nice division into वाचकता and भदकता was introduced clearly by भर्तृहरि; cf. Vākyapadīya Kāṇḍa 2.

शङ्कटच् tad. affix शङ्कट applied optionally with the affix शालच् (शाल) to the prefix वि in the sense of the base itself (स्वायें); e.g. विशङ्कटम् । विशालम् ।; cf. S.K. on P.V. 2.28; cf. Kāś. on P.V.2.28 which states विशाल विशङ्कट शङ्के । तस्माद् गौरपि विशङ्कट उच्यते ।

स्तिण्डकादि a class of words headed by the word शण्डिक which have the taddhita affix य (ज्य) added to them in the sense of 'domicile' or 'native place'; e.g. शाण्डिक्यः, सार्व-सेन्यः, cf. Kāś. on P. IV. 3. 92.

शत् tad. affix शत् as seen in the words त्रिंशत्, चत्वारिशत् etc., cf. पाङ्किविशतित्रिं- शचल्विरिशत् P. V.1.59.

इातपाद conventional name given to the fourth pada of the fifth adhyāya of Pāṇini's Aṣṭādhyāyī which begins with the sūtra पादशतस्य संख्यादेवीं सायां दुन् छोपश्च P. V. 4.1.

शांते tad. affix शति applied to the word द्वि to form the word विशति; cf. P. V. 1. 59.

शत kṛt affix अत in the sense of 'the agent of the present time', applied to any root which takes the Parasmaipada personal affixes: cf. छट: शतृशानचावप्रथमासमानाधिकरणे P. III. 2.126,8. The words formed with this शतृ (अत्) affix are termed present participles in the declension of which, by virtue of the indicatory vowel क in शतृ, the

augment नुम् is inserted after the last vowel of the base, and the root receives such modifications as are caused by a Sārvadhātuka affix, the affix शतृ being looked upon as a Sārvadhātuka affix on account of the indicatory letter श्. The word ending in this affix शतृ governs a noun forming its object, in the accusative case.

शतस्वर the acute accent specifically stated for the vowel of the case—affix beginning with a vowel etc. prescribed by the rule शतुरनुमा नग्नजादी P. VI. 1.173; cf. शतृरवर । तुदर्ता नुदर्ता ... शतुरनुमो नग्नजादिरन्तादात्तादित्येष स्वरा यथा स्थात् M. Bh. on P. VIII. 2.6. Vārt 2.

शास्त्रे, शध्येन् kṛt affix अध्ये in the sense of the infinitive added, to a root as seen in the Vedic Literature; cf. तुमर्थे सेसनसअसेन्यसेकस्त्रेअध्येन्कध्येक्ध्येन्कध्येक्ध्येन्कध्येक्ध्येन्कध्येक्ध्येन्कध्येक्ध्येन्कध्येक्ध्येन्कध्येक्ध्येन्कध्येक्ष्येक्ध्येन्कध्येक्षेत्रेक्षेत्रेक्ष्येक्ष्येक्षेत्वेक्ष्येक्षेत्रेक्षेत्रेक्षेत्रेक्षेत्रेक्ष्येक्षेत्

शप् a vikaraņa affix (conjugational sign) applied to roots of the first conjugation and in general to all secondary roots i. e. roots formed from nouns and from other roots before personal-endings which are Sārvadhātuka and which possess the sense of agent, provided there is no other vikarana affix prescribed; e.g. भवति, एधते, कारयति, हारयति, बुभुषति, पुत्रीयति, पुत्रका म्यात, कामयते, गोपायति, कण्ड्रयति, पटयति, दिनन्ति (यामिन्यः) etc. cf. कर्तरि शप्, P. III.1 .68. This affix হাবু is dropped after roots of the second conjugation (अदादि) and those of the third conjugation (जुहात्यादि) and in Vedic Literature wherever observed; cf. P.II.4.72, 73, 75, 76.

श्वरस्वाभिन् a grammarian to whom a metrical treatise on genders named लिङ्गानुशासन is ascribed. This शवरस्वाभिन् was comparatively a modern grammarian who was given the

title बालयोगिश्वर. This लिङ्गानुशासन has a commentary written by हर्षवर्धन. Evidently these grammarians शवरस्वामिन् and हर्षवर्धन are different from the famous author of the मीमांसामाष्य and the patron of the poet Bāṇa respectively.

श्रावादेश the Vikaraṇa affixes रुपन्, राज्यम्, उ and आ according to those who hold the view that these affixes do not form the exceptions of राप्, but they are substituted for राप् . cf. राबादेशा: रुपत्राद्य: करिष्यन्ते M. Bh. on P. I.1.27, II.2.3, III.1.33 and III.1.67.

शब्द lit. 'sound' in general; cf. शब्दं कुर शब्दं मा कार्षी: । ध्वनिं कुर्वनेवमुच्यते । M.Bh. in Āhnika 1; cf. also হাল্ব: সক্রারি: सर्ववर्णानाम् । वर्णप्रक्तः शब्दे। वाच उत्पत्तिः T. Pr. XXIII.1, XXIII.3.In grammar the word शब्द is applied to such words only as possess sense; cf. प्रतीतपदार्थको लोके ध्वनिः शब्दः M. Bh. in Ahnika 1; cf. also येनोचारितेन अर्थः प्रतीयते स शब्द: Sringara Prakasa I; cf. also अथ शब्दानशासनम् M.Bh. Ahnika 1. In the Vājasaneyi-Prātisākhya, शब्द is said to be constituted of air as far as its nature is concerned, but it is taken to mean in the Prātiśākhya and grammar works in a restricted sense as letters possess-The Vajasaneyiof sense. Prātisākhya gives four kinds of तद्धित and समास words तिङ्, कृत्, while नाम, आख्यात, निपात and उपसर्ग are described to be the four kinds in the Nirukta. As दान्द in grammar, is restricted to a phonetic unit possessed of sense, it can be applied to crude bases, affixes, as also to words that are completely formed with case-endings or personal affixes. In fact, taking it to be applicable to all such kinds, some grammarians have given twelve subdivisions of शब्द, viz. प्रकृति, प्रत्यय,

उपस्कार, उपपद, प्रातिपदिक, विभाक्ते,उपसर्जन, समास, पद, वाक्य, प्रकरण and प्रबन्ध; cf. Sringāra Prakāśa I.

राब्दकीस्तुम a treatise on grammar, critically explaining and discussing the meaning of Pāṇini's Sūtras in the order of the author himself. The work is written by Bhaṭṭojī Dīkṣita and is mainly based on the Mahābhāṣya.

इान्द्रकोस्तुभगुण a short gloss on Bhattoji's Sabdakaustubha written by a grammarian named इन्द्रदत्तापाच्याय.

शब्दकीस्तुभटीका or शब्दकीस्तुभप्रभा a commentary on Bhattoji's Sabdakaustubha written by Vaidyanātha Pāyaguņḍe.

शब्दकोस्तुभव्याख्या a commentary on Bhattoji's Sabdakaustubha, named विषमपदन्याख्या, a name probably given to a commentary written by Nāgeša.

शब्दचान्द्रकोद्धार name of a commentary on the Sārasvata-Vyākaraņa by Kamsavijaya.

मार्क्स lit. the essence of a word; the ultimate sense conveyed by the word which is termed स्पोट by the Vaiyākaraṇas. Philosophically this Sabdatattva or Sphota is the philosophical Brahman of the Vedāntins, which is named as Sabdabrahma or Nādabrahma by the Vaiyākaraṇas, and which appears as the phenomenal world on the basis of its own powers such as the time factor and the like; cf. अनादिनियनं अस शहतत्त्वं यदस्यस् ! विवर्ततिर्थमायेन प्रक्रिया जगतो यतः ॥ Vākyapadīya, I.1; cf. also Vākyapadīya II.31.

शब्द्रीपिका name of a commentary on the Mugdhabodha Vyākaraņa by Govindarāma.

शब्दद्योत्यत्व the indicatory power to show the sense; the word is used in connection with the potentiality to convey the sense possessed by the Nipātas.

शब्दानित्यत्व the doctrine of the Vaiyākaraṇas as also of the Mīmāmsakas that word is permanent, as contrasted with that of the Naiyāyikas who advocate the impermanence of words.

शब्दपरविप्रतिषेध the comparatively superior strength possessed by a word, which in the text of a particular sūtra is later than another word, which is put in earlier in the Sutra. This राब्दपरविप्रातिषेधे is contrasted with the standard शास्त्रपरविप्रतिषेध which is laid down by Pāṇini in his rule विपतिषंधे परं कार्यम् and which lays down the superior strength of that rule which is put by Pāṇini later on in his Astadhyāyī; e. g. in the rule विभाषा गमहनविदाविशाम्, it is not the word इन् although occuring earlier, but the word निश् occuring later in the rule, which helps us to decide which विद should be taken. cf.ज्ञानार्थस्य सत्यिप विदिरूपत्वे अर्थस्य भेदकत्वेन रूपवदाश्रयणात्प्रतिषेषाभावः । यद्यीप हन्तिना साहचर्य विदेरस्ति तथापि शब्दपराविधातिषेधाद् विशिज्येवस्थाहेतुर्न हान्तिः। Kaiyata on P VII.2.18; cf. also, P.VI.1.158 V.12.

शब्द्रप्रभा name of a commentary on Bhartrhari's Vākyapadīya which is available only on the first Kāṇḍa.

शब्दपारायण recital or enumeration of one word after another in a language; cf. वृहस्पतिरिन्दाय दिव्यं वर्षसहस्रं प्रतिपदाक्तानां शब्दानां शब्दपारायणं प्रोवाच नान्तं जगाम M.Bh. Ahnika I.

इाब्द्रयोग use of a word in the spoken language which forms in a way the basis of grammar.

राज्दबोधप्रक्रिया a grammar treatise on the denotation and relation of words written by a grammarian named Rāmakṛṣṇa.

- হাত্যমূষ্ণ name of a short gloss on the Sūtras of Pāṇini, written by Nārāyaṇa Paṇḍita.
- इान्द्रभेदनिरूपण name of a small grammatical work written by Rāmacandra Dīksita.
- মাৰ্মজাৰী name of a short grammar work written by Nārāyaṇa Paṇḍita.
- शब्दरन name of a scholarly gloss written by Haridiksita on the Manoramā, a commentary by Bhattoji Diksita his Siddhāntakaumudī. The proper name of the commentary is लघ्न-शब्दरत्न of which शब्दरत्न is an abridged form.The commentary ल्युशब्दरत्न is generally studied along with the Manorama by students. There is a bigger work named बृहच्छन्दरस्न written by Hari Diksita, of which the लघुशदूरन is an abridgment.
- হাত্বন্দোহীকা known by the name মানসকাহীকা, a commentary on Hari Dīkṣita's Sabdaratna, written by Vaidyanātha Pāyaguṇḍe.
- राज्यस्नदीप a commentary on the Laghusabdaratna written by a grammarian named Kalyāṇamalla.
- शब्द रूप the actual form of a word as a collection of letters or वर्णसमूह or वर्णसमूह or वर्णसमूह irrespective of the sense. In grammar it is the शब्द रूप that is mainly considered and not the meaning of the word; cf. स्व रूप शब्दस्थाशब्दसंज्ञा, P.I.1.68.
- হাত্ৰ ভ্যাৰন্তি a very brief treatise on declension giving the forms of the seven cases of a few choice-words. The work is studied as the first elementary work and is very common without the name of any specific author. There are different works named হাত্ৰভ্যাৰতি giving declensions of different words which

- are all anonymous, although from the dates of manuscripts mentioned, they appear to be more than five or six hundred years old.
- शब्दबाच्यत्व expression of its sense by a word which occurs to the mind of the hearer as soon as a word is heard.
- जान्द्विवरण a grammar work on the meaning of words and how it is conveyed, written by a grammarian named वर्णिकुवेरानन्द. The work forms a part of his bigger work दानभागवत. See वर्णिकुवेरानन्द.
- गञ्द्रात्पात derivation of a word by tracing it to the root from which it is formed.
- शब्दव्युत्पत्तिकौमुदी a small treatise on the derivation of words written by a grammarian named Rājārāma-Sāstrin.
- হাত্যাকা the sciene of words. The term is generally applied to grammar, although strictly speaking the Mīmārinsā Śāstra is also a science of words.
- शब्द्संचय an anonymous elementary booklet on declension similar to Sabdarūpāvalī.
- इान्द्संज्ञा a technical term given to a wording irrespective of the sense element as contrasted with अर्थसंज्ञा. See.e.g. घु, भ or the like; cf. रान्दसंज्ञायां हाथीसंप्रत्यये। यथान्यत्र P.I. 1.44 Vart. 2.
- इान्द्सत्त्वप्रकाश a work on grammas said to have been written by a grammarian named इन्द्रत.
- इान्द्साध्यप्रयोग a grammar work on the formation of words written by a grammarian named रमानाथरामी.
- शब्दासाद्ध (1) formation of a complete word fit for use by adding proper suffixes to the crude base and making the necessary modifications; cf. नैव ब्याकऱणाहते शब्दासिद्धः।

(2) name of a commentary by महोदेन on the Kātantra sūtravitti by Durgasimha.

शब्दसुधा name of a grammar work by a grammarian named अनन्तमह.

शब्दानशासन lit. science of grammar dealing with the formation of words, their accents, and use in a sentence. The word is used in connection with standard works on grammar which are complete and self-sufficient in all the abovementioned features. Patañjaji has begun his Mahabhasya with the words अथ शब्दानुशासनम् referring possibly to the vast number of Värttikas on the Sütras of Pāṇini, hence the term शब्दानुशासन according to him means a treatise on the science of grammar made up of the rules of Panini with the explanatory and critical Varttikas written by Kātyāyana and other Vārttikakāras. The word शन्दानुशासन later on, became synonymons with Vyākaraņa and it was given as a title to their treatises by later grammarians, or was applied to the authoritative treatise which introduced a system of grammar, similar to that of Panini. Hemacandra's famous treatise, named सिद्धहैमचन्द्र by the author, came to be known as हैमशब्दानुशासन. Similarly the works on grammar written by पाल्यकीर्तिशाकटायन and देवनन्दिन् were called शाकटायनशन्दानुशासन and जैनेन्द्र-शब्दानुशासन respectively.

इाब्दान्तर a different wording, as it results from modifications such as agama, or ādeśa, or lopa; cf. इाब्दान्तरस्य प्राप्नुवन् विधिरनित्यः Par. Sek. Pari. 43.

शब्दामृत a work, explanatory of the Sutras of Panini, written by a grammarian named वित्रराजेन्द्र.

शब्दार्थप्रतिपत्ति, शब्दार्थप्रत्यय knowledge

of the meaning of a word from that word when heard, the word being either denotative (বাचक) or indicative (হারেক).

ज्ञाब्दार्थरहस्य a grammatical work on the interpretation of words by Ramanatha Vidyavacaspati.

शब्दार्थसंबन्ध the connection between a word and its sense which is a permanently established one. According to grammarians, words, their sense and their connection, all the three, are established for ever; cf. सिद्धे शब्दार्थसंबन्धे P. I.1. Varttika I, and the Bhasya thereon सिद्ध शब्द: अर्थ: संबन्धश्चेति । Later grammarians have described twelve kinds of शब्दार्थसंबन्ध viz. अभिया, विवसा, तात्यर्थ, प्रविभाग, ब्यपेक्षा, सामर्थ्य अन्वय, एकार्थीमाव, दोषहान, गुणोपादान, अलंकारयोग and स्सावियोग; cf. Sringāraprakāśa.I.

इाड्याकरण explanation of the sense of a word as arising from the word by stating the base, the affixes and the modifications to the base and the affixes.

शब्दाथेशास्त्र a science fully dealing with the words in a language and their sense; the same ae शब्दानुशासन which see above.

शब्देन्दुशेखर a popular name given to the Laghusabdendusekhara written by Nagesabhatta. See लग्जराब्देन्दुशेखर.

शब्देन्दुशेखरटीका, शब्देन्दुशेखरव्याख्या See लघुशब्देन्दुशेखरटीका and लघुशब्देन्दुशे-खरव्याख्या.

इान्दोपदेश scientific and authoritative citation or statement of a word as contrasted with अपरान्दोपदेश; cf. कि शन्दोपदेश: कर्तन्य: आहोस्विदपशन्देश: आहोस्विदपशन्देश: आहोस्विदपशन्देश: आहोस्विद्पशन्देश: अति । M. Bh. in Ahnika 1.

शमादि a class of eight 'roots headed by शम् which get their vowel lengthened before the conjugational sign य (स्थन) as also before the kṛt. affix इत् (धिनुण्) in the sense of 'habituated to'; e.g. शाम्यात, शमी, भ्राम्यात, भ्रमी etc.; cf. P.VII.3.74 and P. III.2.141.

शम्भ

शम्भु God Siva who is supposed to have composed, or to have inspired Pāṇini to compose, the fourteen Sūtras अइउण्, ऋळूक् etc. giving the alphabet of the Pāṇini system; cf. निषष्टि: चतुःषा्टियों वर्णाः शम्भुमते मताः Pān. Siksā, St. 3.

হাই a brief term or Pratyāhāra standing for the three sibilant or spirant consonants লু, জু and स.

ज्ञारणदेव a prominent grammarian of Eastern school of Pānini's system of grammar who lived in the thirteenth century and wrote works on Panini's grammar. His work named दुर्घट्याति which ex. plains according to Panini's rules, the Vārttikas thereon, and the Thapakas deduced from them, the various words difficult to be explained, is much appreciated by scholars of grammar. He has quoted from a large number of classical works, and referred to many works of the Eastern grammarians who followed the Kāśikā school.

श्रारम्भित the words of the type of श्रार such as विपाश, अनस, मनस, उपान etc. which have the compound-ending अ (टच्) added to them when they are at the end of the Avyayībhāva compound; e.g प्रतिशरदम्, प्रतिविपाशम्.cf. Kāś. on P.V. 4.107.

डारादि a class of words headed by the word शर which have the tad. affix मय (मयट्) added to them in the sense of 'product' or 'portion'; e.g. शरमयम्, दभैमयम्, मृष्मयम्; cf. Kāś. on P. IV.3.144; (2) a class of words headed by शर which get their final vowel lengthened before the

tad.affix मत् when the whole word forms a proper noun; e.g. शरावती, वंशावती, हतूमान ; cf. P.VI.3.119.

शकेरादि a class of words headed by शकेरा to which the tad. affix अ (अण्) is added in the sense of इव viz. similarity; cf. शकेरेव शाकरम्, कापालिकम्, पौण्डरीकम् Kāś. on P. V. 3.107.

श्वेवमो a reputed grammarian who is believed to have been a contemporary of the poet Gunadhya in the court of Sātavāhana. He wrote Grammar rules which are named the Katantra Sutras which are mostly based on the Sütras of Pāṇini. In the grammar treatise named 'the Kātantra Sūtra' written by Sarvavarman the Vedic section and all the intricacies and difficult elements are carefully and scrupulously omitted by him, with a view to making his grammar useful for beginners and students of average intelligence.

शब्देवाय intervention by any one of the spirants श्, ष् and स्, which prevents the substitution of ण् for न् but allows the substitution of ण् for स्; cf. चुदुतुलशब्देशये न M.Bh. on P. VIII.4.2 as also नुम्बसर्जनीयशब्देवायेपि P. VIII.3.58 Vārt. 1.

हाल् short term (प्रत्याहार) for the sibilants इ, षू, स् and हू; cf. शर्लं इगुपभादनिटः क्स: P.III.1.44.

शक्ये class of letters beginning with श् i.e. the consonants श्, श्, स् and ह् . शिद्ववृत्ति name of a work on grammar by शाशिद्व which is mentioned by Al Beruni.

शस् (1) case affix (अस्) of the accusative plural; cf. स्वीजसमीट्यस्० P.IV. 1.2; (2) tad.affix applied to words, meaning much or little as also to a numeral; e.g. बहुशा ददाति, अल्पशो ददाति, द्विशः, त्रिशः, पादशः etc., cf. P. V.4.42, 43.

bhatta's Vaiyākaraṇabhūṣaṇasāra by Saṃkara; (2) name of a commentary on the Paribhāṣenduśekhara of Nāgeśa written by Sankarabhatta; (3) The Vyākaraṇa vidyā or instructions in Grammar given by God Siva to Pāṇini on which the Sikśā of Pāṇini has been based.

शाकट a tad. affix added optionally with शाकिन to the words इक्षु and others in the sense of a field producing the thing; e.g. इक्षुदाकटम्; cf. P. V.2.29.

शाकटायन (1) name of an ancient reputed scholar of Grammar and Prātisākhyas who is quoted Pāṇini. He is despisingly referred to by Patanjali as a traitor grammarian sympathizing with the Nairuktas or etymologists in holding the view that all substantives are derivable and can be derived from roots; cf. तत्र नामान्याख्यातजानीति शाकटायना नैस्क्तसमयश्च Nir.I.12; cf. also नाम च घातुजमाह निरुक्ते ब्याकरणे शकटस्य च तीकम् M. Bh. on P.III.3.1. Sākatāyana is believed to have been the of the Uṇādis**ū**trapāṭha as also of the RkTantra Pratisakhya of the Samaveda; (2) name of a · Jain grammarian named पाल्यकीर्ति शाकटायन who lived in the ninth century during the reign of the Rāstrakūta king Amoghavarsa and wrote the Sabdanuśasana which is much similar to the Sütrapätha of Panini and introduced a new system of Grammar. His work named the Sabdānusāsana consists of four chapters which are arranged in the form of topics, which are named सिद्धि. The grammar work is called शब्दानुशासन.

शाकटायनतरङ्गिणी a commentary on Sākatāyana's Sabdānusāsana.

शाकटायनव्याकरण the treatise on grammar written by Sakațayana. See शाकटायन.

शाकटायनशब्दानुशासन name of the treatise on grammar written by पाल्यकोतिं-शाकटायन.

शाक्रपार्थिचादि a class of irregular samānādhikaraņa Samāsas, or Karmadhāraya compound formations, where according to the sense conveyed by the compound word, a word after the first word or so, has to be taken as omitted; cf. समानाधिकरणधिकारे शाकपार्थिवादीनामुप्तर्यन्तुपदलेपश्च वक्तब्यः। शाकमोजी पार्थिवः शाकपार्थिवः। कुतपनासाः सौक्षतः कुतपनीश्चतः। यिष्ठभानो मोद्रस्य; यष्टिमोद्रस्यः। M.Bh. on P.II.1.69 Vārt. 8.

शाकपूणि an ancient writer of Nirukta who is quoted by Yāska; cf. विद्युत् तिड्युत्ति शाकपूणि; Nir. III. 11, or मानेन अन्यान् जहातीति महानिति शाकपूणिः Nir. III. 13 or ऋत्विकस्मात् । ईरणः । ऋग्यष्टा मनतीति शाकपूणिः Nir.III.19.

হাানত a word frequently used in the Mahābhāṣya for a grammatical operation or injunction (विधि) which forms a specific feature of the grammar of शाकल्य, viz. that the vowels इ, उ,ऋ, and ल remain without phonetical combination and a shortening of them, if they are long;cf.इकोऽसवर्णे शाकल्यस्य ह्रस्वश्च P.VI. 1. 127; शाकल्यस्य इदं शाकलम् ।; cf. also M.Bh. on P.VI.1.77, VI.1.125,VI. 1.27; VI.2.52, VII.3.3 and VIII. 2.108; (2) pupils of शाकल्य; cf. যাকল্যান্য হাকিলা: M. Bh. on P. IV.1.18; (3) a village in the Vāhīka district; cf. शाकलं नाम वाहीकग्राम: M. Bh. on IV.2.104 Vart. 3.

शाकलप्रकृतिभाव absence of a phonetic coalescence (प्रकृतिभाव) as specifically mentioned by शाकल्य. See शाकल.

शाकलप्रतिषेध prohibition of the

coalescence of any of the vowels হ, ভ, স্ম and ল with any dissimilar vowel following it. See যান্কল.

शाकल्य name of an ancient grammarian and Vedic scholar who is supposed to have revised the Vedic texts and written their Pada-pāṭha. He is often quoted by Pāṇini and the writers of the Prātiśākhya works; cf. शाकल्यस्य संहितामनुभावर्षत् M. Bh. on P.I.4.84; also on P.I.1.18, IV. 1.18; cf. also उपचारं लक्षणतश्च सिद्धं आचार्या ज्यालिशाकल्यगार्था: R.Pr.XIII.12.

शाकिन tad. affix (originally a word formed from शाकी by affixing न as given in M. Bh. on P.V.2.100), applied to the word इक्षु in the sense of a field producing it; e. g. इक्षुशाकिनम्.; cf. मवने क्षेत्रे इक्ष्वादिभ्यः शाकटशाकिना Kās. on P. V. 2.29.

शासादि a class of words headed by the word शासा which have the taddhita affix य added to them in the sense of इव i.e. similarity; e.g. शास्यः, मुख्यः, जवन्यः etc.; cf. Kāś. on P. V.3.103

शानच् (1) krt affix (आन) substituted for the Atmanepada छट् affixes, to which म is prefixed if the base before the affix ends in आ; c. g. एचमान, विद्यमान, etc; cf. P. III. 2. 124, 125, 126; (2) Vikarana affix (आन) substituted for आ before the personal ending हि of the imperative second person singular, if the preceding root ends in a consonant; e. g. पुषाण, मुषाण, cf. P. III. 1.83.

शानन् krt affix (आन) substituted for the Ātmampada affixes instead of शानच, prescribed after the roots पू and यज्; the application of शानन् for शानच् is for the acute accent on the initial vowel of the root;e.g. प्रमान: with the acute accent on the initial vowel as contrasted with विद्यमान; with the acute accent on the last vowel; cf. P. III. 2.128.

মান্বৰৰ an ancient scholar of grammar who wrote a treatise known as the Phit sūtras on accents.

शान्द्बोध verbal interpretation; the term is generally used with reference to the verbal interpretation of a sentence as arising from that of the words which are all connected directly or indirectly with the verb-activity. It is defined पदजन्यपदार्थोपस्थितिजन्यबोधः. According grammarians, verbal activity is the chief thing in a sentence and all the other words (excepting the one which expresses verbal activity) are subordinated to the verbal activity and hence are connected with it; cf. पदशानं तु करणं द्वारे तत्र पदार्थधी:। शाब्दबोध: फलं तत्र शक्तिभीः सहकारिणी । मुक्तावली III.81.

शाब्दबोधतराङ्गिणी a treatise on the theory of verbal import written by ईश्वरानन्द.

साब्दबोधमकाशिका a treatise on the theory of शब्दबोध written by रामिक- शारचकवर्तिन्

or congnition; the theories to be noted in this respect are those of the Grammarians, the Naiyāyikas and the Mīmāmsakas, according to whom verb-activity, agent, and injunction stand respectively as the principal factors in a sentence.

शायच् Vikaraṇa affix (आय) substituted for the Vikaraṇa आ in Vedic Literature; e. g. ग्रभाय जिह्नया मधु; cf. Kāś. on P. III 1.84.

शार्ज़रबादि a class of words headed by the word शार्ज़रन which take the feminine affix ई (डीन्) making the initial vowel of the word(to which ई of the feminine is added) an acute-accented one; e.g. शार्क्सवी;cf. शार्क्सवायो होन P, IV. 1.73.

য়ান্তৰ্ tad. affix যান্ত applied to the prefix वि in the sense of the base itself (खार्थे). See হাছ্কুত্ৰ.

মাভানুমীৰ name of the great grammarian Pāṇini given to him on account of his being an inhabitant of হাভানুম an old name of the modern Lahore or a name of a place near Lahore; cf. P IV.3.14

शाश्वातिक eternal or permanent, as contrasted with कार्य i. e. produced; cf.एतस्मिन्वाक्ये इन्दुमेत्रेययोः शाश्वतिको विरोधः Sīradeva Pari. 36; cf. also एके वर्णाञ्च शाश्वतिकान् न कार्यान् R.Pr.XIII.4.

হান্তে scientific treatment of a subject; a system of thoughts giving a scientific treatment of any subject. The word is applied to the rules of Panini and sometimes to an individual rule; cf. হান্তেৰাম or অহান্তেৰাম or বিমানিব্যহান্তে, frequently used by the commentators; cf. ন হি संदेहादलक्षणं शालामित्यर्थ: Nageśa's Par. Śek. on Pari. 1; cf. पदान्तादिष्येच विकारशास्त्रम् R.Pr.II.2.

शास्त्रकृत् the originator or the founder of a Sastra or system of particular thoughts. The word was used by ancient grammarians for Pāṇini, the founder of the great system of grammar, or of grammar in general; cf. ब्यत्ययमिच्छति शास्त्रकृदेशां सोपि च सिध्यति बाहुलकेन M.Bh. on P. III. 1. 85.

शास्त्रकृत brought about by a rule; brought about by the science of grammar; cf. शास्त्रकृतो योमश्च Nir.I. 2; cf. also काचिन्च संनिपातकृतमानन्तर्यं शास्त्रकृतमनानन्तर्यम् M.Bh. on P. VII. 3.54, VIII.2.38.

शास्त्रहानि harm or injustice to a science; i.e. non-application of a rule although it could apply,there being no prohibition for it; cf.

शास्त्रहानिश्च । समुदायैकाचः शास्त्रं हीयते M. Bh. on P. VI.1.1 Vārt. 12.

शास्त्रातिदेश supposition of the original in the place of the substitute merely for the sake of the application of a grammatical rule as contrasted with रूपातिदेश, the actual restoration of the original form; cf. किं पुनर्य शास्त्रातिदेश: । तृत्रो यच्छास्त्रं तदातिदिश्यते । आहोस्विद्पातिदेश: तृत्रो यद्भं तदतिदिश्यते M. Bh. on P. VII.1.95.

शास्त्रार्थ the purpose of a rule of grammar; cf. अतोत्राप्यवयेवन शास्त्रार्थः संप्रतीयते M.Bh. on P.VI.1.84 Vārt. 5; cf. also, तद्यथा। लेके वसन्ते ब्राह्मणे- मीनादधीतेति सङ्दाधाय छतः शास्त्रार्थ इति पुनः प्रवृत्तिने भवति । M. Bh. on VI.1. 84 Vart. 3; VI.4.104 Vārt. 3.

शास्त्रासिद्धत्व the supposed invalidity of a rule or a set of rules by virtue of the dictum laid down by Pāṇini in पूर्वत्रासिद्धम् VIII.2.1; cf. शास्त्रासिद्धत्वमनेन क्रियते। एकादेशशास्त्र तुक्शास्त्र असिद्धं भवति। M.Bh. on P.VI.1.86 Vārt. 5.

शि case affix इ substituted for the case-affixes जस and शस् of the nom. pl. and the acc. pl. in the neuter gender; cf. जदासो: शि: P. VII. 1.20. This affix शि is called सर्वनामस्थान just like the first five case- affixes in the masculine and fem. gender. This case affix is seen dropped in Vedic passages; cf. शेच्छन्दसि बहुल (होप:) P. VI. 1.70.

হিঃমা general name given to a work on Phonetics. Although there are many such works which are all called शिक्षा, the work, which is often referred to, by the word, is the Siksā named पाणिनीयारीक्षा, about authorship of which, the however, there îs a doubt whether it was the work of Panini or of somebody belonging to his school. The Siksa works are help363

ful, no doubt, for the study of grammar, but no topic belonging to Sikṣā is given by Pānini which apparently means that these works do not come under the subject or province of Grammar. The reason why the Sīkṣā topics are not given by Pānini, is worth consideration. These Sikṣā works are not specifically related to a particular Veda and it cannot be said whether they preceded or succeeded the Prātišākhya works.

शिखा one of the subdivisions of the artificial recitals of the Vedic texts.

शिद् a term for सर्वनामन् (a pronoun) in the works of ancient grammarians; cf. स्वाङ्गशिटामदन्तानाम् Phit Sūtra 29, where शिद् is explained as सर्वनामन् in the gloss.

शिल् possessed of, or characterized by, the indicatory letter श; the kṛt affixes which are marked with the indicatory श are termed Sārvadhātuka affixes (cf. P.III.4.113), while, the Ādeśas or substitutes, marked with the indicatory श, are substituted for the whole of the Sthānin or the original and not for its final letter according to the rule अलेक्स्यस्य P. I.1.52; e. g. शि is substituted, not for the final स् of जस् and शस but for the whole जस and the whole शस; cf. P.I.1.55.

शिरस्य produced at the top of the orifice, cerebral.

शिरोमणिमद्वाचार्य a grammarian who wrote the grammatical works कारकविवेक, तद्धितकोश and तिङन्तशिरोमणि.

शिवभद्द a grammarian, who wrote a commentary named कुङ्कुमिकिस on the Padamanjari of Haradatta. He was the grandson of Nilakantha Diksita who was also a grammarian and who wrote an indepen-

dent work on the Paribhāṣās, named the Paribhāṣāvṛtti.

হাৰ্থাম (অন্নৰ্নী) a grammarian who wrote a commentary on the Kātantraparisista called the Siddhāntaratnānkura.

शिवरामेन्द्र (सरस्वती) a grammarian who wrote (1) a gloss on the sūtras of Pānini, (2) a commentary named सिद्धान्तरत्वाकर on the Siddhāntakaumudī, and (3) a commentary on the Mahābhāsya named Mahābhāsyaprakāsa.

शिवसूत्र name given to the fourteen small sūtras giving the alphabet which Pānini took as the basis of his grammar. The Sivasūtras have got a well-known explanation in verse, named नन्दिकेश्वरकारिका on which there is a commentary of the type of Bhāṣya by उपमन्यु. The origin of the Sivasūtra given by the writer of the Kārikā is summed up in the stanza — हत्तावसाने नटराजराजो ननाद दक्षां नवपञ्चवारम्। उद्धतुकामः सनकादि- सिद्धानेतद् विमर्शे शिवसूत्रजालम् ॥ Nand. 1.

शिवादि a big class of about ninety words headed by the word शिव which have the tad. affix অ (অণু) added to them in the sense of a descendant (अपत्य) in spite of other affixes such as इञ्, ण्यत् and others prescribed by other rules, which sometimes do not take place, or do so optionally; e. g. ताक्षण्यः; गाङ्गः गाङ्गयः; शैव:; ताक्ष्ण:, गङ्गायनि:; cf. Kāś. on P.IV.1.112. This class is looked upon as आकृति-ग्ण and a word is supposed to be included in this class, when the affix is noticed in spite of some other affix being applicable by some other rule.

বিছে (1) cultured and learned people who want to speak correctly and who therefore have studied gra-

mmar; cf. के पुन: शिष्टा; । वैयाकरणाः । कुत एतत् । शास्त्रपूर्विका हि शिष्टिवयाकरणाश्र शास्त्रज्ञाः । M. Bh. on P. VI. 1.109; (2) enjoined, prescribed; cf. विपर्ययो ध्रुवशिष्टेऽपरेषाम् । R.Pr.VI.120.

शिष्टप्रयोग the forms of words used by the learned people; the expression used by such persons; cf. स चावन्यं शिष्टप्रयोग उपास्य: | M. Bh. on P.I.3. 1 Vart. 13.

शिष्ट्याख्यान explanation (of doubtful things or expressions) given by the learned people.

शिष्यहिता (वृति) a work on grammar written by उप्रमृति of which a mention is made by Al Beruni in his work.

शी (1) case affix (ई) substituted for the nom. pl. affix जस् (अस्) in the declension of the pronouns, when the affix जस् is preceded by the vowel अ; e.g. सर्वे, विश्वे; cf. Kāś. on P VII.1.17; (2) case affix (ई) substituted for औ of the nom. and the acc.dual after fem. bases ending in आ, as also after bases in the neuter gender; e. g.सर्ट्रे समे; कुण्डे, चने; cf. Kāś. on P. VII.1.18, 19.

शोधतर lit.over-rapid; an extra quickness of breath (प्राण) which characterizes the utterance of a sibilant which has got one more property viz. जन्मत्व in addition to the three properties (बाह्मप्रयत्न) possessed by the other consonants; cf. शीधतर सोध्मस प्राणमेके। R. Pr. XIII. 6.

शोधी a person reciting Vedic passages more rapidly, when his recital results into a fault of utterance.

र्शिषेण्य principal; chief; the word is used in connection with the utterance of Veda passages which are uttered loudly at the time of the third pressing (तृतीयस्वन); cf. शिएसे तास T. Pr.XXIII.12;cf. शिर्षण्य: स्वरः M.Bh. on P. VI,1.61.

श्रक्रयजः प्रातिशाख्य name Prātisākhya treatise pertaining to the White Yajurveda which is also called the Vājasaneyi-Prātiśākhya. This work appears to be a later one as compared with the other Prātiśākhya works and bears much similarity with some of the Sūtras of Panini. It is divided into eight chapters by the author and it deals with letters, their origin and their classification, the euphonic and other changes when the Samhitā text is rendered into the Pada text, and accents. The work appears to be a common work for all the different branches of the White Yajurveda, being probably based on the individually different Pratiśākhva works of the different branches of the Shukla Yajurveda composed in ancient times. Kātvāvana is traditionally believed to be the author of the work and very likely he was the same Kātyāyana who wrote the Varttikas on the Sūtras of Pānini.

হ্যুতিভ্ৰনাৰি a class of words headed by হ্যুতিভ্ৰনা to which the taddhita affix অ (অণ্) is added in the sense of 'who has come from'; e.g. খীতিভ্ৰন:, কাৰ্কণ:; cf. Kāś. on P. IV. 3.76.

शुद्ध pure, unmixed; the term is used (1) in connection with a vowel which is not nasalized (अनुनासिक); cf. मान्यमानेन सवर्णानां ग्रहणं नेति शुद्धी-यमुचार्यते, Kās. on P. VII.1.85; as also, (2) in connection with words which are used in their primary sense and not in any secondary sense: cf. शुद्धानां पठितानां संज्ञा कर्तन्या। संज्ञोपसर्जनीभूतानि न सर्वादीनि M.Bh. on P.I.1.27 Vārt. 3.

शुद्धाशुबोधस्त्रार्थव्याकरण a gloss on the Asubodha-grammar, written by a grammarian named Rāmesvara,

शुभादि a class of words headed by the word शुभ्र to which the taddhita affix एय (ढक्) is added in the sense of a descendant in spite of other affixes being prescribed by some other rules which sometimes are added optionally with this एय; e.g. शौभ्रेय:, वैधवेय: राहिणेय:. This class is looked upon as आकृतिन् जा and hence if this affix एय is seen applied although not prescribed actually as in the word गाड़िय, the word is supposed to have been included in this class; cf. P. IV. 1.123.

शून utterance with a swollen mouth which is looked upon as a fault of Vedic recital; cf. दुंध मुखेन सुधिल शूनम् R.Pr.XIV.2.

श्रूपिंद्ध nume of a grammarian who wrote a gloss named दीपिका on the Sārasvata Vyākaraņa.

हो case-ending seen in Vedic Literature substituted for any one of the 21 case-endings as found in Vedic Language; words ending in this हो (ए) are not coalesced with a vowel that follows; e.g अस्मे इन्द्राबृहस्पती; cf. P.VII..1.39 and I.1.13.

होष (1) any other senses than what are given above; cf. ইাথ P.IV.2.92; (2) surname of a reputed family grammarians belonging to Southern India which produced grammarians, from the fifteenth century to the eighteenth century. Rāmacandra Sesa was the first grammarian in the family who wrote the Prakriyakaumudi in the fifteenth century. His descendants developed the system of studying grammar by the study of topics as given in the Prakriya Kaumudī and wrote several works of the nature of glosses and comments.

शेषक्षण one of the prominent grammarians belonging to the Seşa family, who was the son of नरासिंहशेष. He wrote a gloss on the Prakriyaand two small works kaumudi Prakttacandrika and drikā. Two other minor grammar works viz. the Yanlugantasiromani and Upapadamatinsūtravyākhyāna are ascribed to হাবক্রতা who may be the same as शेषकृष्ण the son of नरसिंह. or another, as there were many persons who had the name Krsna in the big family.

शेषचक्रपाणि a grammarian of the Sesa family who wrote a small treatise on case-relations named कारकतन्त्व.

रोषराभेन also known by the name मनीषिरोषशर्मन् ,a grammarian who has written सर्वमङ्गला, a commentary on Nagesa's Paribhasendusekhara.

शेषशास्त्री a grammarian who wrote a commentary on the Paribhā sendusekhara of Nāgesabhaṭṭa.

देखाद्धे a grammarian of the seventeenth century who has written a work, Paribhāṣābhāskara, on the Paribhāṣās of the Pāṇini system; the treatise is written in the manner of Sīradeva's Paribhāṣāvṛtti which has been taken as a basis by him.

হাৰ ঘণ্টা the genitive case used in any other senses than those given in the specific rules. The expression হাও ঘণ্টা মাণ্ডিঘার is often found in commentary works.

शैल्यायन an ancient Grammarian and Vedic scholar who is quoted in the Taittiriya Prātiśākhya for recommending a sharp and distinct nasalisation of the anusvāra and the fifth class-consonants; cf. तीत्रतरमानुनासिक्यमनुस्वारोत्तमेषु इति शैल्यायन; T. Pr. XVII. 1.

शौशिरीय recital of the Rgveda in the school named after Sisira, a pupil of Sakalya.

शैषिक remaining, or remnant; the term is used with reference to a tad. affix prescribed in senses other than those mentioned before the rule शेष P. IV. 2.92; cf. शैषिकान्मतुवर्थीयाच् शैषिको मतुवर्थिकः। सहपः प्रत्ययो नेष्टः सन्ततान सनिष्यते।

হাতৈভাবি a class of words headed by the word হাতিভ which are compounded with a noun in the locative case to form a locative tatpurusa compound; e. g. অধ্যয়াত্ত;, অধ্যয়ুর্ন: etc.; cf. Kāś. on P.II.1.40.

शीनक a great ancient Vedic scholar who is believed to have written the Rk. Prātišākhya, which is said to be common for the two main branches of the Rgveda but which at present represents, in fact, all the different branches of the Rgveda.

शौनकप्रातिशाख्य a popular name of the well-gnown Prātiśākhya of the Rgveda, named कम्प्रातिशाख्य as well as क्रग्वेदप्रातिशाख्य.

शोनकादि a class of words headed by the word शौनक to which the taddhita affix इन् (णिनि) is added in the sense of 'instructed by', provided the word so formed is a portion of what is looked upon as a part of the sacred Vedic Literature; cf. शौनकेन शोक्तमधीयते शौनकिन:, वाजसेनायन: cf. Kāś. on P.IV. 3.106.

भ्चुत्व the substitution of the palatal consonants श्र्च्रज़्ज़्ज़्झ् and ज respectively for the similar consonants स्, त्, ध्, ध्, ध्, ध्, व्र प् and न् of the dental class; cf. स्ते: श्चना श्च: P.VIII.4.10.

रितप् the syllable ति applied to the Vikarana-ending form of a root to denote a root for a grammatical operation. The specific men-

tion of a root with शित्र added. shows that the root of the particular class or conjugation shown, is to be taken and not the same root belonging to any other conjugation; cf. इक्।श्तिपौ धातुनिर्देशे; e.g. अस्यतिविक्तिस्यातिभ्योऽ ङ P.III. 1. 52. Although operations prescribed for a primary root are applicable to a frequentative root when the frequentative sign q has been omitted, operations prescribed for a root which is stated in a rule with ति (दितप्) added to it, do not take place in the frequentative roots;cf. ित्तपा शपान्बन्धेन ... पञ्चेतानि न यङ्ख्राके.

श्चम् a vikaraṇa or conjugational sign of the āgama type to be inserted after the last vowel of the roots of the seventh conjugation (रुधादि); e.g. रुणद्वि, भिनत्ति etc.; cf. रुधादिभ्य: अम् P.III.1.78.

श्चा a vikaraṇa or conjugational sign of the ninth conjugation, to be added to roots headed by की before the Sārvadhātuka affixes; e.g. कीणाति; cf. कथादिन्य: आ.P.III.1.81. आ is added optionally with श्च (तु) to the roots स्तम्म, स्तुम्म, स्कम्म, स्कुम्म and स्यु. e.g.स्तभाति, स्तभोति, स्कुभाति, स्कुभोति etc; cf. P.III.1.82.

श्रु a vikarana or a conjugational sign to be placed after the roots headed by सु (i.e. roots of the fifth conjugation) as also after the root श्रु when श्रु is to be changed into श्रु, and the roots अझ and तक्ष; e.g. सुनोति, सुनुते; cf. स्वादिम्यः श्रु: P.III. 1.73. It is also added optionally with श्रा to the roots स्तम्म्, स्तुम्म् etc. See श्रा.

इयन् a vikarana or conjugational sign of the fourth conjugation added to roots headed by दिन्, before the Sārvadhātuka affixes; e.g. दीन्यति, पुष्यति, etc. स्यन् is added optionally

with शप् (अ) to the roots भ्राह्, भ्रम्, क्रम and others, as also to यस्.

সত্ত্বা a technical term for nounstems ending in আ in the feminine gender used in the Katantra Grammar; cf. আ প্রস্তা Kat. II. 1.10.

अमणादि a class of words headed by the word अमणा with which words in the masculine or the feminine gender are compounded when they stand in apposition; cf. कुमारी अमणा कुमारअमणा, युवा अध्यापक: युवाच्यापक: Kāś. on P.II.1.70.

श्रवण hearing of a phonetic element or a word in the actual speech; audition: cf. तस्य चोदात्तस्वरितपरत्वे श्रवणं स्पष्टम S. K. on P.I.2.32. In many technical grammatical terms, affixes and substitutes, there is sometimes a portion of them which is not a vital part of the word, but it is for the sake of causing certain prescribed grammatical operations. The letters or syllables which form such a portion are called इत् and they are only for the sake of grammatical operations (कार्यार्थ), as contrasted with the other ones which are actually heard (श्रुत्यथे or श्रवणार्थ).

आविन lit. that which is heard; cf. अवर्ण आव: । भावे घन् । सोस्यास्तीति आवी Nyāsa on Kās. V.2.37. The term is used in connection with an affix for which no elision is prescribed and hence which remains and is heard; cf. संश्वे आविण वस्यति M. Bh. on P.V.2.37. Kās. on P.V.2.37.

श्रीकणोक्त a grammarian who has written a small treatise on corrupt words or ungrammatical words, which is named অধ্যাত্তব্যুত্তন্ত্ৰ,

শ্ৰীষাৰ্থ a grammarian of the last century who has written a commentary named গ্ৰীষ্বী after him, on the Paribhāṣenduśekhara. শ্লীঘ্রন্থ name of a commentary on the Paribhāṣenduśekhara written by Śrīdhara. See গ্লীঘ্ৰ.

श्रीनिवास a grammarian who has written a commentary on the Paribhāṣābhāskara of Haribhāskara.

श्रीमणिकण्ठ a famous grammarian who held the titles महामहोपाच्याय, प्रगल्भतकंसिंह and भट्टाचार्य and who has written a systematic work on caserelations named कारकखण्डनमण्डन; the work is also known by the name षटकारकखण्डनमण्डन.

শ্রীমানহামা a famous grammarian of Eastern India who has written a short scholarly gloss named Vijayā on Nāgeśa's Paribhāṣenduśekhara. For details refer to Paribhāṣāsamgraha.

अत lit. what is actually heard; the word is used in connection with such statements as are made by the authoritative grammarians, Pāṇini and the Vārttikakāra by their actual utterance or wording, as contrasted with such dictums as can be deduced only from their writings. cf. अतान्मित्योः श्रीतः संबन्धा बळीयान्. Par. Sek. Pari. 104.

श्रुतके बालिन् a term of a very great honour given to such Jain monks as have almost attained perfection; the term is used in connection with Pālyakīrti Śākatāyana, the Jain grammarian शाकरायन, whose works शाकरायनशब्दानुशासन and its presentation in a topical form named शाकरायनप्रक्रिया are studied at the present day in some parts of India. See शाकरायन above.

श्रुति (1) lit. hearing; sound.cf. श्रुतौ च रूपप्रहणम् M. Bh. on P. I. 2.64; perception, as a proof contrasted with inference; cf. ननु च श्रुतिकृतोपि मेदोस्ति M. Bh. on P. VII. 1.72 Vart. 1; cf. also M. Bh. on P.

,

VIII. 2.25; cf. also तस्मादुच्चश्रुतीनि R. T. 61; (2) authoritative word; the word is sometimes used in connection with the utterances of the Sūtrakāras viz. the Sūtra.

श्रुतिसामान्य common hearing; common form of technically different wordings, such as आ of टाप, डाप् and चाप् feminine affixes, or ई of ङाप्, ङाष्, and ङीन् fem. affixes; cf. र इति श्रातिसामान्यमुपादीयंत Kāś. on P.VIII. 2.18; cf. also Kāś. on VIII. 2.42 and VIII. 4.1.

श्रूयमाण heard, presented; cf. द्वन्द्वान्ते श्रूयमाणः शब्दः प्रस्पेकमभिसंबध्यते; cf. श्रूयमाणिष नुमि स्वरो भवति । पश्चत्रपुणा M. Bh. on P. VII. 1. 73.

भ्रेण्यादि a class of words headed by the word श्रेणि, which are compounded with words like इत if they stand in apposition, provided the word so compounded has got the sense of the affix च्वि i. e. having become what was not before; cf. अश्रेणय: श्रेणय: इताः श्रेणिकृताः, एककृताः Kāś. on P. II. 1. 59.

স্থাৰন্থ a loose connection as obtaining between the various words in the Pada recital, as contrasted with স্থিয়ৰন্থ in the Samhita text.

সৈত or স্তিহৰ-ৰ compact arrangement as seen in the Samhita text.

बंखु a term used in the sense of elision or lopa in the case of the affix श्रम् when it is elided after the roots headed by हु, i. e. roots of the third conjugation as also after any root wherever it is so seen in the Vedic Literature; cf. बहुलं छन्दास P. III. 4. 76. This श्र्ष्ठ is looked upon as a substitute zero, or nil for the general vikarana श्रम् in the case of these roots; cf. जहोत्यादिग्य: श्र्ष्ठ: P. II. 4. 75. The specific feature of this elision of the vikarana श्रम् by means of the term श्रष्ठ,

is that it causes reduplication of the roots to which it is added; cf. ङ्कि प्रकृते श्ङ्किधानं द्विवचनार्थम् Kāś. on. P. II. 4. 75 and P. III. 1. 10.

रखुबद्धाव treatment as before the elision named श्लु, i. e. reduplication of the preceding root. This श्लुबद्धाव is prescribed in the case of the roots भी, ही, भ and हु; cf. भीही। भृहुवां श्लुबच्च P. III. 1. 39.

হত্তবিক্রণে roots characterized by the addition or application of the conjugational sign which is elided by the use of the term মন্ত্র for elision; roots of the third conjugation; cf. য एते ন্তাৰিকলো: মন্ত্রিৰ-কলোগ্ল M.Bh.on P.III. 1.67 Vart.2, as also on P. III 1.91.

হন্ত্ৰিখি the specific operation caused by মন্ত viz.the reduplication for the preceding root; cf. বন ন্তান মন্ত্ৰ-বিধিমনিষ্টা, M. Bh. on P. I. 1. 62 Vart. 6.

स्रोकचार्तिक Vārttika or supplementary rule to Pāṇini's rules laid down by scholars of grammar immediately after Pāṇini, composed in verse form. These Slokavārttikas are quoted in the Mahābhāṣya at various places and supposed to have been current in the explanations of Pāṇini's Aṣṭādhyāyī in the days of Patañjali. The word is often used by later commentators.

श्वस्तनी a term of ancient grammarians for the first future called छुट् by Pāṇini; cf. परिदेवने श्वस्तनी भविष्यन्त्येशें। इयं नु कदा गन्ता यैवं पादी निदधाति M. Bh. on P. III, 3.15.

required for uttering some letters; the term is used in the Prātišā-khya and Vyākaraṇa books in the sense of breath which is prominently required in the utterance

of the hard consonants, sibilants, visarga and the Jihvāmūliya and Upadhmānīya letters; the term is used in connection with these letters also; the usual term in use is, of course, খালানুমহান, the term খ্রান্ত showing the property of the breath, with which these letters are characterized.

श्वासानुप्रदान caused by the emission of breath; the term is used in contrast with नादानुप्रदान in connection with hard consonants, surds, visarga, the Jihvāmūlīya and the Upadhmānīya letters; see श्वास above.

श्वोभूतिचृति a grammatical work of the type of a gloss on the Sūtras of Pāṇini written by an ancient grammarian श्वोभृति mentioned in the Mahäbhāṣya; cf. स्ताच्यान्यहं पादिकमौदवाहिं ततः श्वोभृते शातनीं पातनीं च M. Bh. on P. I.1.57. Possibly the grammarian श्वोभृति is referred to in the word श्वोभृत in the verse.

Ø

¶ (1) a sibilant letter of the cerebral class of consonants possessed of the properties श्वास, अघोष, कण्ठविवार and महात्राण; (2) mute indicatory letter ब्र. attached to nouns as also to affixes with which nouns are formed. such as खुन्, ष्कन्, ष्टरच्, ष्ट्रन् etc. showing the addition of the feminine affix ई (ङीव्); cf. षिद्रौरादिभ्यश्च P. IV. 1.41; (3) changeable to ₹ when placed at the beginning of roots in the Dhatupatha except in the case of the roots formed from nouns and the roots ष्टिव् and ष्वष्कु; (4) substitute for the last consonant of the roots ब्रश्च, भ्रस्ज्, सज्, मृज्, as also यज्, राज्, भ्राजु, roots ending in ন্তু and গু fore a consonant excepting a nasal and a semivowel, as also when the consonant is at the end of the word; e.g. भ्रश, स्रष्टा, यष्ट्रम् सम्राट् etc. cf P. VIII.2.36; (5) substitute for a visarjanīva preceded by a vowel except 3 and followed by a consonant of the guttural or the labial class which does not begin a different word, as also before words पाश, कल्प, क, काम्य etc. cf. P. VIII. 3.39; cf. also P. VIII 3.41, 43, 44, 45 and 48 for some specified cases; (6) substitute for \ when placed near a consonant of the cerebral class or near the consonant ष ; e. g. वृक्षच्चण्डे, वृक्षष्टकार: Kāś. on P. VIII. 4.41.

ष (1) consonant ष्, the vowel अ being added for facility of pronunciation; (2) compound-ending अ, substituted for the final of the word मूर्धन at the end of a Bahuvrihi compound when the word मूर्धन is preceded by द्वि or न्नि e. g. द्विमूर्धः, निमूर्धः cf. द्विनिभ्यां च मूर्नः P, V. 4.115 (3) a technical term for तत्पुरुषसमास in the Jainendra Vyākaraņa.

षच् the compound-ending (समासान्त) अ added for the final of the words सिक्थ, आक्ष and दार standing at the end of a Bahuvrihi compound under specific conditions. e. g. विशालाक्ष:, दीर्घसक्थ:, द्रयङ्गुलं (दार); cf. P. V. 4.113, 114.

षद्कारक (1) the six Kārakas or instruments of action, which are differently connected with the verbal activity, viz. कर्तृ, कम, करण, संप्रदान, अपादान and अधिकरण; for details see कारक above: cf. तत्र शक्तिमतो द्रव्यस्य कारकाख्यायामवान्तरव्यापारानिवन्धना षडुपाख्या भवन्ति। कर्तां कर्मं करणं संप्रदानमपादानमधिकरणं चिति। Sringara Prakāśa IV; (2) a work of the name (षट्कारक) written by a Jain grammarian Maheśanandin.

षट्कारकखण्डनमण्डन known also as कारकखण्डनमण्डन a grammar-work on the six case-relations written by a scholar of grammar named श्रीमणिकण्ट.

षद्कारकानिरूपण a work dealing with the six kinds of instruments of the verbal activity (karakas) written by Trilokanatha.

षद्कारकवालवोधिनी a short work in verses on the six case-relations written by a grammarian Prabhudāsa who has added his own commentary to it.

बद्कारकछश्चण a small work in verses on the six case-relations ascribed to Amarasimha, but very likely the author was Amaracandra a Jain grammarian of the fifteenth century. The work is also named बटकारकविवरण.

षद्कारकविचार an anonymous small treatise on the six case-relations in verse-form with a commentary.

षद्कारकविवेचन a small treatise on the six case-relations written by a grammarian Bhavānanda who held the title Siddhantavāgīśa.

पडिकामस्ताच a popular name given by grammarians to the topic of grammar which deals with the abbreviated popular forms of proper nouns which are names of persons, as for example the form षडिक for षडक्गुलिदत्त; cf. टाजादावू ध्वे द्वितीयादवः P. V. 3.83.

षड्गवस् lit. a collection of six cows; secondarily 'a collection of six animals or quadrupeds.'The word षड्गव was prescribed by later grammarians as a tad-affix by means of a Vartika when they saw the the word षड्गव used in language after the word अश्व etc. e. g, अश्व-षड्गवम्; cf. प्रकृत्यर्थस्य पर्वे षङ्गवस् Kāś. on P. V.2.29.

षड्भाषाचिन्द्रिक। a work on six dialects written by a Jain grammarian लक्ष्मणस्रि.

षण् a term used instead of the desiderative affix सन् prescribed by P. III. 1.5 to 7, especially when the स् of the affix is changed into ष् as for instance in तुष्ट्रवित etc.; cf. स्तातिण्यंन्तानां षण्भृते च सनि परतः अभ्यासानुत्तरस्य मूर्धन्यादेशो भवति Kās. on स्तौतिण्योरेव षण्यभासात् P. VIII.3.61.

ष्ट्य change of the consonant म into म् in certain conditions in the formation of a word, or after prepositions in the case of verbs beginning with म्. This cerebralization of म् was a peculiar phonetic change which naturally occurred when म् in utterance came after a vowel excepting अ. Some of the Prātiśākhya works have exhaustively treated this change and Pāṇini has also mentioned many rules in connection with it.

षष् (षट्) a technical term used in Paṇini's grammar for such numeral words (संख्याशब्द) as end with ष् or न् e.g. षष्, पञ्चन्, सप्तन् etc.; cf. ष्णान्ता षट् P. I. 1.24,

ষষ্ট a term used in connection with the sixth of the spirants viz. the Jivhāmūlīya letter cf. ক্ষকাকেরবেশ ঘদ্ত ক্রন্দা R. Pr. I.18; the term is also used in the sense of the sixth vowel viz. ই. in the Rk. Prāti-śākhya; cf. मুख्ये पर पञ्चमषष्ठयोश्च R. Pr. II.29.

पष्टी the sixth case; the genitive case. This case is generally an ordinary case or বিদাক্তি as contrasted with কাকেবিমাক্তি. A noun in the genitive case shows a relation in general, with another noun connected with it in a sentence. Commentators have mentioned many kinds of relations denoted by the genitive case and the phrase एक्शतं पश्चर्या: (the genitive case ha

senses a hundred and one in all), is frequently used by grammarians; cf. बष्टी देखे P. II. 3.50; cf. also बहुनो हि षञ्चर्याः स्वस्वाम्यनन्तरसभीपसमह-विकारावयवाद्यास्तत्र यावन्तः शब्दे संभवन्ति तेषु सर्वेषु प्राप्तेषु नियमः कियते षष्टी स्थानेयोगा इति । Kāś. on P. I. 1.49. The genitive case is used in the sense of any karaka when that karaka: is not to be considered as a kāraka: cf. कारकत्वेन आविवक्षिते शेषे षष्टी भविष्यति. A noun standing as a subject or object of an activity is put in the genitive case when that activity is expressed by a verbal derivative and not by a verb itself; cf. कर्तृकर्मणो: क्रिंति P. II. 2.65. For the senses and use of the genitive case, cf. P. II. 3.50 to 73.

षष्ट्रीतत्पुरुष a tatpurusa compound with the first member (rarely the second member as in the case of अवयवतत्पुरुष) in the genitive case. The compound is very common as prescribed in the case of a word in the genitive case with any other word connected with it; e. g. राजपुरुषः, गुरुपत्नी etc.; the other tatpurusa compounds viz. द्वितीयातत्पुरुष, तृतीयातत्पुरुष and others prescribed in connection with specific words or kinds of words, The word षष्ठीसमास is also used in this sense.

पष्टीनिर्देश a word put in the genitive case; a substitute given as connected with a genitive case which replaces the whole word which is put in the genitive case unless the substitute consists of a single letter or is characterized by the mute letter ङ्. cf. पष्टी स्थानेयोगा। अल्यान्त्यस्य । अनेकालिशस्पिय etc. cf. P. I. 1.49 to 55.

षष्टीसमास a compound word formed by one noun with another in the genitive case; see षष्टीतस्पुस्त्र above.

ষ্ট্রমুম্ব sense of the genitive case, which is 'a relation in general. See ৰম্মী above.

षाकन a kṛt affix applied to the roots जल्प्, मिश् इंड्, छुण्ट् and द्य in the sense of an agent, the mute letter ष् signifying the addition of the fem. affix ङीष् e. g. जल्पाक:, मिश्लाक: etc.; fem. base जल्पाकी, वराकी. etc.; cf. P. III. 2.155.

षिकन् tad. affix इक added to the word पथिन् in the sense of 'a student of ' or 'a scholar of ' when the word पथिन् is preceded by the word হাत or षष्टि. e. g. হাतपथिकः, হাतपथिकी । cf. হাतपष्टिः षिकन् पथः Kāś. on P. II. 2.60.

षित an affix or sometimes a word marked by the mute letter q. The mute letter & attached to roots signifies the addition of the krt affix अङ् (अ) in the sense of the verbal activity; e.g. क्षमा from the root क्षमूब् (क्षम्), जरा from जुब् (ज़ृ); cf. बिद्धिदादिम्भोऽङ् P. III. attached to affixes, q signifies the addition of the fem. affix ই (ভাষু), e. g. वराकी, शतपथिकी etc. cf. धिद्रीरा-दिभ्यश्च P. IV. 1.41. A few roots headed by घट् (roots from घट् to खर) are to be looked upon as शित् for the purpose of the addition of the krt. affix अ; e.g. घटा, व्यथा etc. cf. घटादयः षित: | Gana sūtra in Dhatupatha.

बास्त्रम combination of the verbal ending ध्वम् with the augment सीयुद्द prefixed to it, which is changed into बाद्द्रम after a root-base ending in a vowel excepting आ; cf. इण: बाध्व छङ्किटां घोड्नात् P.VIII. 3.78, 79.

षुक् augment q added to (1) मनु before the tad. affixes अञ् and य e.g. भानुष: मनुष्य:; cf. P. IV. 1.161; (2)

স্থু and জন্তু before the tad. affix স্থা e.g. সাথুগদ, জানুগদ; cf. P. IV. 3.138; (3) ঘনু before the tad. affix u, e.g. ঘনুগ্যা cf. P. IV. 4.89; (4) the root দা before the affix থা of the causal, e.g. মাগ্যন cf. P.VII 3.40; (5) the root না before the affix নুন (নু) e.g. নিয়া; cf. ন্যা: বুক্ ব P. III. 2.135 Vārt 2 and Vārt 4.

षेण्यण् tad. affix एन्य added to the word समिन्न, e. g. समीधिन्यो मंन्त्र: सामिधेनी ऋक्: cf. समिधामाधान विण्यण्, P. IV. 3.120 Vārt. 10.

पोडशकारिका an anonymous work consisting of only 16 stanzas discussing the denotation of words and that of the case-relations with a commentary by the author himself.

ष्कन् tad. affix क added to the word पाथन् in the sense of 'one who goes', e.g. पथिकः पथिकी; cf. पथः कान् P. V. 1.75.

प्रम् tad. affix तर added to the words कास and गोणी in the sense of small-ness; cf हस्वा कास: कासूतरी, गोणीतरी Kāś. on P. V, 3.90.

ष्टुत्व cerebralization of the dental consonants as prescribed by the rule हुना हु: P. VIII. 4. 41; e. g. कोयश्चिकशिकते, पेष्टा, उड्डीन: etc; cf. Kāś. on P. VIII. 4.41.

ष्ट्रन (1) kṛt. affix न्न, signifying the acute accent of the initial vowel and the addition of ई to the base in the feminine, added to the root घा in the sense of object (कर्मन) and to the roots दाप्, नी, शस् and others in the sense of instrument (करण); e.g. बान्नी, दानम्, नेनम्, स्तोनम्, पोत्रम् etc; cf. P. III. 2. 181-183; (2) Uṇādi affix न्न as seen in the word गान्न from the root इ; cf. अन्नवधनगान्नविचक्षणाजिराद्यथम् P. II. 4.54 Vārt 12.

ছুন্তস্ tad. affix ভ, causing Vrddhi to the initial vowel and the addition

of the fem. affix ई, applied to the word रामी in the sense of product or portion; राामील भरम; cf. P. IV. 3.142.

ष्ट्य tad. affix इक added to the word दशैकादश in the sense of censurable giving of interest or profit; दशैकाद- शिक:, दशैकादशिकी; cf. Kāś. on P. IV. 4.31.

ष्ट्रन tad. affix इक (1) added to the word कुसीद in the sense of giving a sum or something on an objectionable rate of interest or profit; cf. कसीदं प्रयच्छति कुसीदिक:, कुसीदिकी; cf. P. IV. 4.31; (2) added to the words पैरोडाश an प्रेडाश in the sense of 'explanatory book thereon'; e.g. पुरोडाशिक: पौरोडाशिक:, पुरोडाशिकी, पौरो-डाशिकी; cf. P. IV. 3.70; (3) added to the words qq and others as also to श्वगण, मस्त्रा and others, विवध, वीवध কিহাৰ and others, the words হালাল্ড पात्र and the words आहक, आचित and पात्र at the end of Dvigu compounds in the specific senses mentioned; e. g. पर्विकः, श्वगणिकः, भास्त्रिकः, शलालुकः ब्यादिककी etc.; cf. P. IV. 4.10, 11, 16, 17, 53, 54, V. 1.46, 54, 55.

ष्ठल् tad. affix इक added (1) to the word आकर्ष (touchstone) in the sense of 'living thereby'; e.g. आकर्षक:, आकर्षकी; cf. P. IV. 4.9; (2) to the word आवसथ in the sense of 'dwelling in', e.g. आवसथे वसति आवसाथक:, आवसथिकी; cf. P.IV. 4.74.

च्फ feminine affix आयनी, termed also तिंद्धत (1) added, according to the Eastern school of grammarians, to words ending with the tad. affix यज् (prescribed by rules like गर्गोदिस्यो यज् IV.1.105) e. g. गार्थायणी, वात्स्यायनी as contrasted with गर्गा or वात्सी according to the Western school of Pāṇini; (2) added to form feminine bases of the words from लेहित to कत to which

यज् has already been added as also to the words कौरब्य and माण्ड्रक. e. g. छौहित्यायनी, बाभ्रब्यायणी, कात्यायनी, कौरब्यायणी, माण्ड्रकायनी cf. P. IV. 1.17-19.

ष्पतक् tad. affix आयन, added to the words कापिशी and रङ्कु as also to the words बाही, उर्दि in the residual or miscellaneous tad. senses; e.g. कापिशायनं मधु, कापिशायनी द्राक्षा, राक्ष्वायणो गौ;, बाहायनी, और्दायनी, पादीयनी, cf. M. Bh. on P. IV. 2.99 and 100.

ष्यङ्क tad. affix य (taking Samprasaraņa change i. e. ई before the words पुत्र and पति and बन्धु in the Bahuvrīhi compound) added, instead of the affix अणु or হুস, in the sense of offspring, (1) to words having a long (गुर) vowel for their penultimate, only in the formation of feminine bases; e.g. कारीवगन्त्या कौमुद-गन्ध्या, वाराह्या; कारीषगन्धीपुत्रः, गन्धीपति:, कारीषगन्धविन्धः (Bah. comp.); cf P.IV.1.78; (2) to words expressive of family names like पुणिक, मुखर etc. as also to the words क्रोंडि, लाडि, न्यांडि आपिशाले etc. and optionally to the words देवयाज्ञ and others in the formation of feminine bases; e. g. पौणिक्या, भौखर्या, क्रौड्या, ब्याड्या, आपिशस्या etc.; cf. P. IV.1.79, 80, 81.

च्यञ् tad. affix (1) in the sense of nature' applied optionally with the affix इमानेच् to words showing colour as also to words headed by हद; e.g. श्रीक्टम, हिंदिमा etc.; cf. P. V. 1.123; (2) in the sense of nature as also in the sense of professional work to words of quality and words headed by ब्राह्मण; e.g. जाङ्यम्, ब्राह्मण्यम् cf. P.V. 1.124; (3) to the words चतुर्वर्ण, त्रिलेको and others in the same sense as that of those very words; e.g. चातुर्वर्ण्यम्, त्रेलोक्यम् बाह्मण्यम्, सन्यम् etc. cf. P. V. 6.124 Vart. 1.

च्चुन kit. affix अक added to a root in the sense of a skilled artisan नर्तक:, नर्तकी; खनक: खनकी; रजक:, रजकी; cf.P. III. 1.145.

स

स् (1) a sibilant letter of the dental class of consonants possessed of the properties श्वास, अवाप, कण्डविवार and महाप्राण; (2) substitute for visarjaniya if followed by a hard consonant excepting a sibilant cf. P. VIII. 3.34, 36, 38, 40, 42, 46, 47, 48-54.

स (1) short term for समास used by ancient grammarians; the term is found used in the Jainendra Vyakarana also; cf. तिशका-रकाणां प्राक् सुबुत्पत्तेः कृद्धिः सविधिः Jain. Pari. 100; cf. also राजाऽसे; (2) Uṇādi affix स placed after the roots वृ, तृ, वद्, हन and others; cf.Uṇādi-Sūtras 342-349; (3) tad. affix in the quadruple senses (ভারুংখিক) applied to the words त्य and others. e.g. तुगस:; cf. P. IV.2.80; (4) tad. affix et applied to the मृद् when praise is intended e.g. मृत्सा, मृत्स्नाः; also cf. P. V. 4.41; (5) substitute for the preposition सम् before the words हित and तत; cf. समो हितततयोवी छोप: M. Bh. on P. VI.1.144 Vart. 1.

संकर्ष non-resolution of the consonants य and व into इय and उव् e.g. ज्यमकम् as contrasted with त्रियम्बकम् which is called विकर्ष.

संक्रम (1) joining with a subsequent word after omitting a word or two occurring between; cf. गललदमतिकम्य अगलता सह संघान संक्रमः; e. g. शुद्रे अर्थे for शुद्रे यद्ये where यत् is passed over in the krama and other recitals; cf. V. Pr. IV. 77, 165, 194; (2) a term used in

ancient grammars for such affixes and others which do not allow the substitution of guṇa or vṛddhi for the preceding vowel; the term is also used for the letters क्, ग् and ङ् when they are mute, serving only the purpose of preventing guṇa or vṛddhi; cf. मृजर-जादो संकमे विभाषा इद्विमारमन्ते M. Bh. on P. I.1.3. Vãrt. 10.

संक्षिप्तसार name of a complete grammar-work written by क्रमदीश्वर for facility of study. This grammar appears to have been written before the time of कैयटं or हेमचन्द्र, as can be seen from the popular stanza परेत्र पाणिनीयज्ञाः केचित् कालापकी-विदाः। एके विश्रान्तियद्याः स्युरन्ये संक्षितसारकाः।

संख्या (1) a numeral such as एक, दि etc. In Pāṇinis Asṭādhyāyī, although the term is defined as applicable to the word बहु, गण and words ending with the tad. affixes बतु and इति, such as ताबत, कित and the like, still the term is applied to all numerals to which it is seen applied by the people; cf. M. Bh. on P. I. 1.23 also Pari. Sek. Pari. 9; (2) numerical order; cf. स्वशिष्व पंख्या V. Pr. I. 49.

संख्यातानुदेश application respectively of terms stated in the उद्देश्य and विधेय portions in their numerical order when the stated term; are equal in number: cf. यथातंख्यमनुदेश: समानाम् P. 1.3.10; cf. also पञ्चागमास्त्रय आगमिन: वैषम्यात् संख्यातानुदेशो न प्राप्तेशित M. Bh. Āhnika 2.

संख्यान enumeration; statement; cf. एकाजनेकाच्यहणेषु चाद्यतिसंख्यानादनेकाच्यहं भविष्यति, M.Bh. on Sivasütra i Värt. 10.

संख्यापूर्व with a numeral word placed first or at the beginning; a term used for defining the Dvigu compound; cf. संख्यापृत्रों द्विगु: P. II. 1.52. संख्येय lit. those that are to be counted; objects of enumeration; cf. बहुत्रीहों संख्येय डजनहुगणात् P. V. 4.73; cf. also अथवा संख्या नाम इयं परप्रधाना । संख्येयननया विशेष्यम्, M. Bh. on P. II. 2.24 Vart. 9.

संगतार्थ a word unit where the senses of two words are mixed together completely as in a compound word such as राजपुरुष: etc.; cf. संगतार्थ समर्थम् M. Bh. on P. II. 1.1. Vart. 4.

संगम combination of things coming one after another; cf. उदात्तपूर्वोप्य- नुदात्तसंगम: where the term is used with respect to a combination of grave syllables; cf. also ब्यञ्जनसंगमं संयोगं विद्यात, R. Pr. XVIII. 19.

संगृहीत included; the word is often used in the Mahābhāṣya in connection with instances which are covered by a rule, if interpreted in a specific way; cf. अथ निमित्तेऽ- भिसंवध्यमाने यत्तदस्य योगस्य मूर्धभिषिक्तमु-दाहरणं तदिष संगृहीतं भवति M. Bh. on P. I. 1. 57; cf. also एकार्थीभावे सामध्ये समास एकः संगृहीतो भवति, M. Bh. on P. II. 1.1.

संग्रह name of a very vast work on grammar attributed to an ancient grammarian Vyāḍi who is supposed to have been a relative of Pāṇini; cf. संग्रहेस्तमुपागते Bhartrhari's Vākyapadīya cf. also संग्रह प्रतिकञ्चके; cf. संग्रहो नाम लक्षक्षोकात्मको न्याहिकृतो ग्रन्थ: I Some quotations only are found from the Samgraha in grammar works, but the work is lost long ago.

संघात (1) aggregate, collection; the word is often used in grammar in connection with letters (वर्ण); cf. वर्णसंघात; पदम् cf. also संघातस्यैकार्थात् सुवभावो वर्णात् M.Bh. on Siva sūtra 5 Vārt. 13; the word is also used in connection with a collection of

words; cf. संघातस्य समाससंज्ञा प्राप्नोति । कद्धस्य राज्ञ पुरुष: M. Bh. on P. I.4.13 Vart. 8; (2) effort made in the utterance of a word; cf संघातो नाम प्रयत्न: स बाह्याभ्यन्तरत्वेन द्विधा । अनन्त-महभाष्य on V. Pr. I. 9. cf. also स संघातादीन् वाक् V. Pr. I.9.

संघाताथे collective sense given by a combination of letters called पदार्थ. When the collective sense is given by a combination of words it is called पदार्थ, and when the idea is complete it is called वाक्यार्थ. Sometimes the meaning of a compound word is taken individually and not collectively; such a meaning is called संवातिवयहीताथे टर. नामाख्यातप्रहणं संवातिवयहीताथे दर कि. on IV. 3.72 Vart. 1.

संचय a collection or a group; cf. वर्णसंचय which means अक्षरसमाम्नाय or alphabet.

संज्ञा a technical term; a short wording to convey ample sense; a term to know the general nature cf things; convention; cf. बृद्धिशब्दः संज्ञा: आदेच: संज्ञिन: M.Bh. on P.I-1.1. There are two main divisions of संज्ञा—क्षत्रिमसंज्ञा or an artificial term such as हि. ञ. or भ which is merely conventional, and अक्रुत्रिमसंज्ञा which refers to the literal sense conveyed by the word such as अन्यय, सर्वनाम and the like. Some grammar works such as the Candra avoid purely conventional terms. These samjñas are necessary for every scientific treatise. In Pānini's grammar, there are the first two chapters giving and explaining the technical terms whose number exceeds well-nigh a hundred.

संज्ञाधिकार a topic or a chapter or a portion of a treatise in which technical terms are given and explained; cf. संज्ञाधिकारायम्; M. Bh.

on P. I. 1.46, I. 1.56, I. 4.1, I. 4.23; see the word 共和.

संज्ञापूर्विक an operation with respect to which a technical term has been expressly mentioned; cf. संज्ञापूर्विको विधिरानित्य:, Par. Sek. Pari. 93.1; Vyādī Pari. 53.

संज्ञाभूत (1) that, which by usage has become a technical word possessed of a conventional sense; cf. किं पुनर्यानि एतानि संज्ञाभूतानि आख्यानानि तत्र उत्पन्या भावितन्यम्, M. Bh. on III. 1. 26 Vart. 7; (2) which stands as a proper noun or the name of a person; cf. संज्ञाभूतास्तु न सर्वादय: S. K. on P. I.1.27.

संज्ञाविधि a rule laying down the defi-. nition of a संज्ञा or a technical term : as contrasted with कार्यविधि or a rule laying down a grammatical operation; cf. संज्ञाविधी शुद्धिरादेच् अदेड्जुणः इति M.Bh. on Sīva Sūtra 3, 4.

संज्ञाशब्द one of the four divisions of words— জানিয়াৰ, गुणशब्द, কিয়ায়ৰ and संज्ञाशब्द; the संज्ञाशब्द is called also यहच्छाशब्द a word forming the name of a thing by virtue of a convention; see यहच्छाशब्द.

संज्ञिन् the recipient or the bearer or possessor of a technical term; cf. संज्ञासंज्ञ्यसंदेहश्च । कुतो ह्यातद् शृद्धिग्रन्दः संज्ञा, आदेचः संज्ञिन इति । M. Bh. on P. I. 1.1 Vart. 3; cf. also रवभावात् संज्ञाः संज्ञिनः प्रत्याय्य निवर्तन्ते M. Bh. on P. I. 1.1. Vart. 7.

संतान continuity; line; continuous recital.

संदर्भामृत name of a commentary on the Mugdhabodha Vyākaraṇa of Bopadeva, written by a grammarian, named Bholānātha.

संद्ध a fault of pronunciation when the constituent letters of a word are uttered with the teeth kept close together. Kaiyata has explained the word as বার্গন.

संदेह ambiguity; doubt regarding the wording of a rule or its interpretation or regarding the correctness of a word. It is looked upon as the main purpose of grammar to solve doubts regarding the correctness of words; cf. ज्यास्थानता विशेषप्रति-पात्तर्नीह संदेहादलक्षणम् Pari. Sekh. Pari. 1.

संदेहिनवृत्यर्थ lit. meant for the removal of doubt; the word is used in connection with a word or an expression or an addition of a mute letter, as seen in the expression of the sūtrakāra for the purpose of leaving no kind of doubt regarding the wording or its meaning; cf. तत्र अवस्य संदेहनिवृत्यर्थ विशेषार्थिना विशेषोनुप्रयोक्तस्य: M.Bh. on P.II. 2.24 Vārt. 6.

संधारण putting very close in utterance; slurring of a phonetic element when it appears as almost suppressed; cf. संघारण वर्णश्रुते: संवरणम् Uvvața on R. Pr. VI. 5.

संधि euphonic combination; phonetic combination of two vowels or two consonants or one vowel and one consonant resulting from their close utterance; many kinds of such combinations and varieties are given in the Prātiśākhya works. In the Siddhāntakaumudī, Bhaṭṭojī Dīkṣita has given five kinds of such Sandhis at the beginning of his work; cf. पदान्तपदाद्योः संधिः। यः कश्चिद्विदक्यास्तरं धिरुच्यते स पदान्तपदाद्योवेदितन्यः।ते संध्यश्चत्वारो भवन्ति। स्वरयोः ब्यञ्जनयोः स्वरव्यञ्जनयोश्च V. Pr. III. 3.

संध्य a diphthong; see below the word संधि: cf. अस्थनामनी संध्यम् .

संध्यक्षर diphthong, a vowel resulting from a combination of two vowels, but which is to be looked upon as one single vowel by reason of only a single effort being required for its pronunciation; the letters ए, ऐ, ओ and औ are termed as संध्यक्षर as contrasted with समानाक्षर. cf. अशौ समानाक्षराण्यादितस्ततश्चलारि संध्यक्षराण्युत्तराणि R. Pr. I. 10; cf. also T. Pr. II. 13, R. T. 111; cf. also संध्यक्षराणामिद्रती हस्वादेशे Kāt. Pari. 43

संनमन interpretation, explanation; cf. यथायथं विभक्ती: संनमयेत् Nir. 1.

संनिकर्ष contact, juxtaposition; this contact between two letters is called संहित। when it is very close; cf. परः संनिकर्षः संहिता P. I. 4,109.

संनिधापन putting together too close, so that the two phonetic elements which are so placed, coalesce together and result into a third, or one of the two merges into another.

संनिधि juxtaposition; coming together phonetically very close; cf. पदानामाविलम्बितेनोच्चारणम् Tarka Samgraha; अन्यवधानेन अन्वयप्रातियोग्युपास्थितिः Tattvacintāmaṇi 4; the same as संनिक्ष which see above.

संनिपात (1) a contact or relation of two things. cf. संनिपातो द्वयो: संबन्ध: 1 Pari. Sek. Pari. 85; (2) coming together; cf. न लक्ष्यत विकृति: संनिपाते M. Bh. on P. III. 2.123 Vart 5.

संनिपातपरिभाषा the maxim or convention that an operation which is based upon, or is caused or occasioned by, a relationship between two things cannot break their relation; in short, such an operation as results in breaking relationship between two things on which it is based, cannot take place. This dictum is many times followed in grammar in preventing the application of such rules as are likely to spoil the formation of the correct word; many times, however, this dictum has to be ignored; For details

see Pari. Šek. Pari. 85; also Mahābhāṣya on P. I. 1.39.

संनिपातलक्षण an operation which is characterized by the relationship between two words or two phonetic elements. See संनिपातपरिमाषा above.

संनियोग occurrence together of two or more words in one sentence or in one grammatical rule; cf. संनियोगशिशनामन्यतरापाये उभयोरप्यपाय: M. Bh. on IV 1.36 Vārt. 4; cf. also एष एव न्यायो यदुत संनियोगशिशनामन्यतरापाये उभयोरप्यभाव: ! तद्यथा देवदत्त्त्यशदत्ताभ्यामिदं कर्तन्यमिति देवदत्तापाये यज्ञदत्तोपि न करोति, M. Bh. on V. 1.64 and 76.

संनिविष्ट placed together in a particular order at a particular place; cf. क संनिविष्टानां प्रत्याहार: M. Bh. on P. III. 1.40 Vart. 3; III. 2.127 Vart. 6.

संनिचेश order or arrangement of letters; cf. वर्णानामानुपूर्व्येण संनिवेश: समवाय: M. Bh. Ahnika I. Vart. 15; cf. also संनिवेशोन्य: प्रत्याहारार्थ: R. T. I. 3.

संनिद्धित (1) present by implication; taken as granted; cf. अपि च ऋकारमहणे लृकारमहणे सेनिहितं भवति M. Bh. on P. I. 1.9. Vārt. 5; (2) nearby, at hand; cf. इह सर्वेषु साधनेषु सांनिहितेषु कदाचित् पचतीत्येतद् भवति, कदााचित्र भवति । M. Bh. on I. 3.1. Vārt. 2; I. 4.23 Vārt. 15.

संपद्यकर्त the agent of the activity or of the event which is to take place; cf. अभृततद्भावे संपद्यकर्तीर च्विः । संपद्मते: कर्ता संपद्मकर्ता Kāś. on P. V. 4.50.

संपृक्त completely mixed in such a way that one of the two or more letters mixed together can neither be distinguished as different, nor can be separated; cf. तद्यथा। क्षारोदके संपृक्ते आमिश्रीभृतत्वात्र ज्ञायते कियत् क्षीरं कियदुदकम्। एवमिहापि न ज्ञायते कियदुदात्तं

कियदनुदात्तम् । M.Bh. on P. I. 2.32. संप्रातिपात्त understanding, comprehension of the sense; cf. गौणमुख्ययो-मुंख्य संप्रतिपात्तिः, M. Bh. on P. VIII. 3.82 Vārt. 2.

संप्रत्यय the same as संप्रतिपत्ति which see above; cf. इंतरिया ह्यसंप्रत्ययो यथा छोके M. Bh. on P. I. 1.1 Vart. 2; cf. also येनोच्चारितेन सारनाळाङ्गूळककुद-खुरविषाणिनां संप्रत्ययो भवति स राज्दः M. Bh. on Ahnika 1.

संप्रदान a kāraka relation or a relation between a noun and the verbal activity with which it is connected, of the type of the donation and the donee; the word is technically used in connection with the bearer of such a relation; cf. कर्मणा यमभित्रेति स संप्रदानम् P. I.4.32.

संप्रधारणा simultaneous occurrence. अल्लोपस्य च यणादेशस्य नास्ति संप्रधारणा, M. Bh. on I. 4.2 Vart. 9; cf. also सिद्धासिद्धयोश्च नास्ति संप्रधारणा M. Bh. on P. VI, 1.9. Vart. 7.

संप्रयुक्त used together with; cf. ळ्हकार-मेति स एव चास्य ढकार: सन्नूष्मणा संप्रयुक्त: R. Pr. I. 22.

संप्रसारण lit. extension; the process of changing a semi-vowel into a simple vowel of the same sthana or place of utterance; the substitution of the vowels इ, उ, ऋ and ल for the semi-vowels यु, ब्, र् and ल् respectively; cf. इंग्यण: संप्रसारणम् P. 1.1.45. The term संप्रसारण is rendered as a 'resultant vowel' or as 'an emergent vowel'. The ancient term was प्रसारण and possibly it referred to the extension of य and व् into their constituent parts इ+अ, उ+अ etc. the vowel अ being of a weak grade but becoming strong after the merging of the subsequent vowel into it; e. g. cf. सर्वत्र प्रसाराणिभ्यो ड: P. III. 2.8 Vart.1. For the words taking this samprasāraņa change, see P. VI. 1.13 to 19. According to some grammarians the term संत्रसारण is applied to the substituted vowels while according to others the term refers to the operation of the substitution; cf. M. Bh. on P. I. 1.15. The substitution of the samprasāraņa vowel is to be given preference in the formation of a word; cf. संत्रसारण तदाश्रयं च कार्य बळवत् Pari. Sek. Pari. 119.

संप्रसारणबळीयस्य the relative superior strength of the samprasāraņa change in comparison with other operations occurring simultaneously. The phrase न वा संप्रसारणबळी- यस्वात् is often used in the Mahābhāṣya which is based upon the dictum of the superior strength of the samprasāraṇa substitution, which is announced by the writer of the Vārttikas; P. VI. 1.17 Vart. 2. See संप्रसारण.

संबद्धार्थ with senses (of the two words) inerely connected with each other and not completely mixed into each other; cf. संगतार्थं समर्थं संस्टार्थं समर्थं संग्रह्मार्थं समर्थं संस्टार्थं समर्थं संग्रह्मार्थं समर्थं संग्रह्मार्थं समर्थं संग्रह्मार्थं समर्थं संग्रह्मार्थं समर्थं संग्रह्मार्थं समर्थंमिति।... कः पुनिरह वज्ञात्पर्थः। संग्रह्म इत्युच्यते यो रज्ज्ञा अयसा वा कांळे व्यतिषयतो भगति, M. Bh. on P. II. 1,1. Vārt.4. This संग्रह्मार्थत्व is connected with the definition व्यपेक्षा out of the two definitions एकार्थीभाव and व्यपेक्षा cited with respect to the word सामर्थं.

संबन्ध (1) lit.connection in general; cf. धातुसंबन्ध प्रत्यया: P.III. 4.I. The word is explained by the general term विशेषणविशेष्यभाव; cf. संबन्धा विशेषणविशेष्यभाव: Kāś. on P.III.4.1; (2) context, cf. संबन्धादतद् गन्तन्थं यं प्रति यदप्रधानं तं प्रति तदुपसर्जनं भवति M. Bh. on P. I. 2.43. Vārt. 5.

संबन्धपाद name given by convention by grammarians to the fourth pāda of the third adhyāya of Pāṇini's Aṣṭādhyāyī which begins with the sūtra घातुसंयन्धे प्रत्यया: P. III. 4.1.

संविध्याब्द relative term; the term refers to words connected in such a way by their meaning that if one of them is uttered, the other has to be anticipated and understood; e. g. पितृ, आतृ, मातृ, मार्या etc. cf. तद्यथा। संविध्याब्दाः। मातिर वर्तितब्यम्। पितिर शुश्र्षितब्यम्। न चोच्यते स्वस्यां मातिर स्वस्मिन्वा पितिर इति। cf. also M.Bh. on I 1.71; cf. also प्रधानमुपसर्जनं च संविध्याद्यांवेतो M. Bh. on P. I. 2.43 Vart. 5; I. 2.48 Vart. 4.

संबुद्धि (1) a term used in Pāṇini's grammar for the case-affix of the vocative singular; cf. एकथचनं संबुद्धिः P. II. 3. 49; the vocative is, however, not looked upon as a separate case, but the designation संबोधन is given to the nominative case, having the sense of संबोधन; (2) the word is also used in the general sense of संबोधन i. e. addressing or calling; cf. एकधुति दूरात्संबुद्धाः किमिदं पारिभाषिक्याः संबुद्धग्रेदणमेकवचनं संबुद्धिः (II. 3.49) आहोस्विदन्धर्थग्रहणं संबोधनं संबुद्धिः M. Bh. on P. I. 2.33.

संबोधन calling or address which is given as one of the additional senses of the nominative case affixes (cf. संबोधने च P. II. 3. 47) in addition to those given in the rule प्रातिपदिकाधीलङ्गपरिमाणवचन-मात्रे प्रथमा P. II. 3.46; cf. आमिमुख्य-करणं संबोधनम् Kāś. on P. II. 3.47.

संभव lit. possibility. The word is used in the general sense of the possibility of the application of a rule or of the occurrence of a rule; cf. बिधिनियमसंभवे विधित ज्यायान् M. Bh. on VI. 4.49 Vart.; Pari. Sek. Pari. 100; cf. also असति संभवे बाधनं भवति। आस्ति च संभवे। यदुभयं स्थात्। Sīra-

deva Pari. 35.

संयुक्त (1) closely connected; cf. गृहपतिना संयुक्ते ज्यः P. IV. 4.90; (2) joint, conjoint; the term is used frequently in connection with two or more consonants in juxtaposition; cf. अननुस्वारसंयुक्तम् T. Pr. XXII. 15.

संयोग connection in general; the word is used as a technical term in the grammar of Pāṇini, in the sense of two or more consonants coming closely together unseparated by any vowel; cf.हकानन्तराः संयोगः cf. P. I. 1.7; cf. also अनन्तरं संयोगः V. Pr. I. 48.

संयोगादिलोप the elision of the first of the conjunct consonants if it is स or क्, provided the conjunct consonants are at the end of a word or followed by a consonant which is not a semi-vowel nor a nasal; e. g. तक, तरवान from the root तक; cf. स्को: संयोगाद्योरन्ते च P. VIII. 2.29.

संयोगान्तलोप the elision of the final of the conjunct consonants when they are at the end of a word provided they are not formed of ्as the first member and any consonant except स् as the second member; e. g. गोमान, उर्क् etc.; cf. संयोगान्तस्य लोगः, रास्तस्य P.VIII.2.23,24.

संवरण lit. concealment; slurring over a consonant by practically merging its sound into that of the following one; the technical term अभि-िधान is also used in the same sense; e.g. षड्डा हा; cf. संघाणं संवर्ण श्रुतेश्च R. Pr. VI. 5.

संवादाचिन्तामणि name of a small treatise on roots and their meanings written by a grammarian named इन्द्रदत्तीपाध्याय who has also written a commentary on the Sabdakaustubha called कोस्तुमगुण and सिद्धान्तकी मुदीगृदका किकापकार.

संवार one of the external efforts in the production of a sound when the gullet is a little bit contracted as at the time of the utterance of the third, fourth and the fifth of the class-consonants; cf. कण्टबिलस्य संकोच: संवार: Uddyota on P. I. 1.9.

संविज्ञात conventional; lit. known widely among the people, as a result, of course, of convention; cf. संविज्ञातानि तानि यथा गौरश्वः पुरुषो हस्तीति Nir. I. 12.

संविज्ञान apprehension; cf. बहुत्रीहाँ तद्गु-णसंविज्ञानमपि.

संब्रुत lit. covered or concealed; name of an internal effort in the production of sound which is accompanied with a laryngeal hum; cf. संवृतों घोषवान्; cf. also हस्वस्थावर्णस्य प्रयोगे संवृतम् । प्राक्रियादशायां तु विवृत्तमेव S. K.: on P.I.1.9; cf. also तत्रास्यतः प्रायदा जिह्नायोगपामम्यपूलानि तत्तद्वर्णीस्यित्तस्थानानां तास्वादीनां समीपमेव केवलं अवतिष्ठन्ते तदा संवृतता Sabdakaus. on P. I. 1.9.

संश्विष्ट very closely held together just as the sound of the consonant in the vowel कः cf. कलवर्णे रेपलकारों संक्षिशे अश्वतिषरी एकवर्णा where Uvvata has explained the word संक्षिट as एकी भूत; cf. Uvvata on V. Pr. IV. 148.

संसर्ग lit. contact, connection; (1) contact of the air passing up through the gullet and striking the several places which produce the sound, which is of three kinds, hard, middling and soft; cf. संसर्ग वायुम्थानसंसर्गः अभिनातासमः। स त्रिविषः। अभः पिण्डवहारिण्डवहूणीिण्डवहिति। तदुवत-मापिशलशिक्षायाम्। स्पर्शयमवर्णकरे वायुः अयः- पिण्डवत्थानमापीडयित। अन्तस्थावर्णकरो दारु- पिण्डवत्। कष्मस्थस्वरवर्णकर कर्णापिण्डवत्। कष्मस्थस्वरवर्णकर कर्णापिण्डवत्। कष्मस्थस्वरवर्णकर कर्णापिण्डवत्। syntactical connection between words themselves which exists between pairs of words as between

nouns and adjectives as also between verbs and the kārakas, which is necessary for understanding the meaning of a sentence. Some Mīmāmsakas and Logicians hold that samsarga itself is the meaning of a sentence. The syntactical relation between two words is described to be of two kinds अभेद-संसर्ग of the type of आधाराध्यमान and भेदसंसर्ग of the type of विषयाविषयिमान, समनाय, जन्यजनकभान and the like.

संस्थ words syntactically connected with each other, and hence, capable of expressing the sense of a sentence; cf. संस्था वाक्यार्थ; Vākyapadīya II. 2.

संस्थ्यादिपक्ष the theory, that the meaning of a sentence is a novel thing (अपूर्व), held by some Mīmā-msakas who believe that words connected with activity display their phenomenal capacity (अनुभा-विकाशक्ति) after the recalling of the senses of words by the recalling capacity (स्मारिकाशक्ति).

संस्कार (1) preparation such as (a) that of a word by placing the affix after the base and accomplishing all the necessary changes, or (b) that of a sentence by placing all words connected mutually by syntax and then explaining their formation; these two views are respectively called the पदसंस्कारपञ्च and the वाक्यसंस्कारपक्ष; (2) grammatical formation; cf. स्वरसंस्कारयोश्छन्दसि नियमः । संस्कारो लोपागमवर्णाविकारप्रकृतिभाव-छक्षण: Uvvata on V.Pr. I.1; cf. also तद्यत्र स्वरसंस्कारी प्रोदेशिकेन गुणेन अन्वितौ स्याताम् etc. Nir.I.

संस्कृतमञ्जरी a short handbook on declension and case-relations written by a grammarian named Sādhusundara, who lived in the beginning of the eighteenth century.

संस्पृष्ट lit. formed by combination or compact; the term is used in the Prātiśākhyas for diphthongs which are combinations, in fact, of two vowels which are completely mixed being produced with a single effort. The diphthongs and ऋ also, are called संस्पृष्ट्वणे.

संस्वाद a peculiar phonetic element described along with another one named निगार both of which have got no definite place of utterance in the mouth; cf. अविशेषस्थानों संस्वादिनगारों। पकारनकारयकाराः वा संस्वादे। हकारमकारना. सिक्या वा निगारे। com. on R.T.11.

संस्वार a combination or collection of the Svāras or musīcal notes for purposes of singing the Sāma hymns.

संहत a tone in which two or more accents or tones are mixed up with one another; cf. Bhāradvāja Sikṣā.

संहार unnecessary contraction of the place (स्थान) as also of the instrument (करण), which results into a fault of utterance called पाँडन; cf. विहार-संहारयोग्यांसपीडने R. Pr.XIV.2.

संहिता position of words or parts of words in the formation of a word quite near each other which results into the natural phonetic coalescence of the preceding and the following letters. Originally when the Vedic hymns or the running prose passages of the Yajurveda were split up into their different constituent parts namely the words or padas by the Padakāras, the word संहिता संहितापाठ came into use as contrasted with the पदपाठ. The writers of of the Pratisakhyas have consequently defined संहिता as पदप्रकृतिः संहिता, while Panini who further split up

the padas into bases (प्रकृति) and affixes (प्रत्यय) and mentioned several augments and substitutes, the phonetic combinations, which resulted inside the word or pada, had to be explained by reason of the close vicinity of the several phonetic units forming the base, the affix, the augment, the substitute and the like, and he had to define the word संहिता rather differently which he did in the words qर: संनिकर्ष: संहिता; cf. P.I.4.109; cf. also संहितैकपदे नित्या नित्या धातुपसर्गयोः । नित्या समासे वाक्ये तु सा विवक्षामपेक्षते Sabdakaustubha on Māheshvara Sūtra 5.1.

संहितापाठ the running text or the original text of the four Vedas as originally composed. This text, which was the original one, was split up into its constituent padas or separate words by ancient sages शौनक, आत्रेय and others, with a view to facilitating the understanding of it, and consequently to preserving it in the oral tradition. The original was called मूलप्रकृति of which the पदपाठ and the क्रमपाठ which were comparatively older than the other artificial recitations such as the जटापाठ, घनपाठ and others, are found mentioned in the Pratisakhya works.

सक् augment स added to the roots यम् रम्, नम् as also to roots which end in आ before affixes of the aorist tense; e. g. अयंसीत्, व्यरंसीत्, अयासीत्, cf. P. VII. 2.73.

सकर्मक a root which, by virtue of the nature of its meaning i.e. verbal activity, requires or expects an object which is covered by the activity; a transitive root. In the passive voice of these roots the object is expressed by the verbal termination and hence it is put in the nominative case.

सकारक accompanied by the qualifying words such as the different
Kārakas or causal agents for the
verbal activity: cf. आस्यातं सान्ययं
सकारकं सकारकाविशेषणं वाक्यम्। सकारकम्।
ओदनं पचति। M. Bh. on P. II. 1.1.
Vārt. 9.

सक्तदाख्यातिर्माद्या capable of being understood on being mentioned only once just as the notion of genus or generality which is so understood; the phrase सक्दाख्यातिनमीद्या is cited as a definition of जाति; cf. सक्दाख्यातिनमीद्या गोत्रं च चरणै: सह, M.Bh. on P.IV.1.63.

सङ्द्रित or सङ्द्रितिन्याय the maxim or convention of the non-application of a grammatical rule or operaton any longer when, on conflict with another, it has been once set aside. The maxim is सङ्द्रतो विप्रतिषेधे यद्वाधितं तद्वाधितमेव M. Bh. on P. I. 1. 56, I.4. 2, VI.3. 42 etc. cf. also Par. Sek. Pari. 40.

सिकियाविदेशिषा accompanied by a word qualifying the verbal activity; sometimes a verb with such a word makes a sentence; cf. सिकियाविदेशियां चिति वस्तब्यम् । सुष्ठु पचिति | M.Bh. on P. II.1.1 Vart. 9.

सगिति or सगितिक accompanied by a preposition which is called गित; cf. सगितिरिप तिङ् P. VIII. 1.68; cf. also सगितिरिप । प्रपचिति M.Bh. on P. VIII.1.68.

सङ् a short term or प्रत्याहार made up of the स of सन् in गुप्तिन्द्रियः सन् P.III.1.5, and the ङ् of महिङ् in P.III.4.78 with a view to include all affixes from सन् to महिङ्; cf. सङ् झलीत बुत्वादयो न सिध्यान्त, M. Bh. on P.VI.1.9 Vart. 7; cf. also M. Bh. on P. VIII.2.22.

सण् tad. affix सण् prescribed after the word पर्श in the sense of collection; e. g. पार्श्वम; cf. पर्श्वा: सण् P.IV.2.43

Vārt. 3 for which there is an alternative reading पर्यो णम् चक्तब्यः; for facility of grammatical operations णस् is recommended with preference in the Mahābhāṣya; cf. एवं तिईं णस् वक्तब्यः M.Bh. on P. IV.2.43 Vārt. 3; (2) सण् is given as a technical term for संयोग in the Prāti-sākhya works; cf. सयुक्त सण् 1 संयुक्तं व्यक्तनं संयोगसंज्ञं भवति R.T.27.

सत् a short term used for the affixes शत् (अत्) and शानच् (आन) which are applied to roots to form the present and the future participles; cf. तौ सत् P III. 2. 127; cf. also लूट: सद्या P III. 3. 14.

सितिशिष्ट prescribed subsequently; occurring after the preceding has taken place; cf. सित शिटोपि विकरणस्वरः सार्वधातुकस्वरं न बाधते; although the words सित and शिष्टः are separate still it is habitual to take them combined in an adjectival sense and make the word सितिशिट an adjective to the word स्वर as in the dictum सितिशिटस्वरबळीयस्व च P. VI. 1. 158 Vart. 9.

स्तिशिष्ट्रवरबद्धीयस्त्व the comparatively superior strength of a subsequent accent which prevails by the removal of the accent obtaining before in the process of the formation of a word; cf. VI. 1.158 Vārt. 9. See सर्तिशिष्ट above.

existence; the Jati par excellence which is advocated to be the final sense of all words and expressions in the language by Bhartrhari and other grmmarians after him who discussed the interpretation of words. The grammarians believe that the ultimate sense of a word is the which appears manifold and limited in our everyday experience due to different limitations such as

deśa, kāla and others. Seen from the static viewpoint, ধলা appears as র ভ্রম while, from the dynamic viewpoint it appears as a ক্রিয়া. This ধলা is the soul of everything and it is the same as মুন্বল্ল or ল্লান্ or অন্দেশ্য; cf. Vākyapadiya II. 12:. The static existence, further, is called ভ্যক্তি or individual with reference to the object, and জানি with reference to the common form possessed by individuals.

सत्व an aspect of सत्ता of the type of the static existence possessed by substantives as contrasted with भाव the dynamic type of existence possessed by verbs; cf. भाव-प्रधानमाख्यातम् ! सत्त्वप्रधानानि नामानि. Nir. I; cf. also सत्त्वाभिधायकं नाम निपातः पादपूरण: R.Pr. XII. 8. V. Pr. VIII. 50.

सत्त्वगुण qualities of a substantive such as स्त्रीत्व, पुंस्त्व, नपुंसकत्व, or एकत्व, द्वित्व and बहुत्व cf. स्त्रीपुंनपुंसकानि सत्त्वगुणाः एकत्विद्वित्वबहुवचनानि च। M. Bh. on P. I. 1.38 Vārt. 6, also on P. I. 2.64 Vārt. 53.

सत्त्वशब्द the word सन्ध meaning द्रब्य; cf. चादयोऽसन्धे । अथं सत्त्वशब्द: अस्येव द्रव्यपदार्थक: । M.Bh. on P. I. 4. 57.

सत्यत्रवोध name of commentary work on the Sārasvataprakriyā.

सत्सतमो the locative case prescribs ed by the rule यस्य च भावेन भावलक्षणम् P. II.3.37 as seen in गोपु दुद्यमानासु गत:; cf. लाके इति नेषा परसत्मी। का तर्हि । सत्सतमी । छाके सति इति M. Bh. on P.I.2.49 Värt. 2. On account of the frequent occurrence of the word सति in a large number of examples of this locative absolute, the term सतिसतमी is used by modern grammarians for better word सत्सतमी in the Mababhāsya; cf. M.Bh. on P.VI.4.23 as also on P.VIII, 3.61.

सदाशिव-अग्निहोत्री name of a modern grammarian of the seventeenth century who has written a gloss on Pratisakhya works called प्रति- शाल्यदोपिका.

सदाशिव-पण्डित a grammarian of the seventeenth century who has written a commentary on the Sūtras of Pāṇini and a brief commentary on the Mahābhāṣya called गृहार्थदीपिनी or गृहार्थ-दीपिना which is incomplete.

सदाशिवमह (घुळे) a prominent grammarian of the latter half of the eighteenth century who was a resident of Nagpur and whose gloss on the Laghusabdendusekhara by name सदाशिवमही is well known to scholars.

सदाशिवमद्दी name of a commentary written by सदाशिवमद्द ঘুন্ত on the Laghuśabdenduśekhara of Nāgeśa.

सदेश lit. belonging to the same place; the word is used in the sense of immediately near; or quite in proximity; cf. अनन्त्यविकारे अन्त्य-सदेशस्य Pari. Sek. Pari. 103.

संघीनर् tad. affix अधीन proposed by the Vārttikakāra in the sense of 'something in that or from that'; e.g. राजनीदं राजाधानं; cf. तस्मा-तंत्रदमिति सधीनर् P. V. 4.7 Vārt. 2. The standard affix in such cases is ख (ईन) by the rule अषडक्ष ... अध्युत्रपदात् ख; P. V. 4.7.

सन् (1) desiderative affix स applied to any root in the sense of desire; e. g. चिकोषीत, जिहीषीत, बुम्पत; cf धातो: कर्मण: समानकर्तृकादिच्छायां वा P.III. 1.7; (2) applied in specific senses possessed by the root to the roots गुप्, तिज्ञ. कित्, मान्, बध्, दान् and शान्; e. g. जुगुप्सते, तितिक्षतं, चिकित्सति, मीमांसते, बीमांसते, दीदांसते, शोशांसते; cf. P. III. 1. 5 and 6. The roots to which सन् is applied are redupli-

cated and the reduplicated form ending with सन् (स) is looked upon as a different root from the original one for purposes of conjugation, which takes, however, conjugational affixes of the same Pada as the original root; cf. सनाइन्सा घातन: III. 1.32.

सञ्जर graver, comparatively more grave; a term used in connection with a grave accent which is followed by a vowel with an acute or circumflex accent; e.g. the vowel इ of सरस्वित in इमं मे गङ्ग यमुन सरस्वित ग्रुतिह; cf. सम्रं दृष्ट्या सम्रतर इत्येतद् मवित M. Bh. on P. I. 2.33.

सन्बद्धाय behaviour like that of the affix सन् in point of its specific features, viz. causing reduplication in the case of the previous root by the rule सन्यक्षेः VI.1.9, as also the substitution of इ for आ in the reduplicated syllable (अभ्यास) by P. VII. 4.79. This सन्वद्धाव is prescribed in the case of a root ending in इ (णिच्) before the aorist sign (विकरण) चङ्. cf. सन्वछन्जनि चङ्गरेनग्छोपे VII. 4.93.

सपादसमाध्यायी a term used in connection with Pānini's first seven books and a quarter of the eighth, as contrasted with the term Tripadi, which is used for the last three quarters of the eighth book. The rules or operations given in the Tripadī, are stated to be asiddha or invalid for purposes of the application of the rules in the previous portion, viz. the Sapadasaptādhyāyī, and hence in the formation of words all the rules given in the first seven chapters and a quarter, are applied first and then a way is prepared for the rules of the last three quarters. It is a striking thing that the rules in the Tripādī mostly concern the padas or formed words, the province, in fact, of the Prātišākhya treatises, and hence they should, as a matter of fact, be applicable to words after their formation and evidently to accomplish this object, Pāṇini has laid down the convention of the invalidity in question by the rule प्वत्रासिद्धम् P. VIII. 2,1.

सपूर्व together with a word that is put before, and not with any suffix like बहुच placed before; cf. सपूर्वाचाः प्रथमाया विभाषा. P. VIII. 1 26; सपूर्वाच्च P. V. 2.87.

सम्प्तम the seventh of the vowels stated in the alphabet; a word used for the vowel ए (ऋ) by ancient grammarians; cf. ओंजा हस्याः सप्तमान्ताः स्वराणाम् R. Pr. I.14.

स्तमी (1) the seventh case; the locative case; a term used for the locative case by ancient grammarians and Pāṇini; cf. न सप्तम्यामन्त्रितयोः V. Pr. III 139; cf. ईदृतौ च सप्तम्यथं P. I. 1. 19. or सप्तम्यास्त्रल् P. V. 3. 10; cf. also द्वितीयादयः राज्दाः पूर्वाचायः सुपा त्रिकेषु स्मर्यन्ते Kāś. on P. II. 3.2; (2) the seventh of the moods and tenses; the optative mood; cf. Kāt. III. 1. 20; Hemacandra III. 3. 7.

समस्बर lit. the seven accents; the term refers to the seven accents formed of the subdivisions of the three main Vedic accents उदात, अनुदात्त and स्वरित viz उदात्त, उदात्ततर. अनुदात्त, अनुदात्ततर, स्वरित, स्वरितोदात्त, and एकश्रुति; cf. त एत तन्त्रे तरनिर्देशे सम स्वरा मवन्ति । उदात्तः । उदात्ततरः । अनुदात्तः । अनुदात्ततरः । स्वरितः । स्वरिते य उदात्तः सोन्येन विशिष्ट:। एकश्रुतिः सप्तमः ॥ M. Bh on P. I. 2. 33. It is possible that these seven accents which were into the seven notes of the chantings of the samans developed into the seven musical notes which have traditionally come down to the present day known as सारे गमप घनी; cf. उदाचे निषादगान्यारी अनुदाचे ऋषभयेवती। स्वित्तप्रमना हाते षड्जमध्यमपञ्चमाः। Pān. Sikṣā. The Vājasaneyi Prātis'ākhya mentions the seven accents differently; cf. उदाचादयः परे सत। यथा-अभिनिहितक्षप्र-प्रास्तिष्ट-तरोज्यञ्जन-तरोविराम-पादवृत्ताथाभाज्याः Uvvaṭa on V.Pr.I.114.

सप्ताच्यायी a term used for the first seven chapters or books of Pāṇini's grammar; cf. येन्ये सप्ताच्यायां स्वरास्ते न संगृहाता:। स्यु:। M. Bh. on P. VI 1. 158 Vārt. 1.

सम equal in number to something given; cf. यथासंख्यमनुदेशः समानाम् cf. Kāś.. on P. I. 3.10.

समन्तमद्भ a Jain scholar of great repute who is believed to have written, besides many well-known religious books such as आप्तमीमांसा गन्धहस्तिमाध्य etc. on Jainism, a treatise on grammar called Cintāmaṇi Vyākaraṇa.

समन्वयप्रदीपसंकेत a treatise on the philosophy of Vyākaraņa written as a commentary by the author देवशमेन on his own Kārikās on the subject.

समाभिन्याहार utterance together of several vocal elements or words; verbal concomitance; cf अनया परिभाषया स्त्रीप्रत्ययसमभिन्यहार तद्रहिते दृष्टानां ... पर्यातत्वमातिदिक्यते Par. Sek. Pari. 71.

समाभिहार repetition of an action; intensity of an action. पाँन:पुन्यं भृशार्थों वा समिमहार: Kāś. on P. III. 1. 22.

समय the omission of words which have already occurred before in the recital of the Pada and other Pāthas or recitals, with a view to avoiding an unnecessary repetition; cf. हएकमत्वात्समयान संद्रध्यात् सर्वशः कमे। पदेन चपदाभ्यां च प्रागवस्थेदतीत्य च।R.Pr.X.12.

समर्थ (1) having an identical sense; cf प्रोपाभ्या समर्थाभ्याम् । . . तौ चेत् प्रोपौ समर्थौ तल्यार्थी भवतः । क चानयोस्त्रल्यार्थता । आदि-कर्मणि। Kāś. on P. I. 3. 42: (2) mutually connected in meaning in such a way that the meanings are connected together or commixed together: समर्थ: शक्व: । विग्रहवाक्या-र्थाभिधाने यः शक्तः स समर्थो वेदितन्यः । अथवा समर्थपदाश्रयत्वात्समर्थः । समर्थानां संबद्धार्थानां संस्थार्थानां विधिवैदितव्यः । Kāś. on P. II. 1. 1; cf. also एकार्थीमावो ब्यपेक्षा वा सामर्थ्यम् :। (3) connected with relationship of senses, as between the activity and the subject object. instrument etc., or as between the master and the servant or the possessor and the possessed; cf. ধার: पुरुष: or ग्रामं गच्छति,or सर्पि: पिब, but not सिपें: पिब in the sentence तिष्ठत सिपें: पिब त्यमुदकम् । ; (4) capable of expressing the sense e.g. a word with the sandhis well observed; cf. समर्थोनां प्रथमाद्वा । सामर्थ्ये परिनिष्ठितत्वम् । कृतसान्धिकार्यत्वमिति यावत् । S. K. on IV. 1. 82; cf. also समर्थ: पद्र: राक्तः इति पर्याया:। शक्तत्वं च कार्योत्पादनयोग्यत्वम etc. Bālamanoramā on the above.

समर्थनीय that which can be justified; justifiable; एकेन वा द्रव्यवस्वभिति समर्थनी-यम्, Kāś. on P. V. 2. 118.

समर्थपाद name given by Sīradeva and other grammarians to the first pāda of the second adhyāya of Pāṇiniś Aṣṭādhyāyī which begins with the sūtra समर्थ: पदाविधि: P.II.1.1.

समर्थविमानित a case which is appropriate to express the sense of the tad. affix prescribed; e.g. तस्यापत्यम् । तस्येति षष्ठी समर्थविभाक्तिः; cf. P. IV.1.92; तेन रक्तं रागात् । तेनेति तृतीया समर्थविभाक्तिः; cf. P. IV. 2.1; cf.प्रकृता समर्थविभाक्तिरनुवंते तस्येदामाते । M. Bh. on P. IV. 3. 134 Vārt. 2.

समर्थसूत्र the rule समर्थः पदिविधिः P. II. । 1.1.cf. समर्थसूत्र उद्गातार इति भाष्यप्रयोगात् ।

S. K. on P.VI. 4.11.

समर्थाधिकार the province or the jurisdiction of the rule समर्थानां प्रथमाद्वा (P. IV. 1. 82), all the three words in which continue further on, and become valid in every rule upto the end of the second pada of the fifth adhyāya; cf. समर्थानां प्रथमाद्वा । त्रयमप्यधिक्षयते समर्थानामिति च प्रथमादिति च वेति च । स्वार्थिकप्रत्ययावधिश्चा- यमिकारः । प्राग्दिशो विभक्तिरिति यावत् । स्वार्थिकेषु ह्यस्य उपयोगो नास्ति । विकल्पोपि तत्रानवस्थितः । Kāś. on P.IV.1.82.

समबस्थित appearing together, presenting themselves together; cf. द्वयोहिं सावकाशयो: समवस्थितयोविंशतिषेधो भवति । M. Bh. on P. I. 1.3 Vart 6.

समवाय (1) combination as contrasted with ज्यवाय disjunction or separation; (2) the enumeration of the letters of the alphabet in a particular order so as to facilitate their combination, technically termed प्रत्याहार; cf. वृत्तिसमवायार्थ उपदेश:। का पुनर्वृतिः । शास्त्रप्रवृत्तिः । अथ कः समवायः । वर्णानामानुपूर्वेण संनिवशः । M. Bh. Ahnika 1 Vart. 15. cf. also समवाया वर्णगतः कमविशेषः । Uddyota on the Bhāṣya mentioned above; (3) contact; cf. रक्ते रागः समवाये स्वराणाम् R. Pr. XIV.24.

समसण् tad. affix समस् applied to the word इदम् to form the word ऐषमः meaning 'this year'; cf. इदमः समसण् । इदमः समसण् प्रत्यया निपात्यते संवत्सरेभिधेये। आस्मन्संवत्सरे ऐषमः। M.Bh. on P. V. 3.22 Vart. 3.

समागम concourse, coming in close quarters; cf. शङ्गसमागमे R.T. 224.

समाधान, समाधि, reply to remove the objection; conclusion.

समान common; the same; cf. समान-स्थानकरणा नासिक्योष्ट्या: । एतेषां यदेव स्थानं तदेव करणम्; V. Pr. I. 80. समानश्च खद्विगमो गम्यायां च अगम्यायां च M. Bh. on Ahnika 1. समानकर्त्रक having got the same agent; the word is used in connection with actions (क्रिया) having the same agent of the activity; cf. समानकर्त्रकेषु तुम्न P. III. 3. 158.

समानपद the same word as contrasted with भिन्नपद a compound word which consists of two or more words. cf. रबाभ्यां नो ण: समानपदे P. VIII.4.1.

समानाक्षर simple vowels or monophthongs अ, इ and उ as contrasted with diphthongs (संध्यक्षर); cf अष्टी समानाक्षराण्यादितस्ततश्रत्वारि संध्यक्षराण्युत्तराणि R. Pr. I. 11. cf. also अथ नवादितस्तमानाक्षराणि T. Pr. I. 2. Some writers of Prātiśākhyas held ऋ as संध्यक्षर and not as समानाक्षर; cf. अन्यतु मतम्-ऋकारादीनां त्रयाणां त्यस्त्यसंधिरूपत्वाभावेषि रूपद्वयसद्भावोदेषा संज्ञा न युक्तेति नवानामेवाहेति । gloss on T. Pr. I. 2.

समानाधिकरण words which have got the same individual object (द्रव्य) referred to by means of their own sense, and which are put in the same case; co-ordinate words; cf. तत्पुरुष: समानाधिकरण: कमधारय: P. I. 2.42; cf. अधिकरणशब्द: अभिधयवाची । समानाधिकरण: समानाभिषेय: । Kās. on P. I. 2.42.

समानाश्रय having got the same wording to operate on; the word is used in connection with operations which occur in the same word or wording as contrasted with न्याश्रय;cf.समानाश्रय कार्ये तदसिद्धं स्यात् S. K. on P. VI. 4.22; cf. also अंत्रेति समानाश्रयश्तिपत्त्यर्थम् Kāś. on P.VI.4.22.

समापित restoration of the resultant to the original, as for instance, restoration of the padapāṭha and the kramapāṭha to the Saṁhitāpāṭha; cf. प्रकृतिदर्शन समापत्ति: A. Pr. III. I.7.

समाम्नाय traditional enumeration or list of words or letters; cf. अक्षर- समाम्नाय, वर्णसमाम्नाय, शब्दसमाम्नाय etc.; cf. अथातो वर्णसमाम्नायं व्याख्यास्यामः V. Pr. VIII.1. अथ वर्णसमामनायः T. Pr. I.

1; cf. also समाम्नायः समाम्नातः स ब्याख्या-तब्यः Nir.I.1. समाम्नायः पाठकमः। Com. on T. Pr. I. 1.

समारोपित superimposed; secondary notion.

समावेश placing together at one place, simultaneous application, generally with a view that the two or more things so placed, should always go together although in a few instances they may not go together; cf. तदधीत तदेद। नैतयोरावस्थमः समावेदाः। भवति हि कश्चित्सं पाठं पठित न च वेति। मश्चिच्च वेति न च सं पाठं पठित। M. Bh. on P.IV.2.59;cf. also ब्याकरणिप कर्तब्यं हर्तब्यभित्यत्र प्रत्ययञ्चत्कृत्कृत्यसंज्ञानां समावेद्यो भवित M. Bh. on P. I.4.1.

समास placing together of two or more words so as to express a composite sense; compound composition; cf. प्रथगर्थानामेकार्थीमाव: समासः। Although the word समास in its derivative sense is applicable to any wording which has a composite sense (মুনি), still it is by convention applied to the समासद्वति only by virtue of the Adhikārasūtra সাক্ कडारात समास: which enumerates its province the compound words only. The Mahābhāsyakāra has mentioned only principal kinds of these compounds and defined them; cf. पूर्वेपदार्थन प्रधाने।व्ययीभावः । उत्तरपदार्थप्रधानस्तत्पुरुषः । अन्यपदार्थप्रधाना बहुबीहिः । उभयपदार्थप्रधानो इन्द्र: M.Bh. on P.II.1.6; cf. also M.Bh. on P.II.1.20, II.1.49, II.2.6, II.4.26, V.1.9. Later grammarians have given many subdivisions of these compounds as for example दिगु, कमेघारय and तत्पुरुष (with द्वितीयात-त्पुरुष, तृतीयात्पुरुष etc.as also अवयवतस्पुरुष, उपपदतत्पुरुष and so on) समानाधिकरणबह-बीहि, व्यधिकरणबहुबीहि, संख्याबहुबीहि, समा-हारद्वन्द्व, इतरेतरद्वन्द्व and so on.

समासचक a short anonymous treatise

on compounds which is very popular and useful for beginners. The work is attributed to वरहाचि and called also as समासपटल. The work is studied and committed to memory by beginners of Sanskrit studies in the Pāṭhaśālās of the old type.

समासमञ्जरी a metrical work on compounds which has no author mentioned in or assigned to it.

समासवाद (1) a short treatise on compounds by गाविन्दचक्रवर्तिन्; (2) a small compendium on compounds written by a grammarian named सार्वभाग.

समासशोभा a short treatise on compounds by यशःसागर.

समासान्त secondary suffixes which are prescribed at the end of compounds in specific cases and which are looked upon as taddhita affixes; e.g.the Samāsānta হল্ল (অ), causing elision of the last syllable of the compound word, is added to compounds called संख्याबहुत्रीहि; e.g. उपदशाः,पञ्चलाः Samāsānta अ is etc. P.V.4.73. added to compounds ending with ऋच्,पुर, अप्, and धुर,and अच् to words ending with सामन्, लोमन्, अक्षन्, चतुर् पुंस्, अनडुहू, मनस्, वर्चस्, तमस्, श्रेयस्, रह्म, उरम्, गो, तावत्, अध्वन् , etc ;under specific conditions; cf. P.V.4.68 to 85. अचु (अ) is added at the end of the tatpurusa compounds to the words অভ্যুন্তি, and रात्रि, under specific conditions; cf. P.V. 1.86, 87; टचु (अ) is added at the end of tatpurusa compounds ending in राजन्, अहन्, साखि, गो, and उरस् and under specific conditions to those ending in तक्षन्, धन्, साक्य, नौ, खारी, and अन्जलि as also to words ending in अस् and अन् in the neuter gender in Vedic Literature, and to the word नहान under specific condi-

tions; cf. P.V. 4.91 to 105; टच्च is added at the end of समाहारद्वन्द्व compounds ending in च्, छ्, ज्, झ्, ज्, दु, ब and a at the end of अन्ययोभाव compounds ending with the words शरद्, विपाश्, अनम्, and मनस etc. as also at the end of words ending in अन् or with any of the class consonants except · nasals, cf. P.V.4.106-112; গ্ৰন্থ (अ) is added to Bahuvrihi compounds ending with साक्य and अक्षि as limbs of the body, as also with अङ्गुलि, while ष, अप and अच् are added to specified words under special conditions; the Samāsānta affix असिच (अस्) is added at the end of a Bahuvrihi compound ending in प्रजा, and मेथा, the Samasanta affix इच is added at the end of the peculiar Bahuvrīhi compound formed of दण्ड, मुसल etc. when they are repeated and when they show a fight with the instruments of fight exchanged; cf. P. V.4, 113-128. Besides these affixes, a general समासान्त affix कप् is added necessarily or optionally as specified in P.V. 4.151-159.

समासान्तराब्दादेश a substitute for a word or its part at the end of a compound prescribed for certain specified words under specified conditions; e. g. ज for जान, ऊधन् for ऊधम्, धन्वन् for धनुम्, जानि for जाया, गान्ध for गन्ध, पाद् and पद्, for पाद, दत् for दन्त, कमुद् for कमुद; cf. P. V. 4.129-150.

समासान्तोदात्त the acute accent prescribed in general at the end of compounds excepting the Bahuvrihi and some specified compounds; cf. P.VI.1.223 and VI.2.1 to end.

समाहार collection, collective notion, which is one of the four senses of the indeclinable न. The collective

notion by nature being single, the dvandva compound formed of words showing such a collection takes the neuter gender and singular number affixes; cf. यदा तिराहितावयव-विवक्षा सहित: प्रधानं तदा समाहार: Siradeva Pari. 16; cf. also P. II.2,29 and II. 1.51.

समुच्य accumulation which is one of the four senses of the indeclinable च and which means the anticipation of an allied another by the express mention of one, in which sense the Dvandva compound prescribed by the rule चार्ये द्वन्द्व: does not take place; cf. समुच्च: । प्लक्षम्र इत्युक्ते गम्यत एतक्यमोधश्चेति M. Bh. on P. II. 2.29 Vart. 15.

समुदाय aggregate, totality, collection of individual members; cf. समुदाय प्रवृत्ताः शब्दाः क्षचिद्वयवेष्वपि वर्तन्ते also cf. समुदाये न्याकरणशब्दः अवयवे नोपपद्यते M.Bh. Ahnika 1 Vart. 14; cf. also समुदाये वाक्यपरिसमाप्तिः।Par.Sek.Pari.108.

समुद्देश specific individual mention or discussion; the term is used in connection with the several sections of the third Kanda or book of Bharthari's Vakyapadiya.

समुपस्थापन simultaneous presentation of different grammatical operations; cf. वसुसंप्रसारणादीनामाभाच्छा-स्त्रीयाणोमव असिद्धत्वादन्तरङ्गयोर्थुगपत्समुपस्थानं नास्तीति परिभाषा न प्रवर्तते । Kāś. on P. VI.4.22.

समुपस्थित presenting themselves simultaneously; the word is used in connection with two grammatical operations which present themselves simultaneously.

समृह aggregate, group or collection; one of the prominent senses in which the tad. affixes अण and others are prescribed. These affixes are called सामृहिक; e.g. काकम् (काकानां समृह:); similarly भेक्षम्,

राजकम्, कदार्थम्, जनता, मायूरम्, पास्या, रथ्या etc. cf. P. IV. 2.37 to 51.

संयुक् connected, the word was used by ancient grammarians in the sense of संयुक्त; cf. संयुक्त सण् R. T. 27.

सर Uṇādi affix सर mentioned in the rule तितुत्रतथसिमुसरकसेषु च P. VII. 2.7. e.g.अक्षरम्; cf. अशे: क्सरन् Uṇādi.III.70.

सरक्, सरन् (क्सरन्) Uṇādi affix सर e.g. इसरः, धूसरः, वर्सम्, तर्सम् cf. Uṇādi III. 70-77.

सरङा name of a comparatively modern lucid commentary written by Tārānātha Tarkavācaspati on the Siddhāntakaumudī.

सरस्वतीकण्ठाभरण called also सरस्वतीस्त्र. name of a voluminous grammar work ascribed to king Bhoja in the eleventh century. The grammar is based very closely on Pāṇini's Astādhyāyī, consisting of eight chapters or books. Although the affixes, the augments and the substitutes are much the same, the order of the Sūtras is considerably changed. By the anxiety of the author to bring together, the necessary portions of the Ganapatha, the Unadipatha and the bhāṣās, which the author has included in his eight chapters, the book instead of being easy to understand, has lost the element of brevity and become tedious for reading. Hence it is that it is not studied widely. For details see pp. 392, 393 Vyākaraņa Mahābhāsya Vol. VII. D. E. Society's edition.

सरूप (1) having the same form for practical purposes such as the form आ po sessed by टाप्, डाप् and चाप or the form आ possessed by the affixes अण्. अच्, च, क, ण and others; (2) having the same form even literally, but possessed of different senses; e.g. the words माष, अञ्च, पाद etc.;

समानानामेकरोष इत्युच्यमाने यत्र सर्वे समानं राज्दोर्थश्च तत्रेव स्यात् । वृक्षाः एठक्षाः इति । इह न स्यात् । अक्षाः पादाः माषाः इति । रूपप्रहणे पुनः क्रियमाणे न दोषो भवति । M. Bh. on P. I. 2.64.

सर्वत्र lit. at all places, on all occasions; the word is used in connection with an essential application of a rule and not optionally in some cases; cf. सर्वत्र लोहितादिकतन्तेम्यः। पूर्वेण नित्ये प्राप्ते विकल्पार्थ वचनम् Kās. on P. IV. 1.18; cf. also प्रत्यये माषायां नित्यवचनम् P. VIII.4.45 Vārt. 1, सर्वत्र शाकल्यस्य VIII. 4.51. etc.

सर्वथा at all costs, in any case, in all places; cf. सर्वथावरकालेव M. Bh. on P. I. 1.69 Vārt 4; cf. also तथा तेषां घोषिण: सर्वथोष्मीभ: XII.2.

सवेनामन् pronoun; lit. standing for any noun. There is no definition as such given, of the word pronoun, but the words, called pronouns, are enumerated in Pānini's grammar one after another in the class or group headed सर्व (सर्व, विश्व, उम, उभय, words ending in the affixes डतर and डतम, अन्य etc.) which appear to be pronouns primarily. Some words such as पूर्व, पर, अवर, दक्षिण, उत्तर, अपर, अधर, स्व, अन्तर etc are treated as pronouns under certain conditions. In any case, attention has to be paid to the literal sense of the term सर्वनामन which is an ancient term and none of these words when standing as a proper noun, is to be treated as a pronoun; cf. सर्वादोनि सर्वनामानि P. I.1. 27. cf. also संज्ञोपसर्जनीभूतास्तु न सर्वोदय:: M.Bh. on P. I. 1, 27 Vart. 2; (2) The word सर्वनामन् means also a common term, a general term; cf. एकश्रुतिः स्वरसर्वनाम, यथा न्पंसकं लिङ्गसर्वनाम M. Bh. on P. VI. 4.174 Vart 4.

सर्वनामस्थान a term used in Pāṇini's grammar, for the first five caseaffixes मु, ओ, अस, अम् and ओ as also for the nom. and acc. pl. affix इ (शि) of the neuter gender. The term appears to be an old one, which was used, by a specific mention, for the first five case-affixes which caused a special change in the base before them in the case of many words; cf. शि सर्वनामस्थानम् । मुझनपुस्तरस्य P.I.1.42-43. For details see Vyākaraṇamahābhāṣya Vol. VII. D. E. Society's ed. p. 239 footnote.

सर्वनिघात grave accent (अनुदात्त) for the whole word, generally for a verbal form or a word in the vocative case, if preceded by another word which is not a verb. The term is used in contrast with राष्ट्रियात the grave accent for the remaining vowels of a word when a particular vowel is definitely fixed as an acute or an independent Svarita or circumflex; cf. P.VIII. 1.28 to 74.

सर्वपदादेश a substitute for the entire word and not for a part of it. This doctrine of सर्वपदादेश everywhere is advocated by grammarians in consonance with their doctrine of शब्दनित्यत्व; cf. सर्वे सर्वपदादेशा दाक्षीपुत्रस्य पाणिनेः । एकदेशिवकारे हि नित्यत्वं नोपपद्यते ॥ M.Bh. on P. I. 1. 20, VII.1.27.

सर्वप्रतिषेध a general prohibition of every grammatical operation that presents itself; cf. नान्तः पादमिति सर्वप्रतिषेध: | M.Bh. on P.VI.1.115.

सर्वप्रसङ्ग a presentation of all the substitutes for all the original ones indiscriminately; an application in all cases irrespective of any special consideration; cf. स्थानिन एकत्वनिर्देशादनेकादेशनिर्देशाच सर्वप्रसङ्ग: M.Bh.on P. I. 1. 50 Vart, 1 and 12; cf. also M.Bh. on P.I.1.60, I.3.2, 3,10 etc.

सर्वप्रातिपदिक any noun-base irrespective of any discrimination; cf. अपर आह सर्वप्रातिपदिकेश्य आचारे किञ्चक्तव्याश्वति गर्दभतीत्येवमर्थम् M.Bh. on P. III.1.11 Vārt. 3.

सर्वमङ्गळा a commentary on Nāgeśa's Paribhāṣenduśekhara written by a grammarian of the nineteenth century named देशवामन् or मनीशिदावदामन्. The work is incomplete.

सर्वमुखस्थान the whole orifice of the mouth as a place of utterance, as for example for the vowel अ; cf. सर्वमुखस्थानमवर्णमेक इच्छन्ति । M.Bh. on P. I. 1.9 Vart. 2.

सर्वरक्षित spelt as श्वरक्षित also; a Buddhist grammarian who is believed to have redacted or revised the grammar work Durghatvṛtti of Saraṇadeva.

सर्वलकार the personal affixes in general pertaining to all the ten lakāras लट्, लिट् etc., cf. सर्वलकाराणामपवाद: । Kās.on P.III. 3.144.

सर्विछिङ्गता use in all the genders; cf. सर्विछिङ्गता च वक्तव्या । ब्राह्मणार्थे प्यः । ब्राह्मणार्थे स्पः । ब्राह्मणार्थे यवागूः ।

सर्वेळोप the elision of the entire wording instead of the final letter only, which is prescribed by P. I.1. 52, cf. तु: सर्वस्य लोपो वक्तब्य: अन्त्यस्य लोपो मा सदिति। M Bh. on P. VI. 4.154.

सर्वचर्मन spelt as शर्ववर्मन् also, the reputed author of the Kātantra Vyākaraṇa. He is believed to have been a contemporary of the poet Guṇāḍhya at the Śātavāhana court, and to have revised and redacted the Kātantra Sūtras already existing for the benefit of his patron. With him began the Kātantra school of grammar, the main contribution to which was made by दुर्गसिंह who wrote a scholarly gloss on the Kātantra Sūtras. For details see कातन्त्र,

सर्वविभक्त्यन्त lit. ending with all cases; the term is used as an adjective of the word समास and refers to a compound which can be dissolved by putting the first member in any case; cf. सर्वविभक्यन्त: समासो यथा विज्ञायत। अल: परस्य विधि:; अलि विधि-रित्याद M. Bh. on P.I.1.56.

सर्वस्यहेपाद conventional name given to the first pada of the eighth adhyaya of Paṇini's Aṣṭādhyayī which begins with the Sūtra सर्वस्य द्व VIII.1.1.

सर्वादि lit. a group or a class of words beginning with the word सर्व as the first word in the list; the term is used in general as a synonymous term with Sarvanāman; cf. संज्ञोपसर्जनाभ्तास्त न सर्वादय: Kāś. on P.I.1.27.

सर्वादेश a substitute for the entire wording instead of the final letter as prescribed by the rule अल्लान्यस्य P.I.1.52; cf. अनेकााल्दीत्सर्वस्य P.I.1.55.

सर्वानुदात्त the grave accent for the entire word. See सर्वनिधात.

सर्वान्त्य final of all those that are denoted or enumerated; cf. यदेव सर्वान्त्यमर्थादेशनं तस्यैव विषये स्यात् । M.Bh. on F. IV.2.67.

सर्वोपसर्जन all the constituent members of which (compound) are subordinated to quite a different word and not mutually in the manner of one member to another. The Bahuvrihi compound, as contrasted with other compounds, is described to be such an one, as all its members are subordinate in sense to another word; cf. यस्य सर्वे अवयवा उपर्यजनीभ्ता: स सर्वोपसर्जनी बहुवीहिर्गहाते। Kāś. on P.VI. 3.82.

सर्वोपाधिव्यभिचारार्थ a term used by the authors of the Kāśikā in connection with the application of a rule irrespective of all limitations and not of any one limitation: cf. अन्यभ्योपि दृश्यते । आपिशब्द: सर्वोपाधिन्यभि-चारार्थ: Kāś. on P.III. 2.75;cf. also Kāś. on P.III.1.32, III.2.101, VII. 1.38.

सिछिङ्ग inclusive of the notion of gender; the word is used in connection with the sense of a Prātipadika or a crude base as inclusive of the notion of gender and number; cf. अर्थप्रहणस्येतत् प्रयोजनं कृत्सनः पदार्थो यथाभिघीयेत सद्रव्यः सालिङ्गः ससंख्यश्चेति । M. Bh. on P. II. 2 24 Vārt. 8.

सवचन with the notion of number included in the sense of the base itself; see सलिङ्ग.

स्वर्ग belonging to the same class of letters; cf. उता स्वर्ग: । उकारेण लक्षित आदि: सह वर्गेण प्राह्य: । चो: कु: । Cāndra I. 1. 2.

सवर्ण cognate, homophonic; a letter belonging to the same technical category of letters possessing an identical place of utterance and internal effort; cf. तुल्यास्यप्रयत्नं सवर्णम् P. 1. 1. 9. For example, the eighteen varieties of आ, due to its short, long and protracted nature as also due to its accents and nasalization, are savarna to each other. The vowels and ऌ are prescribed to be considered Savarna although their place of utterance differs. The consonants in each class of consonants are savarna to one another, but by the utterance of one, another cannot be taken except when the vowel 3 has been applied first. Thus the 玉 stands for क्, ख़, ग्, घ़ and ङ्. cf. तुल्यास्यप्रयत्नं सवर्णम् P. 1, 1. 9 and अणुदित्सवर्णस्य चाप्रत्यय: P. I. 1. 69.

सवर्णग्रहण taking or including the cognate letters; a convention of

grammarians to understand by the utterance of a vowel like अ, इ or उ all the 18 types of it which are looked upon as cognate (सवर्ण), as also to understand all the five consonants of a class by the utterance of the first consonant with उ added to it; e. g. कु denoting all the five consonants क्, ख़, ग, च and ङ्; cf. अणुदिस्सवर्णस्य चाप्रस्य : P.I. 1.69.

सवर्णदीर्घ the lengthened form of a vowel which is substituted for two cognate vowels coming near each other; cf. अक: सवर्ण दीर्घ:. P. VI. 1. 101.

सविध of the same kind; having the same accent.

सविभाक्तिक with the suitable case-affix added; cf. प्रयाजा: सविभाक्तिका: कार्याः M. Bh. in Ahnika I.

ससंख्य possessed of the same number एकवचन, द्विवचन or बहुवचन; cf. कृत्सनः पदार्थोभिधीयेत सद्रब्यः सल्लङ्गः ससंख्यः। M. Bh. on P. II. 2. 24 Vart. 8.

सस्थान having got an identical place of utterance; the word is much used in the Prātisākhya works; cf. सरवानेन घोषिणां घोषिणेव R. Pr. XIII. 5.

सस्थानतर more sasthana i. e. nearer among those that have the same sthana or place of production; cf. ननु च एङ: सस्थानतरे अधिकाराधींकारी M. Bh. on P. I. 1.48 Vart. 3.

the term is used in connection with a consonant as connected with a vowel for purposes of syllabication, the vowel being either the previous one or the succeeding one.

सहचारित going together; occurring together; e. g. विषयम्यां जेः (where परा is taken as the preposition परा and not the pronoun परा which is the fem. base of पर on account of the paribhasa सहन्दरितासहन्वरितयोः सहन्व-

रितस्यैव प्रहणम्); cf. Pari. Śek. Pari. 103.

सहिववक्षा the same as युगपद्विवक्षा, the desire to put quite closely with each other; cf. सहिववक्षायामेकराष: । युगपद्विवक्षायामेकराषे । युगपद्विवक्षायामेकराषे भवितब्यम् M. Bh. on P. I. 2.64 Vart 19, I. 2.105 Vart. 5.

सहोक्ति simultaneous expression of words as found in the Dvandva compound; cf. सहोक्ती द्वन्द्व: Hem. III. 1.117.

सांख्य a rule or a topic concerning number; cf. यदि तिई कृत्स्न; पदार्थोभि-धायते छैङ्गाः सांख्याश्च विधयो न सिध्यन्ति, M. Bh. on P. II. 2 24 Vārt. 8,9.

सांग्रहस्तिक a student of संग्रहस्त्र; the word occurs in the Māhābhāṣya along with वार्तिकस्त्रिक, and it may therefore mean a student of the stupendous work named the Samgraha of ज्यांडि which is believed to have consisted of small numerous sūtralike assertions, with an exhaustive gloss thereon. See संग्रह.

सांन्यासिक lit. placed as a deposit, i.e. without any special purpose for the time being; the word is used in connection with a word in a rule which apparently is superfluous; cf. तदेति जित्यप्रहणं सांन्यासिकं तिष्ठत तावत् M. Bh. on P. VII. 1.81; cf. also M. Bh. on III. 2.107, VI. 1.8; VII. 2.86.

सांप्रतिक (1) what is actually expressed or found in the context; cf. सांप्रतिकाभावे भूतपूर्वगतिर्विज्ञायते M. Bh. on P. VI. 1.177 Vārt. 1; (2) original, found in the original context or Prakṛti; cf. सांप्रतिके प्रकृतिस्थे कण्ठे सित हकारो नाम बाह्य: प्रयत्न: कियते T. Pr. II. 6; (3) of the present time; cf. Purus. Pari. 15.

सांहितिक original, as belonging to the Samhitāpātha of the Sūtras and not introduced for some additional purpose without forming a part

of the actual affix; cf. आकर्षात् ष्ठल्। इह केषां चित्साहितिकं षत्वं केषांचित्रिदर्थम् M. Bh. on P. IV. 4.9.

साकच्क together with the affix अकच् which is inserted in a pronoun after its last vowel; cf. साकच्काद्रा सावीच्वप्रतिषेषी वक्तव्य:। असकी असुक:। M. Bh. on P. VII. 2.107; cf. also किम; क:। साकच्करयाप्ययमोदश:। Kaś. on P. VII. 2.108.

साकाङ्क्ष possessed of an expectancy in meaning; cf. भेवत् पूर्व परमाकाङ्क्षतीति साकाङ्क्षं स्थात्परं तु कथं साकाङ्क्षम् M. Bh. on P. III. 2.114.

सागमक possessed of the augment; cf. अनागमकानां सागमका आदेशा: M. Bh. on P. I. 1.20 Vart. 5, also on P. I. 1.46; cf. also the verse सर्वे सर्वपदादेशा दाक्षीपुत्रस्य पाणिने: । एकदेशिवकारे हि नित्यत्वं नेपपदाते । quoted in the Mahābhāsya to support the view that augments are not inserted, but a word with an augment replaces a word without that augment; cf. M. Bh. on P. I. 1.20 Vārt 5.

साति (1) tad. affix in the sense of entirety with respect to the occurrence of a thing where it was not before. e. g. उदकसाद्भवति लगणम्, अभिसाद् भवति cf. P. V. 4.52, 53; (2) tad.affix in the sense of 'handing over' or 'entrusting'; e.g. राजसाद् भवति, बाह्मणसात् करोति, cf. P. V. 4.55.

सास्व of a substantive, belonging to the object; cf. सन्वस्य इदम् । अपि वा मेदसश्च परोश्च सान्वं द्विवचनं स्यात्। Nir. VI. 16.

साधक instrument of an activity; ci. सर्वणि कारकाणि साधकानि M. Bh. on I. 1.42; cf. also साधकं निर्वर्तकं कारकसंद्रं भवतीति वक्तन्यम् M. Bh. on I. 4.23. See the word कारक above.

साधकतम most efficient in the accomplishment of an action; the kāraka called Karaṇa; cf. साधकतमं करणम्। P. I. 4.42. See the word करण.

साधन the same as साधक or कारक which see above; cf.साधनं च कियायाः I कियाभावात्साधनाभावः M. Bh. on P. I. 3. I. Vart. 1; cf. also पूर्वे धातुः साधनेन युज्यते पश्चादुपसर्गेण and its opposite maxim also, पूर्वे धातुः स्पत्रस्पत्रांण युप्यते पश्चात्साधनेन M. Bh. on P. VI. 1.135. Vart. 9. cf. also Siradeva pari. 128, 129.

स्ताधारण common, conveying a common notion; cf. साधारणान्युत्तराणि षट् दिनश्चादित्यस्य च Nir II. 13.

साधुसुन्द्र a scholar of grammar who was a pupil of साधुकीर्तिप्रवर and who wrote a short work on grammar named उक्तिरत्नाकर.

सानुनासिक nasalized; uttered partly through the nose; cf. सान्ते हि यण: सानुनासिका निरनुनासिकाश्च M. Bh. on P. VI. 1. 67.

सानुबन्ध or सानुबन्धक an affix or a root or the like, to which a mute letter has been attached; cf. निरनुबन्धकप्रहणे न सानुबन्धकस्य ग्रहणम् Par. Sek. Pari. 81.

सापनादक an injunction accompanied by a rule or rules of exception. It is a convention that an injunctive rule gets its sense completed when prohibitions or exceptions to it have been fully considered; hence the convention runs, प्रकल्प्य नापनादनिषयं तत उत्सर्गोभिनिश्चित । Par. Sek. Pari 63; cf. also सापनादक: स विधिरयं पुनर्निरपनादक: M. Bh. on P. IV. 3. 155, VI. 2. 177; VIII. 1. 68.

बापेक्ष with an expectancy in sense; although in grammar expectancy is at the root of, and forms a sort of a connecting link for, the various kinds of relations which exist between the different words of a sentence which has to give a composite sense, yet, if a word outside a compound is connected with a word inside a compound, especially with a second

or further member. the sense becomes ambiguous; and expectancy in such cases is looked upon as a fault; e. g. अप्रविष्टविषयो हि रक्षसाम् Raghu XI. When, however, in spite of the fault of expectancy the sense is clear, the compound is admissible; cf. यदि सावेश्रेषणानां वृत्तिर्न वृत्तस्य वा विशेषणं न प्रयुज्यते इत्युज्यते देवदत्तस्य गुरुकुलम् देवदत्तस्य गुरुपुत्रः,अत्र वृत्तिर्न प्राप्नोति। अगुरुकुलपुत्रादीनामिति वक्तन्यम् । M. Bh. on P II.1.1; cf. also the expression सापेक्षत्वेपि गमऋत्वात्समास: often used by commentators.

साप्तामिक prescribed in the seventh chapter or Adhyāya of the Astādhyāyi; cf.साप्तामिक आर्घधातुकस्योडित पुनरयं भवति। M.Bh. on P.VI.4.62, साप्तमिके पूर्वसर्वणे कृते पुनः बाष्टिको भविष्यति। M.Bh. on P.VI.1.70.

साप्य furnished with आप्य or object; a transitive root; the term is used in the Śākaṭāyana, Haimacandra and Cāndra grammars; cf. Cāndra I.4.100, Hema. III.3.21, Śākaṭ. IV. 3.55.

साभ्यास together with the reduplicative syllable; cf. उमौ साभ्यासस्य P. VIII. 4. 21.

साम् the case-ending(आम्) of the genitive plural with the augment स् prefixed; cf. साम आक्रम् P.VII. 1.33.

सामतन्त्रस्थाकरण an anonymous ancient work of the type of the Prātisākhya works dealing with the euphonic changes and accents in the padapāṭha of the Sāmaveda.

सामन equalization of tones; cf. नर्णानां मध्यमन्त्रयोचारणम्।

सामध्ये lit. capacity of a word to express its sense; the word is, however, used rather technically, as derived from समर्थ, in the sense of compositeness; cf. तत्र एकार्थीमाव: ज्येपेक्षा वा सामध्येम्। M.Bh.on P.II.1.1. See समर्थ above. The word is also

used in the sense of 'conformity in sense' or 'connectedness'; cf. इसुसो: सामर्थ्ये P.VIII. 3.41; cf. also उपसर्ग: सामर्थ्ये R. T. 105; cf. also R. T. 98 and 130.

सामवश name of a Samdhi or euphonic change of the type of the vowels अ, इ and उ being lengthened in some specified cases chiefly for the sake of music (साम) or metre. This lengthening is given the name ज़ित in the Rk Prātiśākhya; cf. दीर्घ हरवी ब्यझनेन्यस्वृकाराद् यथादिष्टं सामवश; स सन्धि: | R. Pr.VII.1.

सामवेदप्रातिशाख्य name of a Prātiśākhya work on Sāmaveda. It is probable that there were some Prātisākhya works written dealing with the different branches or Śākhās of the Sāmaveda, as could be inferred from indirect references to such works. For instance in the Mahabhasya there is a passage " ननु च भोक्छन्दे।गानां सात्यमुप्रिराणायनीयाः अर्धमेकारमर्धमोकारं चाधीयते । . . पार्षदकृतिरेषा तत्रभवताम् " which refers to such works. At present, however, one such common to the several branches of the Sāmaveda, called Rktantra is available, and it is called Sāmaveda Prātiśākhya. It is believed to have been written by औदन्रजि and revised by शाकटायन.

सामानाधिकरण्य standing in apposition; the word is used many times in its literal sense 'having the same substratum.' For instance, in चर्ट करोति देवदत्तः, the personal ending ति and देवदत्त are said to be समानाधिकरण. The Samānādhikaraṇa words are put in the same case although, the gender and number sometimes differ. See the word समानाधिकरण.

लामान्य lit. resemblance in any one or many respects. In the Nirukta the word is used in the sense of resemblance between the word to be derived, and any form of a root; the term refers there to grammatical resemblance and may therefore mean grammatical consideration in general; cf. अविद्यमाने सामान्येप्यक्षरवर्णसामान्य त निर्ह्मयात् Nir.II.1.

सामान्यग्रहण mention of a term in such a general way as would include some varieties or specific forms of it to which the expression put is common; e.g. the word आप् (fem. affix) for the affixes टाप्, डाप् and चाप्; cf. सामान्यग्रहणायों णकार: M.Bh. on P.III. 1.30; cf. also च्लयुत्सर्ग: सामान्यग्रहणार्थ: P. III. 1.43 Vārt. 1.

सामान्यग्रहणाविद्यात the preservation of the inclusion of two or more terms by such a wording as is common to those two or more terms; e. g. ङ्गी for ङ्गिप्, ङ्गिष् and ङ्गिन्; आप् for टाप्, डाप् and चाप्; cf. अथवा अवस्यमत्र सामान्यग्रहणाविद्यातार्थः ककारोनुबन्धः कर्तब्यः। M. Bh. on P. III, 1.83 Vart. 7. The phrase सामान्यग्रहणाविद्यातार्थं is very frequently used in the Kāśikāvṛtti.

सामान्यभविष्यत् future tense in general; the general future tense expressed by the verb-endings substituted for लूट. There is also the term गुद्धभविष्यत् or भविष्यन्ती used in the same sense; cf. लूट् रोपे च। रोषे गुद्धे भविष्यिति काल घातीर्लृट् प्रत्यया भविति। Kāś. on P. III. 3.13.

सामान्यविशेषभाच the relationship between the general and the particular, which forms the basis of the type of apavāda which is explained by the analogy of तककी। णिडन्यन्याय; the word also refers to the method followed by the Sūtras of Pāṇini, or any treatise of grammar for the matter of that, where a general rule is

prescribed and, for the sake of definiteneess some specific rules laying down exceptions, are given afterwards: cf. किंन्तित्सामान्यविशेषवस्त्रशं प्रवर्त्य येनात्येन यत्नेन महत: राद्वीधान् प्रतिपद्यस् । M. Bh. Ähnik 1.

सामान्यविद्धित a general rule, a rule laid down in general which is restricted by special rules afterwards; cf. बाधकेनानेन मित्रत्वयं सामान्य-विहितस्य विदेशिषविहितेन M. Bh. on P. II. 1.24 Vart. 5, cf. also M. Bh. on III.1.94, III. 2.77 etc.

सामान्यातिदेश extended application of a thing to others in general; cf. सामान्यातिदेश विशेषानतिदेश: I तेन अनदातन्भूतरूप विशेष विशिष्तयोर्ङ् छिटोर्न 'भूतव्य' (3.3.932) इत्येननातिदेश: I Pāri. Sek. Pāri. 101.

सामान्यातिदेशपरिभाषा name given to the Paribhāṣā सामान्यातिदेशः विशेषानितदेशः Pāri. Sekh Pāri. 101.

सामान्यापेक्ष refering only to a general thing indicated, and not to any specific instances. The word is used in connection with a Jmapana or indication drawn from the wording of a rule, which is taken to apply in general to kindred things and rarely to specific things; cf. इदं च सामान्यापेक्ष ज्ञापकं भावतिकापि पूर्वमुख्यते: | Pari. Sek. on Pāri. 50.

सामान्याभिघान denotation of the genus factor of a word, as contrasted with द्रव्याभिघान denotation of the individual object; cf. तद्यदा द्रव्याभिघान तदा बहुवचन भविष्यति, यदा सामान्याभिधानं तदैकवचनं भविष्यति M. Bh. on P. I. 2. 58 Vart. 7.

सामासिक pertaining to a compound; found inside a compound; cf. मा भूतां यासौ सामासिकी विभक्तिस्तस्याम, यासौ समासिक्रिमिक्तिस्तस्यां भविष्यतः। M.Bh. on P. VII.1.1; cf. also सामासिक्छकः अप्राप्त्या etc. Par. Sek. on Pari. 56.

सामूहिक name given to tad. affixes prescribed in the sense of collection (समूह) by the rule तस्य समूह: and the following ones; P.IV.2.37. to 51.

साम्य similarity, homogeneity: described to be of two kinds- in words and in sense; cf. किं पुन: शब्दतः साम्य संख्यातानुदेशो भनत्याहोस्विदयतः M. Bh. on P. I. 3. 10 Vart 3; cf. also स्थानकरण-कालादिभिः तौल्यम् T. Pr XXIV. 5.

सायण, सायणाचाये the celebrated Vedic scholar and grammarian of Vijayānagar who flourished in the 14th century and wrote, besides the monumental commentary works on the Vedas, a grammatical work on roots and their forms known by the name माधवीया धातुवृत्ति. As the colophon of the work shows, the Dhātuvrtti was written by Sāyaṇācārya, but published under the name of Mādhava, the brother of Sāyanacārya; cf. इति महामन्त्रिणा मायणसु-तेन माधवसहोदरेण सायणाचार्येण विरचितायां माधवीयायां धातुवृत्तौ...Mādhavīyā Dhātuvṛtti at the end; cf also तेन मायणपत्रेण सायणन मनीषिणा । व्याख्येया माधवी चियं धातुवृत्तिार्वरच्यते । Mād. Dhātuvṛtti at the beginning.

सारङ्गकि name of a grainmarian, the writer of प्रयुक्ताख्यातमञ्जरीसारसंप्रह.

सारप्रदीपिका name of a commentary by Jagannātha on the Sārasvata grammar,

सारसत्वरी name of a grammar work written by Kavicandra.

सारसिद्धान्तकामुदी the same as लघुसिद्धान्त-कोसुदी. See लघुकोसुदी.

which was once very popular on account of its brevity, believed to have been written in the sutra form by an ancient grammarian named Narendra who is said to have composed 700 sutras under

the inspiration of Sarasvatī. The exposition of these Sūtras by a reputed grammarian named Anubhūtisvarūpācārya who possibly flourished in the thirteenth century A. D., is known by the name सारखनमाकिया which has remained as a text book on grammar to the present day in some parts of India. This प्रक्रिया is popularly known as सारखनाज्याकरण. The technical terms in this grammar are the current popular ones.

सारस्वतदीका name in general given to commentary works on the Sārasvata Vyākarana out of which those written by Rāmanārāyaṇa, Satyaprabodha, Kṣemamkara, Jagannātha and Mahīdhara are known to scholars.

सारस्वतपरिभाषा a grammar work of the Sārasvata school written by Dayāratna in explanation of the technical rules giving conventions and maxims.

सारस्वतप्रक्रिया the popular name given to the gloss by Anubhūtisvarūpācārya on Narendra's grammar rules. See सारखत above.

सारस्वतप्रक्रियादीका see सारस्वतदीका above. सारस्वतभाष्य a critical gloss on the Sārasvata grammar by a grammarian named Kāsīnātha.

सारस्वतक्याकरण see सारस्वत above.

सारस्वतसार a work giving a short substance of the Sārasvata Vyākaraņa with a commentary named Mitākṣarā on the same by Harideva.

सारस्वतिसद्धान्तचिन्द्रिका a work on the Sārasvata Vyākaraņa by a grammarian named Rāmāśrama.

सारस्वताख्यातदीपिका a work on the Sārasvata Vyākaraņa by Sūrasimha.

सारावळी or सारावळी-व्याकरण an independent treatise on grammar by Nārāyaņa Vandyopādhyāya.

सारासारिववेक name of a commentary on Nāgeśa's Paribhāṣenduśekhara written by बालशास्त्री रानडे,the stalwart grammarian of the nineteenth century at Vārāṇasī.

सार्थक lit. possessed of sense; significant, as contrasted with निर्थक; cf. इतरे च सार्थका; Rk. Prati. XIII. 9.

सार्वकालिक denoting time, irrespective of its divisions such as the past, the present and the future; e. g. the kṛt affixes prescribed by rules before P. III 2.84; cf. अत: सार्वकालिका विषयो वेदितन्याः Kāś. on P. III. 2.83.

सावेधातक a term used in Pānini's grammar for affixes applied to verbs, such as the personal endings and those krt affixes which are marked with the mute letter হা; cf. বিভূ-शित्सार्वधातुकम् P. III. 4. 113. The term was taken into his grammar by Pānini from ancient grammar works and thence in their grammars by other grammarians; cf. सार्वधातुकमिति पूर्वाचार्यप्रसिद्धा संज्ञेयं निरन्वया, स्वभावान्नपुंसकलिङ्गामिति । Trilok-com. on Kāt. III. 1.34. The term सार्वधातका also was used by ancient grammarians before Pāṇini; cf. আণিয়-लास्तुरुस्तुराम्यमः सार्वधातुकासु च्छन्दसीति पठन्ति. Kāś. on P. VII. 3.95.

सार्वनामिक lit. pertaining to pronouns; the term is used in connection with rules or operations concerning exclusively the pronouns; cf. नान्यत्सार्वनामिकम् । Kāt. II. 1.33.

सार्वभौम a grammarian of the eighteenth century who wrote a very brief critical work on compounds named समासवाद.

सार्वविभक्तिक pertaining to all cases, i. e. prescribed to convey the sense of all case affixes; the term is commonly used by commentators with reference to the tad. affix

तस् prescribed by the rule प्रतियोगे पञ्चम्यास्तिस: and the Varttika तिस-प्रकरणे आद्यादिम्य उपसंख्यानम् thereon: cf. P. V. 4.44 and Vart. 1.

सावकाश possessed of scope for its application as contrasted with निरवकाश; a term used in connection with a rule which has got its application to some cases without conflict with any other rule; cf. द्वेगीई सावकाशयो: समवस्थितयोविंप्रतिषेधो मवति। M. Bh. on P.I.1.3 Vart. 6.

सावण्ये the quality of being cognate or allied; see the word सवर्ण above.

साज्यय together with avyaya or indeclinable; cf.आख्यातं साज्ययं वाक्यम्। उच्चैः पठति । नीचैः पठति । M. Bh. on P. II. 1. 1 Vart 9.

साहचर्य presence together, mention together, association; this साहचर्य is many times of use in cases of doubt regarding the meaning of a word or the choice of a word in a particular sense; cf. अथवा साहचर्याताच्छन्यं भविष्यति । M. Bh. on P. I.1. 70, I 2. 27; cf. सहचरितो येथ-स्तस्य गतिभीविष्यति साहचर्यात् ; M. Bh. on P. I. 2. 51 Vart. 3.

सि (1) personal ending सिप् of the sec. pers. sing.; cf. तिप्तस्झिसिप्थस्थ-..महिङ् P.III.4.78; (2) Uṇādi affix क्सि (सि) cf. छाषेकुषिग्राषम्य: क्सि: Uṇ. III. 155.

सिंहावलोकितन्याय the analogy of the backward look peculiar to a lion, who, as he advances, does always look back at the ground covered. The word is used in grammar with reference to a word taken back from a rule to the preceding rule which technically is called अपकर्ष; cf. वक्ष्यमाण विभाषाग्रहण।मेह सिंहावलोकितन्यायेन संवस्थते Kāś. on P.III.3.49.

सिच् one of the substitutes (स्) for the general sign िल्ल of the aorist tense (छुड्); cf. िल्ल छुडि। च्ले; सिच् P. III.1. 43, 44.

सिचिपाद name given by convention to the second pada of the seventh adhyāya of Pāṇini's Aṣṭādhyāyī as the pāda begins with the sūtra सिचि बृद्धि; परसीपदेषु. P. VII. 2. 1.

सित an affix marked with the mute letter स signifying the designation पद for the preceding base to which that affix has been added; for examples where such affixes are noticed, see the words भवदीय:, जगीयु:, कालिय:, पार्श्वम्: cf. सिति च P. I. 4. 16.

सिद्ध (1) established; the term is used in the sense of नित्यor eternal in the Vārttika सिद्धे शब्दार्थसंबन्ध where, as Patanjali has observed, the word सिद्ध meaning नित्य has been purposely put in to mark an auspicious beginning of the शब्दानशासनशास्त्र which commences with that Varttika; cf. माङ्गालिक आचार्यो महतः शास्त्रीघस्य मङ्गलार्थे सिद्धशब्दमादितः प्रयुङ्क्ते M.Bh.on Ahnika 1; (2) established, proved. formed; the word is many times used in this sense in the Mahābhāsya, as also in the Vārttikas especially when a reply is to be given to an objection; cf. P.I. 1.3 Vārt. 17, I. 1. 4. Vārt. 6; I. 1. 5. Vārt.5,I.1.9 Vārt. 2 etc.

सिद्धनाण्ड the chapter or portion of Pāṇini's grammar which is valid to the rules inside that portion, as also to the rules enumerated after it. The word is used in connection with the first seven chapters and a quarter of the eighth chapter of Pāṇini's Aṣṭādhyāyī, as contrasted with the last three quarters called त्रिपादी, the rules in which are not valid to any rule in the preceding portion, called by the name सपासतास्थायी or सपादी as also to any preceding rule in the Tripādī itself; cf. पूर्वत्रासिद्धम् P. VIII.2.1.

सिद्धनिद्दन an ancient Jain sage who is believed to have written an original work on grammar.

सिद्धहमचन्द्र a title given to his grammar by Hemacandra himself, which subsequently came to be called हैमशब्दानुशासन or हैमब्याकरण. For details see हेमचन्द्र.

सिद्धान्त established tenet or principle or conclusion, in the standard works of the different Shāstras.

सिद्धान्तकोमदी a critical and scholarly commentary on the Sutras of Pānini, in which the several Sūtras are arranged topicwise and fully explained with examples and The work is counter examples. exhaustive, yet not voluminous, difficult yet popular, and critical vet lucid. The work is next in importance to the Mahābhāsya in the system of Pāņini, and its study prepares the way for understanding the Mahabhasya. It is prescribed for study in the courses of Vyākaraņa at every academy and Pathasala and is expected to be committed to memory by students who want to be thorough scholars of Vyākarana. By virtue of its methodical treatment it has thrown into the back-ground all kindred works and glosses or Vrttis on the Sūtras of Pānini. It is arranged into two halves, the first half dealing with seven topics (1) র্বরাণ্যিমানা, (2) पञ्चसंधि, (3) षड्लिङ्ग, (4) स्त्रीप्रत्यय, (5) कारक, (6) समास, (7) तद्धित, and the latter half dealing with five topics, (1) दशगणी, (2) द्वादश-प्रक्रिया (3) कृदन्त (4) वैदिकी and (5) स्वर. The author भट्टोजीदीक्षित has himself written a scholarly gloss on it called श्रोदमनारमा on which, his grandson, Hari Diksita has written a learned commentary named लघुशब्दरत्न or simple शब्दरत्न. The Siddhantakaumudi has got a large number of commentaries on it out of which, the commentaries प्रौदमनोरमा, बालमनोरमा, (by वासदेव-दीक्षित) तत्त्वबेगधिनी and लघुशब्देन्दुशेखर are read by almost every true scholar of Vyākarana. Besides these four, there are a dozen or more commentaries some which can be given below with their names and authors (1) सुबा-धिनी by जयकृष्णमानि, (2) सुबोधिनी by रामकृष्णभट्ट (3) बृहच्छब्देन्दुदोखर by नागेदा. (4) यालमनारमा by अनन्तपण्डित, (5) वैयाकरणसिद्धान्तरहस्य by नीलकण्ठ, रत्नार्णव, by कृष्णमिश्र (7) वैयाकरणसिद्धान्त-रत्नाकर by रामकृष्ण, (8) सरला by तारा-नाथ,(9) सुमनोरमा by तिरुमछ,(10)सिद्वान्त-कौमुदीव्याख्या by लक्ष्मीनृसिंह, (11)सिद्धान्त-कौ मुदी न्या स्या by विश्वेश्वरतीर्थ, (12) रत्नाकर by शिवरामेन्द्रसरस्वती and (13) प्रकाश by तोलापदीक्षित. Although the real name of the work is वैयाकरणसिद्धान्ततकोमुदी, as given by the author, still popularly the work is well known by the name सिद्धान्तकौमुदी. The work has got two abridged forms, the Madhyakaumudi and the Laghukaumudī both written by Varadarāja, the pupil of Bhattojī Dīksita.

सिद्धान्तकोमुदीगृढफिककाप्रकाश a small gloss on Bhattoji's Siddhāntakaunudī, explaining its difficult lines and passages, written by a grammarian named इन्द्रदत्तीपाच्याय.

सिद्धान्तकोमुदीवादार्थ an explanatory work, discussing the difficult sentences and passages of the Siddhāntakaumudī, written by a grammarian named Rāmakṛṣṇa.

सिद्धान्तरत्न a gloss on the Sarasvatisutra written by a grammarian named Jinacandra.

सिद्धान्तरत्नाङ्कर name of a commentary on the Katantraparisista by Śivarāmacakravartin.

सिद्धान्तसारस्वत an independent work on grammar believed to have been written by Devanandin.

सिद्धान्तिन् a term used in connection with the writer himself of a treatise when he gives a reply to the objections raised by himself or quoted from others, the term पूर्वपक्षिन् being used for the objector.

सिद्धि formation of a word; establishment of the correct view after the removal of the objection; e. g. संज्ञासिद्धि, कार्यसिद्धि, स्वरासिद्धि.

सिप् (1) the personal ending (सि) of the second person singular (मध्यमपुर-वैकवचन) substituted for the affix ल, of the ten tenses and moods लट्, लिट्, लुट् and others; cf. P.III.4.78; (2) Vikaraṇa affix स added to a root before the affixes of लेट् or Vedic Subjunctive.

सिम् a technical term used in the Vājasaneyi-Prātisākhya for the first eight vowels of the alphabet, viz. अ, आ, इ, ई, उ, ऊ, क and ऋ; cf. सिमादितोशै स्वराणाम् V. Pr., I.44.

सीयुद् augment सीय, prefixed to the personal affixes which are substituted for the छिड् affixes in the Atmanepada; e.g. पचेत पनेयाताम् cf. P. III. 4.102.

सीरदेव a prominent grammarian of the Eastern part of India who lived in the twelfth century A. D. He was a very sound scholar of Pāṇini's grammar who wrote a few glosses on prominent works in the system. His Paribhasavrtti is a masterly independent treatise the recognised among on the Paribhasas in which he has quoted very profusely from the works of his predecessors, such as the Kāśikā, Nyāsa, Anunyāsa and The reputed scholar others.

Maitreya Raksita is more often quoted than others.

सु (1) case affix (स) of the nominative singular and (स) of the locative plural; cf. P. IV. 1.2; (2) Uṇādi affix सु (क्सु) applied to the roots इष्; e.g. इक्ष: cf. इष: क्सु: Uṇādi 437.

सुक् augment सुक् added according to some grammarians to any word optionally with असुक्, which is prescribed in the case of the words अश्व, बृष, क्षीर and लवण before the affix क्यच् (य) in the sense of desire. e.g. दिषस्यित, मधुस्यित etc. cf. P. VII. I 51 Varttika.

सुच् (1) tad. affix स् applied to दि, त्रि, चतुर् and to एक optionally, in the sense of 'repetition of the activity' e. g. दि: करोति etc. cf. Kāś. on P. V. 4. 18, 19; (2) Uṇādi affix स, see स above.

सुजनपण्डित a grammarian who wrote a small treatise on genders named छिड्डार्थचन्द्रिका

सुद् (1) short term (प्रत्याहार) for the first five case-affixes which are called सर्वनामस्थान also, when they pertain to the masculine or the feminine gender; cf. सुडनपुंसकस्य I.1.43; (2) augment \forall prefixed to the root ৰু and to the root ৰু when preceded by certain prepositions and as seen in the words ক্রন্তুম্ব্রুক and others as also in the words अपरस्पर गोष्पद, आस्पद, आश्चर्य, अपस्कर, विष्कर, हरिश्चन्द्र, प्रस्कण्व, मस्कर, कास्तीर, अजस्तुन्द, कारस्कर and words in the class of words headed by पारस्कर, under certain conditions; cf. P. VI. 1.135-57; (3) augment Hprefixed to the case-affix आम् after a pronoun; e.g. सर्वेषाम् cf. P. VII. 1.52; (4) augment \(\forall\) prefixed to the consonant of or a pertaining to लिङ् affixes, e. g. द्वबंद्य cf. P. III. 4.107.

सुघाञ्जन an anonymous commentary on the Siddhāntakaumudī of Bhaṭṭoji Dīkṣita.

सुष् (1) locative case affix स; (2) short term for case-affixes, as formed by the syllable # (the nom, sing, affix) at the beginning and the final consonant q of Hq, the locative plural case-affix in the rule स्वीजसमीट...ङ्योस्सूप P. IV. These case affixes are called 'vibhakti' also. These सुपु affixes are elided after an indeclinable word: cf. अन्ययादाप्सप: P. II. 4.82; in Veda स्, श (ए), या, डा, ड्या, याच and আন্ত as seen, are substituted for these case affixes, which sometimes are even dropped or assimilated with the previous vowel of the base; e. g. सन्तु पन्था:, आर्द्रे चर्मन् etc. cf. P. VII. 1.39. These caseaffixes are as a rule, grave-accented (अनदात्त) excepting in such cases as are mentioned in P. VI.1. 166 to 184 and 191.

सुपद्मन्याकरण an independent work on grammar written by a scholar of grammar named पद्मनाम, who flourished in Mithila in the fifteenth century A. D.

सुपद्मक्याकरणटीका a commentary written by a scholar of grammar named विणुमिश्र on the Supadmavyākaraņa, which see above.

सुपद्मसमाससंग्रह a treatise written by a grammarian named रूपनारायण, on the सुपद्मव्याकरण, which see below.

सुपद्मसमाससंग्रहटीका a commentary by a grammarian named विष्णुमिश्र, on the सुपद्मसमाससंग्रह which see above.

सुद्धासमास a popular name given to a compound formed of two nouns, which cannot be ordinarily explained by the rules of grammar laid down in definite terms by Panini in II.1.5I to II. 2.29. These so called irregular compounds are explained as formed in accordance with the rule सह सुपा II. 1.4 wherein the word पद presents itself by अनुदृत्ति from सुवामन्त्रिते पराङ्गवत स्बरे II. 1. 2, the rule सह सुपा as a result being explained as सुप सुपा सह समस्येत. As these compounds cannot be put under the topics of अन्ययोभाव, तत्पुरुष and mentioned by Panini in II. 1.5 to II. 2.29 they are called सुरस्राप्त-मास or केवलसमास.

सुबन्त name given to a word formed with the addition of a case-affix and hence capable of being used in a sentence by virtue of its being called a पद by the rule सुन्तिङन्तं पदम्. The ancient grammarians gave four kinds of words or padas viz. नाम, आख्यात, उपमर्ग and निपात which Pāṇini has brought under two heads सुबन्त including नाम, उपसर्ग and निपात and तिङन्त standing for आख्यात; cf. सुतिङन्तं पदम् P. I. 4. 14.

सुनोधिनी name given to (1) a commentary on the Siddhāntakaumudī by Kṛṣṇamaunin or Jayakṛṣṇamaunin; (2) a commentary on the Sārasvata Vyakaraṇa by Amṛtabhāratī; (3) a commentary on the Sārasvata Vyākaraṇa by Candrakīrti.

सुन्धातु a root formed from a noun or a subanta by the addition of any of the following affixes— क्यच् (by P. III. 1.8, 10 and 19), काम्यच् (by P.III.1.9), क्यङ् (by P. III.1.11, 12 and 14-18), क्यच् (by P.III.1.13),णिङ् (by P III.1.20), णिच् (by P.III.1.21) and 25) and यक् (by P.III.1.27)and also by किप् or zero affix by P. III.1.11 Vārttika 3. All these formations ending with the affixes mentioned above are termed roots 401

by the rule सनायना धानवः (P.III. 1. 32) and are regularly conjugated in all the ten tenses and moods with the general conjugational sign श्व added to them in the conjugational tenses, and स्य, तास् and others in the other tenses and moods, and have verbal derivatives also formed by the addition of suitable krt affixes.

सुमनोरमा name of a commentary written by a Southern grammarian तिरमञ्ज on Bhattoji's Siddhantakaumudi.

सूत्र a short pithy assertion laying down something in a scientific treatise; aphorism; the word is sometimes used in a collective sense in the singular, referring to the whole collection of Sūtras or rules; cf. व्याकरणस्य सूत्रम् M. Bh. on Ahnika 1. The term is defined as आल्पाक्षरमसंदिग्धं सारवद्विश्वतोमुखम्। अस्तो-भमनवर्धं च सूत्रं सूत्रविदो विदु:. There are given generally six kinds of Sūtras viz. संज्ञासूत्र, परिभाषासूत्र, विधिसूत्र, नियमसूत्र, प्रतिवेधसूत्र and अधिकारसूत्र; cf. also संज्ञा च परिभाषा च विधिर्नियम एव च प्रतिषधोधि-कारश्च षड्डिघं सूत्रलक्षगम् ॥ Com. on Kāt. I. 1.2.

सूत्रकार the original writer of the sutras; e. g. पाणिनि, शाकटायन, शर्ववर्मन्, हेमचन्द्र and others. In Pāṇini's system, Pāṇini is called Sutrakāra, as contrasted with Kātyayana, who is called the Vārttikakāra and Pataūjali, who is called the Bhāṣyakāra; cf. पाणिन: सूत्रकारस्य M.Bh. on P.II 2.1.1.

handed down by oral tradition from the preceptor to the pupil. Although it is said that the actual text of Pāṇini was modified from time to time, still it can be said with certainty that it was fixed at the time of the Bhāṣyakāra who has noted a few different readings

only. The Sūtra text approved by the Bhāṣyakāra was followed by the authors of the Kāśikā excepting in a few cases. It is customary with learned Pandits and grammarians to say that the recital of the Sūtras of Pāṇini was originally a continuous one in the form of a Saṁhitātext and it was later on, that it was split up into the different Sūtras, which explains according to them the variation in the number of Sūtras which is due to the different ways of splitting the Sūtrapāṭha.

स्त्रभेद (1) splitting up of a grammatical rule (येगिविभाग); (2) change in the wording of a rule; cf. स एष स्त्रभेदेन लकारोपदेशः ख्ह्याद्यर्थः सन् प्रत्याख्यायेत तेषा महतो वंशस्तम्बाङ्कद्वानुक्षण्यते M. Bh. on Siva Sūtra 2 Vārt. 5.

सूत्रशादकन्याय reference to something as present, when, in fact, it is yet to come into existence, on the analogy of the expression अस्य सूत्रस्य शादकं वय; cf. भाविनी संज्ञा विज्ञास्यते सूत्रशादकवत्। M. Bh. on P. I. 3. 12 Vart. 2.

सक्रन the place of the articulation or production of the sound व्.

ন্থান্থয় name of the famous commentator on Purusottamadeva's Bhāṣāvṛtti, who lived in the fifteenth century A.D.

से (1) one of the several affixes found in Veda in the sense of तुमृत् (तुम् of the infinitive); e. g. बृक्ष राय:; cf. Pāṇ. III. 4.9; (2) personal-ending substituted for यास in the pres., perfect, and other tenses; cf. यास: से P. III. 4.80.

सद् together with the augment 'it' prescribed in general for being prefixed to an Ārdhadhātuka affix beginning with any consonant except यू. The word is also used

in the sense of a root which allows the augment इट् (इ) to be prefixed to valādi Ārdhadhātuka affixes placed after it, in contrast with such roots which do not allow it and hence which are termed अनिट्. सदक possessed of the augment इट्. See सेट्.

सतुंसग्रह name of a commentary on Bopadeva's Mugdhabodha Grammar written by a grammarian named Gangādhara.

सेन one of the several affixes found in Veda in the sense of the infinitive affix तुम्; e.g. एवे रथानां, cf. P. III.4.9.

सेनक name of an ancient grammarian quoted by Pāṇini in the rule गिरेश्च सेनकस्य P. V. 4.112.

सोढ tad. affix साढ prescribed in the sense of 'milk', optionally along with the affixes दूस and मरीस after the word अबि; e. g. अबिसोडम् cf, अबेर्दुग्धे सोढदूसमरीसन: P. IV. 2.36. Vart. 5.

सोपसर्ग together with a preposition (उपसर्ग) prefixed; the term is used in connection with a root to which a preposition such as प्र, परा etc. has been prefixed; cf. अकर्मका अपि वै सोपसर्गाः सकर्मका मवन्ति M. Bh. on P. I. 1,44.

सोम, सोमयार्थ name of the writer of a gloss named त्रिमाध्यरत on the Taittiriya Prātiśākhya.

सोमदेव a Jain Grammarian, the writer of a gloss on the commentary Jainendra Vyākaraņa named शब्दार्णवचन्द्रिका by the author, who was a resident of the Deccan and lived in a village named Arjurikā (called आजरें to-day) near Kolhapur in the twelfth century.

सोमयाजिन a modern grammarian of the nineteenth century who wrote a short grammatical work as a hand-book for scholars who aspired to be poets. The work was called वैयःकरणशब्दमाला.

सोध्मन् accompanied by a rush of breath. The word is taken to apply to the second and fourth consonants which are produced by the rush of unintonated breath through the open mouth like steam through a pipe; the second and fourth class consonants; cf. युग्मा: सोध्माण: R. T. 16.

सौत्र belonging to the sūtra; found in the sūtra as contrasted with what is given elsewhere; cf. सौत्रोचं घातु: or सौत्रं पुंस्त्रम् etc. cf. also सौत्रो निदेश: M. Bh. on P. III. 2.139, III. 4.60, 64, IV. 2.64 etc.

सौनाग name of a school of ancient grammarians who composed Vārttikas in explanation of the sūtras of Pāṇini; cf. सौनागा: पटन्ति P. III. 2.56 Vārt. 1, IV. 1.74 Vārt. 1. cf. एतदेव सौनागैविंस्तरतरेकण पठितम् M. Bh. on II. 2.18 Vārt. 4.

सौर्यभगवान् an ancient grammarian quoted in the Mahābhāṣya; cf. तत्र सौर्यभगवतोक्तमनिष्टिशो वाडवः पठति। इग्यत एव चतुर्भात्रः ५६तः M. Bh. on P. VIII. 2.106 Vārt. 3.

सौवादिक a root of the स्वादिगण or the Fifth Conjugation.

स्कन्धच् a tad. affix in the sense of collection, added to the words नर, किर and तुरङ्ग; cf. Vārttika on P. IV. 2.51 quoted in the Kāśikāvrtti.

स्तु a term used for the sibilant स् and dental class consonants for the substitution of the sibilant श् and palatal consonants in respective order; cf. स्तो: अना आ: P. VIII. 4.40.

स्त्री (1) the sense of the feminine; cf. क्लियाम् P. IV. 1.3-81 (2) a word

ending with an affix in the sense of feminity such as टाप्, डाप् or चाप् or डीप्, डीप् or डीप् or the like; cf. स्त्रीम्यो ढक् IV. 1.120; (3) a word in the sense of feminine cf. स्त्री पुवच P. I. 2.66.

स्त्रीप्रत्यय (1) affixes added to the masculine base of a word to show the sense of the feminine, such as आ in टाप, डाप and चाप and ई in डाप, डाप and चाप and

स्था based upon; the word is peculiarly used in the Prātišākhya works in the sense of 'based on' 'belonging to' or 'made up of'; cf. अस्थनामिनी सन्ध्यम्, R. T. 91, so also cf. वं नैगि उस्थ R. T. 162.

स्थिविरकोाण्डिन्य name of an ancient writer of Prātiśākhya works who is quoted in the Taittirīya Prātiśākhya cf. T. Pr. XVII. 4.

स्थान place of articulation; place of the production of sound, which is one of the chief factors in the production of sound; cf. अनुष्रानात संसगीत स्थानात करणविन्ययात । जायते वर्ण-वैशेष्यं परीमाणाच्च पञ्चमात्, T.Pr. XXIII. Generally there are given five places of the production of sound viz. कण्ठ, तालु, मूर्वन्, दन्त and ओष्ठ, respectively for the articulation of guttural, palatal cerebral, dental and labial letters and नासिका as an additional one for the articulation of the nasal consonants ञ्, म्, ङ्, ण् and न्. For the Jihvamuliya sound (४क), जिह्नामुल is given as a specific one. For details and minor differences of views, see T. Pr. III, R. Pr. 1.18 to 20,R. T. 2-10; V. Pr. I. 65 to 84 and M. Bh. on P. I. 1. 9. (2) place, substratum, which is generally understood as the sense of the genitive case-affix in rules which prescribe substitutes; cf. षष्ठी स्थोनेयागा. P. I. 1. 49.

स्थानपञ्ची one of the several kinds of the genitive case when it means a place or substratum, see the word स्थान.

स्थानिन the original word or part of a word such as a syllable or two of it or a letter of it, for which a substitute (आदेश) is prescribed; cf. स्थानिवदादेशोऽनाल्विधा P. 1.1. 56.

स्थानिवत् similar to the original in behaviour; cf. स्थानिवदादेशोनिव्वधे। P. I. 1.59. See स्थानिवद्गाव.

स्थानिवस्व acting like the original. See स्थानिवद्भाव.

स्थानिवज्ञाव behaviour of the substitute like the original in respect of holding the qualities of the original and causing grammatical operations by virtue of those qualities. By means of स्थानिवद्भाव,the substitute for a root is, for instance, looked upon as a root; similarly, a noun-base or an affix or so, is looked upon like the original and it can cause such operations or be a recipient of such operations as are due to its being a root or a noun or an affix or the like. स्यानिवद्धाव cannot be, and is not made also, a universally applicable feature; and there are limitations or restrictions put upon it, the chief of them being अल्विधौ or in the matter of such operations as are caused by 'the property of being a single letter' (अखिधौ). There are two views regarding this 'behaviour like the original': (1) supposed behaviour which is only instrumental in causing operations or

undergoing them which is called शास्त्रातिदेश and (2) actual restoration to the form of the original under certain conditions only as prescribed which is called रूपातिदेश. The रूपातिदेश is actually resorted to by some grammarians in the case of the reduplication of roots; cf. Kāś. on द्विवेचनिच P.I.1.59 and M.Bh. on P.I.1.59.See the word रूपातिदेश also. For details see Vol. VII p.p. 241–243, Vyākaraņa Mahābhāṣya D.E. Society's Edition.

स्थानेद्विचनपक्ष one of the two alternative views regarding reduplication according to which two wordings or units of the same form replace the original single wording, cf. स्थानेद्विचनपक्षे स्थानिवद्धावाद्मकृति व्यपदेश: Stradeva Pari. 68. The other kind of reduplication is called द्वि:-प्रयोगाद्विचनपक्ष which looks upon reduplication as the mere placing of an exactly similar unit or wording after the original first unit. This alternative view is accepted in the Kāśikā; cf. Kāś. on P. VI.1.1.

स्थानेयोगा a variety of the genitive case when it is connected in sense with the Pratipadika by the relationship of स्थान or place, as contrasted with the relationships of the kind of विषय-विषयिभाव, अवयवावयविभाव and others. As grammar is a science of words, in those places where one word is mentioned for another by the use of the genitive case it should be understood that the word mentioned is to be substituted for the other:cf. the rule of Panini for that purpose पश्ची स्थानेयोगा explained by Bhattoii Dīksita as आनिर्धारितसंबन्धविशेषा षठी स्था-नेयोगा बोध्या; cf. S.K. on P.I.1.49. In some grammars the sthanin and adesa are expressed in the same case, viz. the nominative case.

स्थान्यादेशभाव the relation between

the original and the substitute which is described as of two kinds (1) supposed and actual; cf.आनुमा-निकस्थान्यादेशमानकस्थानेप श्रीतस्थान्यादेशमानकस्य न त्यागः Pari Sek. Pari.

स्थापितच्य to be established, to be brought about.

स्थित (1) happened, come to pass; e. g. राम डस् इति स्थिते etc.; (2) established; remaining intact after the removal of doubts; cf. एवं हि स्थितमेतत; (3) remaining unaffected as referring to अस्पृष्टकरण; cf. स्वराणामनुस्वारस्य ऊप्मणां च अस्पृष्टं करणं वेदितन्यम् तब स्थितमित्युच्यते। यत्र वर्णस्थानमाश्रित्य जिह्नावतिष्ठते तत् स्थितमित्युच्यते। Uvvaṭa on R.Pr. XIII. ; (4) established or stated in the Padapāṭha; cf. स्थिते पदे पदपाठे इस्पर्थ; gloss on T. Pr. XX.2.

स्थिति utterance of a pada or padas in the Padapātha without इति; the utterance with इति being called उपस्थिति; cf. पदं यदा केवलमाइ सा स्थिति: R. Pr. XI.15; (2) established practice or view; cf. शाकल्यस्य स्थिवरस्यतरा स्थिति:। R. Pr. II. 44.

स्न tad. affix स्न added optionally with स, to the word मृद् in the sense of praiseworthy; c. g. मृत्स्ना also मृत्सा; cf. सस्ना प्रशंसायाम्। P.V.4.40.

स्त्रञ् tad.assix स्न,added in many taddhita senses, अपत्य, जात समूह, आगत and others mentioned upto P. V. 1st pada end; e. g. स्त्रेण: पोंस्त:, cf. स्त्री- पुंसाम्यां नक्सन्त्रों भवनात् P.IV.1.87.

स्पर्ध a word used in the sense of 'a conflict of two rules' (विप्रतिषेष) in some grammars such as those of Jainendra, Śākaṭāyana and Hemacandra; cf. Jain. I.2.39,Sāk. I.1.46 and Hema. VII.4. 119.

used in connection with the consonants of the five classes, verily because the karana or the tip of the tongue touches the place of

utterance in the mouth in their pronunciation; cf. कादयो मावसाना: स्पर्शाः S.K. Samijnā prakaraņa on P. VIII. 2.1; cf. also आद्याः स्पर्शाः पञ्च ते पञ्चवर्गाः R.Pr. I.78; cf. also T.Pr.I.7.

स्पष्टार्थ an expression used often by commentators with reference to a line or a passage of the text the meaning of which is clear and no explanation is necessary.

स्पृष्ट name of one of the four internal efforts when the instrument (करण) of articulation fully touches the sthāna or the place of the production of sound in the mouth. See the word स्पर्श above; तत्र स्पृष्ट प्रयतनं स्पर्शानाम् S.K. on P. VIII.2.1; cf. also M.Bh. on P.I.1.9.

स्फ a short technical term used in the Jainendra Vyākaraṇa instead of the सेवाग in Pāṇini's grammar.

स्फोट name given to the radical Sabda which communicates the meaning to the hearers as different from ध्वनि or the sound in ordinary experience, The Vaiyakaranas, who followed Pānini and who were headed by Bhartyhari entered into discussions regarding the philosophy of Grammar, and introduced by way of deduction from Panini's grammar, an important theory that which communicates the meaning is different from the sound which is produced and heard and which is merely instrumental in the manifestation of an internal voice which is called Sphota.सुख्यतेनेन अर्थः इति स्फोट: or स्फोट: शक्दो ध्वानस्तस्य ब्यायमा-दुपजायते Vākyapadīyā; cf. also अभि-व्यक्तवादको मध्यमावस्य आन्तरः शब्दः Kaiyata's Pradīpa. For details see Vākyapadīya I and Sabdakaustubha Ahnika 1. It is doubtful whether this Sphota theory was I

advocated before Pānini. The word स्पाटायन has been put by Panini in the rule अवङ् स्पोटायनस्य only incidentally and, in fact, nothing can be definitely deduced from it although Haradatta says that स्काटायन was the originator of the स्क्रीटबाद. The word स्कोट is not actually found in the Prātiśākhya works. However, commentators on the Pratisakhva works have introduced it in their explanations of the texts which describe वणेंत्यात्त or production of sound: cf. com. on R.Pr.XIII.4, T.Pr. II.1. Grammarians given various kinds of sphota; cf. स्फोटो द्विधा । ब्याक्तस्फोटो जातिस्फोटश्च । ब्यक्ति-स्पीटः सरवण्ड अखण्डश्च । सरवण्ड । वर्णपदवास्य-भेदेन त्रिधा । अखण्डः पदवाक्यभेदेन 🏻 द्विधा । एवं पञ्च ब्यार्थतस्पाटाः । जातिस्पाटः वर्ण-पदवाक्यभेदेन त्रिधा । इत्येवमधौ स्फोटाः तत्र अखण्डवावयरेपाट एवं मुख्य इति नव्याः । वाक्य जातिस्फोट इति त प्राञ्च: ||; cf. also पदप्रकृतिः संहिता इति प्रातिशाख्यमत्र मानम् । पदानां प्रकृतिरिति षष्ठीतत्परुषे अखण्डवाक्यरफो-टपक्षः । बहुन्नीही सखण्डवाक्यस्भाटः।।

स्फोटचटक a small treatise on the theory of Sphota by a sound modern scholar of Vyākaraņa and Nyāya, by name Kṛṣṇaśāstrī Ārade who lived in Benaras in the earlier part of the nineteenth century.

स्फोटचिन्द्रका a small treatise on the theory of Sphota written by Jayakṛṣṇa Maunī of the famous Maunin family. The author is known as Kṛṣṇabhaṭṭa also.

स्फोटतस्वानिरूपण a work on the Sphota theory by the famous grammarian Kṛṣṇaśesa of the Śesa family of grammarians.

exhica (1) manifestation of the sense of a word by the external sound or dhvani; the same as sphota; (2) separate or distinct pronunciation of a consonant in a way by breaking it from the corjunct consonants; cf. स्कोटनं नाम पिण्डीभूतस्य संयोगस्य पृथमुचारणम् स देाषो वा न वा । V. Pr.IV.165.

स्फोटनिरूपण name of a work discussing the nature of Sphota written by Apadeva.

स्फोटबाद a general name given to treatises discussing the nature of Sphota written by the Vāiyakaraṇas who defend and establish the theory of Sphota and by the Naiyāyikas who criticise the theory. Famous among these works are (1) स्फोटबाद by a stalwart Grammarian Koṇḍabhaṭṭa, the author of the Vaiyākaraṇabhūsaṇa and (2) स्फोटबाद by Nāgeśa, the reputed grammarian of the eighteenth century.

स्फोटासिद्धान्त the doctrine of Sphota, as advocated by the grammarians and criticised by others. See the word स्पोट.

स्कोट सिद्धि (1) name of a short treatise on the nature of Sphota, written by a grammarian named Bharata Misra; (2) name of a short disquisition on Sphota by Mandanamisra.

स्फोटायन an ancient grammarian referred to by Pāṇini in the rule अवङ् स्फोटायनस्य P.VI.1.123. Great grammarians like Haradatta observe that this स्फोटायन was the first advocate of the Sphota theory and hence he was nicknamed स्फोटायन; cf. स्फोट: अयनं परायणं यस्य स स्फोटायन: स्फोटप्रतिपादनपरो वयाकरणाचार्य: I Padama नुंबरों on P. VI.1.123.

स्मात् case-ending स्मात् substituted for the ablative sing. case-affix ङसि placed after pronouns; cf. ङसिङयो: स्मास्मिनो P. VII. 1.15, 16.

स्मृति an authoritative dictum of an ancient grammarian before the

famous author of the Vārttikas;cf. तथा च स्मृति: क्तिपा रापानुबन्धेन निर्दिष्टं etc, Siradeva Pari. 68.

स्मै case ending स्मै, substituted for the dative sing. case-affix के after pronouns; cf. सर्मनाम्न स्मैP. VII.1.14.

स्य (1) case-ending स्य substituted for the genitive singular case-affix after bases ending in ञ; cf. टाङासिङसामि-नास्या: P. VII.1.12; (2) Vikaraṇa affix स्य placed before the personal endings of लृट् and लृङ् (the second future tense and the conditional mood); cf. स्यतासी लृङ्टो: P. III.1.33.

स्याद् augment स्या affixed to a caseaffix marked with the mute ङ् i.e. ङ, ङसि, ङस् and ङि of the dat. abl. gen. and loc. singular after a pronoun and optionally after तृतीय and द्वितीय ending with the fem. affix आ; cf. सर्वस्य सर्वस्या; सर्वस्याम् द्वितीयस्य, द्वितीयाय, तृतीयस्य, तृतीयाय; cf. P. VII. 3.114, 115.

स्यादि the Vikaraṇas headed by the Vikaraṇa स्य mentioned in P.III.1. 33 upto III.1.90.

स्व (1) personal-ending of the second person sing. Atmanepada in the imperative mood; cf. थास: से। सवाभ्यां वामी। P.III.4.80, 91; (2) a term used in the sense of स्त्रवगीय (belonging to the same class or category) in the Pratisakhya works; cf. स्पर्शः स्वे R.T.25; cf. also कान्त् स्वे R. T. 1. 55; cf.also R. Pr.IV.1; and VI.1; (3) cognate, the same as सवर्ण defined by Panini in तुल्यास्यप्रयत्नं सवर्णम् P. P.I.1.9; the term is found used in the Jain grammar works of Jainendra, Sākatayana and Hemacanda cf. Jain. I.1.2 Sik- I.1.2; Hema. I.1.17.

स्वतन्त्र lit. independent; independent in activity; the subject or agent of an action (कर्ती) is defined as स्वतन्त्र independent in his

activity, i. e. not depending upon any one for the same; cf. स्वतन्त्र: क्ती P. I. 4. 54.

स्वतन्त्रपदोपस्थितिपक्ष an alternative view regarding the explanation of the rule 'इको गुणहृद्धो ' P. I. 1. 3 by taking an additional word गुणहृद्धो supplied in the sūtra. For full explanation see Sabdakaustubha on P. I. 1. 3.

स्वपदार्थ meaning of one's own, as possessed by a word. In many compounds especially in the Bahuvrihi compounds the meaning expressed by the compound word is quite different from the one expressed by the constituent words; cf. स्वपदार्थे कर्मधारय:। अन्यपदार्थे बहुनोहि:। M. Bh. on P. II. 1. 69.

स्वपाठ the original recital of the Veda; the Samhitāpāṭha as opposed to the Padapāṭha which is looked upon more or less as artificial.

स्वर (1) vowel, as contrasted with a consonant which never stands by itself independently. The word स्वर is defined generally as स्वयं राजन्ते ते स्वरा: (M. Bh. on pan. The word स्त्र is always used in the sense of a vowel in the Pratisakhya works; Pāṇini however has got the word স্ত্ৰ (short term or Pratyāhāra formed of आin 'अइउण्' and च at the end of ऐऔच Māheśvara sūtra 4) always used for vowels, the term स्वर being relegated by him to denote accents which are also termed स्वर in the ancient Pratis'akhyas and grammars. The number of vowels, although shown differently in different ancient works, is the same, viz. five simple vowels अ, इ, उ, ऋ, ल, and four diphthongs ए, ऐ, ओ, and औ. These nine, by the addition of the long varieties of the first four such as आ, ई, ऊ, and 汞, are

increased to thirteen and further to twentytwo by adding the pluta forms, there being no long variety for & and short diphthongs. All these the twentytwo varieties have further subdivisions, made on the criterion of each of them being further characterized by the properties अनुदात्त and स्वरित निरन्नासिक and सानुनासिक. (2) word स्वर also means accent, a property possessed exclusively by vowels and not by consonants, as they are entirely dependent on vowels and can at the most be said to possess the same accent as the vowel with which they are uttered together. The accents are mentioned to be three; the acute (उदात्त), the grave अनुदात्त and the circumflex (स्वरित) defined respectively as उच्चेरदात्तः, नीचैरनदात्तः and समाहार: स्वरित: by Pāṇini (P. I. 2.29, 30,31). The point whether समाहार means a combination or coming together one after another of the two, or a commixture or blending of the two is critically discussed in the Mahābhāsya. (vide M. Bh. on P. I. 2.31), There are however two kinds of svarita mentioned by Pāņini and found actually in use: (a) the independent स्वरित as possessed by the word स्वर् (from which possibly the word स्वरित was formed) and a few other words as also many times by the resultant vowel out of two vowels (उदात्त and अनुदात्त) combined, and (b) the enclitic or secondary svarita by which name, one or more grave vowels occurring after the udatta, in a chain, are called; cf. P. VIII. 2.4 VIII. 2.6 and VIII 4.66 and 67. The topic of accents is fully

discussed by the authors of the Prātiśākhyas as also by Pānini. For details, see R. Pr. III. 1.19; T.Pr. 38-47 V. Pr. I. 108 to 132, II. 1.65 A. Pr. Adhyaya 1 padas 1, 2, 3 and Rk. Tantra 51-66; see also Kaivata on P. I. 2.29; (3) The word स्वर is used also in the sense of a musical tone. This meaning arose out of the second meaning 'accent' which itself arose from the first viz. 'vowel', and it is fully discussed in works explanatory of the chanting of Sāmas. Patanjali has given seven subdivisions of accents which may be at the origin of the seven musical notes. See समस्य above.

स्वरप्रतिरूपक a word or Prātipadika which is exactly similar to a single vowel such as उ or आ or ए and; the like; such words are to be looked upon as Avyayas and the case-affixes after them are dropped when they are used. cf. स्वरमतिरूपकमञ्चयम्.

स्वरमक्ति a vowel part; appearance of a consonant as a vowel; the character of a vowel borne by a consonant. Many times a semivowel which consists of one letter has to be divided especially for purposes of metre, as also for accentuation into two letters or rather, has to be turned into two letters by inserting a vowel before it or after it, for instance y is to be turned into इयु e. g. in त्रियम्बकं यजामहे, while रू or रेफ is to be turned into र्क as for instance in कहिं चित which is to be uttered as 羽玉邦 信 This prefixing or suffixing of a vowel is called स्वरभक्ति; cf. स्वरभाक्तिः पूर्वभागक्षराङ्गं द्रावीयसी सार्वमात्रतरे च। अर्घोनान्या। R. Pr. I. 32.35; cf. also न संयोगं स्वरभाक्तिर्विहान्त R. Pr. VI. 35; cf. also रेफात् स्वरोपहिताद् व्यञ्ज- नादयाद् ऋकारवर्णा स्वरमाक्तिरुत्तरा; R. Pr. VI. 46. In Pāṇini's grammar, however, the word अज्माक्त, which means the same, is used for स्वरमिक्ति; ट्रा. ऋति क वा ऌति ल वा इत्युमयत्रापि विधयं वर्णद्वयं द्विमात्रम् । आद्यस्य मध्ये द्वौ रेफो तयोरिका मात्रा। अभितोष्मक्तेरपरा। S. K. on VI. 1.101.

स्वरभिन्न differing in the matter of accent; words so differing are practically looked upon as one and the same; cf. स्वरभिन्नानां यस्योत्तरस्वरविधित्त्तस्येकशेषो वक्यव्यः। अक्षश्च अक्षश्च अक्षो। M. Bh. on I. 2. 64 Vart. 24. For technical purposes, they are sometimes looked upon as different; cf. स्वरभिन्नस्य च प्राप्नुवन् विधिरनित्यः। Par. Sek. Pari. 49.

स्वरभेद difference in accents. See स्वराभित्र above.

स्वर्शिये a rule prescribing an accent or a modification of accent.

स्वर्शियाम a pause between two vowels in one and the same word as in तितउ or पडन or in two different words coming close by the visarga or य between the two being elided, as for instance in देवा इह.

स्वरविद्वात (1) the same as स्वरिष्ण which see above; (2) a short treatise on Vedic accents written by a modern Vedic scholar and grammrian named Indradattopadhyaya.

स्वरसंधि euphonic combination of two vowels, a detailed description of which forms a small topic in the Prātis'ākhya and grammar works; vide R. Pr. chapters II. 1-26; T. Pr. chapters 9 and 10 V. Pr. III and अञ्चाल्यकरणम् in the Siddhāntakaumudī.

स्वरसर्वनाम a common accent; the accent which is supposed to be present in a word when none of the three accents are definite. cf. एक्श्रुतिः स्वरसर्वनाम यथा नपुंसकं लिङ्क्सर्वनाम

M. Bh. on P. VI. 4.174.

स्वरसहितोचारण recital of the Veda Samhita text with intonation or accents, as contrasted with एकश्रत्य-च्चारण which is specially prescribed in a few cases; tonal system distinction showing between words of different senses although pronounced alike, in the Samhita text, e. g. नतेन and न तेन.

स्वरार्थ for purposes of accent, meant for accent; cf. अवश्यं चेषा परिभाषा (असिद्धं बहिरङ्गमन्तरङ्गे) आश्रयितव्या स्वरार्थम M. Bh. on P. I. 1.57.

स्वारित the circumflex accent, the accent between the acute (.ভৱাৰ) and the grave (अनुदात्त); for details see स्वर.

स्वरितकरण marking or characterizing by a svarita accent, as is supposed to have been done by Panini when wrote down his sutras of grammar as also the Dhatupatha. the Ganapatha and other subsidiary appendixes. Although the rules of the Astadhyayi are not recited at present with the propossessed by the per accents various vowels as given by the Sūtrakāra, still, by convention and traditional explanation, certain words are to be believed as possessed of certain accents, the Dhatupatha, by oral tradition the accents of the several roots are known by the phrases अथ स्वरितेत:. अथाद्यदाताः, अथान्तोदात्ताः, अथानदात्तेतः put therein at different places. In the sūtras, a major purpose is served by the circumflex accent with which such words, as are to continue to the next or next few or next many rules, have been marked. As the oral tradition, according to which the Sutras are recited at present, has preserved no acc- required mention by the verbal form,

ents, it is only the authoritative word, described as 'pratijna' of the ancient grammarians, which now is available for knowing the The same holds good svarita. of the case nasalization (आननासिक्य) which is used as a factor for determining the indicatory nature of vowels as stated by the rule उपदेशेजननासिक इत: cf. प्रतिज्ञाननासिक्याः पाणिनीयाः S. K. on P. I.3.2.

स्वरितप्रतिज्ञा the conventional dictum that a particular rule or part of a rule, is marked with the accent स्वरित which enables the grammarians to decide that that rule or that part of a rule is to occur in each of the subsequent Sūtras, the limit of continuation benig ascertained from convention. It is possible that Pānini in his original recital of the Astadhyavi recited the words in the rules with the necessary accents; probably he recited every word, which was not to proceed further, with one acute or with one circumflex vowel. while, the words which were to proceed to the next rule or rules, were marked with an actual circumflex accent (स्रोत), or with a neutralization of the acute and the grave accents (स्वरितत्व), that is, probably without accents or by एकश्रुति or by प्रचय; cf स्वरितेनाधिकारः P. I.3.11 and the Mahabhasya thereon.

स्वरितेतmarked with a mute circumflex vowel; the term is used in connection with roots in the Dhatupatha which are said to have been so marked for the purpose of indicating that they are to take personal endings of both the padas; cf. स्वरितञित: कर्त्रीभप्राये कियापले P. I.3.72.

and not by the description of characteristics; e.g. मृजेर्नृद्धिः P. VII. 2.114; सृजिहशोझंत्यमाकिति VI. 1. 58; cf. धातोः स्वरूपप्रहणे तत्प्रत्येये कार्यविज्ञानम् M.Bh. on P.VI.1.58.

स्वरूपयोग्यता deserving by virtue of one's own form.

स्वरूपविधि an operation prescribed for the verbal form of the word and not for such words as possess the meaning of the word; cf. आसि कश्चित्परुधारम्भः । कः । स्वरूपविधिनाम । इन्ते-रात्मनेपदम्चयमानं हन्तरेव स्याद्वधेर्न M.Bh. on P.I.1.56 Vart, 1. In grammar there is a general dictum that in connection with words of a Sūtra, unless they are technical terms, the word-forms are to be understood, and not those shown by the sense of the word; cf. स्वं रूपं शब्दस्याशब्दसंज्ञा P. I.1.68. This rule has some exceptions; for example in the rule नदीनिश्च P.II.1.20 the various rivers are to be understood and not the word नदी.

स्वस्थ lit. remaining in its own form without admitting any cuphonic change for the final letter; an ancient term for 'pragṛhya' of Pāṇini.

स्वस्वामिसंबन्ध relationship of the possessor and the possessed; one of the general meanings of the type of relation, expressed by the genitive case; cf. अधिराक्षरे। ईश्वरः स्वामी। स च स्वमपेक्षते तद्यं स्वस्वामिसंबन्धः कमेप्रवचर्ना- यसंहो भवति। Kas. on P. I.4.97.

स्वाङ्ग (1) one's own limb, as contrasted with that of another person; cf. स्वाङ्गकर्मकाच्चेति वक्तव्यम् । स्वाङ्गं चह न परिन्माधिकं राह्यते । किं तर्हि स्वमङ्गं स्वाङ्गम् । Köś. on P.I. 3.28; (2) forming a part, a portion; cf. स्वाङ्गाच्चोपसर्जनादसंयोगोप्यात् । किं स्वाङ्गं नाम । अद्रवं मूर्तिमस्याङ्गं प्राणिस्थमविकारजम् । अतस्थं तत्र दृष्टं च तस्य चेत्तत्त्था युतम् ॥ अप्राणिनोपि स्वाङ्गम् । M. Bh. on P. IV.1.54.

स्वातन्त्र्य independence, or autonomy as a characteristic of the agent (कर्ता); cf. कमंकर्तिर कर्तृत्वमास्त । सुतः । स्वातन्त्र्यस्य विवाक्षतस्वात् । स्वातन्त्र्यणैवात्र कर्ता विवक्षितः । M.Bh. on P. III. 1. 87 Vart.5.

स्वादि the affixes headed by सु; a general term for case-affixes; cf. स्वोजसमाट्यास्यां ... ङ्वासमुप् P. IV.1.2.

स्वाद्युत्पत्ति the addition of case-affixes which requires the designation प्रातिपदिक for the preceding base by the rule अर्थवदघातुरप्रत्ययः प्रातिपदिकम् or कृत्ताद्वितसमासाश्च । P.I. 2.45,46. The addition of a case-affix entitles the word, made up of the base and the case-affix, to be termed a Pada which is fit for use in language; cf. अपदं न प्रयुक्तात; cf. निपातस्य अनर्थकस्य प्रातिपदिकसंज्ञा वक्तव्या । कि पुनरत्र पदसंज्ञया प्रार्थते । प्रातिपदिकादिति स्वाद्युत्पत्तिः, सुवन्तं पदमिति पदसंज्ञा, पदस्य पदादिति निघातो यथा स्यात् । M. Bh. on P.I.2.45 Vart.12.

स्वाभाविक natural, unartificial; the word is used frequently in connection with the capacity of denotation which words naturally possess; cf. आमिशानं पुनः स्थाभाविकम् P. I. 2.64 Vart. 36.

स्वाभाज्य inherence; natural capacity; the word is used many times in connection with the power of denotation; cf. शब्दशक्तिस्वाभाज्यात् l Nyāsa on P. III.1. 112 or अभिधान- शाक्तिस्वाभाज्यात् Nyāsa on P. IV. 4.60.

स्वार a term used in the Prātiśākhya works for स्वरित or the circumflex accent; स्वार: स्वरित: । Com. on T.Pr. XVII.6; cf. also T.Pr.XX.20; XXIII.24. There are seven varieties of स्वार given in the Prātiśākhya works, viz. क्षेत्र, नित्य, प्रातिहत, अभिनिहत, प्रारुष्ट, पादवृत्त and तरोज्यञ्जन, cf. T. Pr. XX.1-7.

स्वार्थ one's own sense possessed by a word, such as जाति, गुण, किया or संज्ञा

which is called प्रवृत्तिनिमत्त in the case of nouns, and किया in the case of verbs; cf. also आनीर्द्धार्थाः प्रत्ययाः स्वार्थे भवान्ति M. Bh. on P. III. 2. 4 Vart. 2.

स्वाधिक prescribed (after a base) in the sense of itself; i.e. in the sense of the base. The word is used in connection with a large number of tad. affixes which are prescribed without any special sense attached to them; vide P. V.3.36 to P. V. 4.67. The Samāsānta affixes prescribed from P.V.4.68 onwards can also be called स्वाधिक of स्वाधिक अकृतितो लिङ्गव वान्यनुवर्तन्ते। M.Bh. on P. V. 4.14, 27. See the word स्वाधि.

स्वाश्रय possessed as its own, as contrasted with artificial or intentionally stated (आनुदेशिक);cf. अस्त्वन आनुदेशिकस्य वलादित्वस्य प्रतिषेधः । स्वाश्रयमत्र वलादित्वं भाविष्यति M. Bh. on P. I. 1. 59 Vart. 6.

Ē

ह् the last of the spirant consonants, which is a glottal, voiced letter called also जन्म or spirant of a partial contact, i. e. possessed of the properties कण्ट्य, नादान्यदान, ऊष्म and ईषत्स्प्रष्टत्व. This letter has been given twice in the Paninian alphabet, viz. the Maheśvara Sūtras, and the Bhāşyakāra has given the purpose of it, viz. the technical utility of being included among soft consonants along with semi-vowels, nasals and the fifth, the fourth, and the third class-consonants (ह्य अश्etc.), as also among the hard consonants along with the fourth and the third class-letters and spirants (झलु,). The second letter ह in हल appears, however, to have only a technical utility, as the purpose of its place there among spirants is served by the Jihvāmūliya and the Upadhmānīya letters which arc,in fact,the velar and the labial spirants respectively, besides the other three इ,इ and स्.The Rk Prātišākhya calls ह as a chest sound. For details, see Mahābhāsya on the Siva Sūtra ह्यवरद् Vārttikas 1, 2 and 3.

ਵ (1) representation of the consonant g with 의 added for facility of pronunciation; (2) a technical term for the internal effort between विवृत and संवृत, which causes घोष in the consonants; cf. संवृतविवृतयोर्भध्ये अभ्यमप्रकारे यः शब्दः क्रियते स हकारसंज्ञो भवति। संज्ञायाः प्रयोजनं 'हकारो हचतुर्थेष ' इति (तै. प्रा.रा९)। Tribhasyaratna on T.Pr. II.6; (3) name of an external effort causing घोष; cf. सांप्रतिके प्रकृतिस्थे कण्ठे सति हकारो नाम बाह्यः प्रयतनः कियते । तेन च व्यञ्जनेषु घोषो जायते । Vaidikābharaņa on T.Pr. II.6; (4) name of a kind of external effort of the type of अनुप्रदान found in the utterance of the consonant () and the fourth class-consonants; cf. हकारी हचतुर्थेषु T.Pr.II.9.

हंसपदा name given to a kind of svarabhakti, when the consonant ?, followed by ष्, is read as र + ष् + ह्.

हकार See ह् as also ह.

हनु inside of the chin, mentioned as a स्थान or place which is touched by the tongue when a peculiar sound described as something like किट्-किट् is produced; cf. किट्किडाकारो इन्वां तिष्ठति R.T.10.

हरद्ता name of a reputed grammarian of Southern India who wrote a very learned and scholarly commentary, named पदमञ्जरी, on the Kāśikāvṛtti which is held by grammarians as the standard vṛtti or gloss on the Sūtras of Pāṇṇi, and studied

especially in the schools of the southern grammarians. Haradatta was a Drāvida Brāhmana, residing in a village on the Bank of Kaveri. His scholarship in Grammar was very sound and he is believed to have commented on many grammarworks. The only fault of the scholar was a very keen sense of egotism which is found in his work, although it can certainly be said that the egotism was not ill-placed and could be justified; cf. एवं प्रकटितोस्माभिर्भाष्ये परिचयः परः। तस्य निःशेषतो मन्ये प्रतिपत्तापि दुर्छभः ॥ also अकियातकंगहने प्रविष्टो हृष्टमान्सः इरदत्तहरिः स्वरं विहरन् केन वार्यते ॥ Padama हे jari, on P. I.l. 3, 4. The credit of popularising Pāṇini's system of grammar in Southern India goes to Haradatta to a considerable extent.

हारे a short form used for भतृंहरि, the stalwart grammarian Bhartrhari, by later grammarians and commentators in their references to him. See the word भतेंहरि above.

हरिक्रण a scholar of grammar who wrote a short treatise on the nature and function of prepositions named उपसीवाद.

हरिणी name of a kind of svarabhakti when r (र) followed by s (श्) and s (स्) is read as र + इ + श् and र + इ + स् respectively.

हरितादि a class of words headed by the word हरित to which the taddhita affix पक् (आयन) is added in the sense of a descendant after the affix अ (अञ्) has already been added to them by P. IV. 1. 104, the word so formed possessing the sense of the great grandchild (युवापत्य) of the individuals denoted by हरित and others; e. g. हारितायन:; cf. इह तु गोत्राधिकारेपि सामर्थ्याद् यूनि प्रत्ययो-भिषायते Kāś. on P. IV. 1.100.

हरिदत्त a grammarian who wrote a commentary on the Uṇādi Sūtras, called उणादिसूत्रदीका.

हार्रेदीक्षित a reputed grammarian of the Siddhantakaumudi school of Pānini who lived in the end of the seventeenth century. He was the grandson of Bhattoji Diksita and the preceptor of Nagesabhtta. His commentary named लघुराब्दरत्न, but popularly called शब्दरन on Bhattoii Praudhamanoramā, is Dīksita's widely studied by pupils along with the Praudhamanorama in the Vyākaraņa pāthasālās. There is a work existing in a manuscript form but recently taken for printnamed 'Brhatsabdaratna' which has been written by Harialthough some scholars beijeve that it was written by Nāgesa who ascribed it to his preceptor. For details see लघुशान्दरस्त.

ांगियद्विवेदी a grammarian of the nineteenth century who has written a commentary named अकाण्डताण्डव on Nagesa's Paribhasendusekhara.

हरिमास्कर (अग्निहोत्री) a grammarian of the Deccan who lived in the seventeenth century at Nāśik and wrote commentaries on grammarworks out of which his treatise on Paribhāṣās (परिभाषाभास्कर) written independently but based upon Sīradeva's Paribhāṣāvṛtti, deserves a special notice and mention.

हरिराम (हरिराम केशव काळे) a modern grammarian who has written a commentary named Kāśikā on Koṇḍabhaṭṭa's Vaiyākaraṇabhūṣaṇasāra. He lived in the second half of the eighteenth century and the commentary Kāśikā was written by him in 1797, He is said to have been a pupil of the great

grammarian Bhairavamisra.

हरिवञ्जभ a grammarian who has written commentaries named द्वेणा on the Vaiyākaraṇabhūṣanasāra of Kondabhaṭṭa, and Laghubhūṣanakānti on the Sabdakaustubha of Bhaṭṭojī Dīkṣita.

हरिशास्त्री (भागवत) a grammarian of the nineteenth century who has written Vākyārthacandrikā, a commentary on Nāgeśa's Paribhāsenduśekhara.

हर्षवर्द्धनस्वामिन् a fairly old grammarian who wrote an extensive metrical compendium on genders named लिङ्गानुशासन on which a commentary was written by a grammarian named शबरखासन्. These grammarians were, of course, different from the reputed king हर्षवर्धन and the Mimārisaka शबरखासन.

ह्न् a short term (प्रत्याहार) for consonants, made up of the first letter ह in ह्यवरट् and the last letter ह in ह्ल. The term is universally used for the word ब्यझन in Pāṇini's grammar; cf. हलोनन्तरा: संयोग: P.I. 1.7. हलनाच्च I. 2.10 etc.

हरून्त a term used for words ending in consonants; cf. हरून्तस्येत्येवं भविष्यति M. Bh. on P.I.1.3 Vart.10; cf. also the term हरून्तरुक्षणा वृद्धि for the Viddhi prescribed by the rule बदबजहरून्तस्याचः P.VII. 2.3.

हलादि beginning with a consonant; cf. इलादयो विभक्तयः, M.Bh. on P. II. 4.32 Vārt. 2; घातुर्य एकाज् इलादिः M. Bh. on P. III. 1. 22. Vārt. 2. etc.

हलादिशेष a term frequently used by commentators for the omission of all consonants except the initial one in the reduplicative syllable as prescribed by the rule of Pāṇini हलादि: शेष: VII. 4. 60. The word 'हलादि: शेष ' as one word, is also found used in the same sense.

हल्स्वरमांसे a possibility of the application of an accent to the consonant by the literal interpretation of rules prescribing an accent for the first or the last letter of a word, to prevent which a ruling is laid down that a consonant is not to be accented; cf. इल्स्वरप्राप्ती ब्यज्जनमविद्यमानवत् Par. Śek. Pari. 80.

ह्या a short term (प्रत्याहार) for semivowels, इ, and the fifths, the fourths and the thirds of the classconsonants; cf. हशि च P. VI.1.114.

हारिता name given to a kind of Svarabhakti when the consonant ल is followed by श् and the conjunct consonant ल्झ is read as ल्लुश् or ल् इ श; cf. बनस्पते शतबल्झा विरोह Tait. Samh. 1.

हि (1) personal-ending of the second pers. sing. substituted for सि in the imperative mood; cf. सहांपिच P. III. 4.87; (2) a sign-word used in the Vājasaneyi-prātisākhya to mark the termination of the words of the Adhikārasūtra V. Pr.III.5, IV.11.

हुन्करण the use of the sign-word हुन्, put in the grammar of Apisali according to some grammarians who read हुन्करण for पुन्करण in the Kāsīkāvṛtti on P. IV.3.115.

हृद्यहारिणी name of a commentary written by a grammrian named दण्डनाथ on the Sarasvatīkaņṭhābharaṇa of Bhojarēja.

हेतु (1) cause; cf नते: परस्योभयहेतुसंग्रहात् R. Pr.XI.2; also cf. हेती P. II.3.23; हेतुहेतुमतोलिंङ् P.III.3. 126; (2) causal agent cf. यः कारयति स हेतुः Kāt. II. 4.15; cf. also तत्प्रयोजको हेतुश्च P. I. 4.55.

हेतुमाणिच् the affix णिच् added to a root in the sense of the activity of the causal agent; see हेतुमत् above; cf. तत्र हेतुमण्णिच; प्रतिषेध: P. I.1. 62, Vart. 7.

हेतुमत the activity of the causal agent to express which a root has the affix णिच् added to it; cf. हेतु: स्वतन्त्रस्य कर्तु: प्रयोजकः । तदीयो ब्यापार: प्रवणादिलक्षणो हेतुमान् । तिसम्त्रामिषेये धाताणि-च स्यात् । Kās. on P. III. 1.26.

हेमचन्द्र a Tain sage and scholar of remarkable erudition in the religious works of the Jainas as also in several Shāstras. He was a resident of Dhandhukā in Gujarat, who, like Sankarācārya took संन्यास-दीक्षा at a very early age and wrote a very large number of original books and commentaries, the total number of which may well nigh exceed fifty, during his long life of eighty-four years (1088 11 2). He stayed at Anhilavada-Pattana in the North Gujarat and was patronised with extreme reverence by King Kumārapāla who, in fact, became his devoted pupil. Besides the well-known works on the various Shastras like Kāvyānuśāsana, Abhidhānacintāmaņi, Desīnāmamālā, Yogasāstra, Dvyāsrayakāvya, Trisastīśalākāpurusacarita and others which are well-known, he wrote a work on grammar called सिद्धहेम-चन्द्रby him, but popularly known by the hame हैमन्याकरण or हैमशब्दानुशासन. The work consists of books or Adhyayas, out of which the eighth book is devoted to Prākrit Grammar, and can be styled as a Grammar of all the Prakrit dialects. The Sanskrit Grammar of seven chapters is based practically upon Pāṇini's Astādhyāyī, the rules or sūtras referring to Vedic words or Vedic affixes or accents being entirely omitted. The wording of the Sūtras is much similar to that of

Pāṇini; at some places it is even identical. The order of the treatment of the subjects in the सिद्धहैम-शन्दानुशासनमृत्र is not, however, similar to that obtaining in the Astadhyāyī of Pāṇini. It is somewhat topicwise as in the Katantra Vyakarana. The first Adhyaya and a quarter of the second are devoted to Samjñā, Paribhāṣā and declension; the second Pada of the second Adhyava is devoted to kāraka, while the third Pāda of it is devoted to cerebralization and the fourth to the Stripratyayas. The first two Pādas of the third Adhyāya are devoted to Samāsas or compound words, while the last two Padas of the third Adhyaya and the fourth Adhyāya are devoted to conjugation. The fifth Adhyava is devoted to verbal derivatives or krdanta, while the sixth and the seventh Adhyayas are devoted to formations of nouns from nouns, or taddhita words. On this Sabdanuśāsana, which is justilike Pāņini's Astādhyayī, the eighth adhyāya of Hemacandra being devoted to the grammar of the Arsa language similar to Vedic grammar of Pănini, Hemacandra has himself written two glosses which are named लघुश्वित and बृहद्श्वित and the famous commentary known the Brhannyasa. Besides these works viz. the इमहानदानुशासन, the two Vrttis on it and the Brhannyāsa, he has given an appendix viz. the Linganusasana. The Grammar of Hemacandra, in short, introduced a new system of grammar different from, yet similar to, that of Panini, which by his folwas made completely similar to the Paniniya system by writing works similar to the Siddhāntakaumudī, the Dhātuvṛtti, the Manoramā and the Paribhāṣen-duśekhara.

हेमहंसगणि a grammarian belonging to the school of Hemacandra, who lived in the fifteenth century and wrote a work on Paribhāṣās named न्यायसंग्रह, on which he himself wrote a commentary called न्यायर्थमञ्जूषा and another one called by the name न्यास.

ইন্তাৰ্থান্ত a learned grammarian who wrote a commentary on the third Kāṇḍa of the Vākyapadīya of Bhartṛhari to which he has given the name স্কীগীসকায়.

हैमकौमुदी an exhaustive commentary on the Śabdānuśāsana of Hemacandra written by a Jain grammarian Meghavijaya in the seventeenth century which is similar to the Siddhāntakaumudī of Bhaṭṭojī Dīkṣita.

हैमधातुव्याख्या written by a Jain grammarian named पुण्यसुंदर which is similar to the Mādhavīyā Dhātuvṛtti.

हैमबृहत्यिकिया a work very similar to the Siddhantakaumudi written by a comparatively modern Jain scholar named Girijāshaukar Shāstrī.

हैमबृहद्द्यति a gloss written on the Haima Sabdānusāsana sūtrapātha by Hemacandra himself. See हेमचन्द्र above.

हैमवृहत्त्र्यास an extensive critical commentary written by Hemacandra on his own work, Haima Sabdanusasana. See हमचन्द्र.

हैमलघुपाक्रियावृत्ति a topicwise work based on Hemacandra's Śabdānuśāsana written by Vinayavijaya, a Jain scholar of grammar.

हैमलघुनुत्ति a short gloss on the Sabdanusasana, written by Hemacandra himself. See हेमचन्द्र above.

हैमाळिङ्गानुशासन a treatise on genders written by हेमचन्द्र. See हेमचन्द्र above.

हैमालेङ्गानुशासनविवरण a commentary, written in the seventeenth century by Kalyāṇasāgara on the हैमालेङ्गानुशासन.

हैमालिङ्गानुशासनव्याख्या a commentary named उद्घार also, written by Jaya-nanda on the हैमलिङ्गानुशासन.

हैमन्याकरण a treatise on grammar written by हेमचन्द्र, called by the name हैमराब्दानुशासन. See हेमचन्द्र above.

हैमशब्दानुशासन a treatise on grammar written by Hemacandra. See हेमचन्द्र above.

हैमशब्दानुशासनलघुन्यास a short commentary on Hemacandra's Sabdānusāsana written by Devendrasūri.

हैमशब्दानुशासनवृत्ति a short gloss called अवचूरि also, written by a Jain grammarian नन्दसुन्दर on the हैम-शब्दानुशासन.

used by ancient grammarians for the affixes of the immediate past tense, but not comprising the present day, corresponding to the term रुड् of Pāṇini. The term is found in the Kātantra and Haimacandra grammars; cf. Kāt. III. 1.23, 27; cf. Hema. III. 3.9.

हस्व short, a term used in connection with the short vowels taking a unit of time measured by one mātrā for their utterance; cf. ककालोज्इस्वदीधिष्ट्वत: P. I. 2.27.

॥ ग्रन्थप्रशास्तिः ॥

प्रातिशाख्यमहाभाष्यकौ मुदीकाशिका दिकान् । प्रन्थान् वाक्यपदीयादीश्वाभ्यस्य श्रमपूर्वकम् ॥ १ ॥ प्रन्थानां प्रन्थकाराणां नामानि प्रत्ययांस्तथा । विशिष्टशास्त्रीयार्थस्य वाचकान् पारिभाषिकान् ॥ २ ॥ शब्दान् समीक्ष्य संज्ञादीनादेशानागमांस्तथा । यदारब्धं संप्रथनं कालात् प्राक् सुबहोर्भया ॥ ३ ॥ अभ्यंकरोपाह्नकुले वासुदेवस्य सूनुना । काशिनायाभिधेनेदं कोषरूपं समापितम् ॥ ४ ॥ शालिवाहनशाकेस्मित्रष्टादशशतोत्तरे । त्र्यशीत्यधिकवर्षेस्मिश्चेत्रस्य प्रतिपत्तिथौ ॥ ५ ॥ द्राग् व्याकरणकोषाद्यं कृपया परया प्रभो: । निर्च्यूढं कार्यमेतन्मे कुर्याद्विद्वद्भृदि स्थितिम् ॥ ६ ॥ इह न्याकरणे शास्त्रे प्रन्यभूयस्त्वकारणात् । कोषार्हा बहव: राब्दा दिङ्मात्रमिह दर्शितम् ॥ ७ ॥ बुद्धिवैचित्रयतः केचित् कोषानर्हाः स्थिता यदि । रान्दास्तदर्हा गलिताः प्रार्थये क्षम्यतां बुधैः ॥ ८ ॥

